




3 1761 02459141 4


UNIV. OF
TORONTO
LIBRARY




Presented to
The Library
of the
University of Toronto
by

Professor Jackson.







Digitized by the Internet Archive
in 2007 with funding from
Microsoft Corporation

Bot
Thalloph
A

CULTURES
OF
UREDINEAE

1899 - 1921

By

Joseph Charles
J. C. ARTHUR

240921
17.2:30

B

RECEIVED
JAN 10 1902

JAN 10 1902

JAN 10 1902

K. A. 1902

Bot. Gaz. vol. 29.

No. ①

CULTURES OF UREDINEÆ IN 1899.¹

J. C. ARTHUR.

WITH the exception of the very important results achieved by Thaxter in the study of American Gymnosporangia, together with similar work by Farlow, Halsted, Stewart, and Carver, only a few attempts have been made in America to trace the connection experimentally between the forms of the Uredineæ.

The three stages of the clover rust (*Uromyces Trifolii*) were shown by Howell to be genetically connected and the two forms of the raspberry rust (*Gymnoconia interstitialis*) by Clinton. A slight amount of work in this line of research, chiefly of a confirmatory character, was carried out between 1889 and 1898 by Bolley, Stuart, and the writer. The yet unpublished results of Carleton, obtained as part of the work of the division of vegetable physiology and pathology at Washington,² complete the mention of all American efforts in this line that now occur to the writer.

The cultures made during the present season (1899), herein to be described, were conducted, with the exception of a single trial, under glass in the greenhouses of the Experiment Station at Purdue University, and upon plants in pots, the plants remaining under cover until the observations were completed. Material bearing teleutospores of a number of species was collected during the previous autumn and winter and preserved until needed by tying in loose muslin and placing on the ground out of doors.

The method generally adopted to secure infection was the same, whether æcidia, uredo, or teleutospores were in hand. The potted plant was first wet with an atomizer, parts covered with a bloom being rubbed with the fingers until the water

¹ Read before the Botanical Section of the Am. Assoc. Adv. Sci., Columbus meeting, August, 1899.

² Issued as Bulletin No. 16 since the paper was read.

adhered. The spores were scraped from the host material with a knife blade and placed on definite areas of the plant to be infected, the parts marked by bits of string, and a bell jar placed over the whole plant. After a day or two the bell jar was removed. With most species, if the operation had been successful, the results began to appear in six to fourteen days.

In order that the simple procedure here outlined may uniformly give information that can be relied upon, many small precautions must be observed that cannot now be spoken of. In every case it is wise to first make a drop culture, to be sure that the spores are viable.

In the following outline of the work accomplished it is impossible to go into much detail, or mention all the items of interest that are naturally brought to mind. It is also impossible to adjust the nomenclature in accordance with the new knowledge which the cultures have furnished.

I. PUCCINIA PHRAGMITIS (*Schum.*) *Körn.*

The host of this species, *Phragmites communis*, does not grow in the vicinity of Lafayette, Indiana, where the work was done, and I am indebted to Dr. J. J. Davis of Racine, Wis., and Professor C. E. Bessey, of Lincoln, Neb., for teleutosporic material. Abundance of æcidia were obtained by sowing the teleutospores upon *Rumex crispus* and *R. obtusifolius*, thus confirming the results obtained by European investigators. The dates are as follows:

- May 2, Teleutospores (Wis.) sown on *Rumex crispus*; May 12 spermogonia; May 15, æcidia.
- May 4, Teleutospores (Wis.) sown on *Rumex obtusifolius*; May 15, spermogonia; May 16, æcidia.
- May 9, Teleutospores (Neb.) sown on *Rumex crispus*; May 15, spermogonia; May —, æcidia.
- May 9, Teleutospores (Neb.) sown on *Rumex obtusifolius*; May 15, spermogonia; May —, æcidia.

The preliminary drop cultures showed the most vigorous germination of teleutospores obtained with any species, and far surpassing most of those under observation. The sowings also

produced a wealth of æcidia. From these facts one would infer that æcidia on *Rumex* should be common, for the teleutospore condition occurs throughout the United States. Yet I am not aware of a single authentic record of *Æcidium rubellum* being found in North America. To be sure, it occurs in the earliest published list of American fungi by Schweinitz, who was a notably accurate observer. But his remark that the spots were usually sterile, makes it fairly certain that what he collected were not æcidia, but the spots made by *fungi imperfecti*. Both Professor Bessey and Dr. Davis at my suggestion made repeated and thorough search about the places where the teleutospores were found in their localities, but saw no æcidia. Improbable as it may seem, there yet appears to be no explanation of the remarkable vigor of this heteroecismal species, but to suppose that the æcidia do occur in America, and that, so far, they have been overlooked.

2. PUCCINIA CONVULVULI *Cast.*

The teleutospores of this very common species of rust on *Convolvulus sepium* were sown on the host, before the weather permitted it to start out of doors, and were duly followed by a rich development of spermogonia and subsequently of æcidia. It was thus experimentally shown to be an autæcious species, as has always been tacitly accepted. The dates are as follows: May 8, Teleutospores sown; May 16, spermogonia; June 6, æcidia.

3. PUCCINIA CARICIS (*Schum.*) *Reb.*

The æcidiospores from *Æcidium Urticæ* were sown May 17 on the young leaves of *Carex stricta* and in eleven days were followed by uredospores. A sowing at the same date on *Carex cephalophora* gave no infection. This shows that *Carex stricta* is a host for *Puccinia caricis*, but there is reason to believe that it also acts as a host for other species of *Puccinia*. The American rusts on *Carex* are yet little understood.

4. UROMYCES EUPHORBIAE *C. & P.*

There has been an almost uniform opinion among American botanists that the *Æcidium* occurring abundantly upon many

species of *Euphorbia* is not genetically related to the brown rust equally abundant upon the same hosts. The evidence I have to offer is not conclusive, but, so far as it goes, must change this view. On June 20 æcidiospores from *Euphorbia nutans* were sown upon two plants of the same species and upon one plant of *Euphorbia maculata*. Nine days afterward uredo appeared upon one of the plants of *Euphorbia nutans*, and in eleven days upon the other, followed in both cases by teleutospores after a time, the exact date not recorded, but the plant of *E. maculata* showed no infection.

Instead of speculating upon such meager data, I am inclined to believe that *Uromyces Euphorbiæ* is an autœcious species, and to await further cultures showing if it is separable into races.

5. PHRAGMIDIUM SPECIOSUM Fr.

The intimate association of a cæoma, which is not distinguishable from *Cæoma miniata* Schl., with this exclusively American species of *Phragmidium*, would have been accepted as sufficient evidence of its genetic connection, if the same form apparently had not been considered in Europe as the first stage of the very different *Phragmidium mucronatum*, a species that is also common in this country.

At the time when the teleutospores of *Phr. speciosum* were in germinating condition no potted plants of native roses were available, and sowings were made upon the leaves of a tea rose, the Kaiserin Augusta Victoria. The work was done by my assistant, Mr. William Stuart, and the dates are not at hand, but in due course of time many pustules of cæoma appeared. These bore every resemblance to the usual form, although they did not become very large, which may have been due to the host not being congenial.

It is probably safe to assume that the rose cæoma in this country belongs wholly to *Phragmidium speciosum*, or else that there are two species not at present separable.

6. TRIPHFRAGMIUM ULMARIAE (Schum.) Lk.

This species of rust, not heretofore reported for America, so far as the writer knows, was found in considerable abundance

this spring near Lafayette, Ind., upon *Ulmaria rubra* (*Spiræa lobata*), in the bright red cæoma stage. Feeling at first uncertain of the identity of the rust, the cæoma spores were sown upon the *Ulmaria*, and also upon *Salix*, *Convolvulus*, and *Ipomœa*, with the result that it grew only upon *Ulmaria*, producing at first uredospores and afterward teleutospores. An after-sowing of uredospores upon *Ulmaria* gave a crop of more uredospores. The dates are as follows:

May 17, Cæomospores sown on *Ulmaria rubra*; May 30, uredo; July — teleutospores.

May 17, Cæomospores sown on *Salix longifolia*; no infection.

May 23, Cæomospores sown on *Convolvulus sepium*; no infection.

May 24, Cæomospores sown on *Ipomœa pandurata*; no infection.

June 16, Uredospores sown on *Ulmaria rubra*; July —, uredospores.

7. PUCCINIA AMERICANA Lagh.

This grass rust on various species of *Andropogon* is very common throughout North America, but has been generally confounded with *Puccinia Andropogi* Schw., which has the same range and affects the same hosts. The teleutospores are barely distinguishable, but the uredospores are entirely unlike those of *P. Americana*, being large and thin walled, those of *P. Andropogi* small and thick walled. The detection of the æcidium is due to the careful observation of Mr. William Stuart, who noticed that plants of *Pentstemon pubescens*, growing near *Andropogon* bearing teleutospores of the previous year, were well covered with æcidia (*Æcidium Pentstemonis* Schw.), while the same species in other localities was quite free. With this hint sowings were undertaken. Teleutospores from *Andropogon scoparius* were sown on *Pentstemon pubescens* and æcidia appeared in great abundance and vigor; æcidiospores were sown on *Andropogon* and large, thin-walled, brown uredospores appeared. The results were ample and complete, and were further emphasized by similar results subsequently obtained by Mr. Stuart. The dates are as follows:

May 3, Teleutospores from *Andropogon scoparius* sown on *Pentstemon pubescens*; May 11, spermogonia; May 20, æcidia.

May 4, Teleutospores from *A. furcatus* sown on *Oenothera biennis*; no infection.

May 15, Æcidiospores from *P. pubescens* sown on *A. scoparius*; May 29, uredo.

8. PUCCINIA ANGUSTATA Pk.

The detection of the æcidium of this common rust on *Scirpus* was also due to a fortunate observation. It was noticed that some plants of *Lycopus*, growing within a few feet of *Scirpus atrovirens* covered with last year's teleutospores, were well besprinkled with æcidia (*Æcidium Lycopi* Ger.), while plants some distance away were free. Sowings of æcidia were made on the leaves of the *Scirpus* and characteristic uredo obtained. The hint was secured so late in the season that only one sowing was possible, but the result is thought to be measurably reliable.

May 23, Æcidiospores from *Lycopus Americanus* sown on *Scirpus atrovirens*; June 6, uredo.

9. PUCCINIA WINDSORIÆ Schw.

This rust occurs, often in great abundance, upon the much benamed grass, *Triodia cuprea* (*Sieglingia seslerioides* Scrib.), which in the days of Schweinitz was standing in the genus *Windsoria*. The name of the rust was applied in Burrill's *Parasitic Fungi of Illinois* fourteen years ago, to the very different rust on *Muhlenbergia*, hence great confusion has arisen, and in nearly all recent lists and treatises the name is misused.

The hint that led to successful cultures came from an observation upon proximity, as in the previous cases. A small shrub of *Ptelea trifoliata* was made conspicuous by the bright yellow spots of *Æcidium Pteleæ* B. & C., and not ten feet away was a large clump of the grass with the dead stems and leaves black with teleutospores. Successful sowings of æcidiospores were made on the grass, but the season by this time had advanced so far that germinating teleutospores were no longer obtainable with which to try the reverse cultures. The dates are as follows:

May 15, Teleutospores sown on *Ambrosia trifida*; no infection.

May 17, Teleutospores sown on *Napæa dioica*; no infection.

June 8, Æcidiospores sown on *Triodia cuprea*; June 15, uredo.

June 16, Æcidiospores sown on *Triodia cuprea*; June 23, uredo.

10. PUCCINIA VILFÆ A. & H.

This species of rust, better known as *P. Sydowiana* Diet., is necessarily restricted in the vicinity of Lafayette to the few localities where the host, *Sporobolus longifolius*,³ is to be found. My attention was called to the fact by Miss Lillian Snyder that in such localities the exceedingly common upright verbenas were richly covered with *Æcidium verbenicola* K. & S., and with no other species of æcidia in the vicinity. Going over the ground myself, I found that the verbenas plants, *Verbena stricta* being particularly abundant, were more thickly studded with æcidia the closer they stood to tufts of rusted *Sporobolus*, and that fifty feet away from such source of infection they would be entirely free.

Cultures were undertaken in 1898, but too late in the season to secure results. In the mean time a morphological resemblance was observed between the spores of *Æcidium verbenicola* and the uredospores of *Puccinia Vilfæ*, that gave another hint at genetic relationship. Both sorts of spores were approximately obovate, with colorless walls, greatly thickened at the apex, and papillose instead of echinulate. Successful cultures have shown that these rather uncommon characters meant more than a coincidence in this case. It is the first time, so far as the writer knows, that any significant resemblance has been pointed out between the spores of æcidia and uredo of the same species.

For some unexplained reason I was unsuccessful in germinating the teleutospores of *P. Vilfæ*, although they were taken a number of times directly from the field. But with æcidiospores the results were ample and convincing. The dates are as follows:

May 31, Æcidiospores from *Verbena stricta* on *Sporobolus longifolius*; June 10, uredo.

June 9, Æcidiospores from *Verbena stricta* on *Sporobolus longifolius*; June 21, uredo.

³Since this paper was read I have discovered that the grass under observation was *Sporobolus longifolius* (Torr.) Wood, instead of *S. asper*, as given in the manuscript, and printed in Science 10: 565, and Proc. A. A. S. 48: 299. The latter grass does not grow in this region.

II. PUCCINIA PERIDERMIOSPORA (E. & T.) Arth.

In studying the grass rusts it was noticed that a form on *Spartina*, well represented in American herbaria and usually called *Puccinia Phragmitis*, had uredospores similar to those of *Puccinia Vilfæ*, just described. I searched through my collection of *Æcidia* to see if any species with corresponding apically thickened spores could be found, and was rewarded in the case of *Æcidium Fraxini* Schw. With this morphological hint as the sole guide cultures were undertaken.

Spartina does not grow within many miles of Lafayette, and I am indebted to the kindness of Professor C. E. Bessey, of Lincoln, Neb., and Mr. H. H. Hume, of Ames, Iowa, for teleutospore material upon *Spartina cynosuroides*. The teleutospores germinated with marked vigor, and were first sown on *Ptelea trifoliata*, the small plants obtained being mistaken for *Fraxinus*. When the mistake was discovered, and sowings were made on *Fraxinus viridis*, infections were first secured. As no small plants of *Fraxinus* were available, the spores were sown upon cut twigs placed in water in the greenhouse, and upon a low branch of a large tree out of doors. There could be no fear of spontaneous infection, as the species does not occur in the region, either upon *Spartina* or *Fraxinus*, but the usual precautions were taken. The sowings were both successful. The dates are as follows:


- May 8, Teleutospores (Neb.) sown on *Ptelea trifoliata*; no infection.
- May 9, Teleutospores (Neb.) sown on *Ptelea trifoliata*; no infection.
- May 9, Teleutospores (Iowa) sown on *Ptelea trifoliata*; no infection.
- May 15, Teleutospores (Neb.) sown on *Ptelea trifoliata*; no infection.
- May 17, Teleutospores (Iowa) sown on cut twigs of *Fraxinus viridis*; May 24, spermogonia; June 6, æcidia.
- May 17, Teleutospores (Neb.) sown on tree out of doors of *Fraxinus viridis*; May 29, spermogonia; June 8, æcidia.

SUMMARY.

The following are the eleven species of Uredineæ, whose æcidial and teleutospore forms have been definitely connected by cultures:

1. *Puccinia Convolvuli* Cast. and *Æcidium Calystegiae* Desm. with sowings of teleutospores.
2. *Puccinia Phragmitis* (Schum.) Körn. and *Æcidium rubellum* Pers. with sowings of teleutospores.
3. *Puccinia Americana* Lagh. and *Æcidium Pentstemonis* Schw. with sowings of æcidiospores and teleutospores.
4. *Puccinia Windsoriæ* Schw. and *Æcidium Pteleæ* B. & C. with sowings of æcidiospores.
5. *Puccinia Vilfæ* A. & H. and *Æcidium verbenicola* K. & S. with sowings of æcidiospores.
6. *Puccinia peridermiospora* (E. & T.) Arth. and *Æcidium Fraxini* Schw. with sowings of teleutospores.
7. *Puccinia Caricis* (Schum.) Reb. and *Æcidium Urticæ* Schum. with sowings of æcidiospores.
8. *Puccinia angustata* Pk. and *Æcidium Lycopi* Ger. with sowings of æcidiospores.
9. *Uromyces Euphorbiæ* C. & P. and *Æcidium Euphorbiæ* Am. Auct. with sowings of æcidiospores.
10. *Phragmidium speciosum* Fr. and *Cæoma miniata* Am. Auct. with sowings of teleutospores.
11. *Triphragmium Ulmariae* (Schum.) Lk. and *Cæoma Ulmariae* Thüm. with sowings of æcidiospores and uredospores.

PURDUE UNIVERSITY,
Lafayette, Ind.



(Reprinted from the *Journal of Mycology*, Vol. 8, June 1902.)

CULTURES OF UREDINEAE IN 1900 AND 1901

BY J. C. ARTHUR.

The first especially important cultures of plant rusts made by the writer were conducted in 1899, and the results published in the *Botanical Gazette* for April 1900 (29:268-276). During the two following years only a small number of cultures were made, and for a number of reasons the results have not been put into type until now. This article is, therefore, the second of the series.

The method pursued in most cases in making the cultures has been stated in the preceding article. It was, in brief, to remove spores with a knife from the host, and place them on a dampened plant which it is desired to infect. The plants are grown in pots. After the spores are sown the whole plant is covered with a belljar and kept shaded for a day, or sometimes two days. The plants are then uncovered and placed on a greenhouse bench, where they remain until the period of observation is ended.

In 1900 the only cultures made that require mention were with *Euphorbia* rust. The results supplement and confirm those made in 1899 (*Bot. Gaz.* 29:270-271). It was again found that spores from *Euphorbia nutans* would grow upon the same species, but not upon *E. maculata*. It seems quite probable that this rust, *Uromyces euphorbiae* C. & P. possesses specialized forms. The record is as follows:

July 21, Aecidiospores from *Euphorbia nutans* sown on *E. nutans*; July 30, uredo.

July 21, Aecidiospores from *E. nutans* sown on *E. maculata*; no infection.

July 21, Uredospores from *E. nutans* sown on *E. nutans*; July 31, uredo.

July 21, Uredospores from *E. nutans* sown on *E. maculata*; no infection.

There are two ways in which the right species of plant may be selected on which to make a sowing of a heteroecious rust. One is to sow upon any species known to harbor an aecidium, hoping after making a smaller or larger number of tests to hit upon the right one. This method in my own work has led to very meagre results, so slight, in fact, as scarcely to be worth the trouble. During 1901 the following rusts were tried in this blind way, all being very common forms in this vicinity, only to ascertain that wrong plants were selected for the sowings or else the spores did not gain entrance possibly through defective treatment.

Puccinia emaculata Schw. on *Panicum capillare* was sown twice on *Onagra biennis*, with no infection.

Puccinia caricina DC. A form of this aggregate on *Carex tetanica* was sown on *Erigeron annuus* and *Onagra biennis*, with no infection.

Puccinia atkinsoniana Diet. on *Carex lurida*. The name of this species was unknown at the time the cultures were made, but through the kindness of Professor Atkinson, it has since been compared with type material and its status definitely settled. It was sown on *Aster cordifolius*, *Aster paniculatus*, *Solidago serotina*, *Xanthium canadense*, *Ambrosia trifida*, *Impatiens aurea* and *Ribes cynosbati*, with no infection.

Puccinia peckii (DeT.) Kellerm. on *Carex trichocarpa*. The names of both host and rust were unknown at the time the cultures were made. The host has since been found in fruit, and the rust has been successfully grown by Professor Kellerman and also the writer, as recorded in the preceding number of this Journal (8:20). Spores were sown on *Aster cordifolius*, *Aster paniculatus*, *Solidago serotina*, *Solidago canadensis*, *Ribes cynosbati*, *Erigeron annuus*, and *Eupatorium perfoliatum*, with no infection.

Puccinia rubigo-vera DC. A form of this aggregate of *Bromus ciliatus* was sown on *Hepatica acuta* and *Viola cucullata*, with no infection.

During 1901 the culture of seven species was successfully carried out. Three of these were in confirmation of previous work, as follows:

Puccinia caricis (Schum.) Reb. April 25, teleutospores from *Carex stricta* were sown on *Urtica gracilis*; May 2, spermogonia appeared, and May 5, æcidia.

Puccinia angustata Pk. May 3, teleutospores from *Scirpus atrovirens* were sown on *Lycopus americanus*; May 11, *Spermogonia* appeared, and May 20, aecidia.

Puccinia poculiformis (Jacq.) Wettst. May 2, teleutospores from *Cinna arundinacea* were sown on *Berberis vulgaris*; May 13, *spermogonia* appeared, and May 22, aecidia.

Of the remaining four species, all *Carex* rusts, the clues which led to successful cultures were obtained in the field, and have been mentioned and explained in an article in the *Botanical Gazette* for January of the present year. For three of these species it seems necessary to propose new names. All are yet insufficiently studied to determine their exact boundaries.

PUCCINIA ALBIPERIDIA sp. nov.

O. *Spermogonia* amphigenous, small, pale orange.

I. Aecidia hypophyllous, small in circular clusters; substratum scarcely thickened; peridia white, low, margin incised, reflexed; spores pale yellow when fresh, subglobose, 15-20 μ in diameter; wall thin, smooth.

II. Uredosori hypophyllous, small, round or oblong, soon naked; uredospores oblong, small, echinulate.

III. Teleutosori hypophyllous, globose or oblong, pulvinate, dark brown. Teleutospores oblong-cuneate, 17-24 by 32-45 μ ; apex semi-circular or obtuse, thickened to half the length of the upper cell; side walls thin, slightly or not constricted; pedicel slender, colored, as long as the spore or shorter.

On *Ribes cynosbati* L. grown June, 1901 from teleutospores collected on *Carex pubescens* Muhl, Lafayette, Ind., April 30, 1901.

This species is characterized by the white or nearly white aecidia, which may be called *Aecidium albiperidium*. They are in marked contrast with the deep orange aecidia that are so abundant throughout North America on various species of *Ribes*. The only field collection known to the writer is one on *Ribes gracile* made at Decorah, Iowa, by E. W. D. Holway on June 2, 1901. When dry and faded the two forms of aecidia are much alike. Cultures were made as follows:

May 16, teleutospores from *Carex pubescens* sown on *Aster paniculatus*; no infection.

May —, teleutospores from *Carex pubescens* sown on *Ribes cynosbati*; May 30, *spermogonia*; June 9, aecidia.

PUCCINIA CARICIS-ERIGERONTIS sp. nov.

O. *Spermogonia* epiphyllous, prominent, golden yellow.

I. Aecidia hypophyllous, in circular clusters; substratum slightly thickened; peridia short, much divided and recurved; aecidiospores yellow when fresh, isodiametric, 12-15 μ in diameter, wall thin, minutely tuberculate.

II. Uredosori hypophyllous, small, oblong, tardily naked; uredospores brownish-yellow when fresh, oval or obovate, small, 12-18 by 16-22 μ wall thin, thickly echinulate, pores 3 or 4 scattered.

III. Teleutosori hypophyllous, small, oblong, pulvinate, blackish brown, ruptured epidermis evident; teleutospores clavate or oblong-clavate, 14-20 by 35-42 μ ; septum above the middle; apex obtuse or truncate, much thickened; side walls thin; pedicel firm; colored, one fourth or one half the length of the spore.

On *Erigeron annuus* (L.) Pers. and *Carex festucacea* Willd., Lafayette, Ind.

This species is without doubt the *Caeoma* (*Aecidium*) *erigeronatum* Schw. (Trans. Amer. Phil. Soc. 4:292), and probably occurs on many species of *Erigeron* throughout North America. Cultures were made as follows:

April 25, teleutospores from *Carex festucacea* sown on *Erigeron annuus*; May 2, spermogonia; May 11, aecidia.

April 25, teleutospores from *C. festucacea* sown on *Taraxacum taraxacum*; no infection.

PUCCINIA CARICIS-ASTERIS sp. nov.

O. Spermogonia epiphyllous, yellow, punctiform, sunken in tissue of the leaf.

I. Aecidia hypophyllous, collected in groups on slightly swollen yellow or purplish spots, low, margin much divided and recurved; aecidiospores subglobose, 12-17 μ in diameter, wall thin, minutely roughened.

II. Uredosori hypophyllous, oblong; uredospores oblong or obovate, 12-16 by 18-22 μ ; wall thin, echinulate; pores few, scattered.

III. Teleutosori hypophyllous, oblong to oblong-linear, prominent, soon naked, dark brown, ruptured epidermis noticeable; teleutospores oblong or clavate-oblong, 16-22 by 48-56 μ ; apex rounded, greatly thickened; pedicel slender, colored, half the length of the spore.

On *Aster paniculatus* Lam., *Aster cordifolius* L. and *Carex foenea* Willd. The latter collected at Decorah, Iowa, Dec. 30, 1900 by E. W. D. Holway, and at Lafayette, Ind., April 30, 1901, by the writer.

The common aecidium, found on many species of *Aster*, is probably included in this species, but not the aecidia found on *Erigeron*, *Solidago* or *Geranium*. It is the same as *Aecidium asterum* Schw. The uredospores and teleutospores are very similar to those of the preceding species, and are suggestive of biological species. Much work, however, must be done before an approximately accurate statement can be made regarding the *Carex* species having aecidia upon Compositae. Data for the present separation was obtained as follows:

April 25, teleutospores from *Carex foenea* (Iowa) sown on *Erigeron annuus*; no infection.

April 29, teleutospores from *C. foenea* (Iowa) sown on *Erigeron annuus*; no infection.

May 4, teleutospores from *C. foenea* (Indiana) sown on *Aster paniculatus*; May 13, spermogonia; May 22, aecidia.

May 4, teleutospores from *C. foenea* (Indiana) sown on *Erigeron annuus*; no infection.

May 11, teleutospores from *C. foenea* (Indiana) sown on *Geranium maculatum*; no infection.

May 11, teleutospores from *C. foenea* (Iowa) sown on *Erigeron annuus*; no infection.

May 13, teleutospores from *C. foenea* (Iowa) sown on *Aster paniculatus*; May 20, spermogonia; May 28, aecidia.

May 13, Teleutospores from *C. foenea* (Iowa) sown on *Solidago canadensis*; no infection.

May 13, teleutospores from *C. foenea* (Indiana) sown on *Aster cordifolius*; May 23, spermogonia; May 30, aecidia.

May 13, teleutospores from *C. foenea* (Indiana) sown on *Solidago canadensis*; no infection.

PUCCINIA BOLLEYANA SACC.

This species is first mentioned in the Amer. Mo. Micr. Journal for 1889 (10:169), with an illustration but no description. It was first described in Saccardo's Sylloge (9:303), two years later. It was collected originally on a sterile sedge, presumably a *Carex*, growing from two to four feet high. The type locality is within two miles of Lafayette, Ind., and only an area ten or fifteen feet across supports the sedge, but almost every leaf over this area has been thickly covered with the rust each season since its discovery. Last year it was found in another locality about four miles distant. It has not been reported from any other place in this or other states, but a specimen sent from Kenosha county, Wisconsin, by Dr. J. J. Davis has proved to be this species. The species is especially characterized by the large teleutospores, and the brown, fusiform uredospores. Within the last month a fruiting specimen of the host has been found upon the type area, which shows it to be *Carex trichocarpa* Muhl. This in brief is the history of the rust up to the time of making the following cultures. Whether the aecidium, which has been found to grow on *Sambucus canadensis*, is the wide-spread *Aecidium sambuci* Schw., or not, it would be premature to say.

May 2, teleutospores from *Carex trichocarpa* sown on *Sambucus canadensis*; May 10, spermogonia; May 22, aecidia.

May 3, teleutospores from *C. trichocarpa* sown on *Xanthium canadense*; no infection.

May 3, teleutospores from *C. trichocarpa* sown on *Impatiens aurea*; no infection.

June 15, aecidiospores from *Sambucus canadensis* sown by Wm. Stuart on *Carex trichocarpa*; July 16, abundant uredospores first noticed, but probably not the first sori to appear.

SUMMARY.

During 1900 and 1901 the life cycle of the following eight species of rusts was demonstrated by cultures. Of these successful cultures, the first four have been previously reported, while the cycle of the second four is here reported for the first time.

1. UROMYCES EUPHORBIAE C. & P. and Aecidium euphorbiae Amer. Auct. with sowings of aecidiospores and uredospores.
2. PUCCINIA CARICIS (Schum.) Reb. and Aecidium urticae Schum. with sowings of teleutospores.
3. PUCCINIA ANGUSTATA Pk. and Aecidium lycopi Ger. with sowings of teleutospores.
4. PUCCINIA POCULIFORMIS (Jacq.) Wettst. and Aecidium berberidis Pers. with sowings of teleutospores.
5. PUCCINIA ALBIPERIDIA Arth. and Aecidium albiperidium Arth. with sowings of teleutospores.
6. PUCCINIA CARICIS-ERIGERONTIS Arth. and Aecidium erigeronatum Schw. with sowings of teleutospores.
7. PUCCINIA CARICIS-ASTERIS Arth. and Aecidium asterum Schw. with sowings of teleutospores.
8. PUCCINIA BOLLEYANA Sacc. and Aecidium sambuci Schw. (?) with sowings of teleutospores and aecidiospores.

Purdue University, Lafayette, Ind., June, 1902.

CULTURES OF UREDINEAE IN 1902.¹

J. C ARTHUR.

THE present article forms the third of a series of reports by the author upon the cultures of plant rusts. The first one² covered the year 1899, the second³ combined the years 1900 and 1901, and the third covers the year 1902. Like the preceding ones, the present report is devoted largely to the heteroecious grass and sedge rusts. The methods employed have already been described in connection with the previous reports.

The work was much more extended during the present season than had been possible in preceding years through the interest taken in it by the authorities of Purdue University, who generously defrayed the expense of additional assistance during the months of May and June, when the largest part of the work must be done. In this way it became possible to have the help for a time of Mr. Oliver P. Terry, an undergraduate of the university, and an unusually skilful manipulator. But the larger part of the testing with drop cultures and of the application of the spores to the plants throughout the whole of the busiest period was undertaken by Miss Julia Titus Emerson, of New York City, coming from the New York Botanical Garden, who showed great earnestness and rare judgment in carrying on the work.

During the present season 123 collections of material were employed, and 314 drop cultures were made from them to test the germinating condition of the spores. Out of these 23 collections refused to germinate, and were consequently useless. There were in all 327 plant cultures attempted, representing 43 species of rusts, and employing 102 species of hosts tempo-

¹ Read before the Botanical Society of America, Washington, Jan. 1, 1903.

² BOT. GAZ. 29: 268-276. April 1900.

³ Jour. Mycology 8: 51-56. June 1902.

rarely grown in pots in the greenhouse. In no case was success attained where definite clues derived from field observations were lacking.

Fourteen species were tried this year by the guessing method, no clues being known, and the following is a record of the failures, together with one instance, that of the *Panicularia* rust, where a seeming clue also failed. Teleutospores were employed in every case.

1. MELAMPSORA from *Populus deltoides* Marsh. was sown on *Larix europaea*, *Abies balsamea*, *Euonymus obovatus*, *Stylophorum diphyllum*, *Helianthus strumosus*, and *H. grosse-serratus*, with no infection.

2. MELAMPSORA on *Salix discolor* Muhl. was sown on *Larix europaea*, *Abies balsamea*, *Picea canadensis*, *Euonymus obovatus*, *Ribes aureum*, *R. gracilis*, and *Helianthus grosse-serratus*, with no infection.

3. UROMYCES JUNCII Tul. from *Juncus tenuis* Willd. was sown on *Iris versicolor*, with no infection.

4. UROMYCES SPOROBOLI E. & E. from *Sporobolus longifolius* (Torr.) Wood was sown on *Ceanothus americanus* and *Verbena stricta*, with no infection.

5. UROMYCES HALSTEDII De T. from *Homalocenchrus virginicus* (Willd.) Britt. was sown on *Senecio obovatus* and *Bidens frondosa*, with no infection.

6. PUCCINIA ELEOCHARIDIS Arth. from *Eleocharis palustris* (L.) R. & S. was sown on *Iris versicolor*, with no infection.

7. PUCCINIA SCHEDONNARDI K. & S. from *Schedonnardus paniculatus* (Nutt.) Trel. was sown on *Lepidium apetalum*, *Ceanothus americanus*, *Oxalis cymosa*, *Apocynum cannabinum*, *Cassia chamaecrista*, *Symphoricarpos racemosus*, *Xanthium canadense*, *Kuhnistera purpurea*, and *Lacinaria scariosa*, with no infection.

8. PUCCINIA MUHLENBERGIAE A. & H. from *Muhlenbergia racemosa* (Mx.) B. S. P. was sown on *Napaea dioica*, *Impatiens aurea*, *Oxalis cymosa*, *Anemone canadensis* and *A. virginiana*, *Hydrophyllum appendiculatum*, *Phlox divaricata*, *Physalodes Physalodes*, *Apocynum cannabinum*, and *Helianthus grosse-serratus*, with no infection.

9. PUCCINIA CHLORIDIS Speg. from *Chloris verticillata* Nutt. was sown on *Quamasia hyacinthina*, with no infection.

10. PUCCINIA SPOROBOLI Arth. from *Sporobolus heterolepis* Gray was sown on *Isopyrum bitematum*, *Oxalis cymosa*, *Xanthoxylum americanum*, *Ribes Cynosbati*, *Cassia Chamaecrista*, *Symphoricarpos racemosus*, *Verbena urticifolia*, *Senecio obovatus*, *Solidago rigida*, *Helianthus Maximiliani*, *Boltonia asteroides*, and *Brauneria purpurea* with no infection.

11. PUCCINIA PURPUREA Cke. from *Tripsacum dactyloides* L. was sown on *Zea Mays*, with no infection.

12. PUCCINIA STIPAE Arth. from *Stipa spartea* Trin. was sown on *Aesculus glabra*, *Cassia Chamaecrista*, *Psoralea Onobrychis*, *Symphoricarpos racemosus*, *Hydrophyllum appendiculatum*, *Xanthium canadense*, *Boltonia asteroides*, *Lacinaria scariosa*, and *Brauneria purpurea*, with no infection.

13. PUCCINIA PANICULARIAE Arth. from *Panicularia americana* (Torr.) MacM. was sown on *Boltonia asteroides*, with no infection, although three sowings were made at different dates and with all conditions apparently favorable. This seems to contradict the inference of the writer drawn from field observations (Bull. Torr. Bot. Club 28: 664).

14. PUCCINIA EMACULATA Schw. from *Panicum capillare* L. was sown on *Impatiens aurea*, *Lactuca canadensis*, and *Eupatorium perfoliatum*, with no infection.

15. PUCCINIA POLYGONI-AMPHIBII Pers. from *Polygonum emersum* (Mx.) Britt. was sown on *Polygonum pennsylvanicum* and *P. virginianum*, with no infection.

Twelve species of rusts were successfully grown, that have been studied with success before, and reported upon by the writer and others. They are enumerated here by way of confirmation, and also in some cases because additional hosts are included. The list is as follows:

1. UROMYCES EUPHORBIAE C. and P.—June 19, aecidiospores from *Euphorbia humistrata* Engelm. were sown on the same host, and were followed by uredo on July 8, and also on *E. nutans* and *E. marginata*, with no infection. July 11, aecidiospores from

E. nutans Lag. were sown on the same host, and were followed by uredo on July 21, and also on *E. humistrata* and *E. marginata*, with no infection. July 22, uredospores from *E. dentata* Michx., were sown on the same host, and were followed by uredo on Aug. 14, and also on *E. humistrata*, *E. nutans*, and *E. marginata*, with no infection. These results, taken in connection with those previously obtained by the writer,⁴ leave no opportunity for doubt that the Euphorbia rust is separable into a number of well established races, or possibly into true species.

2. UREDO RUBIGO-VERA DC.—May 31, uredospores from *Triticum vulgare* Vill. were sown on *Triticum vulgare*, and produced uredo on June 13, and at the same time on *Hordeum jubatum*, *Poa compressa*, *Dactylis glomerata*, and *Bromus ciliatus*, with no infection.

3. PUCCINIA PECKII (De T.) Kellerm.—The connection of a Puccinia on *Carex trichocarpa* Muhl. and *Aecidium Peckii* De T. on *Onagra biennis* (L.) Scop. (*Oenothera biennis* L.) has already been reported by Kellerman,⁵ and it was due to the suggestion from Professor Kellerman, founded upon his field observations, that the writer succeeded in bringing the present season's work to a satisfactory issue.⁶ Eleven collections of teleutospores were used: two from Ohio, sent by Professor Kellerman; two from Racine, Wisconsin, sent by Dr. J. J. Davis; two from Spirit Lake, Iowa, obtained by the writer; and the remainder from different localities near Lafayette, Indiana. Seven of these collections were definitely known to be on *Carex trichocarpa*, and four of them, those from Wisconsin and Iowa, were presumably on that host.

Spores from these collections were sown on *Urtica gracilis*, *Anemone canadensis*, *Geranium maculatum*, *Impatiens aurea*, *Sambucus canadensis*, *Ribes gracile*, *R. cynosbati* and *R. floridum*, *Xanthium canadense*, *Aster Shortii* and *A. paniculatus*, *Solidago canadensis*, *Erigeron annuus*, and *Leptilon canadensis*, with no infection. Successful cultures on *Onagra biennis* were made as follows, the

⁴ Bot. Gaz. 29:271. 1900, and Jour. Mycology 8:51. 1902.

⁵ Jour. Mycology 8:20. 1902.

⁶ For record of previous failures see Jour. Mycology 8:52. 1902.

period between the sowing of the dry spores and the appearance of the spermogonia varying from five to seven days, and between the appearance of the spermogonia and the appearance of the aecidia an equal length of time, the two intervals making ten to thirteen days.

CULTURES OF PUCCINIA FROM CAREX TRICHOCARPA
ON ONAGRA BIENNIS.

Teleutospores sown	Spermogonia appeared	Aecidia appeared
April 26	May 1	May 7
May 2	May 8	May 13
May 2	May 8	May 15
May 2	May 9	May 15
May 5	May 10	May 16
May 7	May 12	May 19
May 7	May 13	May 19
May 7	May 14	May 19
May 7	May 14	May 19
May 9	May 15	May 21
May 27	June 2	June 7
May 28	June 2	June 7
May 29	June 4	June 9

A collection on *Carex stipata* Muhl. also was made near Lafayette, Indiana, spores from which were sown on *Ribes Cynosbati*, *R. floridum*, *R. Uva-crispa*, *Aster paniculatus*, *A. prenanthoides*, *Solidago canadensis*, and *S. serotina*, with no infection. It was not until aecidia were found in the field on seedlings of *Onagra biennis*, growing close to the *Carex* still bearing dead leaves covered with teleutospores, that the right plant was selected for cultures. Teleutospores were sown on *Onagra biennis* June 23; spermogonia appeared in great abundance July 1, and aecidia July 8.

4. PUCCINIA BOLLEYANA Sacc. and P. ATKINSONIANA Diet.—The connection of *Puccinia Bolleyana*, which occurs on *Carex trichocarpa* Muhl., with *Aecidium Sambuci* Schw. has already been reported by the writer.⁷ This has been confirmed by further successful trials. Material gathered from the type locality of *P. Bolleyana*, when examined under the microscope, was found to show only a small proportion of the characteristic spores of

⁷ Jour. Myc. 8: 55.

this species, and a large proportion of much smaller spores, which were surmised to belong to *Puccinia Peckii*. Sowings were made, May 5, on *Sambucus canadensis* and *Onagra biennis*. May 10, abundant spermogonia appeared on *Onagra*, followed May 16 by aecidia. On *Sambucus* spermogonia appeared sparingly May 13, followed by aecidia May 21. The sedge, therefore, bore two species of rust in 1901, intermixed on the same leaves. In addition to this, on May 19, aecidiospores from *Sambucus canadensis* were sown on *Carex trichocarpa*, which gave rise to uredo on May 27. The connection of *Puccinia Bolleyana* with *Aecidium Sambuci* appears to be proven beyond question.

Two collections of *Puccinia Atkinsoniana* on *Carex lurida* Wahl. were sent from Columbus, Ohio, by Professor Kellerman, with the suggestion, which seemed to me at the time very improbable, that the aecidia doubtless occurred on *Sambucus canadensis*. Another collection was secured from the vicinity of Lafayette, Indiana. Two sowings were made on *Onagra biennis* without infection. One sowing from each of the three collections was made on *Sambucus canadensis* with abundant success in each case. The dates are respectively April 28, May 7 and 16; April 29, May 5 and 16; and May 7, 12, and 21. Professor Kellerman has written me that his cultures also gave similar results.

These discoveries led to a careful microscopic study of the two *Carex* rusts, and there appears to be no reason to question that *P. Atkinsoniana* and *P. Bolleyana* are identical. In the designation of the species it seems necessary on grounds of priority to abandon both these names, however, and it becomes ***Puccinia Sambuci*** (Schw.), nom. nov.

5. PUCCINIA CARICIS-ASTERIS Arth.—A collection of this species on *Carex foenea* Willd. was sown on *Solidago serotina*, with no infection. It was also sown, May 2, on *Aster paniculatus* Lam., and was followed by spermogonia May 8, and aecidia May 19, thus confirming the writer's previous work.⁸

6. PUCCINIA CARICIS-ERIGERONTIS Arth.—A collection of this rust on *Carex festucacea* Willd. was used for cultures on *Erigeron*

⁸Jour. Mycology 8: 54. 1902.

1903]

CULTURES OF UREDINEAE

annuus (L.) Pers., *E. philadelphicus* L., and *Leptilon canadense* (L.) Britt., with the most unqualified success. The work of last year⁹ is thus confirmed, and additional hosts ascertained.

7. PUCCINIA CARICIS (Schum.) Reb. — A collection of this rust on *Carex stricta* Lam., sent by Rev. J. M. Bates from Callaway, Nebraska, gave rise to aecidia when sown on *Urtica gracilis* Ait., the dates for sowing, appearance of spermogonia and aecidia being respectively May 24, June 2 and 7. The experimental proof of this connection has been reported¹⁰ twice previously for American material. A collection sent by Mr. E. W. D. Holway from Decorah, Iowa, on *Carex riparia* Curt. was sown on *Ribes cynosbati*, *R. gracile*, *R. aureum*, *R. floridum*, and *R. Uva-crispa*, *Geranium maculatum*, *Onagra biennis*, *Sambucus canadensis*, and *Xanthium canadense*, with no infection. It was sown on *Urtica gracilis* May 21, and gave spermogonia May 27, and aecidia June 2.

8. PUCCINIA VILFAE A. & H. — The alternate form of this rust has been shown¹¹ to be *Aecidium verbenicola* K. & S. These results have been verified this season by sowing teleutospores from *Sporobolus longifolius* (Torr.) Wood, collected at Callaway, Nebraska, by Rev. J. M. Bates, on *Verbena stricta* Vent. (culture dates May 28, June 3 and 10) and on *V. urticifolia* L. (culture dates the same). A collection from Lafayette, Indiana, on the same host, was also sown on *V. urticifolia* with success (culture dates May 2, 10, and 19). To conform to present knowledge the name of the rust should be written **Puccinia verbenicola** (K. & S.), nom. nov.

9. PUCCINIA WINDSORIAE Schw. — A collection of the teleutospores of this species of rust on *Tricuspis seslerioides* Torr. (*Triodia cuprea* Jacq.) was sent from Denton, Texas, by Mr. W. H. Long, Jr., with the statement that *Aecidium Pteleae* B. & C., which has been taken to the alternate form of the rust,¹² had not been observed in that vicinity. This material was sown on *Ptelea trifoliata* L., May 9, and spermogonia appeared May 15, followed by abundant aecidia May 24.

⁹Jour. Mycology 8:54. 1902.

¹⁰BOT. GAZ. 29:279. 1900, and Jour. Mycology 8:52. 1902.

¹¹BOT. GAZ. 29:274. 1900.

¹²BOT. GAZ. 29:273. 1900.

10. PUCCINIA HELIANTHI Schw.—Cultures showing this species to be autoecious have heretofore been made with American material only by Carleton¹³, but have been reported from Europe. Teleutospores gathered in this vicinity on *Helianthus grosse-serratus* Mart. were sown on the same species of host with success (culture dates May 8, 17, and 23) and also on *H. Maximiliani* Schrad. (culture dates May 8, 16, and 22), but sowings at two different dates on *H. strumosus* gave no infection. This evidence of races, so far as it goes, does not accord with Carleton's opinion that "there is no distinction of host forms."

11. PHRAGMIDIUM SPECIOSUM Fr.—A successful culture¹⁴ of this species of rust was again tried, using teleutospores from a hardy garden rose, obtained at Spirit Lake, Iowa, and sowing them on *Rosa humilis* Marsh. The culture was made April 24, and vigorous spermogonia appeared May 3, but the leaves gradually withered without the formation of the aecidial stage.

Beside the foregoing negative and confirmatory results, successful cultures were made establishing aecidial and teleutosporic association, heretofore unknown, for seven species of heteroecious grass and sedge rusts.

1. UROMYCES ARISTIDAE E. & E.—The material for the study of this species was received from Mr. W. H. Long, Jr., who suggested that its aecidial form was to be looked for on various species of *Plantago*. Teleutospores on *Aristida oligantha* Michx. were collected the middle of March, at Denton, Texas. Sowings were made from this material on *Plantago Rugelii* Dec., May 2, from which spermogonia arose May 13, and aecidia May 20. The development was not luxuriant, but very characteristic. A sowing on the same date on *P. lanceolata*, and later sowings on both species gave no infection. It would seem that these two species of *Plantago* are less suited to the ready development of the species than other members of the genus. The middle of April I received from Mr. Long freshly gathered aecidia on *Plantago virginica* L., and on two undetermined species, which are doubt-

¹³Science 13:250. 1901.

¹⁴For previous record see BOT. GAZ. 29:271. 1900.

less *P. Purshii* R. & S. and *P. aristata* Michx. I also have it in my herbarium on *P. virginica* from Illinois (Ellis and Everhart's N. Amer. Fungi, no. 1829), on *P. Purshii* from Nebraska (Fungi Columbiani, no. 1475), and on *P. eriopoda* Torr. from Montana, collected by F. D. Kelsey. The aecidium has passed under the name of *A. Plantaginis* Ces., but the identity with the European form needs verification, although microscopically the two are very similar.

2. PUCCINIA BARTHOLOMAEI Diet.—Again I am indebted to Mr. W. H. Long, Jr., for material and suggestions leading to the discovery of the aecidial connection of this host. Under date of April 8, 1902, he wrote: "I have never found *Puccinia vexans* in the state, although it is reported from Texas; *P. Bartholomaei* I have found, also its aecidial stage, which is *Aecid. Jamesianum* on *Asclepiodora decumbens*. I have never found this milkweed with aecidia on it, that I did not find teleutospores of *P. Bartholomaei* thickly covering the leaves of *Bouteloua curtipendula* around and under the milkweed, and the teleutospores when examined had germinated. Later the young grass in and near the bunches of infected milkweed would first show the rust; and where no teleutospores were found under or near the milkweed no aecidia were seen. This I observed repeatedly in my field work last year."

Mr. Long sent teleutospores on *Atheropogon curtipendulus* Fourn. (*Bouteloua curtipendula* Torr.), which were sown on *Asclepias incarnata* L. on May 2, giving rise to spermogonia May 8, and aecidia May 17. They were later sown with success on the same host (culture dates, May 21, 28, and June 5), and on *Asclepias syriaca* L. (culture dates, May 12, 18, and 26). They were also sown at two different dates on *Apocynum cannabinum*, with no infection.

As the specific name of the aecidium is older than that of the teleutosporic stage, the name of the fungus should become ***Puccinia Jamesiana*** (Pk.), nom. nov.

3. AECIDIUM IMPATIENTIS Schw.—The aecidium on Impatiens, and there appears to be but one, is very common throughout the eastern United States. It often occurs in a locality in the great-

est abundance, frequently affecting the leaves and stems of nearly every plant in a large area where the host may be growing thickly. Such a group of plants has been under observation for a number of seasons. In a space some twenty feet across, protected by a group of willows, many hundreds of *Impatiens aurea* Muhl. have sprung up from seeds each succeeding spring, and when from six inches to a foot high have become remarkably infested with aecidia. A rather large number of grass and sedge rusts occur in the vicinity of this spot, and the teleutospores of these have been sown in succession on *Impatiens*, and invariably with no infection. It was not until well into June of the present year that any clue was obtained. A tuft of *Elymus virginicus* L., growing at the edge of this patch of infested *Impatiens*, was found to possess young sori of some uredo. Searching further, dead leaves of the previous season were obtained bearing inconspicuous sori of what has generally been called *Puccinia rubigo-vera*, the teleutospores of which had already germinated. A collection on the same host was in the laboratory, however, that had been obtained early in the season from a locality some miles distant, which was still in germinating condition. Teleutospores from this were sown on *Impatiens aurea*, June 10, spermogonia following abundantly June 17, and aecidia June 25. Spores from the same collection had been sown previously on *Ambrosia trifida* and *Napaea dioica*, with no infection.

There are other creditable species of *Puccinia* on *Elymus* in the Rocky mountain and Pacific states, but this is the most common species and possibly the only one in the eastern states. It should be called ***Puccinia Impatientis*** (Schw.), nom. nov.

4. PUCCINIA SUBNITENS Diet.—I am indebted to Rev. J. M. Bates, of Callaway, Nebraska, for material to make the cultural study of this species, and for the suggestion which made the study fruitful. He wrote that wherever the grass rust occurred he had observed an aecidium on *Chenopodium leptophyllum* (Moq.) Nutt.

Teleutospores from *Distichlis spicata* (L.) Greene were sown on *Chenopodium album* L. on May 24, and on May 31 spermogonia appeared in the greatest luxuriance, followed by aecidia on June

3. A second sowing was made May 27, with spermogonia June 3, and aecidia June 9, in equal abundance. The crumpling of the leaves by the aecidia, and their bright orange color, made these the most striking cultures of the season. This aecidium is undoubtedly *A. Ellisii* Tr. & Gall., founded on a collection from New Mexico.

5. PUCCINIA AMPHIGENA Diet.—In the year 1883 the type collection for this species was made by the writer at Ravenswood, now a part of Chicago. The same season an aecidium was found on *Smilax herbacea* in the immediate vicinity,¹⁵ which appeared to be *A. Smilacis* Schw. Owing to the limited distribution of these two forms, and their association within a seemingly restricted area, their possible genetic connection was thought worth testing. This opinion was strengthened by the fact that the grass rust has been collected a number of times since by the writer in the same locality, but no other aecidium has been found there at all likely to belong to it.

Teleutospores on *Calamovilfa longifolia* (Hook.) Hack., kindly sent by Rev. J. M. Bates from Callaway, Nebraska, were sown May 13 on both *Smilax herbacea* L. and *S. hispida* Muhl., and on May 20 both showed spermogonia, and May 31 aecidia. A second sowing on May 27 was only partially successful, as the leaves prematurely withered.

6. PUCCINIA SIMILLIMA Arth.—At the time of the publication of this species the writer called attention¹⁶ to its probable connection with an aecidium on *Anemone canadensis*, which occurred in great abundance in the immediate vicinity.

Teleutospores on *Phragmites Phragmites* (L.) Karst. (*P. communis* Trin.), obtained by the writer from the type locality at Spirit Lake, Iowa, were sown on *Anemone canadensis* L., May 1, producing spermogonia May 5, and aecidia May 13. They were also sown, partly at the same time and partly later, on *Anemone cylindrica*, *A. virginiana*, *Pulsatilla hirsutissima*, and *Ranunculus septentrionalis*, all seemingly reasonable hosts, but with no infection. The aecidium has passed for *Aecid. Ranunculacearum*, but whether

¹⁵ See BURRILL, Parasitic Fungi of Illinois 238.

¹⁶ BOT GAZ. 34: 18. 1902.

it is distinct or not from the similar aecidia which have been found on the other hosts mentioned cannot now be stated.

7. *AECIDIUM SOLIDAGINIS* Schw.—Having found *Puccinia teleutospores* on *Carex Jamesii* Schw., they were sown on four species of *Ribes*, with no infection. They were then sown on six species of *Aster*, with no infection. At about the same time, May 9, they were sown on *Solidago canadensis* L., and followed by spermatogonia May 15, and aecidia May 22. On May 24 a sowing was again made on *S. canadensis*, and also on *S. ulmifolia* Muhl., *S. caesia* L., *S. rigida* L., and *S. serotina* Ait., all of which produced spermatogonia in ten to twelve days, but only the last developed aecidia. Part of these trials were repeated, and sowings also made on three additional species of *Solidago*, but without success. These failures appear to have been due chiefly to the feeble condition of the host plants.

A collection of *Puccinia* on *Carex stipata* Muhl., sent by Mr. E. W. D. Holway from Decorah, Iowa, was used for cultures on four species of *Ribes*, and on *Erigeron annuus* and *Onagra biennis*, with no infection. Afterward it was tried, May 27, on *Solidago canadensis*, giving spermatogonia June 2 and aecidia June 9. On the same date it was sown on *S. serotina*, giving spermatogonia June 2 and aecidia June 11.

As the specific name *Solidaginis* is already employed in the genus *Puccinia*, I propose for this species the name of ***Puccinia Caricis-Solidaginis***. A comparison of this species with *P. Caricis-Asteris* and *P. Caricis-Erigerontis* shows many resemblances, and it seems not improbable that the three represent more correctly the biological variations of one species. However, in the many cultures so far made no set of teleutospores has been found that would infect more than one of the three host genera, *Aster*, *Erigeron*, and *Solidago*.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1902. It is divided into the two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A. SPECIES PREVIOUSLY REPORTED.

1. UROMYCES EUPHORBIAE C. & P.—Accidiospores from *Euphorbia humistrata* Engelm, sown on same host. Accidiospores from *E. nutans* Lag. sown on same host. Uredospores from *E. dentata* Michx. sown on same host.

2. UREDO RUBIGO-VERA DC.—Uredospores from *Triticum vulgare* Vill. sown on same host.

3. PUCCINIA PECKII (De T.) Kellerm.—Teleutospores from *Carex trichocarpa* Muhl. and *C. stipata* Muhl. sown on *Onagra biennis* (L.) Scop.

4. PUCCINIA SAMBUCI (Schw.) Arth.—Teleutospores from *Carex trichocarpa* Muhl. and *C. lurida* Wahl. sown on *Sambucus canadensis* L., and accidiospores from *S. canadensis* L. sown on *C. trichocarpa* Muhl.

5. PUCCINIA CARICIS-ASTERIS Arth.—Teleutospores from *Carex foenea* Willd. sown on *Aster paniculatus* Lam.

6. PUCCINIA CARICIS-ERIGERONTIS Arth.—Teleutospores from *Carex festucacea* Willd. sown on *Erigeron annuus* (L.) Pers., *E. philadelphicus* L., and *Leptilon canadense* (L.) Britt.

7. PUCCINIA CARICIS (Schum.) Reb.—Teleutospores from *Carex stricta* Lam. and *C. riparia* Curt. sown on *Urtica gracilis* Ait.

8. PUCCINIA VERBENICOLA (K. & S.) Arth.—Teleutospores from *Sporobolus longifolius* (Torr.) Wood sown on *Verbena stricta* Vent. and *V. urticifolia* L.

9. PUCCINIA WINDSORIAE Schw.—Teleutospores from *Tricuspis seslerioides* (Michx.) Torr. sown on *Ptelea trifoliata* L.

10. PUCCINIA HELIANTHI Schw.—Teleutospores from *Helianthus grosse-serratus* Mart. sown on same host, and on *H. Maximiliani* Schrad.

11. PHRAGMIDIUM SPECIOSUM Fr.—Teleutospores from cultivated rose sown on *Rosa humilis* Marsh.

B. SPECIES REPORTED NOW FOR THE FIRST TIME.

1. UROMYCES ARISTIDAE E. & E.—Teleutospores from *Aristida oligantha* Michx. sown on *Plantago Rugelii* Dec.

2. PUCCINIA JAMESIANA (Pk.) Arth.—Teleutospores from *Athelopogon curtispendus* (Michx.) Fourn. sown on *Asclepias incarnata* L. and *A. syriaca* L.

3. PUCCINIA IMPATIENTIS (Schw.) Arth.—Teleutospores from *Elymus virginicus* L. sown on *Impatiens aurea* Muhl.
4. PUCCINIA SUBNITENS Diet.—Teleutospores from *Distichlis spicata* (L.) Greene sown on *Chenopodium album* L.
5. PUCCINIA AMPHIGENA Diet.—Teleutospores from *Calamovilfa longifolia* (Hook.) Hack. sown on *Smilax herbacea* L. and *S. hispida* Muhl.
6. PUCCINIA SIMILLIMA Arth.—Teleutospores from *Phragmites Phragmites* (L.) Karst. sown on *Anemone canadensis* L.
7. PUCCINIA CARICIS-SOLIDAGINIS Arth.—Teleutospores from *Carex Jamesii* Schw. and *C. stipata* Muhl. sown on *Solidago canadensis* L. and *S. serotina* Ait., and also from the former *Carex* host sown on *S. caesia* L., *S. ulmifolia* Muhl. and *S. rigida* L.

It will not be out of place to emphasize again the desirability of making field observations upon the association of aecidial, uredo, and teleutosporic forms within small areas. There is little chance for progress in establishing the connection of spore-forms through cultural work, except by acting upon the hints derived from field notes. Any acute observer is likely to be able to make one or more important deductions of this kind during a season, which may lead to valuable discoveries upon testing by cultures. If collectors would bear the matter in mind, the perplexing tangle of our knowledge of the heteroecious rusts would soon largely yield to experimental study.

I cannot too heartily express my appreciation of the kindness of Professor W. A. Kellerman, Mr. W. H. Long, Jr., Rev. J. M. Bates, Dr. J. J. Davis, and Mr. E. W. D. Holway, for their assistance with material, and especially with suggestions derived from their field observations. Without such help much of the work recorded in this report could not have been undertaken.

PURDUE UNIVERSITY,
Lafayette, Ind.





4

CULTURES OF UREDINEAE IN 1903.

J. C. ARTHUR.

Reprinted from the *Journal of Mycology*, 10:8-21. Jan., 1903.

CULTURES OF UREDINEAE IN 1903.¹

J. C. ARTHUR.

The present article forms the fourth of a series of reports² by the author upon the cultures of plant rusts. They cover the years from 1899 to the present inclusive. This report is devoted both to autoecious and heteroecious species, among which the grass and sedge rusts have had a prominent place. The number of species studied and the number of cultures made have fallen off somewhat from last year, partly because it was late in the spring before assistance was secured to carry on the work, and partly because a less number of collections of teleutospores and field observations were obtained upon which to base the work. The results however, fully equal in interest and importance those of last year, or possibly exceed them.

The expense of additional assistance in carrying on the work, and to some extent the expense of procuring material, was

¹ Read before the Botanical Society of America, St. Louis, December 30, 1903.

² See Bot. Gaz. 29:268-276; Jour. Mycol. 8:51-56; and Bot. Gaz. 35:10-23.

borne this year in part by the Indiana Experiment Station and in part by a grant from the Botanical Society of America. By this means I was enabled to have the services of Mr. J. Clyde Marquis, an undergraduate student of the university, who made part of the preliminary drop cultures and attended to the microscopical technique, and of Mr. Fred J. Seaver, a graduate of Morningside College, Sioux City, Iowa, and a fellow in botany at the University of Iowa, who made most of the sowings and drop cultures and kept the records. The most active period for this work extends from the middle of April to the middle of June, while a smaller portion of the work extends through the remaining months of the year. The grant from the Botanical Society also permitted systematic field observations at Fair Oaks in the oak barrens of northern Indiana, where many species of rusts abound, for the most part unlike those occurring at Lafayette where the chief field observations heretofore necessarily have been made. These excursions into an unworked locality resulted in the discovery of the *Andropogon-Comandra* combination, the undescribed *Carex-Solidago* combination, and the autoecious character of the wide-spread *Lespedeza* rust, as well as minor items.

During the present season 68 collections of material were employed, and 217 drop cultures were made from them to test the germinating condition of the spores. Out of these 26 collections refused to germinate, and were consequently useless. There were in all 215 sowings of spores made, representing 32 species of rusts, and for this purpose were required 72 species of hosts temporarily grown in pots in the greenhouse. As in previous years success was attained in no case except when definite clues derived from field observations were in hand.

In order to provide ample resources, as far as possible, so that whatever suggestions are obtained even late in the season can be tested without delay, a stock of teleutosporic material is laid in of any species obtainable. In consequence there are always some species on hand in germinating condition with no definite guide for their use. So far as time permits these are sown upon any hosts known to bear aecidia in the region where the rust abounds. The results so far have been confined wholly to the negative information that the aecidia could not be produced on certain hosts. The following is a record of such blind attempts made during 1903. Teleutospores were employed in every case.

1. *UROMYCES ACUMINATUS* Arth. on *Spartina cynosuroides* Willd. from Fair Oaks, Ind., was sown on *Hydrophyllum appendiculatum*, with no infection.

2. *PUCCINIA POLYGONI-AMPHIBII* Pers. on *Polygonum emersum* (Michx.) Britt. from Columbus, Ohio, and Fair Oaks,

Ind., was sown on the same host and on *Cicuta maculata*, with no infection. Last year this rust was sown on two other species of *Polygonum* without infection. Recently the preliminary announcement of rust cultures for the season of 1903 by Dr. W. Tranzschel of St. Petersburg has been published. He states that infection was secured on *Geranium*, showing that the widely distributed *Aecidium sanguinolentum* Lindl., commonly found on *Geranium maculatum* in America, is the alternate form of this rust. My own observations in the field all go to affirm the correctness of this result.

3. PUCCINIA on *Carex Pennsylvanica* Lam. from Red Cloud, Neb., and Fair Oaks, Ind., was sown on *Aster paniculatus*, *A. Drummondii*, *A. prenanthoides*, *Solidago rigida*, *S. canadensis*, *Xanthium Canadense*, *Silphium perfoliatum*, *Ribes Cynosbati*, *R. aureum*, *Geranium maculatum*, *Viola cucullata*, and *Onagra biennis*, with no infection.

4. PUCCINIA on *Carex grvida* Bailey from Red Cloud, Neb., was sown on *Aster Drummondii*, *A. paniculatus*, *Senecio obovatus*, *Boltonia asteroides*, *Silphium perfoliatum*, *Ambrosia trifida*, *Xanthium Canadense*, *Cleome spinosa*, *Sambucus Canadensis*, *Ribes Cynosbati*, *Xanthoxylum Americanum*, and *Onagra biennis*, with no infection.

5. PUCCINIA on *Elymus Canadensis* L. from Red Cloud, Neb., was sown on *Impatiens aurea*, *Symphoricarpos racemosus*, and *Napaea dioica*, with no infection. There are various reasons, of which the above is one, for thinking that the rust on the several species of *Elymus*, occurring east of the Rocky Mts., which has heretofore been referred to one species really belongs to several species.

6. PUCCINIA VEXANS Farl. on *Bouteloua curtipendula* (Michx.) Torr. from Red Cloud, Neb., was sown on *Cleome spinosa*, *Physalis heterophylla*, *Physalodes Physalodes*, *Cassia Chamaecrista*, and *Pentstemon hirsutus*, with no infection.

7. PUCCINIA TOSTA Arth. on *Sporobolus neglectus* Nash from Red Cloud, Neb., was sown on *Oxalis cynosa*, *Ceanothus Americanus*, *Symphoricarpos racemosus*, *Cassia Chamaecrista*, *Callirrhoe involucrata*, *Xanthoxylum Americanum*, *Cleome spinosa*, and *Aster ericoides*, with no infection.

8. PUCCINIA EMACULATA Schw. on *Panicum capillare* L. from Fair Oaks, Ind., was sown on *Aster prenanthoides*, *A. Drummondii*, *Solidago rigida*, *Lactuca Canadensis*, *Eupatorium perfoliatum*, *Xanthium Canadense*, *Ambrosia trifida*, *Apocynum cannabinum*, *Polemonium reptans*, *Ribes Cynosbati*, *Onagra biennis*, *Anemone Pennsylvanica*, and *Geranium maculatum*, with no infection.

Five species of rusts were successfully grown, that had been studied with success before, and reported upon by the writer and in part by other investigators. Mention of them here serves to confirm previous work, and in two cases to give additional knowledge regarding hosts.

1. *PUCCINIA IMPATIENTIS* (Schw.) Arth.—Teleutosporic material of this species on *Elymus Virginicus* was obtained near Lafayette, Ind., and sown, May 13, on *Impatiens aurea*. On May 18, an abundance of spermogonia appeared, and on May 26, an equal abundance of aecidia began to show. This result confirms the work of last year.³ The locality from which the teleutosporic material was obtained for this season's work is several miles from the one yielding material last year.

2. *PUCCINIA AMPHIGENA* Diet.—Teleutosporic material was obtained by the writer on *Calamovilfa longifolia* from the type locality at Chicago, Ill. A sowing was made on a mature leaf of *Smilax hispida*, May 23. Spermogonia appeared sparingly on May 29, but were not followed by aecidia. Another sowing was made on a partly grown leaf of the same host species, May 24, from which a great abundance of spermogonia began to appear on May 28, followed by an equal abundance of aecidia, June 5. Some question has been raised regarding the correctness of last year's work,⁴ as the teleutosporic form is known from regions where it is thought that *Smilax* does not grow, but that the genuine *Puccinia amphigena* has its alternate form on *Smilax* can no longer be doubted.

3. *PUCCINIA ANDROPOGONIS* Schw.—Teleutosporic material on *Andropogon scoparius*, collected at Bloomington in southern Nebraska, was sent to Rev. J. M. Bates. It was sown on *Pentstemon hirsutus*, May 19, giving rise to abundant spermogonia on May 25, followed by aecidia on June 4. Previous cultures have been made by Mr. William Stuart and the writer,⁵ and by Prof. W. A. Kellerman.⁶ There can be no question that this is a wide-spread and common species in North America.

4. *PUCCINIA ALBIPERIDIA* Arth.—Teleutosporic material of this species on *Carex gracillima* was most opportunely sent from Racine, Wis., by Dr. J. J. Davis. Sowing was made April 21, on *Ribes Cynosbati*, from which abundant spermogonia appeared on April 30, followed by great numbers of aecidia on May 11. A sowing made at the same time on *R. floridum* gave no infection. Three days later a sowing made on *R. aureum* seemed to have made a slight growth, which, nevertheless, came to naught. A sowing on *R. Uva-crispa*, a cut branch being placed in a glass of

³ Bot. Gaz. 35:18. 1903.

⁴ Bot. Gaz. 35:20. 1903.

⁵ Bot. Gaz. 29:272. 1900.

⁶ Jour. Mycol. 9:10. 1903.

water in the laboratory in lieu of a potted plant, gave some spermogonia, but the leaf fell from the stem before the time for the appearance of the aecidia. It would have undoubtedly been a successful infection, had the conditions been favorable for maintaining the vigor of the host. This species is based upon cultures made by the writer⁷ in 1901. Its exact standing is yet in some uncertainty, and probably can not be settled until the connection of the very common aecidium, or aecidia if more than one kind, on the several species of *Ribes* is ascertained. Dr. J. J. Davis⁸ has expressed the opinion that the whiteness of the aecidial cups is probably due to the conditions under which they are grown, and that they are normally orange-colored and identical with the common form. But the facts can only be ascertained by cultural studies.

5. PUCCINIA HELIANTHI Schw.—Ample teleutosporic material was available in vigorous germinating condition, collected by Prof. W. A. Kellerman at Sandusky, Ohio, and by the writer at Fair Oaks, Ind. All of it was on *Helianthus mollis*. Sowings began on April 29, and continued at intervals until June 2, twenty cultures being attempted. The sowings on *H. strumosus*, *H. tuberosus*, *H. grosse-serratus*, *H. rigidus*, and *H. Maximiliani* gave no infection. The sowing on *H. tomentosus* gave a slight infection, a few spermogonia appearing but reaching no further development, although the leaves were young and the plants exceptionally vigorous. On *H. mollis* and *H. annuus* an exceedingly strong infection was produced, numberless spermogonia appearing, followed by well developed aecidia in great quantity. The first sowings on *H. mollis* were made May 6, the first spermogonia appearing May 16, and the first aecidia May 22 and 23. A second sowing was made May 29, giving spermogonia June 7, and aecidia June 16. The sowing on *H. annuus* was made June 2, showing spermogonia June 8, and aecidia June 17.

Cultures of the Helianthus-rust were made during the previous year's work,⁹ employing spores from *H. grosse-serratus*, which were found to grow upon the same host and the similar *H. Maximiliani*, but not upon *H. strumosus*. Judging from the work of the two years, it appears possible to divide the Helianthus-rust into at least three series, for which the forms on *H. mollis*, *H. strumosus* and *H. grosse-serratus* may be taken as representatives respectively. Dr. E. Jacky¹⁰ of Switzerland has made cultures, and has come to the conclusion that there are two species of Helianthus-rust, for which the names *P. Helianthi* Schw. and *P. helianthorum* Schw. are to be used. It seems to

⁷ Jour. Mycol. 8:53. 1902.

⁸ Trans. Wis. Acad. Sci. 14:88. 1903.

⁹ Bot. Gaz. 35:17. 1903.

¹⁰ Centr. f. Bakt. 9^e:841. 1902.

me that the data are yet too meager to make it worth while to undertake to decide upon the nomenclature of the forms or species, which ever they may be called.

In addition to the foregoing results seven species of rusts were grown, establishing aecidial and teleutosporic connections, not heretofore recorded. The species are partly autoecious and partly heteroecious rusts.

I. MELAMPSORA MEDUSAE Thüm.—Teleutosporic material on *Populus deltoides* Marsh. was obtained in the vicinity of Lafayette, Ind., and although of inferior quality, for the poplar rust was not abundant in this region last year, it was sown on *Larix decidua* Mill. (*L. Europaea* DC.) April 28. After a rather long interval of 16 days I was surprised and gratified to observe the beginning of spermogonia (May 14) in good quantity; and five days later (May 19), the aecidia appeared, and proved to be a caeoma-form. A sowing on this host was tried last year¹¹ without infection, which is, however, easily accounted for by the fact that the host plants employed in 1902 were very feeble. For the supply of *Larix*, used this year I am indebted to the generosity of R. Douglas' Sons, proprietors of the Waukegan Nurseries at Waukegan, Ill. They sent without remuneration 25 very thrifty young larch, suitable for 6-inch pots, which made vigorous growth when brought into the greenhouse.

This species is the American representative of the European *M. populina* Lév., both species having their aecidia on *Larix*. That the American form is specifically distinct from the European was pointed out by Klebahn¹² in 1899, the differences being especially marked in the form, size and markings of the uredospores, and in the apical thickening of the teleutospores. The American form may be characterized as follows:

MELAMPSORA MEDUSAE Thuem.

O. Spermogonia epiphyllous, numerous scattered, inconspicuous, pale yellow, papilliform by vertical sections shown to be columnar or hemispherical, raised above the surface, 40-55 μ , in diameter.

I. Aecidia hypophyllous, numerous, scattered, small, less than .5 mm. in diameter, pale yellow; peridium absent; aecidiospores catenulate, globoid, 20 μ in diameter; wall colorless, nearly 3 μ thick, finely verrucose.

II. Uredospores amphigenous, or sometimes only hypophyllous, roundish, small, less than .5 mm. in diameter, early naked, somewhat pulverulent, orange yellow; uredospores oval, or obovate-oblong, 15-18 by 22-30 μ usually flattened on opposite sides; wall colorless, 2.5-3 μ , thick, or up to 10 μ on the flattened sides, sparsely and evenly echinulate with fine papillae, except on the flattened sides which are smooth; paraphyses

¹¹ Bot. Gaz. 35:11. 1903.

¹² Ztschr. f. Pfl.-Kr. 9:144. 1899.

usually numerous, peripheral, capitate, smooth, 40-50 μ long, head 14-20 μ broad.

III. Teleutosori amphigenous, or sometimes only hypophyllous, small, irregularly roundish and scattered, or somewhat coalescing, subepidermal, at first light reddish brown, becoming deep chocolate-brown; teleutospores prismatic, 12-14 by 30-44 μ , wall smooth, cinnamon-brown, uniformly thin, not thickened at apex.

Spermogonia and aecidia on *Larix*, but not yet collected. Uredo and teleutospores on *Populus deltoides* Marsh. (*P. Medusae* Benth., *P. Canadensis* Moench., *P. monilifera* Ait., *P. angulata* Ait.), *P. grandidentata* Michx., *P. tremuloides* Michx., *P. balsamifera* L., *P. angustifolia* Jas., and *P. trichocarpa* Torr. & Gr. Common throughout the United States and Canada.

2. *UROMYCES PHASEOLI* (Pers.) Wint.—This is a very common rust on various species of *Phaseolus*, *Strophostyles* and *Vigna*. Nevertheless its aecidial form is rarely seen, and it has been suggested that the American form might be heteroecious. Material for the cultures was collected near Lafayette, on *Strophostyles helvola* (L.) Britt. (*Phaseolus diversifolius* Pers.). It was sown, May 1, on *Euphorbia commutata* Engelm., with no infection. On May 15, a sowing was made on *Strophostyles helvola*, which gave abundant spermogonia on May 26, and well developed aecidia began to appear on June 4. Five subsequent sowings were made, but owing to difficulty in keeping the host-plants in flourishing condition only two of these gave positive results, and even these were less abundant than in the first trial. The autoecious character of the American form, however, is well demonstrated. It should be said that the somewhat common aecidium on *Apios* and *Amphicarpa* holds a doubtful relation to the bean rust, and is better considered distinct until positive relationship is established.

3. *UROMYCES LESPEDEZAE-PROCUMBENTIS* (Schw.) Curt. — This is a wide spread, and often abundant rust, occurring on various species of *Lespedeza*. No aecidium has ever been found clearly associated with it. The small and inconspicuous *Aecidium leucospermum* B. & C., rarely collected, has been suggested as a possible alternate form, but not very confidently.

Excellent teleutosporic material was obtained by the writer at Fair Oaks, Ind., in March, on the upright stems of *Lespedeza capitata* Michx. It was not until late in May that a host-plant was well established in the greenhouse. A sowing of spores was made on May 28, the host being *L. capitata*. Infection resulted, but the development was slow, clearly due to inferior growth conditions. On June 14 the first spermogonia protruded, soon becoming exceedingly numerous, and on June 18, the minute, colorless aecidia began to appear in great numbers. The typical form of *Aecidium leucospermum* was the result.

4. *PUCCINIA CAULICOLA* Tr. & Gall.—Fine teleutosporic material of this species on the stems of *Salvia lanceolata* Willd. was

sent to me in March by Mr. Elam Bartholomew, from Rockport, Kans. Seeds of the host were also sent, from which young plants were grown for culture work. A sowing was made on April 27; on May 11, the spermogonia began to appear, and on May 18, the aecidia. One later sowing was also successful, but the host plants did not flourish, and the results were meager. The demonstration, however, proved ample to establish the autoecious character of the species.

The aecidium of this species is so rarely seen as to give rise to the conjecture that the species might not possess an aecidium. The species is usually listed under *Puccinia nigrescens* Pk. This specific name, however, belongs to the somewhat similar European species, as pointed out by Bubák, who unnecessarily bestowed the new name *P. Salviae-lanceolatae* upon the American form. The rust occurs commonly upon the leaves, but is so much more conspicuous upon the stems, especially after the leaves have partly or wholly fallen, that most collections show the cauliculous form only.

5. *UROMYCES* on *Carex*.—A species of *Uromyces* on *Carex* was found at Fair Oaks, Ind., on March 22 in very great abundance, and in fine viable condition. The *Carex* grew in an open sandy woodland, but in a depression of the surface where water sometimes gathered during heavy rains. It grew in tufts over a half acre of ground, and belonged to two species, *C. lanuginosa* Michx., easily told from the abundance of last year's fruiting culms still present, and *C. varia* Muhl., which showed not a trace of last year's culms, and was determined from the fruiting of a plant transferred to the greenhouse, and verified by a subsequent visit to the locality on May 3. On this latter visit a careful search for aecidia was made in the vicinity of the rusted *Carex*, but a few young leaves of a *Solidago* with spermogonia were the only result. These were growing with leaves intermixed and well surrounded by the rusted *Carex*. This was a very doubtful clue, as the common *Solidago* aecidium is known to belong to a *Puccinia*, yet experience has taught that the most improbable clues are not to be despised when the evidence is direct. Before finding this clue, sowings of the rust on *Carex varia* had been made on *Viola cucullaria*, *Isopyrum biternatum*, *Trillium recurvatum*, *Ribes cynosbati* and *R. aureum* with no infection. After the clue was obtained it was sown on five species of *Aster* with no infection, and on five species of *Solidago* with abundant infection. The following is the record of the latter. Sown May 6 on *S. Canadensis* L., showing abundant spermogonia on May 14, and aecidia on May 22. A sowing May 26 on *S. serotina* Ait. gave first spermogonia June 5, and aecidia June 16, the results being especially good. An equally successful culture was made on each of the two hosts at subsequent dates. Positive but less flourishing cultures were made on *S. flexicaulis*

L. and *S. caesia* L., clearly in accordance with the vigor of the host plants, while a sowing on *S. rigida* L. wholly failed, the host showing a weak growth.

The above sowings were all made from material on *Carex varia*. The collection on *C. lanuginosa*, taken at the same time and place, appearing in every way to be the same species, and to be in equally viable condition, was sown under equally favorable circumstances on *Silphium perfoliatum*, *Ribes cynosbati*, five species of *Aster*, and on *Solidago rigida*, *S. serotina* and repeatedly on *S. Canadensis*, all with no infection.

Whether the failure to infect the *Solidago* was due to some undetected oversight in manipulation, or is an indication of specific or racial difference in the rust, is a matter for which the facts do not warrant an opinion.

It is not easy to determine if this rust has been previously described and named or not. Upon morphological grounds it is clearly distinct from *Uromyces caricina* E. & E. and *U. minutus* Diet., but it may be the same as *U. perigynius* Halst. It also agrees well with collections from Wisconsin¹³ on *Carex gracillima* Schw., from Decorah, Iowa,¹⁴ on *C. pubescens* Muhl., and from Greencastle, Ind.,¹⁵ on what was taken to be *C. pubescens*, but which a re-examination shows to be almost certainly *C. virescens* Muhl. If the rust on *C. varia* and *C. lanuginosa* had shown the same cultural behavior, I would have been inclined to unite these several collections under one name. But realizing the need of advancing cautiously among a group of species where only the first step has been taken, it seems wiser to give a separate name to the form about which we have definite knowledge, and leave the others to be dealt with later. The rust on *C. varia* with its alternate form is therefore, characterized under a new name, as follows:

UROMYCES SOLIDAGINI-CARICIS nom. nov.

O. Spermogonia epiphyllous, in small groups on yellow spots, punctiform, honey yellow, subepidermal, in vertical section shown to be globose, about 115 μ in diameter; isticlar filaments free, 60 μ long.

I. Aecidia hypophyllous, in groups, often circinating, peridia pale, low cylindrical, margin revolute, lacerate; aecidiospores globoid, or slightly elongated, 13-16 by 14-18 μ ; wall colorless, thin, 1 μ or sometimes a little more, minutely rugose.

II. Uredosori not seen; uredospores among the teleutospores oval or obovate, about 16 by 23 μ ; wall thin, echinulate.

III. Teleutospori hypophyllous, round, oblong or sometimes elongated, pulvinate, early naked, firm, chestnut-brown; teleutospores obovate, 15-18 by 23-28 μ , rounded or obtuse above, narrowed below; wall smooth, thin, 1.5-2 μ , apex greatly thickened, 6-10 μ ; pedicel slender, tinted, as long as the spore, or longer.

¹³ Trans. Wis. Acad. Sci. 9:180. 1892. Same 14:90. 1903.

¹⁴ Bot. Gaz. 16:226. 1891.

¹⁵ Same, 1. c.

Jan. 1904]

Cultures of Uredineae in 1903.

39
33
17

The collection on *Carex varia* Muhl., made at Fair Oaks, Ind., March 22, 1903, is taken as the type, together with the result of the culture on *Solidago Canadensis* L. obtained by a sowing made June 3, and matured July 1, 1903, at which date it was placed in the herbarium. I would tentatively refer here the collections referred to above on *C. gracillima*, *C. pubescens*, *C. virescens* (?) and *C. lanuginosa*, leaving their exact status to be determined later.

The aecidium of this species does not appear to differ in any marked manner from that of *Puccinia Caricis-Solidaginis* Arth., although, perhaps, the spores are a trifle smaller. I have not, however, had opportunity of collecting it in the field, as the heavy spring rains flooded the type locality and prevented all subsequent development of the rust, so that in subsequent visits at different times during the season the most diligent search failed to reveal any trace of it on either *Solidago* or *Carex*.

6. *AECIDIUM PUSTULATUM* Curt.—In early April, 1902, an observation was made at Spirit Lake, Iowa, that proved very puzzling for a time. On an open prairie, that had been burned over during the late fall, a small area showed *Comandra pallida* A. DC. with aecidia, and in contact with it *Andropogon scoparius* Michx. bearing uredo, of the characteristic thin-walled sort known to belong to the species with aecidium on *Pentstemon*. It was easy to find teleutospores on the grass leaves pressed into hollows, thus protected from the passing fire, and only in part germinated. These were collected and sown on *Pentstemon hirsutus* with no infection. A sowing was not made on *Comandra*, as no suitable growing plants were available. A similar observation was made again this year at Fair Oaks, Ind., and once more under circumstances that seemed to permit of no other inference but that the *Comandra* and *Andropogon* rusts were connected, highly improbable as it seemed. This time plants of *Comandra umbellata* (L.) Nutt. were secured. A sowing of teleutospores from *Andropogon furcatus* Muhl. was made on May 5, and spermogonia began to appear on May 16, but the host plant withered before time for aecidia to appear. A similar sowing was made on a more vigorous host, May 25, spermogonia appearing in great abundance May 30, and aecidia June 9. Another sowing of teleutospores from *A. scoparius* obtained in the same locality at Fair Oaks, was made on *Comandra umbellata* June 1, the first spermogonia appearing June 9, and aecidia June 19. Sowings of both sets of teleutospores were made twice on *Pentstemon hirsutus*, under the most favorable circumstances, with no infection. The conclusion is beyond all question, that a common rust on species of *Andropogon*, not readily distinguishable from *Puccinia Andropogonis* Schw., has its aecidia on *Comandra*, being identical with *Ae. pustulatum* Curt.

A rather careful study of the newly detected species appears to show that it is to be distinguished from *P. Andropogonis* Schw. by the very dissimilar aecidium, and by the pores of the uredospores, which number 5 to 8 and are distributed without order, while in *P. Andropogonis* they usually number 3, and are approximately equatorial. The name for the species should be *PUCCINIA PUSTULATA* (Curt.) nom. nov.

7. *AECIDIUM RANUNCULI* Schw. An exceedingly fortunate observation was made in May, within a few miles of Lafayette, Ind. On a somewhat shaded hillside, an area not exceeding ten feet long by three feet wide, attracted attention by the yellowness of the new vegetation. Looking closer, it was found that the growing mass was made up almost wholly of *Ranunculus abortivus* L. thickly covered with the *Aecidium Ranunculi* Schw., and an equal quantity of *Eatonia Pennsylvanica* (DC.) A. Gray, intermixed, not yet in flower, but every leaf covered with a light yellow uredo. No other rusts occurred for some distance around, and even none on the same hosts elsewhere in the locality.

Healthy plants of *Eatonia Pennsylvanica* were obtained from another locality, transferred to the greenhouse, and spores of *Aecidium Ranunculi* sown on the youngest leaves, May 13. From this sowing uredospores appeared on May 21, and characteristic teleutospores began to show June 3. Although the trial with teleutospores could not be made, yet the demonstration of the genetic relation of the two forms seems beyond question. A confirmatory observation upon the intimate association of the two forms in the field has been reported to me by Mr. E. W. D. Holway, from Decorah, Iowa.

This is one of the numerous grass rusts passing under the name of *Puccinia rubigo-vera*. It can not be called *P. Ranunculi*, as that name is preoccupied, and therefore, I propose the name

PUCCINIA EATONIAE nom. nov. (*Aecidium Ranunculi* Schw.)

O. *Spermogonia* hypophyllous, thickly scattered over large areas, preceding or among the aecidia, punctiform, honey-yellow, inconspicuous, subepidermal.

I. *Aecidia* hypophyllous, evenly scattered over large areas; peridia broad and short, recurved, finely lacerate; aecidiospores subglobose or elliptical, 15-22 by 18-25 μ ; wall colorless, medium thick, 1.5-2 μ , minutely verrucose; mycelium perennial in the host.

II. *Uredosori* chiefly epiphyllous, on yellow spots, small, oblong, pale yellow, ruptured epidermis noticeable; uredospores obovate-globose, 15-18 by 20-23 μ ; wall thin when mature, about 1 μ , pale yellow, finely and evenly echinulate, pores 6-8, scattered.

III. *Teleutosori* chiefly hypophyllous and caulicolous, small, oblong to linear, covered by the epidermis; teleutospores oblong-clavate to linear-cuneate, 12-16 by 35-45 μ , truncate or rounded above, narrowed below, slightly or not constricted at the septum; wall smooth, light brown, thin, 1-1.5 μ , apex a little darker and thicker, 3-4 μ ; pedicel very short, colored; paraphyses none, or few.

8. *AECIDIUM HYDNOIDEUM* B. & C.—Coming upon some bushes of *Dirca palustris* L., the middle of June, that were conspicuous with great numbers of yellow aecidial spots, search was made for grass and sedge rusts in the vicinity. At one side, by a small ravine, was found a most luxurient growth of uredo upon *Bromus ciliatus* L., with last year's teleutospores on the dead radical leaves. The most distant bush of rusted *Dirca* was not over a hundred feet away.

As soon as suitable potted plants of *Bromus ciliatus* could be established in the greenhouse, aecidiospores from the *Dirca* were sown. The first sowing came to naught, as the host plant failed to grow well. A sowing on June 25 gave uredospores in abundance on July 4. Teleutospores were first observed on August 10, although they probably appeared somewhat earlier.

The success of this trial removes another rust from that limbo of grass forms passing under the name of *Puccinia rubigovera*. We may characterize the species as follows, under the name

PUCCINIA HYDNOIDEA (B. & C.) nom. nov. (*Aecidium hydnoideum* B. & C.)

O. *Spermogonia* amphigenous in small groups on large yellow spots, inconspicuous, punctiform.

I. *Aecidia* hypophyllous, usually circinating about the spermogonia; peridia short, cylindrical, pale, margin slightly recurved, finely erose or torn; aecidiospores globose or oblong-globose, 11-15 by 14-19 μ ; wall yellowish, thin, 1 μ , minutely and inconspicuously verrucose.

II. *Uredosori* chiefly epiphyllous, oblong, early naked, pulverulent, fuscous; uredospores globose or obovate-globose, 18-21 by 20-28 μ ; wall brownish, thin, 1 μ , abundantly echinulate, pores 4 or more, scattered.

III. *Teleutosori* chiefly hypophyllous and caulicolous, small and numerous, oblong, covered by the epidermis; teleutospores linear-oblong, 13-18 by 30-50 μ , truncate or oblique above, obtuse or slightly narrowed below, not constricted at the septum; wall smooth, light brown, thin, 1-1.5 μ , thickened at apex, 4-7 μ ; pedicel very short, colored; paraphyses none, or few.

This species, undoubtedly, does not embrace all the American rusts on *Bromus*. It is, doubtless, the common form east of the Rocky Mts. Probably the multicellular form, found in Wisconsin and Minnesota, *Puccinia tomipara* Trel., is distinct, although it has not yet been shown that such irregular multiplication of cells in the teleutospore is a permanent character.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1903. It is divided into the two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A. Species previously reported.

1. *Puccinia Impatientis* (Schw.) Arth. — Teleutospores from *Elymus Virginicus* L. sown on *Impatiens aurea* Muhl.
2. *Puccinia amphigena* Diet. — Teleutospores from *Calamovilfa longifolia* (Hook.) Hack. sown on *Smilax hispida* Muhl.
3. *Puccinia Andropogonis* Schw. — Teleutospores from *Andropogon scoparius* Michx. sown on *Pentstemon hirsutus* (L.) Willd.
4. *Puccinia albiperidia* Arth. — Teleutospores from *Carex gracillima* Schw. sown on *Ribes Cynosbati* L. and *R. Uva-crispi* L. (*R. Grossularia* L.)
5. *Puccinia Helianthi* Schw. — Teleutospores from *Helianthus mollis* Lam. sown on *H. mollis* Lam. and *H. annuus* L.

B. Species reported now for the first time.

1. *Melampsora Medusae* Thuem. — Teleutospores from *Populus deltoides* Marsh. sown on *Larix decidua* Mill.
2. *Uromyces Phaseoli* (Pers.) Wint. — Teleutospores from *Strophostyles helvola* (L.) Britt. sown on same host.
3. *Uromyces Lespedezae-procumbentis* (Schw.) Curt. — Teleutospores from *Lespedeza capitata* Michx. sown on same host.
4. *Puccinia caulicola* Tr. & Gall. — Teleutospores from *Salvia lanceolata* Willd. sown on the same host.*
5. *Uromyces Solidagini-Caricis* Arth. — Teleutospores from *Carex varia* Muhl. sown on *Solidago Canadensis* L., *S. serotina* Ait., *S. flexicaulis* L. and *S. caesia* L.
6. *Puccinia pustulata* (Curt.) Arth. — Teleutospores from *Andropogon furcatus* Muhl. and *A. scoparius* Michx. sown on *Comandra umbellata* (L.) Nutt.
7. *Puccinia Eatoniae* Arth. — Aecidiospores from *Ranunculus abortivus* L. sown on *Eatonia Pennsylvanica* (DC.) A. Gray.
8. *Puccinia hydnoidea* (B. & C.) Arth. — Aecidiospores from *Dirca palustris* L. sown on *Bromus ciliatus* L.

Judging from the few instances that have come to my notice, the interest and importance of making observations upon proximity of aecidial and teleutosporic forms are not yet fully appreciated by American collectors of *Uredineae*. This is the most valuable method by which a reasonable conjecture can be made regarding the alternate connection of any one of the many scores of isolated aecidial forms, most of which are probably heteroeci-

* Successful cultures reported by Kellerman, Jour. Mycol. 9:27, Dec. 1903.

ous. Cultural work without such conjectures based on field observations are largely a waste of time, rarely leading to any positive information. The time to make observations is early spring, when the rusts first begin to show, mostly in April and May. Simple record of proximity is not especially important. The observations must show that the inference is well established, that the new growth of spores has come from germinating spores of another sort found near by. The ability to work out such an inference marks the logical and acute observer.

I desire to thank Messrs. Kellerman, Bates, Davis and Bartholomew for providing teleutosporic material, and also Mr. Holway for numerous favors. I have already mentioned the kindness of Messrs. R. Douglas' Sons in providing host plants; strong plants of *Callirrhoe involucrata* were sent by Mr. Bartholomew. My particular thanks, moreover, are due to the Botanical Society of America for providing funds by which the work could be prosecuted, not only in the laboratory but in the field. The observations at Fair Oaks, Ind., by far the most important of those made in a single locality, were rendered possible by the society's generosity.

Purdue University, Lafayette, Ind.



No. 5

43

CULTURES OF UREDINEAE IN 1904.

J. C. ARTHUR.

(Reprinted from the *Journal of Mycology*, 11: 50-67, March 1905)

CULTURES OF UREDINEAE IN 1904.¹

J. C. ARTHUR.

The present article forms the fifth of a series of reports² by the author upon the cultures of plant rusts. They cover the years from 1899 to the present year inclusive. In these studies the grass and sedge rusts hold a prominent place, but some other heteroecious and a few autoecious rusts have been included.

During the period when the cultures are in progress, the constant attention of one person is required to assort the material which is in germinating condition from that not yet ready to germinate, to sow the spores, to maintain a careful watch for the first appearance of the spermogonia and aecidia, and to keep the records with unimpeachable accuracy. At the beginning of the present season the Indiana Experiment Station established a cooperative agreement with the Bureau of Plant Industry of the U. S. Department of Agriculture to mutually assist in carrying on the annual culture work. Through the government assistance Mr. F. D. Kern, a senior student from the University of Iowa, recommended by Professor T. H. MacBride, was secured to take charge of the cultures. Mr. Kern proved an exceptionally able man for the position, having unusually keen and accurate powers of observation, a retentive memory, and scholarly enthusiasm. Mr. Kern's work extended through May, and a part of April and June.

¹ Read before the Botanical Society of America, Philadelphia, December 30, 1904.

² See Bot. Gaz. 29:268-276; Jour. Mycol. 8:51-56; Bot. Gaz. 35:10-23, and Jour. Mycol. 10:8-21.

I am under many obligations to a number of botanists, who have most kindly sent me teleutosporic material, and in some cases particular host plants on which sowings could be made. My especial thanks are extended to those who have made field observations, and provided me with clues to solve the relationship of isolated forms, the information received from Rev. J. M. Bates, and Mr. E. W. D. Holway, being particularly helpful. Further acknowledgments are made under the several species. I should further mention the kindness of Messrs. R. Douglas' Sons, of Waukegan, Ill., who sent twenty-five thrifty young larch without asking payment, as they did a year ago.

During the present season 90 collections of material were employed, and 261 drop cultures and 10 Petri dish cultures were made from them to test the germinating condition of the spores. Out of these 38 collections refused to germinate, and were consequently useless. There were in all 264 sowings of spores made, representing 40 species of rust, and for this purpose were required 119 species of hosts temporarily grown in pots in the greenhouse.

A few cultures were made with material for which no clues were obtainable to indicate the possible relationship, and in every case with negative results. The record is given here, as in previous years, to serve for future reference.

1. PUCCINIA on the leaves of *Elymus Canadensis* L., sent by Rev. Bates from Red Cloud, Neb., was sown on *Baptisia tinctoria*, *Polygala Senega*, *Uvularia perfoliata*, *Mimulus ringens*, *Symphoricarpos pauciflorus*, and *S. racemosus*, with no infection. Two other hosts were tried in 1903, with equally negative results.³

2. PUCCINIA on *Muhlenbergia Mexicana*, sent by Mr. E. Bartholomew from Stockton, Kans., was sown on *Hibiscus militaris*, with no infection. Similar material sent by Rev. J. M. Bates from Red Cloud, Neb., on *M. racemosa*, was sown on *Asclepias incarnata*, and twice on *Hibiscus militaris*, with no infection. What is probably the same fungus on the latter host coming from Callaway, Neb., was sown in 1902 on ten other species of hosts with equally negative results.⁴ It is evident that while some of the rust found upon *Muhlenbergia* undoubtedly is associated with the acidium on *Hibiscus*, as Professor Kellerman clearly proved last year,⁵ there are other forms having entirely different acidia, not yet ascertained.

3. PUCCINIA on *Carex Pennsylvanica*, sent by Rev. Bates from Red Cloud, Neb., was sown on *Ambrosia trifida*, *Polemonium reptans*, *Erigeron annuus*, *Lepidium apetalum*, and *Solidago*

³ Jour. Mycol. 10:10. 1904.

⁴ Bot. Gaz. 35:11. 1903.

⁵ Jour. Mycol. 9:109, 232. 1903.

Canadensis, with no infection. Similar material on the same species of host, gathered at Lafayette, Ind., was sown on *Oxalis violacea*, *Actaea alba*, *Macrocalyx Nyctelea*, *Apios Apios*, and *Solidago ulmifolia*, with no infection. What is probably the same species of rust, on the same host, was sown in 1903 on eleven other species of hosts with negative results.⁶

4. PUCCINIA on *Carex graxida*, sent by Rev. Bates from Red Cloud, Neb., was sown on *Steironema ciliatum*, with no infection. Similar material from the same source was sown in 1903 on twelve other species of hosts with negative results.⁷

5. PUCCINIA LUDIBUNDA E. & E., sent by Mr. E. Bartholomew from Stockton, Kans., was sown upon *Steironema ciliatum*, *Macrocalyx Nyctelea*, and *Xanthium Canadense*, with no infection.

6. PERIDERMIIUM on *Pinus rigida* was sent by Professor W. A. Kellerman from Sugar Grove, Ohio, in fine quantity, with the suggestion that it would probably grow upon *Campanula*. It was sown June 1st on what were supposed to be four plants of *C. Americana*, but which proved to be *Lobelia syphilitica*, when the plants came into bloom. The plants were unusually thrifty, and conditions for success were good, but there was no infection. Part of the same collection of spores grew on *C. Americana*, when sown by Prof. Kellerman,⁸ showing that they belonged to *Coleosporium Campanulae* (Pers.) Lev.

Sixteen species of rusts were successfully grown, that had been studied with success before, and reported upon by the writer and in part by other investigators. Mention of them here serves to confirm previous work, and to give some additional knowledge regarding hosts.

I. MELAMPSORA MEDUSAE Thuem.—Teleutosporic material of this species on *Populus deltoides* was obtained near Lafayette, Ind., and sown May 10 on *Larix decidua* and *Euonymus obovatus*. The latter gave no result, but the former showed spermogonia on May 25, yet owing to weakness of the hosts no aecidia formed. The same collection was used to sow on *Larix laricina* (Du R.) Koch (*L. Americana* Michx.) May 23, which showed spermogonia June 4, but the host was too weak to permit aecidia to form.

Teleutosporic material on *P. deltoides* at Spirit Lake, Iowa, by the writer was sown May 10, on *Larix decidua* and *L. laricina*, with only feeble results on the former owing to the weakness of the hosts. Another sowing was made May 23 on *L. decidua*, which gave abundance of spermogonia on May 30, and an equal abundance of aecidia on June 4.

⁶ Jour. Mycol. 10:10. 1904.

⁷ Jour. Mycol. 10:10. 1904.

⁸ Jour. Mycol. 11:32. 1905.

Teleutosporic material on *Populus tremuloides* Michx. was sent from Racine, Wis., by Dr. J. J. Davis, and was sown on *Larix decidua*, May 25. Abundance of well developed spermogonia appeared on June 5, followed by strongly developed aecidia on June 10. This culture is specially significant in showing that the poplar rust of North America is probably all of one species, as assumed in last year's report of cultures.⁹

2. PHRAGMIDIUM SPECIOSUM Fr. has twice before been the subject of cultures, being grown in 1899¹⁰ on a tea rose from the garden, and in 1902¹¹ on *Rosa humilis*. The teleutosporic material used this season was obtained by the writer at Spirit Lake, Iowa, on *Rosa Arkansana*. It was sown on *R. Arkansana* Port., *R. Carolina* L., *R. humilis* Marsh., and *R. nitida* Willd., with abundant success in each case. It was sown twice on *R. lucida* Ehrh. without success, although the host was in fine growing condition. The dates were as follows:

May 7, Teleutospores sown on *R. Arkansana*; May 14, spermogonia; May 20, aecidia.

May 7, Teleutospores sown on *R. Carolina*; May 14, spermogonia; May 18, aecidia.

May 17, Teleutospores sown on *R. humilis*; May 23, spermogonia; May 30, aecidia.

May 17, Teleutospores sown on *R. lucida*; no infection.

June 1, Teleutospores sown on *R. lucida*; no infection.

June 1, Teleutospores sown on *R. nitida*; June 8, spermogonia; June 15, aecidia.

Whether the failure to infect *R. lucida* was due to the greater mechanical resistance of the firm leaves, or to a physiological difference in the host can not be stated, but I am inclined to favor the former explanation.

3. PUCCINIA HELIANTHI Schw.—Three collections of sunflower-rust were used for cultures this season. A collection was obtained from Spirit Lake, Iowa, on *Helianthus laetiflorus*, one from Fair Oaks, in northern Indiana, on *H. mollis*, and one from Lafayette, Ind., on *H. grosse-serratus*, all by the writer. Another collection was used, but the host could not be determined with certainty, and the results are discarded. Three collections seemed to be in perfect condition, but could not be made to germinate. Forty sowings were made from the three collections used, and as a large space would be required to report the full data, the results will be given in tabular form. In this table decided and complete results are shown by an exclamation point, infection which was meager, grew slowly and gave no aecidia or very few, is shown by a semi-colon, a sowing which gave no infection is indicated by a single period, and where no sowings were made a dash is used. Fifteen

⁹ Jour. Mycol. 10:13. 1904.

¹⁰ Bot. Gaz. 29:271. 1900.

¹¹ Bot. Gaz. 35:17. 1903.

species of *Helianthus* were employed, on which to sow the teleutospores.

CULTURES OF HELIANTHUS RUST.

Hosts for cultures	Source of teleutosporic material		
	<i>H. mollis</i>	<i>H. grosse-serratus</i>	<i>H. laetiflorus</i>
1. <i>H. annuus</i>	!	!	!
2. <i>H. decapetalus</i>	—	.	—
3. <i>H. divaricatus</i>	—	—	;
4. <i>H. grosse-serratus</i>	!	.
5. <i>H. hirsutus</i>	;	.	.
6. <i>H. Kellermani</i>	—	;
7. <i>H. laetiflorus</i>	!
8. <i>H. Maximiliani</i>	—
9. <i>H. mollis</i>	!	.	;
10. <i>H. occidentalis</i>	;	.	;
11. <i>H. orgyalis</i>	;
12. <i>H. scaberrimus</i>	!
13. <i>H. strumosus</i>	;	.	.
14. <i>H. tomentosus</i>	;	.	.
15. <i>H. tuberosus</i>

! Abundant infection.

; Infection, but slow growth and few or no aecidia formed.

. No infection.

— Not sown.

The results of this year accord closely with those of 1902 and 1903. In 1902 some success was attained in sowing spores from *H. grosse-serratus* on *H. Maximiliani*, but no success this year. In 1903 sowing spores from *H. mollis* on *H. strumosus* gave no infection, this year a few spermatogonia were formed, but no further development took place. In all other respects the work of the three years is in perfect accord. Altogether sixty-four sowings have been made.

Looking over the accompanying table it will be seen that each set of spores grew upon the species of host from which derived, but not upon the other two species, except that spores from *H. laetiflorus* sown on *H. mollis* gave a tardy showing of spermatogonia, without further development. Also each set of spores grew luxuriantly upon *H. annuus*, and each made a feeble growth upon *H. tomentosus*, but on all other species they either failed to infect or made a feeble growth, with the single exception that spores from *H. laetiflorus* grew well on *H. scaberrimus*.

From all results so far available, it seems that the following conclusion may safely be drawn. *Puccinia Helianthi* Schw. is a single species, having many races, for which *H. annuus* acts as a bridging host.

4. PUCCINIA SUBNITENS Diet.—Teleutosporic material of this species on *Distichlis spicata* (L.) Greene were sent from Nebraska by Rev. J. M. Bates, to whom I am also indebted for suggestions which led to one of the most interesting series of cultures yet made. In a communication dated April 30, 1904,

Rev. Bates says: "Last spring I found *Aecidium* on *Cleome serrulata* in two nearby localities, and on *Chenopodium album*, closely associated with the rust on *Distichlis spicata*, and no other. Now I have it again under same conditions. I wrote Mr. Holway about it and shocked him; he does not think it possible. But I am well convinced that it is the same as on *Chenopodium*" [proved by cultures in 1902 from *Distichlis*-rust sent by Rev. Bates]. Further reasons were given for believing that the *Cleome* and *Chenopodium* aecidia came from teleutospores on *Distichlis*, among them being that "last year I watched for the uredo from it on the *Distichlis*, and got it May 21, after collecting the first *Cleome* aecidia May 5." All these observations seemed very convincing, yet the deductions seemed very improbable. He followed up the statements by sending seedling plants of *Cleome serrulata* and *Chenopodium album* on which the large, brilliant orange-colored aecidia occurred in remarkable profusion, and so much alike that in appearance and structure they had to be pronounced identical. As the season progressed Rev. Bates also sent freshly collected specimens of aecidia on *Roripa sinuata* (Nutt.) Hitch., *Sophia incisa* (Engelm.) Greene, and *Salsola Tragus* L., which he considered belonged to the same inclusive species. The results of my cultures confirm the above clever observations, and add still other hosts for the aecidium. The data are as follows:

May 17, Sown on *Chenopodium album*; May 25, spermogonia; June 5, aecidia.

May 17, Sown on *Cleome spinosa*; May 25, spermogonia; May 30, aecidia.

May 17, Sown on *Lepidium apetalum*; May 25, spermogonia; June 7, aecidia.

May 30, Sown on *Lepidium Virginicum*; June 7, spermogonia; June 16, aecidia.

May 30, Sown on *Sophia incisa*; June 7, spermogonia; plant injured.

May 30, Sown on *Erysimum asperum*; June 5, spermogonia; June 14, aecidia.

May 30, Sown on *Cleome spinosa*; June 5, spermogonia; June 14, aecidia.

We have here a demonstration of the remarkable fact, not known for any other species of rust so far as I recall, that *Puccinia subnitens* with teleutospores on *Distichlis spicata* has aecidia growing with equal vigor upon species belonging to three families of plants. The teleutospores for the above sowings were all taken from the same collection, and from only a few leaves of the grass, which precludes the possibility of a differentiation in the teleutoform, or any division into races. The aecidium is unusually well marked. Going over my herbarium and taking out the forms which are identical with this species, beyond a doubt, and adding to those already mentioned, we have the following hosts and distribution for the aecidium of this species.

Puccinia subnitens Diet.

On Chenopodiaceae:

Chenopodium album L. Montana, New Mexico, Nebraska.*Chenopodium leptophyllum* (Moq.) Nutt. Nebraska.*Chenopodium glaucum* L. Montana.*Salsola Tragus* L. Nebraska.

On Capparidaceae:

Cleome serrulata Pursh. Nebraska, Montana.*Cleomella parviflora* A. Gr. Nevada.

On Cruciferae:

Lepidium apetalum Willd. Nebraska, Montana.*Roripa sinuata* (Nutt.) Hitch. Nebraska.*Sophia incisa* (Engelm.) Greene. Nebraska.*Stanleya pinnata* (Pursh.) Britt. Colorado.

5. *PUCCINIA PANICI* Diet.—The connection of this rust with *Æcidium Pammelii* Trel. on *Euphorbia corollata* L. was reported by William Stuart¹² based on somewhat meager but seemingly convincing cultures made in 1901. Teleutosporic material for the present trial was obtained at Fair Oaks, Ind., on *Panicum virgatum*. It was sown on *Euphorbia corollata* May 16, and again May 24, and both sowings showed the most abundant results, giving the first spermatogonia respectively on May 24 and June 1, and aecidia May 30 and June 9. There can be no doubt that these two forms are members of one species. While at Lafayette the rust is very rare, at Fair Oaks it is exceedingly abundant one on both the *Panicum* and the *Euphorbia*. It is one of the few glumaceous rusts observed by the writer, having so nearly an equal display of both the aecidial and teleutosporic forms. The aecidial form having first been published, requires the name to be written *PUCCINIA PAMMELII* (Trel.) nom. nov.

6. *PUCCINIA VERBENICOLA* (E. & K.) Arth.—Previous cultures¹³ with this species were verified by sowing teleutospores, from *Sporobolus longifolius* sent by Rev. J. M. Bates from Red Cloud, Neb., on *Verbena urticaefolia*, May 16, resulting in spermatogonia May 23 and aecidia May 30. Also another successful culture was made with similar material sent by Mr. E. Bartholomew from Stockton, Kans., sown on *V. urticaefolia* June 3, showing spermatogonia June 11, and aecidia June 18.

7. *PUCCINIA WINDSORIAE* Schw.—Teleutospores from *Tricuspis seslerioides* Torr., Lafayette, Ind., were sown May 19, on *Ptelea trifoliata* and *Xanthoxylum Americanum*, both members of the family *Rutaceae*, and both known to be hosts to an aecidium. Although the conditions were exceptionally favorable, no infection resulted on *Xanthoxylum*, while *Ptelea*

¹² Proc. Ind. Acad. Sci. for 1901:284. 1902.¹³ Bot. Gaz. 29:274. 1900, and 35:16. 1903.

gave spermogonia May 25, and aecidia May 31, in accordance with results heretofore obtained.¹⁴

8. PUCCINIA FRAXINATA (Schw.) Arth.—Cultures of this species were successfully carried out in 1899,¹⁵ showing that the aecidium occurs upon *Fraxinus*. As similar aecidia have been collected upon *Ligustrum vulgare* L., in New York, and *Adelia segregata* (Jacq.) Small (*Forestiera porulosa* Poir.) in Florida,¹⁶ members of the family Oleaceae, to which *Fraxinus* belongs, a number of trials were made to see if the number of hosts could be extended. Teleutosporic material was obtained at Spirit Lake, Iowa, on *Spartina cynosuroides*. Sowings were made on *Ligustrum vulgare* (2), *Ligustrum ovalifolium* (2), *Syringa vulgaris* (2), *Chionanthus Virginica* (2), *Adelia acuminata*, *Adelia ligustrina*, and *Fraxinus lanceolata*, all members of the family Oleaceae, yet no infection took place except on the last host. Although the conditions for success were seemingly excellent, still I am not fully convinced that some of these failures were not due to accident. I am under obligation to Dr. George V. Nash, of the N. Y. Bot. Garden, for a plant of *Adelia acuminata*, sent from the Garden for this culture work.

9. PUCCINIA IMPATIENTIS (Schw.) Arth.—Teleutosporic material on *Elymus Virginicus* was sent from Racine, Wis., by Dr. J. J. Davis, and sown May 7, on *Clematis Virginiana* and *Impatiens aurea*. The first gave no infection, the second showed spermogonia May 14, and aecidia May 23.¹⁷

10. PUCCINIA POCULIFORMIS (Jacq.) Wettst.—Teleutosporic material was found at Spirit Lake, Iowa, on *Elymus Canadensis* L., and without a careful examination was sown on *Clematis Virginiana* (2), *C. Scottii*, *Cimicifuga Americana*, *C. racemosa*, *Actaea alba*, and *Impatiens aurea*, with no infection. A microscopic study revealed the nature of the rust, and it was sown upon *Berberis vulgaris* May 18, with abundant infection, spermogonia appearing May 25, and aecidia duly following, but not recorded until June 9. Teleutosporic material was also found at Spirit Lake, Iowa, on *Agropyron tenerum*, and was sown on *Berberis vulgaris* May 10, giving an abundant infection, first showing spermogonia May 17, followed in due time by aecidia. Teleutosporic material on *Agropyron repens* was sent from Burlington, Vt., by Mr. William Stuart, and sown on *Berberis vulgaris* May 11. Spermogonia appeared May 18, but the leaves were injured before aecidia developed.

¹⁴ Bot. Gaz. 29:273. 1900, and 35:16. 1903.

¹⁵ Bot. Gaz. 29:275. 1900.

¹⁶ Specimen in herbarium of N. Y. Bot. Garden, and cited by Sydow, Monog. Ured. 1:808, under the erroneous name *F. "paludosa"*.

¹⁷ For previous cultures see Bot. Gaz. 35:18. 1903, and Jour. Mycol. 10:11. 1904.

11. PUCCINIA RHAMNI (Pers.) Wettst. — A number of bushes grow in the garden near the laboratory of *Rhamnus lanceolata*, *R. Caroliniana*, and *R. Cathartica*, on which aecidia appeared this season, not very plentifully, but in about equal abundance. Seedlings of *Avena sativa* were infected from all three sources. Aecidiospores were sown from *R. lanceolata* May 15, from *R. Caroliniana* May 19, and from *R. Cathartica* May 20. In each case uredospores appeared in abundance in about a week, the exact date not being recorded.

12. PUCCINIA ANGUSTATA Peck. — Teleutospores gathered on *Scirpus atrovirens*, Lafayette, Ind., were sown May 12, on *Lycopus Americanus*, giving spermogonia May 20, and aecidia May 27, further confirming previous cultures.¹⁸

13. PUCCINIA PECKII (DeT.) Kellerm. — Successful sowings¹⁹ of teleutospores from undetermined species of *Carex* were made on *Onagra biennis*, from material sent by Rev. J. M. Bates of Red Cloud, Neb., and by Dr. J. J. Davis of Racine, Wis. A sowing was also made, May 20, on *O. biennis*, from material on *C. lanuginosa* sent by Rev. Bates from Red Cloud, Neb., which gave spermogonia May 29, and aecidia June 5. The same material was sown on *Urtica gracilis* twice without success. This gives a new host for the fungus.

Teleutosporic material on *Carex trichocarpa* from the type locality of *Puccinia Bolleyana*, was sown May 6, on *Onagra biennis* and *Sambucus Canadensis*, producing infection on both hosts, and thus repeating the experience of 1902.²⁰ The *Carex* bore teleutospores of both *P. Peckii* and *P. Sambuci* (Schw.) Arth. intermixed, as was easily verified by microscopic examination.

14. PUCCINIA CARICIS-ERIGERONTIS Arth. — Teleutospores gathered at Lafayette, Ind., on *Carex festucacea* were sown on *Erigeron annuus*, May 12, giving heavy infection of spermogonia May 20, and of aecidia May 27. Similar material on the same host, sent by Rev. Bates from Red Cloud, Neb., was sown May 25, on *E. annuus*, and gave spermogonia June 2, and aecidia June 9. These results confirm previous work.²¹

15. PUCCINIA ALBIPERIDIA Arth. While the conviction is gaining ground that the aecidium of this species is the common aecidium on gooseberries, yet the excellent results of this year do not give any particular support to the view. All the aecidia grown in cultures were small and pale, and apparently

¹⁸ Bot. Gaz. 29:273. 1900, and Jour. Mycol. 8:53. 1902.

¹⁹ For previous cultures see Jour. Mycol. 8:55. 1902, and Bot. Gaz. 35:13. 1903.

²⁰ Bot. Gaz. 35:14. 1903.

²¹ Jour. Mycol. 8:53. 1902, and Bot. Gaz. 35:15. 1903.

dissimilar to the bright orange-yellow aecidia on *Ribes* in the fields.

Teleutosporic material was sent by Dr. J. J. Davis from Racine, Wis., on *Carex gracillima*, which was sown on *Ribes floridum* (3), *R. rubrum*, and *R. aureum* (2), with no infection, except that in one case a few spermogonia appeared on *R. aureum* after eleven days, but reached no further development. It was also sown with abundant success on *R. Uva-crispa* (2), *R. Cynosbati* and *R. rotundifolium* (2), thus confirming previous work.²²

Excellent teleutosporic material was found on *Carex crinita* Lam., Lafayette, Ind., and sown May 7, on *Ribes rubrum*, with no infection, on *R. Uva-crispa*, with weak infection, the plant being in poor condition, and on *R. rotundifolium* with strong infection, showing spermogonia May 17, and aecidia May 25. Another equally strong infection was secured with a sowing on the last host June 3. This culture adds another teleutosporic host.

16. PUCCINIA POLYGONI-AMPHIBII Pers. In previous years²³ this rust was sown upon three species of *Polygonum* and *Cicuta maculata* with no infection. After learning of Dr. Tranzschel's successful cultures on two European species of wild geranium²⁴ considerable effort was made to secure teleutosporic material with which to repeat the work. No rust could be found about Lafayette where it usually occurred. At Spirit Lake, Iowa, a diligent search where it had previously been common, only gave a few slightly rusted leaves. No better success was met with at Fair Oaks, Ind. An appeal to my excellent coadjutors, Prof. W. A. Kellerman, Columbus, Ohio, Rev. J. M. Bates, Red Cloud, Neb., and Dr. J. J. Davis, Racine, Wis., brought out the same experience, and only added a few slightly rusted leaves from Wisconsin. The three meager collections were, however, useless, as none of the teleutospores would germinate. I then waited for aecidia to appear on geranium and found them as rare as the teleutospores had been. Finally I obtained a few belated aecidia on *Geranium maculatum* L. (*AE. sanguinolentum* Lindl.) and sowed them on *Polygonum emersum* (Michx.) Britt., June 11, and on June 19, uredospores appeared, and eventually on Aug. 17, teleutospores began to form, the plants being kept in the greenhouse during the culture. The American and European forms are therefore identical.

²² Jour. Mycol. 8:53. 1902, and 10:11. 1904.

²³ Bot. Gaz. 35:12. 1903, and Jour. Mycol. 10:9. 1904.

²⁴ Centr. f. Bakt. 11²:106. 1903.

In addition to the foregoing results five species of rusts were grown, establishing aecidial and teleutosporic connections, not heretofore recorded. The species are heteroecious with one exception.

I. MELAMPSORA BIGELOWII Thüm. — Three collections of teleutospores on *Salix* were secured, but only one, which was obtained at Racine, Wis., on *Salix amygdaloides* Anders., and forwarded by Dr. J. J. Davis, could be made to germinate. This was sown, May 10, on *Larix decidua* Mill., and twenty days later both spermogonia and aecidia were observed in abundance, although they had probably first made their appearance some days earlier. On the same date it was sown on *Euonymus obovatus* without result. A further sowing on *Larix decidua* was made on May 25, and on June 4 spermogonia began to appear in great abundance, followed on June 10 by an equal abundance of aecidia. The aecidia are of the typical caeoma-form, and are very similar to those of *Melampsora Medusae*, the chief difference being in the spores, which are somewhat more distinctly and coarsely verrucose than in the poplar form.

The only American collections of aecidia on *Larix*, that have come to my attention, were made by E. W. D. Holway at Mt. Temple, Aug. 22, 1902, and Laggan, Aug. 23, 1902, both places in Alberta, Canada, and both collections on *Larix Lyallii* Parl. These collections agree perfectly with the aecidia raised in cultures. A comparison of the numerous collections of willow rust in my own herbarium, numbering 80 packets, and representing all sections of the United States and Canada from the Atlantic to the Pacific, shows that both the uredosporic and teleutosporic stages agree closely with one another, and with those on the material used in the culture.

A comparison with European collections shows the American form to be very different from any European species. The nearest approach to the American form is *Melampsora Larici-epitca* Kleb., the most common willow rust of Europe. The two differ, however, in a very marked way. The American form has all three sorts of spores considerably larger, the spores of the aecidia and uredo have walls twice as thick, the pores are far more evident, and the papillae on the surface are much closer together.

The name which I have adopted for this common willow rust was given by Baron von Thuemen to a collection made in California on *Salix Bigelowii*, which he stated had been received from the herbarium of Dr. W. G. Farlow. Von Thuemen's herbarium was burned some years ago, and the type is consequently destroyed. In reply to an inquiry regarding the matter, Dr. Farlow states that he does not recall sending such a specimen to von Thuemen, and is unable to find a correspond-

ing specimen in his herbarium, unless one from Santa Cruz, Calif., collected by Dr. C. L. Anderson, November, 1875, could be the one intended. This specimen, however, is said to be upon *Salix brachystachys*.

Although the type collection can not be accurately identified or duplicated, there seems to be no reason to question the reference of the fungus described to the common willow rust growing throughout California and the other parts of North America. Dr. Farlow kindly sent me a part of his specimen on *S. brachystachys*, and also a specimen on *S. Bigelowii*, collected in Washington by C. V. Piper in 1899, and they agree in all essential particulars with the eastern collections on willow.

I have also had the privilege, through the kindness of Mr. Chas. H. Peck, of examining the type specimen of *Lecythea macrosora* Pk. (Bot. Gaz. 5:35. 1880), collected in Colorado by Brandegee, and thought to be on *Epilobium*, and find that it is the uredostage of this same species of willow rust. An examination of type material of *Melampsora paradoxa* D. & H. shows no important deviation from the common form. The peculiar free teleutospores figured by Dr. Dietel (Hedw. Beibl. 40:33. 1901) appear to be occasional reversional forms, due to disturbed nutrition or some such cause. Similar isolated teleutospores have been described by Klebahn in European material (Ztschr. f. Pf.-Kr. 9:98). The name, *Melampsora maculosa* D. & H., is *nomen nudum*. It was applied to forms showing especially bright yellow discoloration of the leaf about the uredosori, but without other marked characters, as examination of type material shows.

The species may be characterized as follows:

MELAMPSORA BIGELOWII Thuem.

0. Spermogonia amphigenous, scattered, or somewhat gregarious, minute, punctiform, pale yellow, inconspicuous, subcuticular, conical, 60-80 μ in diameter, 40-45 μ high.

I. Aecidia chiefly hypophyllous, scattered or somewhat gregarious, small, .1-.2 mm. across, oblong, pale yellow fading to white, inconspicuous, formed between the epidermis and mesophyll, soon naked, pulverulent; aecidiospores globose, 15-22 by 18-27 μ ; wall colorless, 2-3 μ thick, finely and evenly verrucose, with distinct papillae, pores scattered, noticeable.

On *Larix Lyallii* Parl., Alberta, Can., and probably on other species of *Larix* in various parts of the United States and Canada. Cultivated on *L. decidua* Mill. and *L. laricina* (DuRoi.) Koch.

II. Uredosori chiefly hypophyllous, usually on conspicuous yellow spots, scattered or gregarious, round, .3-.5 mm. across, orange-yellow fading to pale yellow, soon naked, somewhat pulverulent; uredospores globose, 15-19 by 17-24 μ , wall colorless, 2.5-3.5 μ thick, sparsely and evenly verrucose, pores scattered, noticeable; paraphyses intermixed with the spores, capitate, smooth, 50-70 μ long, heads 22-25 μ broad, wall 3-5 μ thick, peripheral paraphyses thinner walled and more clavate.

III. Teleutospores amphigenous, or sometimes partly or wholly epiphyllous or hypophyllous, scattered, roundish or irregular, about .5 mm. across, often confluent, orange-yellow becoming yellowish or purplish

brown, subepidermal; teleutospores prismatic or oblong, 11-14 by 29-42 μ , rounded at both ends; wall cinnamon-brown, smooth, uniformly 1 μ thick.

On *Salix amygdaloides* Anders., and many other species of *Salix*, throughout the United States and Canada.

Beside this common willow rust, another is known to occur on *Salix herbacea* L. in Greenland and on Mt. Washington, N. H., *Melampsora artica* Rostr. One other, *Melampsora repentis* Plowr., on *Salix repens* has been reported from North America, but has not been seen by the writer.

2. PUCCINIA TOMIPARA Trel.—I am indebted to Mr. E. W. D. Holway for the suggestion, which led to the certain demonstration of the aecidial connection for this species. Mr. Holway's observations were made in the field, and showed such close association of the recently germinated teleutospores on over-wintered leaves of *Bromus ciliatus* and the appearing aecidia on *Clematis Virginiana*, that the conclusion seemed foregone. His direct observations extended over two seasons. Teleutosporic material gathered by Mr. Holway at Decorah, Iowa, was sown on *Impatiens aurea*, *Dirca palustris*, *Clematis Virginiana*, *C. Fremontii*, *C. Scottii*, *C. Viorna*, and with no infection except on *Clematis Virginiana*. Teleutosporic material of *Bromus ciliatus* was kindly sent by Dr. J. J. Davis from Kenosha Co., Wis., and sown on *Clematis Virginiana* with most abundant infection. Material was also used, obtained near Lafayette, Ind., on *Bromus ciliatus*, and sown on *Dirca palustris* and *Clematis Virginiana* with no infection of the former and the most plentiful infection of the latter. The record of dates is as follows:

May 12, Teleutospores (Iowa) sown on *Impatiens aurea*; no infection.
 May 12, Teleutospores (Iowa) sown on *Dirca palustris*; no infection.
 May 12, Teleutospores (Iowa) sown on *Clematis Scottii*; no infection.
 May 12, Teleutospores (Iowa) sown on *Clematis Fremontii*; no infection.
 May 12, Teleutospores (Iowa) sown on *Clematis Virginiana*; May 19, spermogonia; May 28, aecidia.
 May 18, Teleutospores (Ind.) sown on *Dirca palustris*; no infection.
 May 25, Teleutospores (Iowa) sown on *Clematis Scottii*; no infection.
 May 25, Teleutospores (Iowa) sown on *Clematis Fremontii*; no infection.
 May 25, Teleutospores (Iowa) sown on *Clematis Viorna*; no infection.
 May 25, Teleutospores (Iowa) sown on *Clematis Virginiana*; May 31, spermogonia; June 9, aecidia.
 May 30, Teleutospores (Ind.) sown on *Dirca palustris*; no infection.
 May 30, Teleutospores (Ind.) sown on *Clematis Virginiana*; June 7, spermogonia; June 15, aecidia.
 June 3, Teleutospores (Wis.) sown on *Clematis Virginiana*; June 9, spermogonia; June 16, aecidia.

This record shows that the report made last year, connecting the teleutosporic stage on *Bromus ciliatus* with the aecidium on *Dirca palustris*²⁵ was a mistake. The teleutosporic material from Lafayette, which grew so abundantly on *Clematis Virginiana* this year, came from the same plants that

²⁵ Jour. Mycol. 10:19. 1904.

were mentioned as bearing teleutospores a year ago, and standing near aecidium-laden bushes of *Dirca palustris*. Last year's supposed results, which were based on a single sowing of aecidiospores, can be explained by supposing that the *Bromus* plants were already infected when brought into the laboratory. The above plentiful data show no escape from the conclusion that the common *Bromus* rust belongs to the aecidium on *Clematis Virginiana*, and not to the aecidium on *Dirca palustris*. The name *Puccinia hydnoidea* (B. & C.) Arth., therefore, does not belong to the *Bromus* rust, but to some teleutosporic form not yet identified. The descriptions of uredospores and teleutospores given at the place cited belong to *Puccinia tomipara* Trel.

There are at least three species of aecidia found upon *Clematis* in the United States. *Aecidium occidentale* Arth. occurs on *C. Douglasii* in the northwestern region; its teleutosporic connection is not known. *Aecidium Clematidis* DC., found on *C. ligusticifolia*, *C. Scottii*, *C. Fremontii*, *C. Drummondii*, *C. lasiantha* and *C. Viorna*, ranging from Iowa to Montana and southwestward to the Pacific coast, is the first stage of *Puccinia Agropyri* E. & E. The third species is *Aecidium Clematidis* Schw., the one under consideration, found on *C. Virginiana*, ranging throughout the United States and Canada east of the Rocky mountains, and belongs to *Puccinia tomipara* Trel. It has larger spermogonia, and somewhat smaller aecidia and aecidiospores than that of *P. Agropyri*. It may be characterized as follows:

AECIDIUM CLEMATIDIS Schw.

0. Spermogonia epiphyllous, in small groups, honey-yellow, punctiform, subepidermal, globose, 90–140 μ in diameter; ostiolar filaments 40–60 μ long.

1. Aecidia hypophyllous, in orbicular groups, crowded; peridia low, margin somewhat revolute, erose; aecidiospores globose, 16–22 by 18–26 μ , wall rather thin, 2 μ , colorless, minutely verrucose.

The teleutospores used in the cultures were all of the normal two-celled form. The original collection on which the name was based does not appear to differ in any appreciable way from the usual two-celled form except in the many-celled teleutospores, which appear to be variations not uncommon in many grass species. The hosts of all three collections used in the cultures were of the form often made a distinct species under the name *Bromus purgans* L., which differs but slightly, chiefly in pubescence, from the typical *B. ciliatus*.

3. PUCCINIA STIPAE Arth. — On May 9, 1903, I found at Spirit Lake, Iowa, spermogonia and young aecidia on leaves near the ground of *Aster multiflorus*, with germinated teleutospores on old leaves of *Stipa spartea* within a few feet, and no other grass or sedge rust noticeable for a considerable distance

about. I was unable to secure material to carry forward this suggestive observation until the season following. Teleutospore material was obtained at Spirit Lake, Iowa, and on May 9, 1904, was sown on *Aster ericoides*, which gave very abundant spermogonia on May 18, and strong aecidia on May 27. A second sowing was made on May 13 and another on May 21, which gave marked results with *Aster multiflorus* and *A. Novae-Angliae*, but no infection with *A. cordifolius*, *A. Drummondii*, *A. paniculatus* and *A. sericeus*, although the host plants were in vigorous growing condition. The data for these sowings are as follows:

- May 9, Teleutospores sown on *Aster ericoides*; May 18, spermogonia; May 27, aecidia.
May 13, Teleutospores sown on *Aster multiflorus*; May 23, spermogonia; May 28, aecidia.
May 13, Teleutospores sown on *Aster cordifolius*; no infection.
May 21, Teleutospores sown on *Aster multiflorus*; May 29, spermogonia; June 4, aecidia.
May 21, Teleutospores sown on *Aster Novae-Angliae*; May 27, spermogonia; June 3, aecidia.
May 21, Teleutospores sown on *Aster Drummondii*; no infection.
May 21, Teleutospores sown on *Aster paniculatus*; no infection.
May 21, Teleutospores sown on *Aster sericeus*; no infection.

The spermogonia and aecidia of this species are wholly unlike those of the common *Carex* rust, both in general appearance and microscopic characters. The leaves of the host are thickened and more or less distorted by the fungus, and the aecidia have the pustular appearance of *AE. recedens* on *Solidago*, *AE. hemisphericum* on *Lactuca*, and other Composite-species having very delicate peridia, or none. The spores instead of being a bright orange-yellow, as in most aecidia, are decidedly brown. It is a very distinctive form, and yet I have been unable to learn of but one collection having been made, beside my own. It was found on *Aster multiflorus*, Bourbon Co., Kans., May 29, 1902, by A. O. Garrett, who kindly sent me a specimen.

Finding the aecidium of *Puccinia Stipae* shows that the American species is wholly distinct from the European species on *Stipa*, which Bubak has proven by cultures belongs to an aecidium on the Labiate-genus *Thymus*. The aecidium does not attack all species of *Aster* alike, but judging from present cultural results, can be expected on the suffrutescent forms having coarse narrow leaves of firm texture. Such species may represent a natural group within the genus, but if so the taxonomists have not defined it. It is somewhat more probable that they represent an ecological group adapted to a dry atmosphere. The aecidium has not been characterized, and therefore a description is appended.

PUCCINIA STIPAE Arth.

0. *Spermogonia* amphigenous, irregularly grouped, punctiform, brownish orange, subepidermal, globose, 95–110 μ in diameter; ostiolar filaments free, 35–50 μ long.

I. *Aecidia* amphigenous, in irregular groups, on hypertrophied spots, brownish orange, small; peridia low, fragile and evanescent, cells abutted or slightly imbricated, smooth outside, tuberculate inside, thin walled; aecidiospores globose, 18–25 μ in diameter, wall medium thick, 1–2 μ , brownish yellow, closely and finely verrucose, pores many, scattered, often conspicuous.

On *Aster multiflorus* Ait., Iowa and Kansas, and also cultivated on *A. ericoides* L., and *A. Novae-Angliae* L.

4. PUCCINIA SORGI Schw.—Through a fortunate observation in the field, June 2, 1904, upon finding aecidia on *Oxalis cymosa* Small, the attempt was made to grow the aecidiospores on young corn plants, which resulted in complete success. On June 2, aecidia-bearing leaves were suspended over potted corn plants, under a large bell jar. On June 10 uredosori broke through the epidermis, and on July 10 teleutosori began to appear. This is taken as demonstrating the genetic connection of *Aecidium Oxalidis* Thuem. and *Puccinia Sorghi* Schw.

A detailed account of this culture, with citation of all collections of the aecidium on various species of *Oxalis*, known to the writer, has already been published in the Botanical Gazette (38:64–67. 1904).

5. PUCCINIA PODOPHYLLI SCHW.—This autoecious species of rust is very common in the vicinity of Lafayette, Ind. Leaves bearing recently opened aecidia were placed above the leaves of two potted plants on May 7, and both kept under bell-jars for three days. On May 23, one plant began to show teleutospores, and, on May 20, the other plant exhibited many whitish spots which began to burst open and display teleutospores on May 24. Both plants proved to be heavily infected over large areas of the leaves.

The principal interest in this culture comes from the fact that the sowing of aecidiospores did not give rise to secondary aecidia, but exclusively to the characteristic teleutospores. Sydow in his Monog. Uredinearum (1:526) states that this species has primary and secondary aecidia, the former being more common and forming extended groups, the latter coming later with the teleutospores and are sparsely distributed with few together in small groups. As many similar species of rusts have repeating aecidia, it would be natural to suppose that in this case the secondary generation arose from the aecidiospores of the first generation. The culture was made from a luxuriant development of the primary form; and from the fact that no secondary aecidia appeared, I think it can be safely assumed, that the so-called secondary generation arises, generally at least, from teleutospores, and its sparse distribution is due to the smaller number of sporidia which strike the leaf, or to

the inhibition of maturer tissues in the leaf. So far as this culture can be taken as evidence, it shows that a true secondary generation of the aecidium probably does not occur in *P. Podophylli*.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1904. It is divided into the two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A. Species previously reported.

1. MELAMPSORA MEDUSAE Thuem.—Teleutospores from *Populus deltoides* Marsh. and *P. tremuloides* Michx. sown on *Larix decidua* Mill., and from *P. deltoides* Marsh. sown on *L. laricina* (Du R.) Koch.

2. PHRAGMIDIUM SPECIOSUM Fr.—Teleutospores from *Rosa Arkansana* Port. sown on *R. Arkansana* Port., *R. humilis* Marsh., *R. Carolina* L., and *R. nitida* Willd.

3. PUCCINIA HELIANTHI Schw.—Teleutospores from *Helianthus mollis* Lam. sown on *H. annuus* L. and *H. mollis* Lam. with abundant infection, and on *H. hirsutus* Raf., *H. occidentalis* Ridd., *H. strumosus* L., and *H. tomentosus* Michx. with slight infection; from *H. grosse-serratus* Mart. sown on *H. annuus* L., and *H. grosse-serratus* Mart. with abundant infection, and on *H. tomentosus* Michx. with slight infection; and from *H. laetiflorus* Pers. sown on *H. annuus* L., *H. laetiflorus* Pers., and *H. scaberrimus* Ell. with abundant infection, and on *H. divaricatus* L., *H. Kellermani* Britton, *H. mollis* Lam., *H. occidentalis* Ridd., and *H. tomentosus* Michx. with slight infection.

4. PUCCINIA SUBNITENS Diet.—Teleutospores from *Distichlis spicata* (L.) Greene were sown on *Chenopodium album* L., *Cleome spinosa* L., *Lepidium apetalum* Willd., *L. Virginicum* L., *Sophia incisa* (Engelm.) Greene, and *Erysimum asperum* DC.

5. PUCCINIA PAMMELII (Trel.) Arth.—Teleutospores from *Panicum virgatum* L., sown on *Euphorbia corollata* L.

6. PUCCINIA VERBENICOLA (E. & K.) Arth.—Teleutospores from *Sporobolus longifolius* (Torr.) Wood sown on *Verbena urticaefolia* L.

7. PUCCINIA WINDSORIAE Schw.—Teleutospores on *Tricuspis seslerioides* Torr. sown on *Ptelea trifoliata* L.

8. PUCCINIA FRAXINATA (Schw.) Arth.—Teleutospores on *Spartina cynosuroides* Willd. sown on *Fraxinus lanceolata* Borck.

9. PUCCINIA IMPATIENTIS (Schw.) Arth.—Teleutospores on *Elymus Virginicus* L. sown on *Impatiens aurea* Muhl.

10. PUCCINIA POCULIFORMIS (Jacq.) Wettst.—Teleutospores on *Elymus Canadensis* L., *Agropyron tenerum* Vasey and *A. repens* (L.) Beauv. sown on *Berberis vulgaris* L.

11. PUCCINIA RHAMNI (Pers.) Wettst.—Æcidiospores on *Rhamnus lanceolata* Pursh. *R. Caroliniana* Walt., and *R. Cathartica* L., sown on *Avena sativa* L.

12. PUCCINIA ANGUSTATA Peck.—Teleutospores on *Scirpus atrovirens* Muhl. sown on *Lycopus Americanus* Muhl.

13. PUCCINIA PECKII (DeT.) Kellerm.—Teleutospores on *Carex lanuginosa* Michx., and *C. trichocarpa* Muhl. sown on *Onagra biennis* (L.) Scop.

14. PUCCINIA CARICIS-ERIGERONTIS Arth.—Teleutospores on *Carex festucacea* Willd. sown on *Erigeron annuus* (L.) Pers.

15. PUCCINIA ALBIPERIDIA Arth.—Teleutospores on *Carex gracillima* Schw. sown on *Ribes Uva-crispa* L., *R. Cynosbati* L., and *R. rotundifolium* Michx., with a slight infection on *R. aureum* Pursh; and on *C. crinita* Lam. sown on *R. Uva-crispa* L. and *R. rotundifolium* Michx.

16. PUCCINIA POLYGONI-AMPHIBII Pers.—Æcidiospores on *Geranium maculatum* L. sown on *Polygonum emersum* (Michx.) Britt.

B. Species reported now for the first time.

1. MELAMPSORA BIGELOWII Thüm.—Teleutospores on *Salix amygdaloides* Anders. sown on *Larix decidua* Mill.


2. PUCCINIA TOMIPARA Trel.—Teleutospores on *Bromus ciliatus* L. sown on *Clematis Virginiana* L.

3. PUCCINIA STIPAE Arth.—Teleutospores on *Stipa spartea* Trin. sown on *Aster multiflorus* Ait., *A. cricoides* L., and *A. Novae-Angliae* L.

4. PUCCINIA SORGHII Schw.—Æcidiospores on *Oxalis cymosa* Small sown on *Zea Mays* L.

5. PUCCINIA PODOPHYLLI Schw.—Æcidiospores on *Podophyllum peltatum* L. sown on same host.

Purdue University, Lafayette, Ind.



(6)

No. (6)

60

CULTURES OF UREDINEAE IN 1905

By J. C. ARTHUR.



Reprinted from the *Journal of Mycology*, 1:11-27 January 1906

CULTURES OF UREDINEAE IN 1905.¹

BY J. C. ARTHUR.

The present article forms the sixth of a series of reports² by the author upon the culture of plant rusts. They cover the years from 1899 to the present year, inclusive. In these studies the grass and sedge rusts hold a prominent place, but other heteroecious and autoecious species have been included, and during the present season the work has been extended to the so-called *opis*, *micro* and *lepto* forms, and also to species with amphispores.

The coöperative agreement between the Bureau of Plant Industry of the U. S. Department of Agriculture and the Indiana Experiment Station, which existed for carrying on the culture work in the spring of 1904, was again established, extending from July, 1904, to April 30, 1905, making it possible to have an assistant during this period, who devoted nearly his whole time to the study of the rusts. The position was first held by Mr. J. C. Marquis, who was succeeded on October 1, 1905, by Mr. Frank D. Kern, and after the expiration of the coöperative agreement Mr. Kern was retained by the Experiment Station to continue the work. After May 10 all the work fell upon Mr. Kern until September, covering the most important part of the culture period, the author being absent in Europe. It could not, however, have been entrusted to better hands, as the fine ability displayed in the work during the previous season, coupled with considerable experience already acquired, enabled him to meet the new conditions as they arose, and the judgment and caution indispensable in securing authoritative results.

Much of the completeness of the work is due to the kindly assistance of correspondents, who have sent teleutosporic material, and especially to Messrs. E. Bethel, Denver, Colo.; J. M. Bates, Red Cloud, Neb.; A. O. Garrett, Salt Lake City, Utah;

¹ Read before the Botanical Society of America at the New Orleans meeting, January 1, 1906.

² See *Bot. Gaz.* 29:268-276; *Jour. Mycol.* 8:51-56; *Bot. Gaz.* 35:10-23; *Jour. Mycol.* 10:8-21 and 11:50-67.

J. J. Davis, Racine, Wis.; E. Bartholomew, Rockport, Kansas; H. H. Whetzel and H. S. Jackson, Ithaca, N. Y.; C. L. Shear and P. L. Ricker, Washington, D. C.; Wm. J. Horne, Santiago de las Vegas, Cuba; Jos. J. Wolfe, Durham, N. C.; Lewis Kaufman, Morrison, Iowa; R. D. Echlin, Washington, Iowa; R. E. Buchanan, Ames, Iowa; H. L. Bolley, Fargo, N. D.; and H. L. Shantz, Lincoln, Neb.; to whom my warmest thanks are extended. I am also much indebted to Messrs. Bethel and Garrett for rooted wild plants on which to make sowings, and to Dr. Davis for field observations and the suggestion which led to successful sowings of *Puccinia Eleocharidis*.

During the present season 85 collections of material with resting spores and 15 collections with active spores were employed, from which 484 drop cultures and 13 Petri dish cultures were made to test the germinating condition of the spores, these being made almost wholly from the resting spores. Out of the 85 collections with resting spores 32 could not be made to germinate, although every condition seemed favorable, and were therefore useless. There were in all 194 sowings of spores made, representing 45 species of rusts, and for this purpose 100 species of hosts were utilized, which were grown temporarily in pots in the greenhouse.

A few cultures were made with heteroecious species for which no clue to the alternate host had been obtained, and with one exception the results were negative. These negative trials are here recorded to serve for reference.

1. PUCCINIA on *Carex Pennsylvanica*, sent by Rev. J. M. Bates from Red Cloud, Neb., was sown on *Urtica gracilis* with no infection. Similar material in former seasons has been tried on twenty-one other species of hosts with negative results.³

2. PUCCINIA EMACULATA Schw. on *Panicum capillare* L. from Lafayette, Ind., was sown on *Ambrosia artemisiaefolia*, *Rudbeckia triloba*, *R. laciniata* and *Steironema ciliatum*, with no infection. This very common and distinctive rust was sown in former seasons on fourteen other species of hosts with negative results.⁴

3. PUCCINIA TOSTA Arth., on *Sporobolus asperifolius*, sent from Denver, Colo., by Mr. E. Bethel, was sown on *Napaea dioica*, *Symphoricarpos racemosus*, *Xanthoxylum Americanum*, *Aesculus glabra* and *Viola papilionacea*, with no infection. Sowings of what is taken to be the same species of rust, but on

³ See Jour. Mycol. 10:10. 1904; and 11:51. 1905.

⁴ See Jour. Mycol. 8:52. 1902; Bot. Gaz. 35:12. 1903; and Jour. Mycol. 10:10. 1904.

another host, were made in 1903 on six other species of hosts with negative results.⁵

4. PUCCINIA CRANDALLII Pamm. & Hume, on *Festuca confinis*, sent from Boulder, Colo., by Mr. E. Bethel, was sown on *Dodecatheon Meadia*, *Hydrophyllum appendiculatum*, *Aquilegia Canadensis*, *Anemone Canadensis*, *Thalictrum dioicum*, *Rudbeckia triloba*, *Gutierrezia Sarothrae*, and *Lonicera Japonica*, with no infection.

5. UROMYCES GRAMINICOLA Burr. on *Panicum virgatum*, sent from Red Cloud, Neb., by Rev. Bates, was sown on *Psoralea Onobrychis*, with no infection; while similar material sent by Mr. Bartholomew from Stockton, Kans., was sown on the same host and also on *Cassia Chamaecrista*, *Polemonium reptans* and *Rudbeckia laciniata*, all with no infection.

6. UROMYCES JUNCII (Schw.) Tul. on *Juncus effusus*, sent by Mr. Jackson from Ithaca, N. Y., was sown on *Rudbeckia laciniata*, *R. triloba*, and *Falcata comosa*, with no infection. What is believed to be the same species of rust, but on another host, was sown in 1902 on a species of *Iris* with negative results.

The following species of rusts were successfully grown, and the data supplement that obtained from previous cultures of this series, or that published by other investigators obtained by means of similar cultures. The results in connection with *Puccinia Pruni-spinosae*, the plum rust, are especially interesting, being the first studies of the kind with American material.

1. MELAMPSORA MEDUSAE Thuem.—Teleutosporic material obtained near Lafayette, Ind., on *Populus deltoides* was sown April 17 on *Larix laricina* and *L. decidua*, which resulted in abundance of spermogonia appearing April 25, and a greater abundance of aecidia May 1, upon both hosts.⁶

2. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw.—Three samples of teleutosporic material were used, one from the eastern states, and two from the central west. The test was designed to show whether any difference existed between the two regions in the power of the species to infect the cultivated apple; the apple orchards of Iowa and the central west generally being well known to be especially free from this rust. All the teleutosporic material was on *Juniperus Virginiana*, and to all appearances equally good. That sent from Durham, N. C., by Mr. Wolfe, was sown on a seedling apple out of doors April 27, and showed abundant spermogonia May 9, but did not develop

⁵ See Jour. Myc. 10: 10. 1904.

⁶ See Jour. Mycol. 10: 13. 1904; and 11: 52. 1905.

aecidia, although conditions appeared favorable. Material from Washington, Iowa, sent by Rev. Echlin, was sown April 22, on a small plant of the York Imperial apple in the greenhouse, and showed abundant spermogonia on May 5; another sowing was made out of doors on a seedling apple April 27, and showed spermogonia on May 13, but further observation was prevented by insect depredation. A second lot of material was received from Ames, Iowa, sent by Mr. Buchanan, and was sown out of doors on seedling apple and *Crataegus coccinea*, and in the greenhouse on *Amelanchier Botryapium*. The sowing on apple gave abundant spermogonia, but failed to make further development, while on the other hosts there was no infection. So far as these tests go there appears to be no difference between the eastern and western forms of the species in their power to infect the cultivated apple. Many cultures have been made showing the full life cycle of this rust (often called *G. macropus*). A good summary of the subject, especially in reference to the question underlying the present work, was given a short time ago by Professor Pammel⁷ of the Iowa State College.

3. PUCCINIA SAMBUCI (Schw.) Arth. — Teleutosporic material of fine quality on *Carex lupulina*, collected in Noble county, near Beavor Dam, Ind., was sent by Mr. Whetzel. It was sown on *Sambucus Canadensis* May 8, giving rise to abundant spermogonia May 14, and aecidia May 25.

4. PUCCINIA ALBIPERIDIA Arth. — Teleutosporic material was gathered near Lafayette, Ind., on *Carex tetanica*, and sown April 7 on *Silphium perfoliatum*, *Polemonium reptans*, *Ambrosia trifida*, *Rudbeckia laciniata*, *Steironema ciliatum*, and *Ribes gracile*. Only the last host showed infection, giving abundant spermogonia April 14, and aecidia April 27, the others remained entirely free from rust.

A part of the teleutosporic material was sent to Dr. H. Klebahn, Hamburg, Germany, who sowed it on *Ribes Uva-crispa*, *R. aureum* and *R. rubrum*. No infection resulted on *R. rubrum*, but on *R. Uva-crispa* spermogonia showed May 8, and on *R. aureum* May 15. The further development, however, was slow, soon coming to naught in the first case, and persisting much longer, but with little advance in the second case. Dr. Klebahn in commenting upon his results says that the imperfect development of the infection on *R. uva-crispa* may be ascribed, in part at least, to the late sowing, for the teleutospores germinated freely. The host plants had already passed the most active period of growth, and the weather was too warm. His results are exactly in accord with our own under similar conditions. The

⁷ Bull. Iowa Exper. Sta., No. 84: 16-24. August, 1905.

failure to secure good aecidia made it impossible to give an opinion on the identity of this species of rust,⁸ as compared with European forms.

5. PUCCINIA CARICIS-SOLIDAGINIS Arth. — Teleutospores on *Carex sparganioides* gathered near Lafayette, Ind., were sown April 22 on *Aster paniculatus* and again on May 11 on *A. paniculatus*, *A. Drummondii*, *Ribes rotundifolium*, *Urtica gracilis*, and *Solidago Canadensis*. No infection occurred except on the last host, this giving spermogonia May 18 and aecidia May 28 in very great abundance. In 1902 cultures of this species were made with teleutospores taken from *Carex Jamesii* and *C. stipata*.⁹

6. PUCCINIA PECKII (DeT.) Kellerm. — Teleutosporic material on *Carex lanuginosa*, gathered at Red Cloud, Neb., by Rev. Bates, was sown May 19 on *Hydrophyllum appendiculatum*, *Steironema ciliatum*, and *Onagra biennis*. On May 26 spermogonia, and May 31 aecidia appeared on *O. biennis*, the other hosts remaining entirely unaffected. This result is a duplicate of that obtained in 1904.¹⁰

7. PUCCINIA CARICIS (Schum.) Reb. — Teleutosporic material on *Carex stipata*, gathered near Lafayette, Ind., was sown April 18 on *Urtica gracilis*, and gave spermogonia April 24, and aecidia May 1, in great abundance.

A collection in excellent condition made at Denver, Colo., by Mr. Bethel, on *Carex aquatilis*, was sown on *Urtica gracilis* April 10, giving few but well developed spermogonia April 18, and numerous aecidia April 29. It was sown again April 25, and gave abundant spermogonia May 1, followed with very numerous aecidia May 8.

Both of these sowings were tried on the evidence of the microscopic examination of the collections. It was found that the medium-sized teleutospores, and large uredospores found intermixed, agreed with those known to belong to this species, and the results confirmed the diagnosis. Both collections give new hosts for the species.¹¹ More interesting still was the presence in the Colorado collection of abundant amphispores, which agree in every particular with those collected on *Carex stricta* by C. H. Peck in New York, distributed in Thuemen's *Myc. Univ.*, No. 746, and first called *Uromyces Caricis* Pk., then *Puccinia Caricis-strictae* Diet. This fortunate collection enables us to show beyond a reasonable doubt, that the *Uromyces Caricis*

⁸ For record of previous cultures see Jour. Myc. 8:53. 1902; 10:11. 1904; and 11:58. 1905.

⁹ See Bot. Gaz. 35:21. 1903.

¹⁰ Jour. Mycol. 11:58. 1905.

¹¹ For previous cultures see Bot. Gaz. 29:279. 1900; 35:16. 1903; and Jour. Mycol. 8:52. 1902.

of Peck is the amphisporic form of *Puccinia Caricis*. What determines the production of amphispores in this species is an interesting question, in view of the fact that only twice have they been found, and at such a great distance apart. The amphispores in the Colorado collection did not germinate in drop culture, although the same conditions gave fine germination of the associated teleutospores.

8. *PUCCINIA FRAXINATA* (Schw.) Arth. — A collection of teleutospores on *Spartina cynosuroides*, sent by Mr. Bartholomew from Hill City, Kans., was used to sow April 29, on *Fraxinus lanceolata*, *Adelia acuminata* and *Ligustrum vulgare*. Only the first host gave results, showing spermogonia May 5, and aecidia May 14, the sowing being made on a cut branch placed in water in the greenhouse.¹²

9. *PUCCINIA AMPHIGENA* Diet. — Teleutosporic material on *Calamovilfa longifolia* sent by Rev. Bates from Red Cloud, Neb., was sown on *Smilax hispida* May 27, and began to show spermogonia June 2, and aecidia June 10, both in abundance.¹³

10. *PUCCINIA VERBENICOLA* (E. & K.) Arth. — Teleutosporic material on *Sporobolus longifolius*, sent from Red Cloud, Neb., by Rev. Bates, was sown on *Verbena urticaefolia* May 3, and showed spermogonia May 9, and aecidia May 20. Another collection on same host, obtained near Lafayette, Ind., was sown on same species of *Verbena* May 27, and showed spermogonia June 2, and aecidia June 10.¹⁴

11. *PUCCINIA PUSTULATA* (Curt.) Arth. — Teleutosporic material on *Andropogon furcatus*, gathered by the writer at English Lake, Ind., was sown on *Pentstemon hirsutus* and *Comandra umbellata* May 27, with no infection of the *Pentstemon*, but abundant growth on the *Comandra*, spermogonia appearing June 2, and aecidia June 14. This result confirms work done in 1903.¹⁵

12. *PUCCINIA PAMMELII* (Trel.) Arth. — The cultural results of 1904¹⁶ were verified by sowing teleutospores from *Panicum virgatum*, obtained by the writer at English Lake, Ind., upon *Euphorbia corollata*. A sowing was made May 26, giving spermogonia June 2, and aecidia June 9.

13. *PUCCINIA SUBNITENS* Diet. Teleutosporic material on *Distichlis spicata*, sent from Red Cloud, Neb., by Rev. Bates, was

¹² For previous cultures see Bot. Gaz. 29:275. 1900; and Jour. Mycol. 11:57. 1905.

¹³ For previous cultures see Bot. Gaz. 35:20. 1903; and Jour. Mycol. 10:11. 1904.

¹⁴ For previous cultures see Bot. Gaz. 29:274. 1900; 35:16. 1903; and Jour. Mycol. 11:56. 1905.

¹⁵ Jour. Mycol. 10:17. 1904.

¹⁶ Jour. Mycol. 11:56. 1905.

sown on *Erysimum asperum*, *Sophia incisa*,¹⁷ *Lepidium Virginicum*, and *Bursa Bursa-pastoris*, with success in each case. The sowing was made April 18, and spermogonia appeared on *Erysimum* and *Sophia* April 25, *Lepidium* April 26, and *Bursa* April 27, while aecidia were observed on all by May 8. The aecidia develop with considerable difficulty on *Bursa*, and Rev. Bates writes that they are not common or abundant in the field on this host. On *Lepidium* they also start with less ease than on the other species, but under good conditions grow well.¹⁸

14. PUCCINIA POCULIFORMIS (Jacq.) Wettst. — Teleutospore material on *Agrostis alba*, sent from Ithaca, N. Y., by Mr. Jackson, was sown on *Berberis vulgaris* April 13, and showed numerous spermogonia April 22, with abundance of aecidia May 4.

15. PUCCINIA SORGHII Schw. — The work of last year,¹⁹ in which only aecidia were used, was verified this season by sowing teleutospores. The material was obtained in Lafayette from an early garden variety of sweet corn. It was sown April 17 on *Oxalis cymosa* (the common wild wood sorrel of the region), *O. Ortgiesii* (a yellow-flowered greenhouse weed), *O. ———*, (a tuberous pink-flowered form of greenhouses), and *O. Bowiei* (a pink-flowered form with large flowers and leaves, also grown in greenhouses.) All remained free, except *O. cymosa*, which showed numerous spermogonia on April 27, and aecidia on May 5. A second sowing was made May 1 on *O. cymosa*, *O. Origiesii*, *O. Bowiei*, and *O. corniculata* (growing out of doors over a grass-covered conduit for steam pipes), and again all remained free except *O. cymosa*, which gave spermogonia May 8, and aecidia May 14. It is not apparent why no infection should occur on the four hosts other than *O. cymosa*, but there is no reason to suppose that it was due in any degree to lack of vigor or suitable conditions.

The aecidiospores raised in the first trial above were sown May 6 on seedlings of the yellow dent field corn variety of *Zea Mays*, and in a week, May 13, showed uredospores, which increased in abundance until teleutospores were observed June 15. The uredospores from this culture (on yellow dent corn) were sown May 16 on small plants of garden sweet corn, and gave

¹⁷ This is probably not the correct name of the plant used for the cultures. It is, however, the name also used last year for the trial host, which is the common species of *Sophia* in this region, and the error in determination is due to the confusion existing in the current manuals. The species is also different from the one on which the fungus was collected last year in Nebraska by Rev. Bates (Jour. Mycol. II: 116. 1905), and that is also incorrectly named. But for the sake of simplicity the name *S. incisa* will be used in this article for both species.

¹⁸ For previous cultures see Bot. Gaz. 35: 19. 1903; and Jour. Mycol. II: 54. 1905.

¹⁹ Bot. Gaz. 38: 64. 1904.

uredospores in plenty on May 23, and would doubtless have been followed by teleutospores in due time, had the culture been continued. These results in transferring the rust from field corn to sweet corn, and the reverse, are in accord with those obtained by Kellerman.²⁰

At the same time the first sowings were made, April 17, teleutospores were also sown on a seedling *Zea Mays*, under favorable conditions, but no infection resulted. The drop cultures, which are made just previous to every sowing, showed that the teleutospores germinated freely, but the few uredospores intermixed were not viable. In this case, at least, the teleutospores appeared to be incapable of infecting the host from which taken, and in so far agree with the general rule regarding grass and sedge rusts.

16. *PUCCINIA POLYGONI-AMPHIBII* Pers.—In 1904²¹ it was possible to verify in a measure the work upon this species by Dr. Tranzschel of St. Petersburg, by sowing aecidiospores from *Geranium maculatum* and obtaining teleutospores on *Polygonum emersum*. This season the reverse order of sowing was tried. Teleutospores from *P. emersum* obtained in this vicinity were sown April 15 on *G. maculatum* and *G. Robertianum*, with no infection of the latter, but most abundant infection of the former, showing spermogonia April 23 and aecidia May 1. A second sowing was made April 27, using the above two hosts and also *G. pusillum*, and again infection occurred only upon *G. maculatum*, which showed great numbers of spermogonia May 3, and aecidia May 9. These results agree with common observation, for the aecidium on *G. maculatum* (*A. sanguinolentum* Lindr.) is common in the United States, while no aecidia have yet been reported on *G. Robertianum* or *G. pusillum*.

17. *PUCCINIA HELIANTHI* Schw.—A sowing of teleutospores, taken from *Helianthus grosse-serratus* growing on the grounds of the University, was made May 17 on *H. grosse-serratus* and two plants of *H. annuus* with equally abundant results in each case, spermogonia showing May 25, and aecidia June 2.

18. *PUCCINIA LATERIPES* B. & Br.—After many vain attempts to secure good fungous and host material of this species for culture work, the present season's excellent results have given much satisfaction. All the material was obtained near Lafayette, Ind. Sowings of teleutospores from *Ruellia ciliosa* were made April 25 on both *R. ciliosa* and *R. strepens*, with equally positive results in both cases, showing spermogonia May 5, and aecidia May 18. Another sowing of the same material was made on *R. strepens* May 27, which gave spermogonia June 5, and aecidia

²⁰ Cf. Jour. Mycol. 11:27. 1905.

²¹ Jour. Mycol. 11:59. 1905.

June 15. A sowing of teleutospores from *R. strepens* on *R. ciliosa* May 8, and another June 7, gave no infection.

Many writers, following Lagerheim, who received his clue from Burrill, have made two species of the rusts on these two hosts. It is true that the gross appearance, and to some extent the microscopic characters of the two are perceptibly different. These differences are shown, so far as the development went, in the results of the cultures. The aecidial groups grown on *R. ciliosa* were small and round, one to two millimeters across, without noticeable hypertrophy of the tissues, and confined to the blade of the leaf. On *R. strepens*, however, they took possession of the veins, petioles and stems, and made large swellings from 20 to 25 millimeters long, and in one case the main stem for a distance of ten centimeters or more was greatly swollen and distorted. The differences also extended to the peridial cups and to the spores. On *R. ciliosa* the cups were mostly one-half millimeter high, and on *R. strepens* fully one millimeter high. The aecidiospores from *R. ciliosa* measured 15-19 by 20-26 μ , and from *R. strepens* 17-21 by 24-30 μ . These two cultures were from the same source of infection, and must therefore be one and the same species. Had uredospores and teleutospores been raised, it is believed that the differences recorded in the books for the two hosts would have been found. In short it is believed that the differences of size and appearance are entirely due to the influence of the hosts. The loose, somewhat succulent tissues of *R. strepens*, and its vigorous habit of growth, are correlated with the greater development of the fungus, while the firm close tissues of *R. ciliosa*, not only prevent luxuriant development of the parasite, but its parts become smaller throughout. These differences in the hosts also account for the failure to infect *R. ciliosa* with spores from *R. strepens*, while the reverse process succeeded. There appears to be no reason to doubt that under very favorable conditions the infection of *R. ciliosa* with spores from *R. strepens* could be accomplished, and the resulting development be the same as when the infecting spores came from *R. ciliosa* itself.²²

19. PUCCINIA PRUNI-SPINOSAE Pers.—The *Aecidium punctatum* Pers. (*A. quadrifidum* DC.) occurring in various parts of the United States and Canada on different species of *Anemone*, *Hepatica* and *Thalictrum* so closely resembles the European form which bears the same name, that little doubt has existed of their genuine identity. In 1904 Dr. Tranzschel²³ of St. Petersburg made cultures of this aecidium, sowing the aecidiospores from *Anemone coronaria* on *Amygdalus communis* (almond) *Prunus spinosa* (blackthorn), *P. divaricata* (cherry-

²² For previous cultures see Kellerman in Jour. Mycol. 9: 107. 1903.

²³ Trav. Mus. Bot. Acad. Sci. St. Petersb. 11: 67-69. 1905.

plum) and from *Anemone ranunculoides* on *P. spinosa*, producing in each the characteristic uredospores of *Puccinia Pruni-spinosae*, the rust of plums and peaches.

This work by Dr. Tranzschel suggested the following trials with American material. Aecidiospores from *Hepatica acutiloba* (*Aecidium heptacatum* Schw.) were sown on three small plants of *Prunus serotina* (wild black cherry), established in pots in the greenhouse, on *Prunus Americana* (native plum), *P. Cerasus* (cultivated cherry), and *Amygdalus Persica* (peach), the last two seedlings. The sowings were made May 1 to 4, and in fifteen days afterward, uredospores appeared on *P. serotina*, but the other plants remained wholly free, watch being continued for a month and more. The successful sowings were as follows:

May 1, Aecidiospores sown on *P. serotina*; May 16, uredospores; May 22, teleutospores.

May 1, Aecidiospores sown on *P. serotina*; May 16, uredospores.

May 2, Aecidiospores sown on *P. serotina*; May 17, uredospores.

On May 23, a sowing of uredospores, which had been grown on *P. serotina*, was made on *A. Persica*, under seemingly most favorable conditions, but no infection took place, watch being kept for two months.

From these results there can be no further question of the general identity of the American and European plum and cherry rusts, and their connection with the *Aecidium punctatum*. It is not possible to state what significance is to be attached to the failure to infect peach, plum and cultivated cherry with spores that readily infected the wild cherry. Careful search for two seasons in the vicinity of the diseased hepaticas, the fungus being perennial, has failed to detect any rust on plums, cherries or peaches, wild or cultivated, although growing in plenty; and furthermore *Puccinia Pruni-spinosae* has not yet been reported from Indiana, although said to occur in the adjoining state of Illinois on *P. serotina*, *P. Virginiana*, and *P. Americana*.

20. PUCCINIA XANTHII Schw. — Teleutosporic material on *Xanthium Canadense*, gathered near Lafayette, Ind., on Nov. 5, 1904, was sown on the second and third leaves of seedlings of the same species of host April 3. On April 8 small yellow dots began to show, which closely simulated spermatogonia, but which microscopic examination by means of sections proved were only the very young teleutosporic sori. The yellow dots increased in size, appearing like small pimples, and finally broke through the epidermis, exposing the teleutospores April 21, eighteen days after inoculation. Another sowing was made April 13, on the cotyledons of the same species of host, and on the second leaves of *Ambrosia trifida*. The *Xanthium* seed-leaves showed yellow dots on April 22, and open sori May 1, also in eighteen days from sowing, but the *Ambrosia* leaves remained free.

These results agree essentially with those reported by Carleton,²⁴ who was able to infect *Xanthium* in eighteen and fourteen days, but could not infect *Ambrosia*. He says, however, that "in all these cases spermogonia preceded the teleutospores in the infected spots." In connection with an account of cultures with *Puccinia heterospora* he adds that "numerous experiments were also made with other *lepto* species, including *Puccinia Grindeliae* Pk., *P. variolans* Hark., *P. Lygodesmiae* E. & E., and *P. Sherardiana* Korn., with results similar to those above mentioned," but he does not report the details of these cultures, if such they were.

Taking the observations here recorded for *P. Xanthii*, especially in connection with those for *P. Silphii* and *P. Grindeliae*, reported below, it seems safe to assume that these species, and those quoted as mentioned by Carleton, belong to a group of rusts in which teleutospores and their resulting sporidia are the only spore-forms produced in the life-cycle, aecidia, uredo, and even spermogonia being wholly absent.

The following nine species have never been tested before by the culture method, so far as the writer knows, either in this country or abroad. They embrace an interesting diversity of habit. Besides the grass and sedge forms, with which this series of cultures has been most concerned, there are two leptopuccinia, one micropuccinia and one brachypuccinia, also one of the grass rusts is chiefly interesting for its amphispores.

1. PUCCINIA SILPHII Schw. — Teleutosporic material was gathered March 31, 1905, near Lafayette, Ind., on dead and weathered leaves of *Silphium integrifolium*, and sown April 10 on vigorous plants of the same host, and also on *S. perfoliatum*. There was no infection on the latter host, but on the former clear yellow dots showed April 15, which sectioned and placed under the microscope proved to be very young teleutosori. These yellow dots rapidly enlarged, forming pale pimples scattered over yellow patches of the leaf, with much hypertrophied tissues, and April 20 broke through the epidermis, exposing the abundant teleutospores. Another sowing on the same two hosts was made April 25, and with the same results: there was no infection of *S. perfoliatum*, and the most abundant infection of *S. integrifolium*, showing as yellow dots May 2, and exposed teleutospores May 5. As the rust occurs on both these species of *Silphium*, and many others as well, the results may be taken as indicative of biological races.

2. PUCCINIA GRINDELIAE Pk. — Excellent teleutosporic material on *Gutierrezia Sarothrae* was sent by Mr. Bethel, collected

²⁴ Bulletin Bureau Pl. Industry, No. 63:26. 1904.

at Boulder, Colo., March 27, 1905, on weathered stems. Mr. Bethel also kindly sent growing plants of the host and of *Chrysanthamnus nauseolus*. The latter is not a recorded host for *P. Grindeliae*, but for a similar species, *P. tuberculans* E. & E. A sowing was made on *G. Sarothrae* April 12, which showed yellow dots April 21, and numerous open teleutosori May 2. Another sowing was made on both hosts April 26, with no infection on *C. nauseolus*, but most abundant infection on *G. Sarothrae*, showing yellow dots May 4, and open teleutosori May 15. The yellow dots were investigated, as in the other instances, and found to be the early stages of teleutosori, with no trace of spermogonia.

3. PUCCINIA SOLIDAGINIS Pk.—Teleutosporic material was sent by Mr. Garrett, collected at Salt Lake City, Utah, on *Solidago trinervata*, April 8, 1905. It was sown on *S. Canadensis* May 17, showing yellow dots June 2, and an abundance of open teleutosori June 7, with considerable hypertrophy of the tissues. Although the yellow dots were not specially investigated, they gave the same appearance of being young sori, as in the above species of leptopuccinia.

4. PUCCINIA TRANSFORMANS E. & E.—Remarkably fine teleutosporic material, forming considerable excrescences on leaves and stems of *Stenolobium Stans* (*Tecoma Stans*), was sent by Mr. Horne, who collected it at Santiago de las Vegas, Cuba, May 3, 1905. It was sown on two young plants of *S. Stans* May 13, and in both cases gave abundance of spermogonia May 29, and of teleutospores June 5.

Fine material gathered by Mr. J. B. Rorer on the pods of *S. Stans* in the Bahama Ids., at Nassau, New Providence, March, 1904, was sent for identification. The pods contained many seeds, which were planted in the greenhouse, and provided the host plants for the above inoculations. The teleutospores of this collection were in good germinating condition. As there were no growing plants of *S. Stans* at hand, they were sown May 20 (1904) on vigorous young plants of *Campsis radicans* (*Tecoma radicans*), but gave no infection, although the conditions seemed particularly favorable.

Since the cultures were made a study of the characters of the species has been undertaken, and the conclusion reached that all North American collections, so far as known, belong to *P. transformans* (*P. exitiosa* Syd. & Holw.). An original specimen of *P. transformans*, collected in Baja California by K. Brandegee in 1893 on *Tecoma Stans*, has been examined, and found to agree with other specimens on the same host from the West Indies, and also with the type material of *P. exitiosa* on *Tecoma mollis*, that is *Stenolobium mollis*, from Mexico. The species possesses considerably smaller spores, with thinner walls and finer sculp-

turing, than *Puccinia elegans* Schröt., reported only from Argentine, South America, an original specimen of which I have been able to examine through the courtesy of Dr. P. Hennings of the Botanical Garden, Berlin. *P. transformans* has not yet been reported from any locality in the United States.

5. PUCCINIA KUHNIAE Schw. — Teleutosporic material, gathered near Lafayette, Ind., Nov. 3, 1904, on *Kuhnia eupatorioides*, was sown on the same host May 19. On May 28 spermogonia appeared sparingly, which were examined under the microscope in section, and these were followed June 5 by uredo in fair abundance. The species, therefore, belongs to the group of brachypuccinia.

6. PUCCINIA CANALICULATA (Schw.) Lagerh. — An observation in the field made in 1904 led to the present successful cultures. Aecidia were found in remarkable abundance on seedling *Xanthium Canadense* over an area 8 to 10 meters in diameter, beyond which the aecidium did not occur, although the hosts were equally plentiful and equally exposed. Later in the season, the middle of June, uredosori were found upon what appeared to be a seedling sedge extending over approximately the same area that had been occupied in the spring by the cocklebur cluster cups, and this was followed in August by teleutosori. Although the sedge did not fruit, yet it was not difficult to ascertain that it was a species of *Cyperus*, and the rust *Puccinia canaliculata*.

On May 11 a sowing of aecidiospores, obtained from the locality mentioned, was made in the greenhouse on *Cyperus esculentus*, other species of the genus not being at hand, and on June 2 uredo were noticed, although they probably appeared earlier and were overlooked, being small and pale. Another sowing was made on the same species of host May 17, and uredo first noticed June 2. The plants did not grow well, and the infected leaves were removed for the herbarium before time enough had elapsed in which to develop telutosori. Cultures with teleutosporic material will doubtless confirm this association of the *Xanthium* and *Cyperus* rusts.

7. PUCCINIA ELEOCHARDIS Arth. — Teleutosporic material on *Eleocharis palustris* was sent by Dr. Davis from Racine, Wis., and with it the information that from observations in the field he believed this to have its aecidial phase on *Eupatorium*. Acting upon this suggestion, a sowing was made May 5 on *Eupatorium perfoliatum*, which gave rise to spermogonia May 13, and aecidia May 22. Another sowing on the same species of host May 11, gave spermogonia May 20, and aecidia May 30. Both trials produced an abundance of aecidia, with all the characteristics of the common and widely distributed form on this host, and closely related species.

8. *PUCCINIA SUBSTERILIS* E. & E. — Fine material on *Stipa viridula* collected in August, 1904, at Boulder, Colo., was sent by Mr. Bethel, who also sent living plants of *S. viridula* and *S. comata*. This material showed a great abundance of amphispores,²⁵ but almost no teleutospores. The amphispores gave good germination, and were sown April 6 on *S. viridula* and *S. comata*. Uredospores of the usual kind began to appear on *S. viridula* April 18, but no infection on *S. comata*. Another sowing was made April 22 on *S. comata*, which also gave no infection. Uredospores continued to form for a month on *S. viridula*, but no amphispores or teleutospores were produced.

Mr. Bethel also sent fine teleutosporic material on *Stipa comata*, collected in March, 1905, at Boulder, Colo. This was sown on *Aster ericoides* April 18, and contrary to expectation gave no infection. When the failure became assured, it was sown again, April 29, on *A. ericoides*, *A. multiflorus*, and *A. Novae-Angliae*, but in each case without infection. This negative result throws some doubt on the assumption that the American *Stipa* rusts on the several species of hosts belong to one species, having its aecidia on certain species of *Aster*,²⁶ and the present very incomplete report is therefore entered under the name *P. substerilis*. Reducing this name to a synonym of *P. stipae*, as the writer did a few months since,²⁷ is now believed to have been premature.

9. *PUCCINIA SEYMOURIANA* Arth. — At the time this species was published,²⁸ it was suggested upon grounds of spore resemblance that its *Aecidium* was *A. Cephalanthi* Seym. From combined morphological and geographical data I was then willing to assert that "although cultures must be awaited, yet there can be little doubt that the early stages of *P. Seymouriana* occur upon *Cephalanthus*." Persistent efforts to secure material for this trial were finally rewarded by the writer finding especially good teleutospores on *Spartina cynosuroides* at English Lake, Ind., in the northern part of the state, in March, 1905. These were sown on *Polygala Senega* April 20, with no infection, and later on *Cephalanthus occidentalis*, May 13, with abundant results. On May 18 great numbers of spermogonia began to show, and on May 27 still greater numbers of aecidia, thus verifying the prediction made three years before.

10. *UROMYCES ACUMINATUS* Arth. — Finding the aecidium of this very common rust was due to a fortunate accident. Of the many trials to find the connection between the two phases

²⁵ For description and illustrations of the amphispores in this species see Bull. Torr. Bot. Club 32: 38. 1905.

²⁶ For cultures of *Puccinia Stipae* see Jour. Mycol. 11: 63. 1905.

²⁷ Jour. Mycol. 11: 11. 1905.

²⁸ Bot. Gaz. 34: 12. 1902.

of a heteroecious rust, during my seven years of experimental work, this is the first instance of success without the aid of some probable clue, and in this case may be ascribed to good luck and the exuberant enthusiasm of Mr. Kern, who made all the sowings of the season.

Teleutosporic material on *Spartina cynosuroides*, collected at Palmer, Neb., by Rev. Bates, was sown May 26, on whatever plants were available in the greenhouse, that are recorded as bearing aecidia of unknown teleutosporic connection. These hosts were: *Polemonium reptans*, *Polygala Senega*, *Cassia Chamaecrista*, *Psoralea Onobrychis*, *Rudbeckia laciniata*, *Ambrosia artemisiaefolia*, *Thalictrum dioicum*, *Viola papilionacea*, and *Steironema ciliatum*. To our great surprise *S. ciliatum* began to show spermogonia June 1, and abundant aecidia June 6, all others having no infection. Another sowing was at once made, June 2, which likewise gave spermogonia June 7, and aecidia June 12.

The aecidium on this host is recorded or known to the writer from Iowa, Illinois, Nebraska, Kansas, Wyoming and Minnesota. A collection made in Wisconsin²⁹ on *S. lanceolatum* is thought by Burrill³⁰ to be specifically distinct. Schlechtendahl's name, *Caeoma Lysimachiae*, sometimes used for American specimens, was founded on an aecidium on *L. thyrsiflora* L. (*Naumburgia thyrsiflora* (L.) Duby) from vicinity of Berlin, and doubtless is entirely distinct from American forms, with the possible exception of the reference in Farlow & Seymour's Host Index,³¹ the basis for which is unknown to the writer. Schweinitz's name³² *Aecidium Lysimachiae* applies to the form on *Lysimachia quadrifolia* and *L. terrestris*, only reported from North Carolina, and may well be considered distinct. What is now much needed is teleutosporic material from the Atlantic and Gulf coasts to be used in cultures for testing the above points, and in general the question whether the eastern and western forms are one species or not.

The great prevalence of this rust on *Spartina*, and the comparative rarity of the aecidia on *Steironema*, is doubtless due in part to the hardiness of the uredospores, which enable them to live over winter and start the uredostage in the spring under favorable conditions. This is the opinion expressed by Mr. Bartholomew in a recent interview, and is my own opinion, founded in part upon finding uredosori upon young blades of *Spartina* only a few inches long at such an early date in spring that infection by means of aecidiospores seemed highly improbable.

²⁹ Trelease, Paras. Fung. Wis. p. 30.

³⁰ Burrill, Paras. Fung. Ill., I. Uredineae, p. 233.

³¹ L. c. p. 75. 1890.

³² Schrift. d. nat. Ges. Leipzig 1: 67. 1822.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1904. It is divided into the two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A. Species previously reported.

1. MELAMPSORA MEDUSAE Thuem. — Teleutospores from *Populus deltoides* Marsh. sown on *Larix laricina* (DuR.) Koch.
2. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw. — Teleutospores from *Juniperus Virginiana* L. sown on *Malus Malus* (L.) Britt.
3. PUCCINIA SAMBUCI (Schw.) Arth. — Teleutospores from *Carex lupulina* Muhl. sown on *Sambucus Canadensis* L.
4. PUCCINIA ALBIPERIDIA Arth. — Teleutospores from *Carex tetanica* Schk. sown on *Ribes gracile* Michx.
5. PUCCINIA CARICIS-SOLIDAGINIS Arth. — Teleutospores from *Carex sparganioides* Muhl. sown on *Solidago Canadensis* L.
6. PUCCINIA PECKII (DeT.) Kellerm. — Teleutospores from *Carex lanuginosa* Michx. sown on *Onagra biennis* (L.) Scop.
7. PUCCINIA CARICIS (Schum.) Reb. — Teleutospores from *Carex stipata* Muhl. and *C. aquatilis* Wahl. sown on *Urtica gracilis* Ait.
8. PUCCINIA FRAXINATA (Schw) Arth. — Teleutospores from *Spartina cynosuroides* Willd. sown on *Fraxinus lanceolata* Borck.
9. PUCCINIA AMPHIGENA Diet. — Teleutospores from *Calamovilfa longifolia* (Hook.) Hack. sown on *Smilax hispida* Muhl.
10. PUCCINIA VERBENICOLA (E. & K.) Arth. — Teleutospores from *Sporobolus longifolius* (Torr.) Wood, sown on *Verbena urticaefolia* L.
11. PUCCINIA PUSTULATA (Curt.) Arth. — Teleutospores from *Andropogon furcatus* Muhl. sown on *Comandra umbellata* (L.) Nutt.
12. PUCCINIA PAMMELII (Trel.) Arth. — Teleutospores from *Panicum virgatum* L. sown on *Euphorbia corollata* L.
13. PUCCINIA SUBNITENS Diet. — Teleutospores from *Distichlis spicata* (L.) Greene, sown on *Erysimum asperum* DC., *Sophia incisa* (Eng.) Gr., *Lepidium Virginicum* L. and *Bursa Bursa-pastoris* (L.) Britt.
14. PUCCINIA POCULIFORMIS (Jacq.) Wettst. — Teleutospores from *Agrostis alba* L. sown on *Berberis vulgaris* L.

15. PUCCINIA SORGHII Schw.—Teleutospores from *Zea Mays* L. sown on *Oxalis cymosa* Small.; aecidiospores from *Oxalis cymosa*, sown on *Zea Mays*; and uredospores from *Zea Mays* sown on same host.

16. PUCCINIA POLYGONI-AMPHIBII Pers.—Teleutospores from *Polygonum emersum* (Michx.) Britt. sown on *Geranium maculatum* L.

17. PUCCINIA HELIANTHI Schw.—Teleutospores from *Helianthus grosse-serratus* Mart. sown on *H. grosse-serratus* Mart. and *H. annuus* L.

18. PUCCINIA LATERIPES B. & Br.—Teleutospores from *Ruellia ciliosa* Pursh, sown on *R. ciliosa* Pursh and *R. strepens* L.

19. PUCCINIA PRUNI-SPINOSAE Pers.—Aecidiospores from *Hepatica acutiloba* D C. sown on *Prunus serotina* Ehrh.

20. PUCCINIA XANTHII Schw.—Resting teleutospores from *Xanthium Canadense* Mill. sown on same host.

B. Species reported now for the first time.

1. PUCCINIA SILPHII Schw.—Resting teleutospores from *Silphium integrifolium* Michx. sown on same host.

2. PUCCINIA GRINDELIAE Pk.—Resting teleutospores from *Gutierrezia Sarothrae* (Pursh) B. & R. sown on same host.

3. PUCCINIA SOLIDAGINIS Pk.—Resting teleutospores from *Solidago trinervata* Greene, sown on *S. Canadensis* L.

4. PUCCINIA TRANSFORMANS E. & E.—Resting teleutospores from *Stenolobium Stans* (L.) Don. sown on same host.

5. PUCCINIA KUHNIAE Schw.—Teleutospores from *Kuhnia eupatorioides* L. sown on same host.


6. PUCCINIA CANALICULATA (Schw.) Lagerh.—Aecidiospores from *Xanthium Canadense* Mill. sown on *Cyperus esculentis* L.

7. PUCCINIA ELEOCHARIDIS Arth.—Teleutospores from *Eleocharis palustris* (L.) R. & S. sown on *Eupatorium perfoliatum* L.

8. PUCCINIA SUBSTERILIS E. & E.—Amphisporae from *Stipa viridula* Trin. sown on same host.

9. PUCCINIA SEYMOURIANA Arth.—Teleutospores from *Spartina cynosuroides* Willd. sown on *Cephalanthus occidentalis* L.

10. UROMYCES ACUMINATUS Arth.—Teleutospores from *Spartina cynosuroides* Willd. sown on *Steironema ciliatum* (L.) Raf.





Reprinted from the *Journal of Mycology*, 13: 189-205, September, 1907.

CULTURES OF UREDINEAE IN 1906.¹

BY J. C. ARTHUR.

The present article forms the seventh of a series of reports² by the author upon the culture of plant rusts, covering the years from 1899 to the close of 1906. As in previous years the grass and sedge rusts have constituted a large part of the list of species under trial. This is partly due to the economic and scientific interest connected with them, but even more, possibly, to the greater ease with which wintered-over and viable spores may be secured for cultural study. Among the species whose life-

¹Read before the Botanical Society of America at the New York meeting, December 31, 1906.

²See Bot. Gaz. 29:268-276, 35:10-23; Jour. Myc. 8:51-56, 10:8-21, 11:50-67 and 12:11-27.

cycle has now been worked out for the first time, the one having the greatest economic import does not belong to the grass or sedge forms, but inhabits flax. The discovery of the full developmental history of this serious menace to successful flax growing, brought about by the cooperation of Professor Henry L. Bolley of North Dakota, widely known for his interest and scientific studies in promoting the flax industry, has been a matter of much satisfaction. It greatly clarifies the problem of controlling the flax rust in the interest of the cultivator.

The work of testing the viability of spores, making the sowings, and recorded data, required, as in previous years, the undivided attention of a person to whom the whole work could be intrusted. The expense of such an assistant was this year met by a grant from the Botanical Society of America. It was the second time the Society has given material aid to this series of investigations.

Through the kindness of Professor R. A. Harper, I was so fortunate as to enlist the interest of Dr. E. W. Olive, lecturer at the University of Wisconsin, who consented to supervise the season's work. The forethought and constant watchfulness, the enthusiastic application, and especially the maturity of judgment and breadth of knowledge brought to bear on the work by Dr. Olive materially increased the completeness of the results.

As in former years correspondents have provided much of the material used in the trials, partly upon their own initiative, and partly in response to suggestion, for all of which I am under heavy obligation. Teliosporic material was sent by Messrs. A. D. Selby, Wooster, Ohio; H. H. Whetzel, Ithaca, N. Y.; Chas. E. Fairman, Lyndonville, N. Y.; W. A. Kellerman, Columbus, Ohio; H. L. Shantz, Columbia, Mo.; J. J. Davis, Racine, Wis.; John L. Sheldon, Morgantown, W. Va.; H. L. Bolley, Agricultural College, N. D.; E. Bartholomew, Stockton, Kans.; Geo. E. Morris, Waltham, Mass.; Guy W. Wilson, Lafayette, Ind.; E. Bethel, Denver, Colo.; and especially by Rev. J. M. Bates, Red Cloud, Neb. Aeciosporic material was sent by Messrs. Herman von Schrenk, St. Louis, Mo.; H. H. Whetzel, Ithaca, N. Y.; C. L. Shear, Tacoma Park, D. C.; D. Reddick, Ithaca, N. Y.; and P. H. Rolfs, Lake City, Fla., all the collections being either *Caecoma* or *Peridermium* on species of *Pinus*. Host plants are often required for the work, which do not grow in this vicinity, and can not be purchased from dealers, and for a number of such plants in good growing condition I am indebted to Messrs. William Trelease of the Missouri Botanical Garden, St. Louis, Mo.; John L. Sheldon, Morgantown, W. Va.; P. B. Kennedy, Reno, Nev.; and J. J. Davis, Racine, Wis.

During the present season 94 collections of material with resting spores and 15 collections with active spores were employed, from which 293 drop cultures and 6 Petri dish cultures

were made to test the germinating condition of the spores. Out of the 94 collections with resting spores 46 could not be made to germinate, although no reason could be assigned why they should not. This gave 48 collections of available material belonging to 30 species of rusts, exclusive of the aecial pine rusts, and from these 223 sowings were made. Beside these 53 sowings were made with *Caeoma* and *Peridermium* spores from pine, all without infection, 27 sowings with teliospores of *Gymnosporangium*, and 23 sowings with various aeciospores. Altogether 326 sowings were made, and for this purpose 134 species of hosts were required, which were grown temporarily in the greenhouse, where practically all the work was done. The results of this work are given in the following paragraphs, and are divided into negative results, positive results with species whose life histories have already been previously determined, and positive results with species whose life histories have not before been fully known.

Of the trials giving negative results the following may be recorded to serve for reference in further studies.

1. PUCCINIA on *Carex Pennsylvanica* Lam., collected near Lafayette, Ind., was sown on *Trillium recurvatum*, *Napaea dioica*, *Anemonella thalictroides*, *Isopyrum biternatum*, *Anemone virginiana*, *Actaea alba*, *Viola cucullata*, *Dirca palustris*, *Polemonium reptans*, *Ambrosia trifida*, *Rudbeckia laciniata*, and *Lactuca canadensis*, with no infection. Similar material in former seasons has been tried on eighteen other species of hosts with negative results.³

2. PUCCINIA on *Carex grvida* Bailey, sent by Rev. J. M. Bates from Red Cloud, Neb., was sown on *Actaea rubra*, *Thalictrum dioicum*, *Isopyrum biternatum*, *Apios Apios*, *Falcata comosa*, *Psoralea Onobrychis*, *Cassia Chamaecrista*, *Polygala Senega*, *Aesculus glabra*, *Ceanothus americanus*, *Smilax herbacea*, *Viola cucullata*, *Napaea dioica*, *Callirrhoe involucrata*, *Althaea rosea*, *Hibiscus Moscheutos*, *Macrocalyx Nyctelea*, *Polemonium reptans*, *Myosotis palustris*, *Phlox divaricata*, *Phlox subulata*, *Triosteum perfoliatum*, *Boltonia asteroides*, *Laciniaria pycnostachya*, *Rudbeckia laciniata*, *Senecio obovatus*, and *Cacalia reniformis*, with no infection. Similar material from the same source has been sown in previous years upon eleven other species of hosts with negative results.⁴

3. PUCCINIA on *Polygonum scandens* L., obtained in the vicinity of Lafayette, Ind., was sown five times on *Geranium maculatum*, twice on *G. Robertianum*, twice on *G. pusillum*, and

³ See Jour. Myc. 10:10. 1904; 11:51. 1905; and 12:12. 1906.

⁴ See Jour. Myc. 10:10. 1904; and 11:52. 1905.

twice on *Thalictrum dioicum*. These sowings were made under seemingly favorable conditions and yet no infection resulted. In 1903 Dr. W. Tranzschel of St. Petersburg established the connection between *Puccinia Polygoni-amphibii* Pers. on *Polygonum amphibium* and the aecia on *Geranium palustre* and *G. pratense*, and a year later the writer corroborated the discovery with corresponding American species of hosts. In 1904 Dr. Tranzschel showed that the rust on climbing species of *Polygonum*, often included with the preceding, is distinct, either as a true species or a biological species, for it produces its aecia on *Geranium pusillum*. To see if this also could be substantiated with American material the above sowings were made with seemingly excellent teliosporic material, but the negative results leave the matter an open question. The only other native *Geranium* on which this form might be expected to grow readily is *G. carolinianum*, which was unfortunately not at hand for the test.

4. PUCCINIA ON *Muhlenbergia diffusa* Schreb., sent by Rev. J. M. Bates from Red Cloud, Neb., was sown on *Trillium recurvatum*, *Actaea alba*, *Anemonella thalictroides*, *Isopyrum biter-natum*, *Caulophyllum thalictroides*, *Apios Apios*, *Viola pubescens*, *Dirca palustris*, *Althaea rosea*, *Callirrhoe involucrata*, *Napaea dioica*, *Hibiscus Moscheutos*, *Marcrocalyx Nyctelea*, *Polemonium reptans*, *Ambrosia trifida*, and *Lactuca canadensis*, with no infection. This taken with previous trials shows that the rusts on different species of *Muhlenbergia* are in all probability biologically complex.

5. PUCCINIA SCHEDONNARDI K. & S., sent by Rev. J. M. Bates from Red Cloud, Neb., was sown on *Callirrhoe involucrata*, *Althaea rosea*, and *Ceanothus americanus*, with no infection. Like material from the same source was sown in 1902 on eight other species of hosts with negative results.⁵ The small sori and fine leaves of the grass make the manipulation of material of this species somewhat uncertain.

6. PUCCINIA EMACULATA Schw. on *Panicum capillare*, obtained in the vicinity of Lafayette, Ind., where it is very common, was sown on *Polygala Senega* and *Napaea dioica*. This rust was sown in previous seasons on eighteen other species of hosts.⁶

7. UROMYCES on *Juncus effusus* L., sent by Dr. Charles E. Fairman from Ridgeway, N. Y., was sown on *Polemonium reptans*, *Houstonia purpurea*, *Ambrosia trifida*, *Rudbeckia laciniata*, *Polymnia canadensis*, *Parthenium integrifolium*, *Silphium integrifolium*, *S. perfoliatum* *S. terebinthinaceum*, and *Senecio obovatus*,

⁵ See Bot. Gaz. 35:11. 1903.

⁶ See Bot. Gaz. 35:12. 1903; Jour. Myc. 8:52. 1902; 10:10. 1904; and 12:12. 1906.

with no infection. What was doubtless the same rust, and also from western New York, was sown in 1905 on two other species of hosts with negative results.⁷

This rust has heretofore been considered to belong to *Uromyces Junci* (Desm.) Tul., but recent study has shown that it is morphologically quite distinct from that species, especially as it has urediniospores that are echinulate and four-pored, instead of verrucose and two-pored, as in the European species, which by the way apparently does not occur in the United States east of Nebraska and Kansas. It was described by Schweinitz (Trans. Am. Phil. Soc. 4:295. 1832.) as a new species under the name *Puccinia Junci*. As that specific name is not now available, I suggest that the species be called *Uromyces effusus*, in allusion to the copious distribution of the sori over the surface of the host, and would characterize it as follows:

***Uromyces effusus* sp. nov.**

O and I. Pycnia and aecia unknown.

II. Uredinia amphigenous, scattered, oblong or linear, 0.1-0.3 mm. wide by 0.3-1.5 mm. long, tardily naked, dark cinnamon-brown, ruptured epidermis very conspicuous; urediniospores broadly ellipsoid or oval, 14-19 by 18-26 μ , wall light yellow about 1.5 μ thick, rather sparingly and bluntly echinulate, pores 4, equatorial.

III. Telia amphigenous, numerous, scattered, oblong or linear, 0.2-0.5 mm. wide by 0.3-2 mm. or more long, rarely confluent, finally naked, ruptured epidermis very conspicuous; teliospores obovate or broadly oval, 13-19 by 24-33 μ , obtuse or rarely acute at apex, usually narrowed below; wall chestnut-brown, 1.5-2 μ thick, much thicker above, 6-10 μ , smooth; pedicel tinted, about as long as the spore.

On *Juncus effusus* L. Type collected by L. von Schweinitz at Bethlehem, Pa. Collections in the writer's herbarium from Ohio, New York, West Virginia, and Maryland, and in the herbarium of the New York Botanical Garden from New Jersey, Massachusetts and South Carolina. It is also found in the following exsiccati: Ellis, N. Am. Fungi. 238; Ellis & Ev., Fungi Columb. 339; Ravenel, Fungi Am. 51; Shear, N. Y. Fungi 76; Kellerm., Ohio Fungi 38.

8. UROMYCES ELEOCHARIDIS Arth. on *Eleocharis palustris* (L.) R. & S., sent by Mr. E. Bartholomew from Stockton, Kan., was sown on *Callirrhoe involucrata*, *Napaea dioica*, *Cassia Chamaecrista*, *Myosotis palustris*, and *Silphium perfoliatum*, with no infection.

9. UROMYCES ACUMINATUS Arth. on *Spartina cynosuroides* Willd., obtained at Fair Oaks, Ind. by Mr. F. D. Kern, was sown four times on *Steironema ciliatum*, twice on *S. lanceolatum*, twice on *Lysimachia quadrifolia* L., and once each on *L. terrestris*, *Polygala Senega*, *Napaea dioica* and *Houstonia purpurea*, with no infection. As teliosporic material of this rust, obtained from Nebraska, was sown on *Steironema ciliatum* with success in 1905,⁸

⁷ See Jour. Myc. 12:13. 1906.

⁸ See Jour. Myc. 12:24. 1906.

it would seem that what now passes under one name is either a segregate, or a series of biological species, and that the Uromyces on *Spartina* in Indiana differs in some way from that in Nebraska.

The following species of rusts were successfully grown, and the data supplement that obtained from previous cultures of this series, or that recorded by other American or European investigators.

1. *MELAMPSORA BIGELOWII* Thuem. — Teliosporic material obtained near Lafayette, Ind., on *Salix* sp., was sown April 25 on *Larix decidua*, pycnia appearing in abundance May 2, and fully grown aecia about May 12.⁹

2. *CRONARTIUM QUERCUS* (Brond.) Schroet. — Work with this species was suggested by Dr. C. L. Shear, who also provided freshly gathered aecia on *Pinus virginiana* Mill., sending these a number of times in varying quantity. Dr. Shear made a number of cultures in the open in the spring of 1905, and presented a paper embodying his observations and conclusions¹⁰ at the New Orleans meeting of the American Mycological Society, but which did not appear in print until June, 1906, after all data to be presented here were secured.

Aeciospores from material provided by Dr. Shear was sown May 12 in the greenhouse on three plants of *Quercus alba* and two plants of *Q. velutina*. On May 19 another sowing was made on two other plants of *Q. velutina*. This work coming late in the season did not receive daily examination, but on June 1 all the plants of *Q. velutina* showed uredinia, and one of them also had developed telia. By June 25 the remaining four plants had produced telia. The plants of *Q. alba* remained free from infection.

The aecia used for these cultures were the typical form of *Peridermium Cerebrum* Peck. There seems no reason to doubt the identity of the American, European and Japanese fungus, which has passed under a number of names, but a discussion of the literature and facts will not be taken up in this place.

3. *PUCCINIA OPIZII* Bubák. — Aecia on various wild species of *Lactuca*, and even on the garden *L. sativa*, are common in the extended region of the upper Mississippi valley. They were described by Burrill (Bull. Ill. Lab. Nat. Hist. 2: 232. 1885), but the name *Aecidium compositarum Lactucae* Burr. was first published three years later (Saccardo, Syll. fung. 7: 799. 1888). This form has often appeared in considerable abundance within

⁹For previous cultures see Jour. Myc. 11:60. 1905.

*¹⁰Jour. Myc. 12:89-92. 1906.

a hundred feet of my laboratory door, and much attention has been bestowed upon it. The first clue to its connection was found on the last day of April of this year, when in company with Mr. F. D. Kern, the writer detected at Fair Oaks, Ind., a hundred miles north of this place, in two well separated spots, some plants of *Lactuca canadensis* thickly covered with aecia, and intermixed with the affected leaves some leaves of a small, narrow leaved *Carex*, bearing teliospores of the previous year's growth. No evidence of fruiting could be found on the *Carex*, and roots brought back and grown in pots have shown no signs of fruit, so that the *Carex* has not been specifically determined. Teliosporic material was obtained from both localities, and May 2 one was sown on *Lactuca canadensis* and *Onagra biennis*, the other on *L. virosa* and two plants of *L. canadensis*. *Onagra* showed no infection, but all plants of *Lactuca* gave rise to pycnia May 9, and aecia May 15, in great abundance. Another sowing was made May 14 on *L. sativa*, which gave pycnia May 14, and aecia May 28, with ample development.

This rust is taken to be the same as the one which Dr. Fr. Bubák studied in Bohemia by means of cultures, and which he has very fully described.¹¹ No Bohemian collections, however, are at hand with which to make comparison, but two European collections of aecia (Sydow, Uredineen 334 and 1100) show essential morphological agreement with American aecia on *Lactuca*. Dr. Bubák (l. c.) has stated that to him the American and European collections appear distinct, but without saying wherein the difference may lie. To me the differences appear to be habitual. On thin leaved hosts both pycnia and aecia are in more open and indefinite groups. On hosts from the western prairies, which have firm and strongly developed leaves the groups of aecia are usually compact and circumscribed, and surround the often amphigenous pycnia. The European aecia belonging to the species are known under the name *Accidium lactucinum* Lagerh. & Lindr.

4. PUCCINIA SAMBUCI (Schw.) Arth. — Teliosporic material on *Carex Frankii* Kunth, brought from Frankfort, Ind., by Mr. F. D. Kern, was sown May 10 on *Sambucus canadensis*, giving numerous pycnia May 16, and abundance of aecia May 26. This adds another host to this common species, those already known being *Carex trichocarpa*, *C. lurida*, and *C. lupulina*.¹²

5. PUCCINIA PECKII (DeT.) Kellerm. — Teliosporic material on *Carex trichocarpa* Muhl., brought from Fair Oaks, Ind., was sown on *Onagra biennis* May 4, and gave rise to pycnia May 14, and to aecia May 17, both in abundance. Another collection on *C. lanuginosa* Michx., sent by Rev. J. M. Bates

¹¹ Centr. Bakt. 9:924. 1902.

¹² See Bot. Gaz. 35:14. 1903; Jour. Myc. 8:55. 1902; 12:14. 1906.

from Wymore, Neb., was sown on *Onagra biennis* May 19, giving rise to pycnia May 26, and aecia June 2, both in abundance.¹³

6. *PUCCINIA ALBIPERIDIA* Arth. — This rust on three species of hosts was obtained in different localities near Lafayette, Ind., and sown with the following results:

From *Carex squarrosa* L., sown in greenhouse April 16 on *Ribes rotundifolium*; April 21, pycnia; April 30, aecia.

From *C. squarrosa* L., sown in garden April 21 on *R. gracile*; April 25, pycnia; May 13, aecia.

From *C. squarrosa* L., sown in greenhouse April 16 on *R. rubrum*; no infection.

From *C. tetanica* Schk., sown in greenhouse April 20 on *R. Cynosbati*; April 27, pycnia; May 9, aecia.

From *C. crinita* Lam., sown on *R. Cynosbati* in greenhouse April 26, then plant transferred to garden; May 4, pycnia; May 17, aecia.

These results add one more telial host to those previously used for cultures.¹⁴ They also have given an opportunity for a study of the differences between the pale aecia obtained by cultures and the highly colored aecia usually observed in the field. The aecia grown wholly in the greenhouse were pale, as in previous years; those on the plant which had the pot plunged into the garden soil after the fungus became established, were much more colored; and those raised from sowings made in the garden were highly colored and presented essentially the same appearance as others that came upon some nearby bushes of *Ribes* from natural infection. The result of observations during the last six years, coupled with the cultures of this year, make the conclusion almost inevitable that shade, moist air, and slow growth, tend to make the aecia smaller, with less coloring matter in the peridial cells and surrounding mycelium, and also tend to produce less hypertrophy of the tissues of the host, and that this accounts for the differences observed between aecia grown in cultures and those very common on *Ribes Cynosbati*, *R. rotundifolium*, *R. gracile*, and similar species of gooseberries throughout the eastern United States. All collections of this sort, therefore, may be called *Puccinia albiperidia*, but whether this is a distinct species from the very similar rust of Europe, *Puccinia Grossulariae* (Schum.) Lagerh., or one of the several biological species established by Klebahn, still remains an open question.

7. *PUCCINIA ANGUSTATA* Peck. — Teliosporic material on *Scirpus atrovirens* Muhl., from the vicinity of Lafayette, Ind., was sown April 28, on *Dirca palustris*, with no infection. On

¹³ For previous cultures see Bot. Gaz. 35:13. 1903; Jour. Myc. 8:55. 1902; 11:58. 1905; and 12:15. 1906.

¹⁴ For previous cultures see Jour. Myc. 8:53. 1902; 10:11. 1904; 11:58. 1905; and 12:14. 1906.

May 4 it was sown on *Lycopus Americanus*, giving rise May 14 to numerous pycnia, and May 18 to aecia in abundance.¹⁵

8. PUCCINIA ELEOCHARIDIS Arth. — Teliosporic material on *Eleocharis palustris* (L.) R. & S., sent by Mr. E. Bartholomew from Stockton, Kans., was sown May 7 on *Eupatorium perfoliatum*, giving rise to pycnia May 14, and to aecia May 22. Similar material on same species of host from near Lafayette, Ind., was sown June 1 on *E. perfoliatum*, giving rise to pycnia June 8, and to aecia June 20. It was also sown on *Napaea dioica*, with no infection.¹⁶

9. PUCCINIA ANDROPOGONIS Schw. — Teliosporic material on *Andropogon scoparius* Michx., sent by Rev. J. M. Bates from Sargent, Neb., was sown April 24 on *Pentstemon hirsutus*, giving rise to pycnia April 30, and to aecia May 10, both in abundance.¹⁷

10. PUCCINIA TOMIPARA Trel. — Teliosporic material on *Bromus purgans* L., from Lafayette, Ind., was sown May 19 on *Clematis virginiana*, giving rise to pycnia May 26, and to aecia June 8, both in abundance.¹⁸

11. PUCCINIA SUBNITENS Diet. — Teliosporic material on *Distichlis spicata* (L.) Greene, sent by Rev. J. M. Bates from Red Cloud, Neb., was sown April 5 on *Chenopodium album*, *Bursa bursa-pastoris*, and *Sarcobatus vermiculatus*, giving a weak infection only on the *Chenopodium*. As the *Sarcobatus* plant soon died, another sowing was made May 5 on two other plants of *Sarcobatus*, but with no infection. It was sown again May 10, and May 19, on *Sarcobatus*, still with no infection. Still a fifth sowing was made May 29 on two plants of *Sarcobatus*, and one of *Chenopodium album*, with a weak infection of the latter, and with apparently a few pycnia showing on one leaf of *Sarcobatus*. The plants of *Sarcobatus* were sent by Dr. P. B. Kennedy from Reno, Nev., and had not become established when the sowings were made. They were obtained where *Distichlis spicata* grew intermixed, well covered with *Puccinia subnitens*, and the *Sarcobatus* was well besprinkled with aecia, not distinguishable from those now known to belong to this grass rust.¹⁹ The particular object in view was to determine experimentally if *Puccinia subnitens* will grow on *Sarcobatus*. The single seeming infection is doubtful, as it may have come from spores transported with the plants. The question remains an open one,

¹⁵ For previous cultures see Bot. Gaz. 29:273. 1900; and Jour. Myc. 8:53. 1902.

¹⁶ For previous cultures see Jour. Myc. 12:23. 1906.

¹⁷ For previous cultures see Bot. Gaz. 29:272. 1900; Jour. Myc. 9:10. 1903; and 10:11. 1904.

¹⁸ For previous cultures see Jour. Myc. 11:62. 1905.

¹⁹ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11:54. 1905; 12:16. 1906.

although I venture the opinion that if the teliosporic material had come from Nevada, instead of Nebraska, the sowings would have been successful.

12. *PUCCINIA POCULIFORMIS* (Jacq.) Wettst. — Teliosporic material on *Agrostis alba* L., brought from Fair Oaks, Ind., was sown May 2 on two plants of *Berberis vulgaris*, both showing abundant pycnia May 9, and aecia May 18.

Aeciospores from these cultures were sown May 31 on *Avena sativa*, *Hordeum vulgare* (Great Beardless), and *Triticum vulgare* (Jones' Silver Sheaf), without infection in the first case, and with sparing infection in the other two cases, the former showing uredinia June 12, and the latter somewhat later.

Teliosporic material on *Elymus canadensis* L., sent from Racine, Wis., by Dr. J. J. Davis, was sown May 2 on *Berberis vulgaris*, showing pycnia May 9, and aecia May 18. Aecia from this culture were sown May 31 on *Triticum vulgare* (Jones' Silver Sheaf), and *Secale cereale* (Mammoth Winter Rye), with no infection.²⁰

13. *PUCCINIA TRANSFORMANS* Ellis & Ev. — Teliosporic material from a greenhouse plant of *Stenolobium Stans*, which had been infected a year previously, was sown May 7 on two healthy plants of the same species, and gave rise to pycnia May 22, and to telia May 30. A sowing on two other plants was made May 10, showing pycnia May 26, and telia May 31.²¹

14. *PUCCINIA XANTHII* Schw. — Teliosporic material on *Xanthium* sp., obtained in the vicinity of Lafayette, Ind., about the middle of April, was sown on *Xanthium* seedlings April 20, and gave rise to translucent papillae simulating pycnia April 26, and open telia May 3. Another sowing May 1 gave pale papillae about May 18, and open telia about May 26.²²

15. *PUCCINIA SILPHII* Schw. — Teliosporic material on *Silphium integrifolium* Michx., obtained the last of March near Lafayette, Ind., was sown April 26 on *Silphium perfoliatum*, giving rise to pale papillae May 1, and open telia May 4. Another sowing was made on *S. terebinthinaceum* May 1, giving rise to pale papillae May 8, and open telia May 14. Similar material from another locality was sown May 3 on *S. integrifolium*, *S. perfoliatum* and *S. terebinthinaceum*, giving infection in usual way in each instance but exact data not taken.²³ It was observed that the infection on *S. integrifolium* was more rapid in its growth and more abundant than on the other hosts. In the report of last

²⁰ For previous cultures see Jour. Myc. 8:53. 1902; 11:57. 1905; 12:17. 1906.

²¹ For previous cultures see Jour. Myc. 12:22. 1906.

²² For previous cultures see Jour. Myc. 12:20. 1906.

²³ For previous cultures see Jour. Myc. 12:21. 1906.

year's cultures the opinion was expressed that this rust may be composed of biological races, but the present work shows that adaptation to the hosts is not so close but that under specially favorable conditions the rust may be transferred from one host to another.

16. PUCCINIA PRUNI-SPINOSAE Pers.—Aecia on *Hepatica acutiloba* DC., from near Lafayette, Ind., were sown April 28 on *Prunus serotina* and *Amygdalus Persica*, giving rise May 21 to uredinia on the former host, but with no infection on the latter host. Like material was sown May 2 on *Prunus serotina* and *P. pumila*, giving rise to the uredinia in both instances May 21. These results abundantly confirm, and somewhat extend, the work of last year.²⁴

17. UROMYCES SCIRPI (Cast.) Burr.—Teliosporic material on *Scirpus fluviatilis* (Torr.) A. Gray, sent by Rev. J. M. Bates from Walbach, Neb., was sown May 22 on *Cicuta maculata*, giving abundance of pycnia May 31, and of aecia June 8. A sowing made June 1 on *Pastinaca sativa*, the plants being especially thrifty, gave no infection. On June 5 another sowing was made on *Oxypolis rigidus* and *Cicuta maculata*, with no infection on the former, but with fine showing of pycnia on the latter June 12, and of aecia June 22.

There is apparently no morphological difference between the American rust and the corresponding European one, and the hosts are also much alike. Sixteen years ago Dr. P. Dietel showed by cultures²⁵ that in central Germany aecia are produced on *Sium latifolium*, which in habit and structure is much like *Cicuta maculata*. He also found that, most curiously, aecia could be grown from the same material on *Hippurus vulgaris*, which belongs to another family of plants, showing that, in all probability, the species is not closely circumscribed.

Cultures made by Dr. Fr. Bubák in 1901 from Bohemian material brought to light a biological form which only infected *Berula angustifolia*.²⁶

In 1902 Dr. H. Klebahn attempted to repeat Dietel's cultures, and found that teliosporic material from the same immediate region, the exact locality having been changed and the rust destroyed, gave abundant aecia on *Pastinaca sativa*, but only slightly infected *Hippurus vulgaris*, and infected *Sium latifolium* and *Glaux maritima* not at all.²⁷ The year following he carried out more extensive cultures. Teliosporic material raised from aeciospores on *Pastinaca sativa*, infected both *Pastinaca* and *Berula angustifolia*. Teliosporic material from central Germany

²⁴ See Jour. Myc. 12:19. 1906.

²⁵ Hedwigia 29:149. 1890.

²⁶ Centr. Bakt. 9:26. 1902.

²⁷ Jahrb. Hamb. Wiss. Anst. 20:33. 1903.

infected both these hosts. Similar material from northern Germany infected only *Berula*. In 1904 aecia were raised in a similar way on *Oenanthe aquatica*.²⁸

One of the earliest cultures with this pleophagic species was made by Mr. C. B. Plowright with English material, raising aecia on *Glaux maritima*, which belongs to the *Primulaceae*.²⁹

A careful microscopic study of all these forms shows close agreement in morphological characters, and altogether there appears to be no reason to treat these cultural forms other than biological races of a single species. *Scirpus fluviatilis* is the American representative of the European *S. maritimus*, and by many authors is given the latter name. The writer has examined American collections that appear to belong to this species, as follows: on *S. fluviatilis* from Iowa, Illinois, Kansas, Nebraska, South Dakota, Ohio, and Wisconsin; on *Cicuta maculata* from Illinois, Iowa, and Colorado; on *Oenanthe californica* from central California, *Sium cicutaefolium* from Wisconsin, and on *Glaux maritima* from Montana and Wyoming.

18. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw.—Galls from a tree of *Juniperus virginiana* near the laboratory, brought in by Mr. F. D. Kern, were used for sowing May 1 on *Malus coronaria*, *Sorbus americana*, and *Crataegus Pringlei*. Only the first gave infection, which showed abundant pycnia on May 14, but failed to develop aecia on account of injuries.²⁵

19. GYMNOSPORANGIUM GLOBOSUM Farl.—Galls from a tree of *Juniperus virginiana*, found in the vicinity of Lafayette, Ind., were brought in by Mr. Guy W. Wilson, and used for making three sowings on *Crataegus Pringlei*, and one each on *Malus coronaria* and *Amelanchier* sp. All sowings on *Crataegus* gave abundance of pycnia, and one plant finally produced well formed aecia, the other plants not growing well. No infection was obtained on the other two hosts.

Similar material was also received from Dr. John A. Sheldon, of Morgantown, W. Va., and sown May 19 on *Crataegus Pringlei*, *Malus coronaria*, and *Sorbus americana*, all giving rise to an abundance of pycnia. As none of the plants grew well, only the sowing on *Sorbus* formed aecia, these finally reaching maturity and showing the characteristic structure of the species.

These results are parallel with, and confirm the work by Dr. Roland Thaxter, done some years ago.²⁶

²⁸ Ztschr. Pfl.-Kr. 15:74. 1905.

²⁹ Gard. Chron. III. 7:682. 1890.

²⁵ For previous cultures see Jour. Myc. 12:13. 1906.

²⁶ Proc. Amer. Acad. Sci. 22:263. 1887; Bot. Gaz. 14:167. 1889.

The following three species have never before been tested by means of cultures, so far as the writer knows. Although few in number, they make an important addition to our knowledge of life histories:

I. MELAMPSORA LINI (Link) Desmaz.—For a number of years attempts have been made to obtain cultures of this cosmopolitan rust, and learn its full cycle of development. Many collections from different parts of the country, gathered at different times from November to April, have been tested, but with uniform failure to secure germination of the teliospores. The most numerous and promising collections were sent by Professor H. L. Bolley, of North Dakota, but equally in vain until one made the last day of April on cultivated flax, dug from under a snow bank, was received. This showed strong germination of the teliospores, and on May 4 was sown on *Linum Lewisii*, *Larix laricina*, and the day following on *Tsuga canadensis*, and *Arisaema triphyllum*. No clues were available, but judging from the willow, poplar, and some other species of the same genus, it was assumed that it might be heteroecious. Nevertheless, on May 16 pycnia began to appear on the flax, and on May 21 aecia. The next sowing was made May 18 on *Linum usitatissimum*, plants of which had not before been available, giving rise to pycnia May 26, and aecia May 30. Another equally successful sowing on the same host was made May 29, but exact record for the appearance of the sori was not kept.

The pycnia are small, pale, and inconspicuous, although numerous. They are globose, subepidermal, and without ostiolar filaments. The aecia are of the caecoma form, that is, are without peridia. They are also rather pale, and not as prominent as the uredinia, for which, however, they might easily be mistaken. So far as I can learn they have never been collected, although probably common throughout the world. This may be due to their being inconspicuous, and quite as much to the earliness of their appearance.

The economic bearing of the discovery is to some extent obvious. Knowing the autoecious nature of the rust makes the destruction of old flax straw in flax growing regions a matter of moment, in order to lessen and retard the appearance of the rust in growing fields of flax. Upon reporting the first success to Professor Bolley he replied under date of May 23, 1906: "I am very much pleased to receive your letter, for with the information I am able to determine the source of a rust epidemic that we had in our flax breeding plots last year. I now find everywhere in the flax stubble plenty of volunteer flax with almost every plant more or less infected with spermogonia and aecidia." It will now be possible to intelligently devise methods for the practical control of flax rust.

2. *UROMYCES* ON *JUNCUS TENUIS*.—This rust, which has generally passed under the name of *Uromyces Junci*, is very common in the United States east of the Rocky Mountains from Canada to the Gulf of Mexico. It is often highly parasitized, so that the sori contain few or no well grown teliospores. A number of attempts to bring the rust under culture have failed because the teliospores could not be made to germinate. In 1902 a sowing was made on *Iris versicolor* without success.

Unparasitized material on *Juncus tenuis* Willd. was found near Lafayette, Ind., April 3, that proved to be viable, and was sown April 20 on *Lactuca canadensis*, *L. virosa*, *Senecio obovatus*, *Rudbeckia laciniata*, *Ambrosia trifida*, *A. artemisiaefolia*, and *Silphium perfoliatum*. Much to our delight pycnia were observed on the last host April 30, and were followed by a great abundance of aecia May 7. Another sowing was made May 4 on *S. perfoliatum* and *S. terebinthinaceum*, and the next day on *Parthenium integrifolium*. Only the first was infected, showing pycnia May 17, and May 31. The plant of *S. terebinthinaceum* was weak and did not grow well. Later sowings May 9 on *Polymnia canadensis*, and June 5 on *Parthenium integrifolium* and *Silphium terebinthinaceum*, gave no infection.

Another collection of teliospores on *Juncus tenuis* was sent by Dr. John L. Sheldon from Morgantown, W. Va., which was found close to *Houstonia caerulea* bearing aecia. This material was sown May 19 on *Houstonia caerulea*, *H. purpurea* and *Silphium perfoliatum*. No infection occurred on the *Houstonias*, but pycnia appeared on the *Silphium* May 29, and aecia June 4, both abundant and well formed.

Since obtaining the unequivocal cultural results, a morphological study has been made of the rust, which clearly demonstrates that it is specifically distinct from *Uromyces Junci* (Desm.) Tul. As it appears never to have been recognized as an autonomous species, the following name and description are submitted:

***Uromyces Silphii* (Syd.) nom. nov.** (*Accidium compositarium Silphii* Burr. Saccardo, Syll. Fung. 7:798. 1888; *Aecidium Silphii* Sydow, Uredineen 1546.)

O. Pycnia chiefly epiphyllous, in small groups, golden brown, subglobose or ellipsoid, subepidermal, 80-100 μ broad by 80-110 μ high; ostiolar filaments up to 65 μ long.

I. Aecia amphigenous, in groups 4-10 mm. across, crowded about the pycnia on discolored spots, deep-seated, short, 0.2-0.4 mm. in diameter; peridium colorless, margin recurved, lacerate, peridial cells rhombic, 20-28 μ across, outer wall thick, 6-8 μ , transversely striate, inner wall thinner, 4-6 μ , moderately verrucose; aeciospores angularly globoid, small, 13-18 μ in diameter, wall colorless, thin, about 1 μ , minutely verrucose.

On *Silphium integrifolium* Michx., Illinois (type, McLean County, May 3, 1881 or 1882, *A. B. Seymour 4852*, recorded in Burrill's Parasitic Fungi of Illinois, page 231), Wisconsin; *S. terebinthinaceum* Jacq., Illi-

nois, Wisconsin, Missouri; *S. perfoliatum* L., Indiana, Iowa, Wisconsin; *S. laciniatum* L., Illinois, Iowa, Kansas.

II. Uredinia amphigenous, scattered, roundish or somewhat elongated, small, 0.2-0.3 mm. wide, by 0.3-0.5 mm. long, tardily naked, dark cinnamon-brown, ruptured epidermis not conspicuous; urediniospores broadly ellipsoid or sometimes obovate, 13-19 by 15-23 μ , wall golden yellow, about 1.5 μ thick, sparsely and bluntly echinulate, pores 5 or 6, scattered.

III. Telia amphigenous, scattered, roundish or somewhat elongated, small, 0.2-0.3 mm. wide by 0.2-0.6 mm. long, tardily naked, firm, somewhat pulvinate, blackish brown, ruptured epidermis noticeable; teliospores angularly obovate, rounded, truncate or occasionally pointed above, usually narrowed below, 12-19 by 26-35 μ , wall chestnut-brown, 1.5-2 μ thick, much thicker above, 7-10 μ , smooth; pedicel light chestnut-brown, one to one and a half times length of spore.

On *Juncus tenuis* Willd., Indiana, Iowa, Wisconsin, Michigan, Minnesota, South Dakota, Missouri, New York, Maine, Massachusetts, West Virginia, Louisiana, Texas; *J. dichotomus* Ell., Florida.

It has been issued in the following exsiccati: aecial stage—Ellis & Ev. Fungi Columb. 1478; Sydow, Ured. 1546; telial stage—Seym. & Earle, Econ. Fungi 52, 528; Griffiths, W. Am. Fungi 244 (host *J. tenuis* not *J. longistylis*); Ellis & Ev. Fungi. Columb. 2394.

The following key will serve to separate the three common species of Uromyces on *Juncus*, when the urediniospores are present. In the absence of uredinia the urediniospores can usually be found to some extent in telial sori, even those that have withstood the winter, and are collected in the spring following their maturity, and especially so if they are parasitized.

Urediniospores verrucose, pores 2, equatorial.....*U. Junci* (Desm.) Tul.
Urediniospores echinulate, pores 4, equatorial.....*U. effusus* Arth.
Urediniospores echinulate, pores 5-6, scattered....*U. Silphii* (Syd.) Arth.

3. GYMNOSPORANGIUM NELSONI Arth. — At the time this species was published it was stated that Prof. Aven Nelson, the collector of the type material, considered it highly probable that the aecia found on *Amelanchier* in the vicinity belonged to the species. Teliosporic material on *Juniperus scopulorum* Sarg., sent by Mr. E. Bethel from Colorado this spring, gave the first opportunity to test the suggestion. Sowings were made May 29 on the leaves of *Amelanchier canadensis*, *Sorbus americana*, *Crataegus Pringlei*, *Pyrus japonica*, and *Aronia nigra*. On June 12 a few pycnia were observed on the *Amelanchier* and *Sorbus*, but owing doubtless to indifferent growth of the hosts no aecia were formed. The other hosts remained without infection. This helps in a small way to confirm Professor Nelson's suggestion, but is not conclusive.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1906. It is divided into two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A. Species previously reported.

1. MELAMPSORA BIGELOWII Thuem. — Teliospores on *Salix* sp. sown on *Larix decidua* Mill.
2. CRONARTIUM QUERCUS (Brond.) Schroet. — Aeciospores on *Pinus virginiana* Mill. sown on *Quercus velutina* Lam.
3. PUCCINIA OPIZII Bubák. — Teliospores on *Carex* sp. sown on *Lactuca canadensis* L., *L. virosa* L. and *L. sativa* L.
4. PUCCINIA SAMBUCI (Schw.) Arth. — Teliospores on *Carex Frankii* Kunth sown on *Sambucus canadensis* L.
5. PUCCINIA PECKII (DeT.) Kellerm. — Teliospores on *Carex trichocarpa* Muhl., and also on *C. lanuginosa* Michx., sown on *Onagra biennis* (L.) Scop.
6. PUCCINIA ALBIPERIDIA Arth. — Teliospores on *Carex squarrosa* L., *C. tetanica* Schk., and *C. crinita* Lam. sown on *Ribes rotundifolium* Michx., *R. gracile* Michx. and *R. cynosbati* L.
7. PUCCINIA ANGUSTATA Peck. — Teliospores on *Scirpus atrovirens* Muhl. sown on *Lycopus americanus* Muhl.
8. PUCCINIA ELEOCHARIDIS Arth. — Teliospores on *Eleocharis palustris* (L.) R. & S. sown on *Eupatorium perfoliatum* L.
9. PUCCINIA ANDROPOGONIS Schw. — Teliospores on *Andropogon scoparius* Michx. sown on *Pentstemon hirsutus* (L.) Willd.
10. PUCCINIA TOMIPARA Trel. — Teliospores on *Bromus purgans* L. sown on *Clematis virginiana* L.
11. PUCCINIA SUBNITENS Diet. — Teliospores on *Distichlis spicata* (L.) Greene sown on *Chenopodium album* L.
12. PUCCINIA POCULIFORMIS (Jacq.) Wettst. — Teliospores on *Agrostis alba* L. and on *Elymus canadensis* L. sown on *Berberis vulgaris* L., and aeciospores from *B. vulgaris* L. sown on *Hordeum vulgare* L. and *Triticum vulgare* Vill.
13. PUCCINIA TRANSFORMANS Ellis & Ev. — Teliospores on *Stenolobium Stans* (L.) Don sown on same host.
14. PUCCINIA XANTHII Schw. — Teliospores on *Xanthium* sp. sown on same host.
15. PUCCINIA SILPHII Schw. — Teliospores on *Silphium integrifolium* Michx. sown on *S. integrifolium* Michx., *S. perfoliatum* L., and *S. terebinthinaceum* Jacq.
16. PUCCINIA PRUNI-SPINOSAE Pers. — Aeciospores on *Hepatica acutiloba* DC. sown on *Prunus serotina* Ehrh. and *P. pumila* L.
17. UROMYCES SCIRPI (Cast.) Burr. — Teliospores on *Scirpus fluviatilis* (Torr.) A. Gray sown on *Cicuta maculata* L.

18. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw. — Teliospores on *Juniperus virginiana* L. sown on *Malus coronaria* (L.) Mill.

19. GYMNOSPORANGIUM GLOBOSUM Farl. — Teliospores on *Juniperus virginiana* L. sown on *Crataegus Pringlei* Sarg., *Sorbus americana* Marsh., and *Malus coronaria* (L.) Mill.


B. Species reported now for the first time.

1. MELAMPSORA LINI (Link) Desmaz. — Teliospores on *Linum usitatissimum* L. sown on *L. Lewisii* Pursh and *L. usitatissimum* L.

2. UROMYCES SILPHII (Syd.) Arth. — Teliospores on *Juncus tenuis* Willd. sown on *Silphium perfoliatum* L.

3. GYMNOSPORANGIUM NELSONI Arth. — Teliospores on *Juniperus scopulorum* Sarg. sown on *Amelanchier canadensis* (L.) Medic. and *Sorbus americana* Marsh.

Distributed September 12, 1907.





Reprinted from the *Journal of Mycology*, 14: 7-26, January, 1907.

CULTURES OF UREDINEAE IN 1907.¹

BY J. C. ARTHUR.

The present article forms the eighth of a series of reports² by the author upon the culture of plant rusts, covering the years 1899 to the close of 1907. The grass and sedge rusts form a prominent part of the year's work, the same as in previous seasons, but it has been possible to include also some very interesting studies of a number of species of *Gymnosporangium*. This was chiefly brought about by two excursions made by my colleague, Mr. F. D. Kern, and myself for the express purpose of securing this sort of culture material, and for making observations regarding probable alternate hosts. The first trip was to Lake Forest, Ill., on April 6, where we secured *G. clavipes*, *G. clava-riæforme* and *G. nidus-avis* in the locality where the last two were obtained by Dr. R. A. Harper for the distribution in Ellis & Everhart's *North American Fungi* and *Fungi Columbiani*. Explicit directions were given us by Dr. Harper to enable us to

¹ Read before the Botanical Society of America at the Chicago meeting, December, 1907.

² See *Bot. Gaz.* 29:268-276, 35:10-23; *Jour. Myc.* 8:51-56, 10:8-21, 11:50-67, 12:11-27 and 13:189-205.

go to the right spots. The second trip was to Colorado where collections were made April 27 at Boulder, May 1 at Glenwood Springs and May 2 at Wolcott. Unusual success attended this search for material, due in large part to the solicitous assistance of Mr. E. Bethel, of Denver, President of the Colorado Academy of Science, who accompanied us to Boulder, and gave detailed directions for finding infested trees at the other places. Mr. Bethel's intimate knowledge of the localities, and his own extensive observations upon these and other rusts of Colorado, all being placed at our disposal, made the few days of our stay in the state remarkably rich in results. The species of *Gymnosporangium* and *Roestelia* obtained upon this trip were found upon subsequent study to be in part quite distinct from the well known species to which they have heretofore been referred, and in part entirely new discoveries. These forms have recently been named and characterized by Mr. Kern,³ and two of the species, *G. Betheli* and *G. inconspicuum*, have been successfully cultivated.

For the third time the Botanical Society of America generously made a grant to forward this series of studies. This year it was sufficient to pay in large part for the assistance needed in testing the viability of spores, making the sowings, and recording the results, the balance being supplied by the Indiana Experiment Station.

The work was done by Mr. Frank Vasku, a senior student of the University of Iowa, recommended by Professor T. H. MacBride. Like the two previous men from the Botanical Department of the University of Iowa, who have assisted in this work, Mr. Fred. J. Seaver in 1903 and Mr. F. D. Kern in 1904, Mr. Vasku showed exceptional skill in conducting this class of work. His quick understanding of the problems, careful and accurate manipulation, and untiring devotion, were large factors in determining the amount and value of the season's results. Most of the sowings of *Gymnosporangium* spores were made by Mr. Kern, who took an especial interest in this part of the work, as it bore upon the subject of a thesis in preparation for the master's degree.

In order to study as many species as possible from a wide range of localities, and in this way to investigate the North American rust flora as a whole, it is necessary to depend upon the good will and generosity of contributors for much of the culture material and for hints regarding probable alternation of hosts. Those who have aided the work this year are Rev. J. M. Bates, Red Cloud, Neb., leading with 30 collections of culture material, and Messrs. E. Bethel, Denver, Colo., W. A. Kellerman, Columbus, Ohio, J. Dearness, London, Ont., C. W. Edgerton, Ithaca, N. Y., A. O. Garrett, Salt Lake City, Utah, H.

³ Bulletin Torrey Club 34:459-463. 1907.

D. House, Clemson College, S. C., J. J. Davis, Racine, Wis., T. D. A. Cockerell, Boulder, Colo., D. Reddick, Ithaca, N. Y., R. J. Pool, Lincoln, Neb., E. W. Olive, Madison, Wis., F. L. Stevens, West Raleigh, N. C., C. F. Baker, Santiago de la Vegas, Cuba, and Geo. W. Carver, Tuskegee, Ala. Host plants suitable to grow in pots and be used for inoculation were contributed by C. S. Sargent, Jamaica Plains, Mass., E. Bethel, Denver, Colo., and J. J. Davis, Racine, Wis. For these favors, and for the hearty co-operation of the above and other correspondents most grateful acknowledgment is here extended.

During the present season 98 collections of material with resting spores and 20 collections with active spores were employed, from which 438 drop cultures were made to test the germinating condition of the spores. Out of the 98 collections with resting spores 29 could not be brought to germination, although seemingly in perfectly healthy condition. This left 68 collections of available material, with which the cultures were made. These 68 collections belonged to 47 species of rusts, a considerable part, however, being forms whose life cycle had already been ascertained, the sowings being made for purposes of verification or extending the range of hosts. Beside these collections of resting spores sowings were made of nine species of *Gymnosporangium*, and of a few species of *Coleosporium*, *Aecidium* and *Peridermium*. Altogether 296 sowings were made, employing for the purpose 113 species of hosts, and more than two and a half times that number of individual plants, all grown temporarily in pots, so that the work could be done in the greenhouse under perfect control. In a few cases where small potted plants were not available cuttings were used, being kept alive by frequently changing the water in which they were thrust, and successively cutting off a bit of the stem to give fresh absorbing surface. The results of this work are given in the following paragraphs, and are divided into negative results, positive results with species whose life cycles have already been ascertained by the writer or other investigators, and positive results with species whose life cycles are now first placed on record.

Of the trials giving negative results the following may be recorded to serve for reference in future studies:

1. PUCCINIA on *Carex Pennsylvanica* Lam., collected at Sargent, Neb., by Rev. J. M. Bates, was sown on *Aesculus glabra*, *Napaea dioica*, and *Symphoricarpus racemosus*. Another collection made near Lafayette, Ind., by Mr. Frank Vasku, was sown on *Anemonella thalictroides*, *Ranunculus septentrionalis*, *Solidago Canadensis*, *Viola striata*, and *Trillium recurvatum*.

Still a third collection made at Boulder, Colo., by the writer, was sown on *Hydrophyllum capitatum*, *Lactuca Canadensis*, *Iris versicolor*, *Phryma leptostachya*, *Artemisia serrata*, and *A. dracunculoides*. None of these sowings gave infection. Similar material had been tried on five of these hosts before, and on twenty-nine other species, all with negative results.⁴ The rust on this host is common in the northern states east of the Rocky mountains, and appears from its morphological characters to be distinct from any described form. Fifty-five sowings have now been made, beginning in 1903, using forty-three species of hosts, and as no inoculation has been effected, the necessity for careful field observations to detect the probable alternate host becomes highly imperative in order to determine the real life cycle.

2. PUCCINIA on *Carex grvida* Bailey, sent twice by Rev. J. M. Bates, first from St. Paul, Neb., was sown on *Aesculus glabra*, *Viola cucullata*, *Ribes Cynosbati*, and *Hydrophyllum Virginicum*, and second from Red Cloud, Neb., was sown on *Hypoxis erecta*, *Houstonia purpurea*, *Laciniaria spicata*, *Lactuca Canadensis*, and *Artemisia dracunculoides*, with no infection. Similar material from the same region has been sown in previous years upon thirty-four other species of hosts with negative results.⁵

3. PUCCINIA on *Carex Douglasii* Boott. collected at Valentine, Neb., by Rev. J. M. Bates, was sown on *Symphoricarpus racemosus*, *Napaea dioica*, *Psoralea Onobrychis*, *Aesculus glabra*, *Laciniaria spicata*, *Hypoxis erecta*, and *Flacata comosa*, with no infection.

4. PUCCINIA ELLISIANA Thuem., on *Andropogon scoparius* Michx., collected at Boulder, Colo., by Mr. E. Bethel, was sown on *Arabis* sp., *Thalictrum dioicum*, *Actaea alba*, *Psoralea Onobrychis*, *Polygala Senega*, *Viola striata*, *Polemonium reptans*, *Solidago Canadensis*, *Boltonia asteroides*, *Senecio obovatus*, *Lepachys pinnata*, and *Smilacina stellata*, with no infection.

5. PUCCINIA VIRGATA Ellis & Ev., on *Chrysopogon avenaceus* (Michx.) Benth., collected at Grand Island, Neb., by Rev. J. M. Bates, was sown on *Ceanothus Americana*, *Napaea dioica*, *Caulophyllum thalictroides*, and *Cassia Chamaecrista*, with no infection.

⁴ See Jour. Myc. 10:10. 1904; 11:51. 1905; 12:12. 1906; and 13:191. 1907.

⁵ See Jour. Myc. 10:10. 1904 11:52. 1905; and 13:191. 1907.

6. PUCCINIA EMACULATA Schw., on *Panicum capillare* L., collected in the vicinity of Lafayette, Ind., by Mr. F. D. Kern, was sown on *Psoralea Onobrychis*, *Viola cucullata*, and *Myosotis palustris*, with no infection. This rust was sown in previous seasons on twenty other species of hosts.⁶

7. PUCCINIA ARUNDINARIAE Schw., on *Arundinaria macrosperma* Michx., collected at Clemson College, S. C., by Mr. H. D. House, was sown on *Myrica cerifera*, *Ilex opaca*, *Smilax hispida*, and *Lysimachia quadrifolia*, with no infection.

8. PUCCINIA SCHEDONNARDI K. & S., on *Schedonnardus paniculatus* (Nutt.) Trel., collected at Boulder, Colo., by Mr. E. Bethel, was sown on *Napaea dioica*, *Sorbus Americana*, *Xanthoxylum Americanum*, *Falcata comosa*, *Triosteum perfoliatum*, *Laciniaria spicata*, and *Aster paniculatus*, with no infection. Like material was sown in previous seasons on eleven other species of hosts.⁷

9. PUCCINIA on *Muhlenbergia tenuiflora* (Willd.) B. S. P., collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown on *Aesculus glabra*, *Lepachys pinnata*, *Napaea dioica*, *Hibiscus Moscheutos*, *Symphoricarpos racemosus*, with no infection.

10. PUCCINIA CRANDALLII Pam. & Hume, on *Festuca confinis* Vasey, collected at Boulder, Colo., by Mr. E. Bethel, was sown on *Draba Caroliniana*, *Bursa Bursa-pastoris*, *Cardamine bulbosa*, *Hydrophyllum Virginicum*, *Mertensia Virginica*, and *Cassia Chamaecrista*, with no infection.

11. PUCCINIA MONTANENSIS Ellis, on *Elymus condensatus* Presl., collected at Glenwood Springs, Colo., by Mr. F. D. Kern and the writer, was sown on *Delphinium tricornis* three times, with no infection. This material was found intermixed with plants of *Delphinium*, species undetermined, but not *D. tricornis*, which exhibited a very abundant development of *Aecidium Delphinii* Barth., and it was assumed that the two forms were alternates. Although the relationship was not established by the attempted culture, yet it cannot be said to be absolutely disproved, as the species of *Delphinium* on which the *Aecidium* occurred was not used.

Another collection of apparently the same species of rust found on *Elymus brachystachys* Scribn. & Ball, at Eldorado Springs, Colo., by the same collectors, was sown on *Delphinium tricornis*, with no infection.

⁶ See Bot. Gaz. 35:12. 1903; Jour. Myc. 8:52. 1902; 10:10. 1904; 12:12. 1906; and 13:192. 1907.

⁷ See Bot. Gaz. 35:11. 1903 and Jour. Myc. 13:192. 1907.

12. PUCCINIA on *Poa longiligula* Scribn. & Will., collected at Boulder, Colo., by Mr. E. Bethel, was sown twice on *Arabis* sp., with no infection. This rust was found so closely associated with aecia on a species of *Arabis*, that it seemed almost certainly to be genetically connected. Healthy plants of apparently the same species of *Arabis* were secured from Colorado, and sowings made, the spores giving strong germination, but without positive results. The grass host was determined by Mr. P. L. Ricker of the U. S. Department of Agriculture.

13. PUCCINIA on *Eriocoma cuspidata* Nutt. (*Oryzopsis cuspidata* Benth.), collected at Glenwood Springs, Colo., by Mr. F. D. Kern and the writer, was sown on *Phacelia bipinnatifida*, *Hypoxis crecta*, *Symphoricarpos racemosus*, *Mertensia* sp. (from Colorado), *Triosteum perfoliatum*, *Aquilegia coerulea*, *Thalictrum polygamum*, *Amelanchier Canadensis*, *Hydrophyllum Virginicum*, *Solidago Canadensis*, *Laciniaria spicata*, *Ranunculus recurvatus*, *Cassia Chamaecrista*, and *Psoralea Onobrychis*, with no infection.

14. PUCCINIA on *Agropyron repens* (L.) Beauv., collected in Kenosha county, Wis., by Dr. J. J. Davis, was sown on *Polymnia Canadensis* and *Hydrophyllum Virginicum*, with no infection. This is a leaf rust having close resemblance to *Puccinia rubigo-vera* on cereals.

15. UROMYCES RHYNOSPORA Ellis, on *Rhynchospora alba* (L.) Vahl., collected at London, Ont., by Mr. J. Dearness, was sown on *Menyanthes trifoliata* and *Decodon verticillatus*, with no infection.

16. UROMYCES JUNCII (Desm.) Tul., on *Juncus Balticus* Willd., collected at Scotia, Neb., by Rev. J. M. Bates, was sown on *Aesculus glabra*, *Symphoricarpos racemosus*, *Napaea dioica*, *Silphium perfoliatum*, *Ranunculus recurvatus*, *Psoralea Onobrychis*, *Polygala Senega*, *Viola cucullata*, *Apocynum cannabinum*, *Polemonium reptans*, *Ambrosia trifida*, *Senecio obovatus*, *Dirca palustris*, *Decodon verticillatus*, and *Bidens frondosa*, with no infection. This rust appears to be morphologically identical with the European *Uromyces Juncii*, which has aecia upon *Pulicaria dysinterica*, a host that was not at hand when sowings were being made. It is clearly distinct from the rust on *Juncus tenuis*, *Uromyces Silphii* (Syd.) Arth., not only on account of its structure, but because it refuses to grow on *Silphium*.

17. UROMYCES OROBI (Pers.) Lev., on *Lathyrus decapetalus* Pursh, collected at Boulder, Colo., by Prof. T. D. A. Cockerell, was sown on *Lathyrus palustris* and *Euphorbia Arkaniana Coloradensis*, with no infection. This rust is believed to be an autoecious species, and the failure to infect *Lathyrus* is not readily explained.

The following species of rusts were successfully grown, and the data supplement that obtained from previous cultures of this series, or that recorded by other American or European investigators. The results with *Gymnosporangium* are the most considerable since the work done by Dr. Roland Thaxter, concluded at the Connecticut Experiment Station in 1890.

1. PUCCINIA ALBIPERIDIA Arth.—Teliosporic material on *Carex crinita* Lam., collected in the vicinity of Lafayette, Ind., by Mr. F. D. Kern, was sown on two plants of *Ribes Cynosbati* on April 16, giving rise to pycnia April 25, and aecia May 6 in one case, and in the other to pycnia April 29, and aecia May 14.⁸

2. PUCCINIA CARICIS-ASTERIS Arth.—Teliosporic material on a narrow leaved *Carex*, collected at Ithaca, N. Y. by Mr. C. W. Edgerton, was sown May 8 on *Aster paniculatus*, *Iris versicolor*, *Ribes Cynosbati*, and *Solidago Canadensis*, with infection only on the first named host, showing pycnia May 16, and aecia May 24. The collection was made adjacent to a clump of *Iris versicolor*, covered with aecia, and there was a possibility of genetic connection, which the culture dispels.

The 24th fascicle of Fungi Columbiani contained a specimen (No. 2366) of *Carex* rust labelled *Puccinia tenuistipes* Rostr., and collected as late as November, 1906, at London, Ont. As this species of rust has its aecia on *Centaurea Jacea*, according to a culture made by Schröter in 1885, and as that host is only occasionally found in North America along the seacoast, and no aecia having been seen on it in these localities, I wrote to Mr. J. Dearness, the collector, for further information and material. He most kindly secured viable material for me from the identical locality. This was sown May 15 on *Ribes Cynosbati*, *Aster cordifolius*, and *Solidago Canadensis*, with no infection. It was sown again May 25 on *Aster cordifolius* and *Erigeron annuus*, this time with the production of a few pycnia by June 10 on the Aster, but without formation of aecia. Still a third essay was made by sowing June 5 on *Aster paniculatus*, followed by an abundance of pycnia June 12, and aecia June 19, thus establishing the identity of the rust.

In visiting the locality in the spring of 1907, Mr. Dearness discovered that the host is not *Carex varia*, as published, but *C. rosea* Schk., and he has forwarded ample material to verify the determination.

In justification for the use of the name applied to the rust, Mr. Dearness writes, under date of June 22, 1907, that a collection was sent to the late Mr. J. B. Ellis in September, 1889,

⁸For previous cultures see Jour. Myc. 8:53. 1902; 10:11. 1904; 11:58. 1905; 12:14. 1906; 13:196. 1907.

who thought it might be a new species and drew up a description. Not long afterward Mr. Ellis sent his notes and material to Dr. Rostrup, of Copenhagen, Denmark, who pronounced it to be *P. tenuistipes* Rostr., by which name it has since been called.⁹

3. PUCCINIA CARICIS (Schum.) Reb.—Teliosporic material on *Carex stipata* Muhl. from the vicinity of Lafayette, Ind., brought in by Mr. Frank Vasku, was sown on *Urtica gracilis* April 19, giving rise to pycnia April 27, and aecia May 2; while a similar collection brought in by Mr. F. D. Kern, and sown April 20, gave rise to pycnia April 27, and aecia May 1.

Teliosporic material on *Carex riparia* Curt., collected in November, 1906, at Scotia Junction, Neb., by Rev. J. M. Bates, was sown April 13, on *Ribes floridum* and *R. rubrum*, with no infection. Another sowing was made April 19 on *Urtica gracilis*, giving rise to abundant pycnia April 26, and aecia May 1. A second collection from the same region, taken in March, 1907, was sown April 4 on *Ribes floridum*, with no infection; and again April 19, on *Urtica gracilis*, giving rise, as in the former case, to abundant pycnia April 26, and aecia May 2. Similar material on *Carex riparia* from Iowa gave the same results in 1902.¹⁰

4. PUCCINIA ANGUSTATA Peck.—Teliosporic material on *Scirpus atrovirens* Muhl., from the vicinity of Lafayette, Ind., brought in by Mr. Frank Vasku, was sown on *Lycopus Americanus* April 22, giving rise to pycnia April 29, and aecia May 7.¹¹

5. PUCCINIA FRAXINATA (Schw.) Arth.—A collection made in November, 1906, on *Spartina cynosuroides* Willd., at Red Cloud, Neb., by Rev. J. M. Bates, was sown on *Fraxinus lanceolata* May 11, giving rise to pycnia May 18. The same collector sent similar material from Grand Island, Neb., in March, 1907, which was sown on *Fraxinus lanceolata* May 25, giving rise to pycnia May 30, and aecia June 13. A like collection taken in April, 1907, similarly sown May 8, gave pycnia May 17. These sowings were all made on cut branches placed in water, which accounts for the slow development and early termination of growth.¹²

⁹ For previous cultures see Jour. Myc. 8:54. 1902; Bot. Gaz. 35:15. 1903.

¹⁰ For previous cultures see Bot. Gaz. 20:270. 1900; 35:16. 1903; Jour. Myc. 8:52. 1902; 12:15. 1906.

¹¹ For previous cultures see Bot. Gaz. 29:273. 1900; Jour. Myc. 8:53. 1902; and 13:196. 1907.

¹² For previous cultures see Bot. Gaz. 29:275. 1900; Jour. Myc. 11:57. 1905; and 12:16. 1906.

6. PUCCINIA SUBNITENS Diet.—Teliosporic material on *Distichlis spicata* (L.) Greene was sent by Rev. J. M. Bates, from Red Cloud, Neb., and sown as follows:

April 10 on *Chenopodium album*; April 19, pycnia; April 23, aecia.
April 10 on *Bursa Bursa-pastoris*; April 26, pycnia; May 1, aecia.
April 10 on *Sarcobatus vermiculatus*; no infection.
April 17 on *Chenopodium album*; April 28, pycnia; May 1, aecia.
April 17 on *Sarcobatus vermiculatus* (two plants); no infection.
April 25 on *Chenopodium album* May 6, pycnia; May 8, aecia.
April 25 on *Sarcobatus vermiculatus*; no infection.

Another collection of the rust on the same host, obtained by the writer at Ogallala, Neb., was sown on *Chenopodium album* April 29, giving rise to pycnia May 9, and aecia May 13. A sowing at the same time on *Sarcobatus vermiculatus*, and again on two plants June 1, gave no infection. It may be definitely concluded that this species of rust as it exists in Nebraska is not transferable to *Sarcobatus vermiculatus*.¹³

7. PUCCINIA AMPHIGENA Diet.—Teliosporic material on *Calamovilfa longifolia* (Hook.) Hack., collected at Burnett, Neb., by Rev. J. M. Bates, was sown on *Smilax hispida* May 2, giving rise to pycnia May 9, and aecia May 16.¹⁴

8. PUCCINIA PHRAGMITIS (Schum.) Körn.—Teliosporic material on *Phragmites communis* Trin., collected at Scotia Junction, Neb., by Rev. J. M. Bates, was sown on *Rumex crispus* May 1, giving rise to pycnia (date not noted) and aecia May 17.¹⁵

9. PUCCINIA SIMILLIMA Arth.—Teliosporic material on *Phragmites communis* Trin., collected at Scotia Junction, Neb., by Rev. J. M. Bates, was sown on *Rumex crispus*, with no infection, being mistaken for the previously mentioned species. Later it was sown on two plants of *Anemone Virginiana*, still with no infection. It was then sown on *Anemone Canadensis* June 3, giving rise to abundant pycnia June 11, and aecia June 19. This is a confirmation of the restricted range of aecial host, only one species of *Anemone* yet being found that can be infected.¹⁶

10. PUCCINIA AGROPYRI Ellis & Ev.—This is a very common rust of the Rocky mountain region. No culture of it has ever been tried in this country, but a collection made at Bozen, in the Austrian Tyrol, was successfully sown on *Clematis Vitalba*,

¹³ For previous cultures see Bot. Gaz. 35:19. 1903; Jour. Myc. 11:54. 1905; 12:16. 1906; and 13:197. 1907.

¹⁴ For previous cultures see Bot. Gaz. 35:20. 1903; Jour. Myc. 11:57. 1905; and 12:16. 1906.

¹⁵ For previous cultures see Bot. Gaz. 29:269. 1900; and Jour. Myc. 9:220. 1903.

¹⁶ For previous cultures see Bot. Gaz. 35:20. 1903.

by Dr. P. Dietel in 1892.¹⁷ While in the foothills of Colorado this spring Mr. F. D. Kern and the writer observed a plant of *Clematis ligusticifolia* with pycnia just starting, which was growing in the midst of some species of *Agropyron*, heavily coated with the wintered telia of *Puccinia Agropyri*. Material was collected for cultures. The host was not in fruit, but is believed to be *A. pseudorepens* S. & S. Sowing of the spores was made on *Viorna Scottii* May 2, sparingly giving rise to pycnia May 15, but failing to develop aecia. A sowing was made May 10 on *Clematis Virginiana*, no plants of *C. ligusticifolia* being available, which gave rise to abundant pycnia May 20, and aecia May 27. This confirms the work by Dr. Dietel, and establishes the identity of the European and American form of the rust, which heretofore rested upon purely morphological grounds. This also shows that *Clematis Virginiana* may be a host for the species, although all collections so far reported on this host pretty certainly belong to the *Bromus* rust, *Puccinia tomipara* Trel.

II. PUCCINIA POCULIFORMIS (Jacq.) Wettst.—Teliosporic material on an undetermined species of *Agropyron*, obtained at Lake Forest, Ill., by Mr. F. D. Kern and the writer, was sown May 17 on *Berberis vulgaris*, showing pycnia May 27, and aecia June 5. Another collection on *Agropyron tenerum* Vasey, from Scotia Junction, Neb., by Rev. J. M. Bates, was sown in like manner April 24, showing pycnia May 3, and aecia May 14. Aeciospores from the latter culture were sown on *Avena sativa* May 25, giving rise to uredinia June 7.¹⁸

12. PUCCINIA PAMMELII (Trel.) Arth.—Teliosporic material on *Panicum virgatum* L., Collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown on *Euphorbia corollata*, with no infection, and later was sown on *E. marginata* May 31, giving rise to pycnia June 6, and aecia June 12.¹⁹

A number of attempts have been made to grow the teliospores of this rust upon *Euphorbia marginata*, but heretofore without success. In these cases the material was collected in Indiana, where *E. marginata* does not occur, but *E. corollata* is common and abundant. The material used this season gives the reverse condition: it was collected in Nebraska, where *E. corollata* does not occur or is rare, but *E. marginata* is conspicuously abundant. From cultures so far attempted there is reason to think that we have to do with physiological species. Whether

¹⁷ Dietel, Ueber den Generationswechsel von *Puccinia Agropyri* Ell. et Ev.—Oesterr. bot. Zeitschrift 42:261. 1892.

¹⁸ For previous cultures see Jour. Myc. 8:53. 1902; 11:57. 1905; 12:17. 1906; and 13:198. 1907.

¹⁹ For previous cultures see Proc. Ind. Acad. Sci. for 1901:284. 1902; Jour. Myc. 11:56. 1905; 12:16. 1906.

any morphological distinctions exist is yet uncertain, but none has yet been detected.

13. *UROMYCES ACUMINATA* Arth.—Teliosporic material on *Spartina cynosuroides* Willd., collected at St. Paul, Neb., by Rev. J. M. Bates, was sown twice on thrifty plants of *Lysimachia quadrifolia*, with no infection. It was sown on *Steironema ciliata* May 14, giving rise to strongly developed pycnia May 22, and aecia May 27; while a second sowing May 30, gave pycnia June 6, and aecia June 11.²⁰

These results confirm the studies of previous seasons, showing that the rust called by this name in different sections of the country should be segregated into distinct species, or else into physiological species. More observations and material for cultures are required from all parts of the region east of the Mississippi river.

14. *UROMYCES SCIRPI* (Cast.) Burr.—Teliosporic material on *Scirpus fluviatilis* (Torr.) A. Gray, collected at St. Paul, Neb., by Rev. J. M. Bates, was sown on *Oxypolis rigidus*, with no infection. It was sown on *Cicuta maculata* May 3, giving rise to abundant pycnia May 13, and aecia May 20, thus confirming the work of last season.²¹

15. *UROMYCES SILPHI* (Syd.) Arth.—Teliosporic material on *Juncus tenuis* Willd., collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown on *Silphium perfoliatum* April 23, giving rise to pycnia May 4, and aecia May 11. Similar material sent by the same collector from Grand Island, Neb., was sown on another plant of the same host May 31, giving rise as before to pycnia June 12, and aecia June 17. These results well confirm the work of last year.²²

16. *PHRAGMIDIUM SPECIOSUM* Fr.—Teliosporic material on *Rosa pratincola* Greene (same as previously reported under the name *R. Arkansana*), collected in a meadow at Eldorado Springs (Boulder county), Colo., by the writer, was sown on *Rosa pratincola* May 20, giving rise to pycnia May 27, and aecia June 1.²³

17. *GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE* Schw.—Teliosporic material on *Juniperus Virginiana* L., collected at Dayton, Ind., by Mr. F. D. Kern, was sown on *Crataegus punctata*, with no infection, and on a cultivated apple, *Malus Malus*,

²⁰ For previous successful and unsuccessful cultures see Jour. Myc. 12:24. 1906; 13:193. 1907.

²¹ For previous cultures and discussion see Jour. Myc. 13:199. 1907.

²² For previous cultures see Jour. Myc. 13:202. 1907.

²³ For previous cultures see Bot. Gaz. 35:17. 1903; Jour. Myc. 11:53. 1905.

April 12, giving rise to abundant pycnia April 24, but injury to the leaves prevented formation of acia.²⁴

18. GYMNOSPORANGIUM GLOBOSOM Farl.—Teliosporic material collected as in the previous instance was sown on the Wealthy variety of *Malus Malus* April 12, giving rise to a few pycnia April 30, and afterward to acia first observed July 12, although appearing much earlier.²⁴

19. GYMNOSPORANGIUM NELSONI Arth.—Teliosporic material on *Juniperus scopulorum* Sarg., collected at Boulder, Colo., by E. Bethel, was sown on *Amelanchier intermedia* Spach (*A. Botryapium* DC., as given in Britton & Brown's Illustrated Flora), April 16, giving rise to pycnia April 25, but further development stopped by injury to leaves.

Another collection made at the same place two weeks later by Mr. F. D. Kern was sown on *A. Canadensis* (L.) Medic. (plant from the Arnold Arboretum), April 30, giving rise to pycnia May 8, and acia May 29. Another sowing was made on another plant of the same sort May 15, which gave a great abundance of pycnia May 22, and a fine development of acia a month later, June 24. The above cultures were on leaves only. The same material was now sown on both leaves and fruit of *Amelanchier erecta* Blanch. (plants received from Edw. Gillett, of Southwick, Mass., under name of *A. Canadensis*, but identified by Mr. W. H. Blanchard as typical *A. erecta*), May 13, and gave pycnia on upwards of thirty fruits and many leaves May 20, and the first acia June 5, reaching full and normal maturity June 24. Another sowing was made on leaves of *Sorbus Americana* May 15, which gave rise to pycnia in fair amount May 21, and normally formed acia, especially on the rachis and midribs, June 24.

The above results confirm and much extend the somewhat uncertain work of last season.²⁶ It leaves no further doubt that *Roestelia Nelsoni* Arth. should be counted a synonym of *G. Nelsoni* Arth., as suggested in the original publication of the name.

20. GYMNOSPORANGIUM CLAVIPES C. & P.—Teliosporic material on *Juniperus Sibirica* Burgsd., obtained at Lake Forest, Ill., by Mr. F. D. Kern, was sown on leaves of *Amelanchier intermedia* April 10, giving rise to a few pycnia May 1, but without maturing acia. Another sowing was made on fruit of *A. erecta*, also giving rise to a few pycnia June 5, but not maturing acia. Checking of development was doubtless due in both instances to inherent weakness of the hosts. A sowing was made on *Malus coronaria* and *Cataegus* sp., with no infection.

²⁴ For previous cultures see Jour. Myc. 12:13. 1906; 13:200. 1907.

²⁶ For previous cultures see Proc. Am. Acad. Sci. 22:263. 1887; Bot. Gaz. 14:167. 1889; Jour. Myc. 13:200. 1907.

²⁸ See Jour. Myc. 13:203. 1907.

Cultures of this species were made by Prof. W. G. Farlow,²⁷ in 1883, from teliosporic material on *Juniperus Virginiana*, which gave rise to pycnia on leaves of *Malus Malus*, *Aronia arbutifolia* and *Amelanchier Canadensis*, but failed to mature aecia. Cultures were also made by Dr. Roland Thaxter²⁸ in 1886, from similar material, producing pycnia on leaves of *Malus Malus*, and both pycnia and well developed aecia on *Amelanchier Canadensis*, especially on stems and midribs. A difference in the source of material used in the earlier cultures, and for the present year, is worth noting. The former was taken from *Juniperus Virginiana*, the red cedar, while the latter came from *Juniperus Sibirica*, the dwarf juniper. This is the only species of *Gymnosporangium* so far known to inhabit both the true cedars and the true junipers, and the situation should receive careful study. Either the species is a more generalized one than usual, which is not borne out by the geographical distribution, or it is an aggregate of two closely related forms thus far confused.

21. *GYMNOSPORANGIUM CLAVARIAEFORME* (Jacq.) DC.—Teliosporic material on the stems of *Juniperus Sibirica* Burgsd., obtained at Lake Forest, Ill., by Mr. F. D. Kern, was sown on leaves of *Malus Malus* (Bechtel Crab variety), with no infection, and also on leaves of *Amelanchier intermedia* April 11, giving rise to a few pycnia April 20, but to no further development owing to withering of the leaves.

The first culture of this species was made in Denmark, by Oersted, in 1867. The numerous subsequent cultures by European investigators are summarized by Klebahn.²⁹ The only definite cultures with American material were made by Dr. Roland Thaxter,³⁰ in 1886 and 1887. He grew an abundance of pycnia and aecia on *Crataegus tomentosa* and *Amelanchier Canadensis*. Uncertain results were obtained in trials by Prof. L. H. Pammel.³¹

22. *GYMNOSPORANGIUM NIDUS-AVIS* Thax.—Teliosporic material on *Juniperus Virginiana* L., obtained at Lake Forest, Ill., by Mr. F. D. Kern, was sown on *Amelanchier intermedia*, with no infection, and also on *Malus Malus* (Whitney Crab variety) April 10, which gave rise to a few pycnia April 17, and aecia May 11, a period of incubation shorter than for most *Gymnosporangia*. The spores for sowing were taken from large sori on the branches. The only previous cultures of this species were made by Dr.

²⁷ Proc. Am. Acad. Sci. 20:313. 1885.

²⁸ Bot. Gaz. 11:236. 1886; Proc. Am. Acad. Sci. 22:264. 1887.

²⁹ Die wirtwechselnden Rostpilze, pages 339-345.

³⁰ Proc. Am. Acad. Sci. 22:262. 1887; and Bot. Gaz. 14:166. 1889.

³¹ Bull. Iowa Exper. Sta. 84:33. 1905.

Roland Thaxter,³² in an extensive series running from 1886 to 1890, inclusive. He grew it on *Amelanchier Canadensis* in great abundance, showing both pycnia and aecia, and in one instance pycnia were formed on the common apple, but failed to develop further. Thaxter also noted the early development of pycnia and aecia.

The following eight species have now been grown in cultures for the first time, so far as the writer knows. The two cases of amphispores and the one autoecious species resulted as anyone might have taken for granted, but in the other five cases the results are wholly unpredicted, and represent very material advancement in the knowledge of American heteroecious rusts.

1. *PUCCINIA VEXANS* Farl.—Material bearing both teliospores and amphispores on *Atheropogon curtispendus* (Michx.) Fourn. (*Bouteloua racemosa* Lag.), was sent from Boulder, Colo., by Mr. E. Bethel, and gave good germination for the amphispores, but the teliospores refused to grow. Sowing was made on *Atheropogon curtispendus* May 29, and uredinia were observed June 21, although they may have appeared earlier and been overlooked. The amphispores were the characteristic, dark-colored, thick-walled and four-pored form, while the urediniospores, to which they gave rise, had the usual light-colored, thin-walled and eight-pored appearance. The difference between the resting form (amphispore) and active form of the urediniospores belonging to this species is very striking. This is the second time, as far as the writer knows, that amphispores of this species have been seen to germinate.

2. *PUCCINIA CRYPTANDRI* Ellis & Barth.—Amphisporic material on *Sporobolus cryptandrus* (Torr.) A. Gray, obtained at Manitou, Colo., by Mr. F. D. Kern and the writer, was sown on a plant of the same species of grass May 9, and uredinia appeared May 24. In this case the difference between the resting or amphisporic form of the urediniospores and the active or summer form is not so marked as in the preceding species, and yet there is no mistaking one for the other.

3. *PUCCINIA OBTECTA* Peck.—Teliosporic material on *Scirpus Americanus* Pers., obtained near Lafayette, Ind., by Mr. F. D. Kern, was sown on *Urtica gracilis*, and *Silphium perfoliatum*, with no infection, and afterward on *Bidens frondosa* June 5, giving rise to a few pycnia June 19, and aecia first noticed July 6, but probably opening earlier. Another sowing was made on *B. frondosa* and also on *B. connata* June 24, both showing a good development of pycnia July 1, and aecia July 6.

³² Bot. Gaz. 11:238. 1886; Proc. Am. Acad. Sci. 22:264. 1887; Bot. Gaz. 14:167. 1889; and Bull. Conn. Exper. Sta. 107:5. 1891.

The telial stage is common and well known throughout the United States and extending into Mexico, but the aecial stage has rarely been collected. Collections of aecia are in the writer's herbarium from Nebraska and Wisconsin, and in the literature one is also recorded from Illinois. On the basis of a single collection on *Bidens frondosa* Professor Burrill separated it as a special form, and De Toni, in the seventh volume of Saccardo's *Sylloge*, supplied the name *Aecidium compositarum* var. *Bidentis* Burrill.

4. PUCCINIA ON CAREX STENOPHYLLA.—Teliosporic material of this rust collected at Boulder, Colo., by the writer, was sown on *Solidago Canadensis* and *Baptisia leucantha*, with no infection.

It was at this point in the work that a brief note of observation was seen in Dr. W. Tranzschel's second report on "Beiträge zur Biologie der Uredineen." This is a translation in full: "In July, 1900, I found in Turkestan, near Irkeschtam on the Chinese border, the *Aecidium Dracunculi* Thüm. on *Artemisia Dracunculus* in great abundance. Associated with the affected *Artemisia* grew *Carex stenophylla* Wahlb., on which was found uredosori." Accepting this as a hint, the Colorado material was now sown on *Artemisia dracunculoides*. As no potted plant was available, a sowing was made in the open, giving no infection, and another in the greenhouse on a cutting placed in water. The latter attempt gave very abundant and unequivocal results. The sowing was made May 31, and pycnia appeared June 6, followed by aecia June 15, both numerous and finely developed.

The type collection of this *Aecidium* was made in Siberia, at Minussinsk, also on the Chinese border, but about a thousand miles northeast of the locality where it was found by Dr. Tranzschel. This collection was distributed in Thuemen's *Mycotheca Universalis*, No. 1223. A collection of aecia on *Artemisia dracunculoides* from Nebraska was distributed in Ellis & Everhart's *Fungi Columbiani*, No 1664. A careful comparison shows no apparent difference between the Asian and American collections, and the two are accepted as the same species.

As a name and description seem to be demanded for this species, the following are submitted:

Puccinia universalis nom. nov. (*Aecidium Dracunculi* Thuem., not *Puccinia Dracunculi* Auers.)

O. Pycnia chiefly epiphyllous, numerous in orbicular groups, punctiform, honey-yellow, rather inconspicuous; subepidermal, slightly depressed-globose, 100-160 μ broad by 90-112 μ high; ostiolar filaments 40-80 μ long.

I. Aecia chiefly hypophyllous, crowded in orbicular groups opposite the pycnia, 1-3 mm. across, peridia cylindrical, 0.5 mm. high, margin usually erect, erose, peridial cells rhomboidal, 20-30 μ long, overlapping,

inner wall medium thick, 3-4 μ , verrucose, outer wall thicker, 5-9 μ , smooth, striate; aeciospores globoid, small, 12-18 by 15-21 μ ; wall very thin, 0.5-1 μ , nearly colorless, very minutely granular.

On *Artemisia dracunculoides* Pursh, Colorado, Nebraska; *A. Canadensis* Michx., Iowa, Nebraska; *A. frigida* Willd., Montana; *A. kansana* Britt., Nebraska. Type on *A. Dracunculus* L., Western Siberia.

II. Uredinia epiphyllous, scattered, oblong, 0.2-0.5 mm. long, rather early naked, cinnamon-brown, ruptured epidermis conspicuous; urediniospores broadly ellipsoid, 15-19 by 20-26 μ , wall cinnamon brown, 1-1.5 μ thick, rather finely echinulate, pores 2, equatorial.

III. Telia epiphyllous, scattered, roundish or oblong, 0.1-0.3 mm. wide by 0.2-1.2 mm. long, early naked, pulvinate, ruptured epidermis noticeable; teliospores clavate-oblong, 16-26 by 35-52 μ , wall dark chestnut-brown, lighter and about 1.5-2 μ thick below, thicker above, 7-12 μ , smooth; pedicel tinted, one-half length of spore, or more.

On *Carex stenophylla* Wahl., Colorado, Nebraska, Montana.

5. PUCCINIA ON CAREX LONGIROSTRIS.—Field observations by Dr. E. W. Olive, and material furnished by him, including aecia host plants, supplied the entire basis for the result reported under this number.

Teliospores from *Carex longirostris* Torr. were sown June 4 on *Aster paniculatus*, *Erigeron annuus*, *Solidago Canadensis*, *Ribes Cynosbati*, and *Phryma leptostachya*, with no infection, except on *Phryma*, which showed pycnia June 10 in great abundance, and aecia June 15. The development was exceptionally strong and characteristic.

No rust has heretofore been reported on this species of *Carex*. The aecial stage was first collected at Spirit Lake, Iowa, by Dr. B. D. Halsted, in 1886, and has since been reported from Minnesota and Nebraska, and found by Dr. Olive this season at Madison, Wis. A description of the species in its several spore-stages is appended:

Puccinia Phrymae (Halst.) nom. nov. (*Aecidium Phrymae* Halst., Jour. Myc. 2:52. 1886.)

O. Pycnia amphigenous, few, crowded in small groups, inconspicuous, honey-yellow, becoming blackish-brown, slightly flattened globoid, 77-110 μ in diameter by 65-80 μ high; ostiolar filaments 40-50 μ long.

I. Aecia hypophyllous, gregarious, in large open groups on discolored spots 4-10 mm. across, very short, 0.2-0.3 mm. in diameter, pale yellow; peridia colorless, margin recurved, erose, peridial cells rhomboidal in longitudinal section, overlapping, inner wall thin, about 1 μ , finely verrucose, outer wall thicker, 3-4 μ , striate, smooth; aeciospores globoid, 12-16 by 14-19 μ , wall pale yellow, thin, 1 μ or less, finely verrucose.

On *Phryma leptostachya* L., Iowa, Wisconsin, Nebraska, Minnesota. Type from Spirit Lake, Iowa.

II. Uredinia hypophyllous, scattered, round or oblong, early naked, ruptured epidermis noticeable; urediniospores broadly ellipsoid, 15-18 by 18-20 μ , wall cinnamon-brown, 1-1.5 μ thick, finely and rather sparsely echinulate, pores 2, in upper part.

III. Telia hypophyllous, scattered, round or oblong, 0.2-0.4 mm. wide by 0.3-0.8 mm. long, early naked, dark chocolate-brown, pulvinate, ruptured epidermis noticeable; teliospores clavate-oblong, 12-15 by 35-45 μ , rounded or obtuse at apex, usually narrowed below, wall chestnut-brown, concolorous, 1-1.5 μ thick, much thicker above, 9-13 μ : pedicel about length of spore or less, tinted.

On *Carex longirostris* Torr., Wisconsin.

6. PUCCINIA MUTABILIS Ellis & Gall.—While collecting for a few days in Colorado about the first of May, wintered-over teliospores were found on a number of species of *Allium*, in most cases not accurately determined for want of the inflorescence. In a few cases young leaves of the season showed freshly formed uredinia, and in one instance immature telia were observed beside the uredinia, evidently arising from the same mycelium. A few very young aecia, well isolated from other spore forms were also found. As it was clearly too early in the season to have had aecia mature and reinfect the host, and in this manner give rise to the uredinia, the question arose whether the aecia did not belong to some heteroecious species, while the uredinia and telia represented a species without aecia. Further search in the field brought to light some leaves which without question had remained alive over winter. In one case the dead tip of such a leaf bore telia of last year's growth, and on the adjoining green part of the leaf uredinia were forming. This seemed to show that the early uredinia were derived from wintered-over mycelium, but it left the question of the origin of the aecia unsolved.

Teliosporic material on what was believed to be *Allium reticulatum* Fraser, was obtained by the writer at Eldorado Springs, Colo., and sown on *Allium recurvatum* Rydb., May 18, giving rise to pycnia June 3, and aecia June 7. The life cycle of the rust with all spore forms is therefore established, although it is clearly possible in exceptional cases for the mycelium to be carried over the winter in leaves that retain their vitality and thus start the rust in the spring at the uredinial stage.

7. GYMNOSPORANGIUM BETHELI Kern. — Teliosporic material on *Juniperus scopulorum* Sarg., obtained at Boulder, Colo., by Mr. F. D. Kern, was sown on *Crataegus* sp. (received from the Arnold Arboretum) April 30, showing pycnia May 8, and aecia June 5, the aecia being fully matured by June 17. Another sowing was made on *Crataegus coccinea* May 15, showing pycnia May 21, and aecia June 24. Another sowing on *Crataegus punctata* May 15, gave pycnia May 21, but the leaves withered before aecia had formed. Another sowing on *Sorbus Americana* May 21, gave rise to numerous pycnia May 29, and an equal abundance of well formed aecia July 25.

Similar material obtained at Wolcott, about one hundred miles west of Boulder, was sown on *Crataegus cordata* (Mill.) Ait. May 5, on a tree out of doors, giving rise to pycnia May 17, and aecia July 1. Another sowing on *Sorbus Americana* May 15, gave a large number of pycnia May 24, and aecia well formed July 25. A sowing on *Amelanchier erecta* gave no infection.

All the foregoing sowings were on the leaves. The ample success attained admits of no question that the aecia, recently described under the name *Roestelia Betheli* Kern, do in fact belong to the large gall form of cedar rust, as suggested by Mr. E. Bethel³³ from field observations.

8. GYMNOSPORANGIUM INCONSPICUUM Kern. — Teliosporic material on *Juniperus Utahensis* (Engelm.) Lemmon, obtained from the type locality at Glenwood Springs, Colo., by Mr. F. D. Kern and the writer, was sown on the leaves of *Crataegus* sp., *Amelanchier Canadensis*, and *Pyrus communis*, with no infection. It was afterward sown on fruit of *Amelanchier erecta* May 10, which gave rise to abundance of pycnia May 24, and aecia June 15, the aecia being mature by June 19. The affected areas of the fruit became somewhat swollen, and of a yellowish white color, making them conspicuous. The aecia prove to be identical with *Roestelia Harknessianoides* Kern, and thus confirm the inference drawn from field observations.³⁴ It is an interesting fact that while the telia of this species of rust are very evanescent, the aecia persist and may be found on mummified fruits the year following infection, so that it is likely to become common in herbaria.

SUMMARY.

The following is a complete list of successful cultures made during the season of 1907. It is divided into two series: species previously reported by the writer or other investigators, and species now reported for the first time.

A Species previously reported.

1. PUCCINIA ALBIPERIDA Arth.—Teliospores on *Carex crinita* Lam., sown on *Ribes Cynosbati* L.
2. PUCCINIA CARICIS-ASTERIS Arth. — Teliospores on *Carex rosea* Schk., sown on *Aster cordifolia* L., and on *Carex* sp., sown on *Aster paniculatus* Lam.
3. PUCCINIA CARICIS (Schum.) Reb. — Teliospores on *Carex stipata* Muhl., and on *C. riparia* Curt., sown on *Urtica gracilis* Ait.

³³ Bull. Torrey Club 34:460. 1907.

³⁴ Bull. Torrey Club 34:463. 1907.

4. PUCCINIA ANGUSTATA Peck.—Teliospores on *Scirpus atrovirens* Muhl., sown on *Lycopus Americanus* Muhl.
5. PUCCINIA FRAXINATA (Schw.) Arth.—Teliospores on *Spartina cynosuroides* Willd., sown on *Fraxinus lanceolata* Borck.
6. PUCCINIA SUBNITENS Diet.—Teliospores on *Distichlis spicata* (L.) Greene, sown on *Chenopodium album* L., and *Bursa Bursa-pastoris* (L.) Britt.
7. PUCCINIA AMPHIGENA Diet.—Teliospores on *Calamovilfa longifolia* (Hook) Hack., sown on *Smilax hispida* Muhl.
8. PUCCINIA PHRAGMITIS (Schum.) Körn.—Teliospores on *Phragmites communis* Trin., sown on *Rumex crispus* L.
9. PUCCINIA SIMILLIMA Arth.—Teliospores on *Phragmites communis* Trin., sown on *Anemone Canadensis* L.
10. PUCCINIA AGROPYRI Ellis and Ev.—Teliospores on *Agropyron pseudorepens* S. & S., sown on *Viorna Scottii* (Porter) Rydb., and on *Clematis Virginiana* L.
11. PUCCINIA POCULIFORMIS (Jacq.) Wettst.—Teliospores on *Agropyron tenerum* Vasey, sown on *Berberis vulgaris* L., and aeciospores from this culture sown on *Avena sativa* L.
12. PUCCINIA PAMMELII (Trel.) Arth.—Teliospores on *Panicum virgatum* L., sown on *Euphorbia marginata* Pursh.
13. UROMYCES ACUMINATUS Arth.—Teliospores on *Spartina cynosuroides* Willd., sown on *Steironema ciliata* (L.) Raf.
14. UROMYCES SCIRPI (Cast.) Burr.—Teliospores on *Scirpus fluviatilis* (Torr.) A. Gray, sown on *Cicuta maculata* L.
15. UROMYCES SILPHII (Syd.) Arth.—Teliospores on *Juncus tenuis* Willd., sown on *Silphium perfoliatum* L.
16. PHRAGMIDIUM SPECIOSUM Fr.—Teliospores on *Rosa pratincola* Greene, sown on same host.
17. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw.—Teliospores on *Juniperus Virginiana* L., sown on *Malus Malus* (L.) Britt.
18. GYMNOSPORANGIUM GLOBOSUM Farl.—Teliospores on *Juniperus Virginiana* L., sown on *Malus Malus* (L.) Britt.
19. GYMNOSPORANGIUM NELSONI Arth.—Teliospores on *Juniperus scopulorum* Sarg., sown on *Amelanchier intermedia* Spach, *A. Canadensis* (L.) Medic., *A. erecta* Blanch., and *Sorbus Americana* Marsh.

20. GYMNOSPORANGIUM CLAVIPES C. & P.—Teliospores on *Juniperus Sibirica* Burgsd., sown on *Amelanchier intermedia* Spach, and *A. erecta* Blanch.

21. GYMNOSPORANGIUM CLAVARIAEFORME (Jacq.) DC.—Teliospores on *Juniperus Sibirica* Burgsd., sown on *Amelanchier intermedia* Spach.

22. GYMNOSPORANGIUM NIDUS-AVIS Thax.—Teliospores on *Juniperus Virginiana* L., sown on *Malus Malus* (L.) Britt.

B. Species reported now for the first time.

1. PUCCINIA VEXANS Farl.—Amphisporos on *Atheropogon curtipendulus* (Michx.) Fourn., sown on same host.

2. PUCCINIA CRYPTANDRI Ellis & Barth.—Amphisporos on *Sporobolus cryptandrus* (Torr.) A. Gray, sown on same host.

3. PUCCINIA OBTECTA Peck.—Teliospores on *Scirpus Americanus* Pers., sown on *Bidens frondosa* L., and *B. connata* Muhl.

4. PUCCINIA UNIVERSALIS Arth.—Teliospores on *Carex stenophylla* Wahl., sown on *Artemisia dracunculoides* Pursh.

5. PUCCINIA PHRYMAE (Halst.) Arth.—Teliospores on *Carex longirostris* Torr., sown on *Phryma leptostachya* L.

6. PUCCINIA MUTABILIS Ellis & Gall.—Teliospores on *Allium reticulatum* Fraser, sown on *A. recurvatum* Rydb.

7. GYMNOSPORANGIUM BETHELI Kern.—Teliospores on *Juniperus scopulorum* Sarg., sown on *Crataegus coccinea* L., *C. punctata* Jacq., *C. cordata* (Mill.) Ait., and *Sorbus Americana* Marsh.

8. GYMNOSPORANGIUM INCONSPICUUM Kern.—Teliospores on *Juniperus Utahensis* (Engelm.) Lemmon, sown on *Amelanchier erecta* Blanch.

9

116

CULTURES OF UREDINEAE IN 1908¹

J. C. ARTHUR

The present article forms the ninth of a series of reports² by the author upon the culture of plant rusts, covering the years from 1899 to the close of 1908. The grass and cedar rusts have been especially prominent in the years' work. Very considerable advance has been made in segregating the subepidermal rusts on grasses that have generally passed under the name of *Puccinia rubigo-vera*, and some particularly notable results were achieved with forms of *Gymnosporangium*, partly in finding unexpected aecial connections for well-known telial species, and partly in segregating species heretofore confused under European names.

This year for the first time since the series of cultures was begun, the Indiana Experiment Station at Purdue University, where all the study has been conducted, assumed the full expense of the work. Heretofore the extra assistance needed during the chief cultural period of about six weeks has been paid for in part or wholly from outside sources. This year the cultural work was made a part of an extended investigation of cereal and other rusts to be conducted by the station, and the expenses met from the Adams fund, derived from the general government. The more definite and certain financial support has made it possible to better systematize and conduct the work.

As in the previous year some collecting trips made expressly

¹ Read before the Botanical Society of America at the Baltimore meeting, December 31, 1908.

² See Bot. Gaz. 29: 268-276, 35: 10-23; Jour. Myc. 8: 51-56, 10: 8-21, 11: 50-67, 12: 11-27, 13: 189-205, and 14: 7-26.

to secure culture material proved helpful to an extent far beyond the proportional amount of time consumed. The earliest one took Mr. F. D. Kern and the writer to Mammoth Cave in Kentucky. It was specifically undertaken to discover a telial form to accompany the aecia known to occur on *Porteranthus stipulatus* (*Gillenia stipulacea*). A careful microscopic examination made during the winter of 1907-8 of the aecia on this host, which were collected by Rev. C. H. Demetrio in 1884 at Perryville, Mo., and distributed as No. 3323 in Rabenhorst-Winter, *Fungi europaei*, under the name of *Roestelia lacerata*, which it much resembles, showed that the fungus was undoubtedly a true *Roestelia*, although the host is an herb belonging to the rose family. As this is the only known instance of the aecial stage of a *Gymnosporangium* occurring on any host outside of the woody plants of the apple family, the detection of the telial form appeared to be a matter of more than usual interest. The original collection was apparently the only one known, until a search was made through the phanerogamic herbaria in a number of places, and a few pycnia were detected on a collection of the host at the New York Botanical Garden, which was made at Mammoth Cave, in June, 1870, by Dr. T. F. Allen. Upon writing to Rev. Demetrio it was learned that the locality of the original collection has been turned into cultivated fields, quite destroying the chances of making a second collection in the original habitat. It was known to the writer that the estate of several thousand acres about the Mammoth Cave has been in litigation for a number of years, and that few changes have taken place in the long period during which the cave has been an object of world-wide interest to tourists. After considering these facts it was decided to visit the vicinity of the cave, hoping to detect material from which cultures could be made. Two days were spent at the cave. The most careful search on the first day was in vain, although the host was found as tender shoots only a few inches high, and also an abundance of red cedar trees. The second day afforded better success, and considerable material of what appeared to be a new form of *Gymnosporangium* was discovered on the trunks of small cedars growing near plants of *Porteranthus*, although pycnia and aecia could not be expected owing to the earliness of the season. Sub-

sequent cultures confirmed the inferences from field observation, and abundantly justified the method pursued in this case in tracing the life history of a little or imperfectly known rust.

The next important excursion to points outside of the state of Indiana was made by my associate, Mr. F. D. Kern, the writer's ill health preventing further active participation in securing material for the work of the season. Mr. Kern reached Denver, Colo., on May 16, and spent five days collecting material and making field observations chiefly along the foot hills from Boulder on the north to Trinidad on the south. During this time he had the invaluable assistance of Mr. E. Bethel, the able mycologist of Denver, who supplied important information about suitable localities to visit, and for part of the time himself went along to help in every way possible. The results fully justified the time and outlay, especially in the way of knowledge regarding the numerous and intricate forms of cedar rusts. The telia of the true *Roestelia cornuta* were collected on this trip for the first time in America. The telia of the true *R. penicillata*, little known in America, were also taken, but owing to misfortune in manipulation did not lead to successful cultures.

On his return journey from Colorado Mr. Kern made a detour to Racine, Wis., where as the guest of Dr. J. J. Davis he visited in an automobile the Wind Lake locality, made familiar to mycologists by Dr. Davis' numerous collections and observations. Here material was obtained of the juniper rust, believed to be associated with the *cornuta*-like aecia on *Aronia*. It had been sent by Dr. Davis for cultures in previous years, but had not been brought to germination. This is the type locality for the species, to which Mr. Kern has given the name *Gymnosporangium Davisii*.³

At our request Mr. H. S. Jackson, of Newark, Del., made some fruitful collecting tours for observations on the Atlantic coast rusts. A two days' trip to Seaford and Lewes, Del., was made the middle of November, 1907, and again to the same places the latter part of April following. The duplicate trip was especially designed to secure observations on the early appearance of aecia in the immediate vicinity where telial culture material had pre-

³ Bull. Torrey Club 35: 507. 1908.

viously been taken. Mr. Jackson proved a keen observer, detecting a new species on *Carex comosa* with its probable aecia on *Smilax*, and both aecia and telia of *Puccinia subnitens*, the first collection of it made on the Atlantic coast, beside much other serviceable information. He also made a trip to Newfield, N. J., on May 15, and secured telial material of cedar rusts from the region made familiar by the late Mr. J. B. Ellis.

The season's cultural work was, with the exception of some cedar rust cultures made by Mr. Kern, in the hands of Mr. A. G. Johnson, a graduate of the South Dakota Agricultural College, and a former special student of Washington University, St. Louis, who was recommended for the position by Dr. E. W. Olive. He was diligent and enthusiastic in the work, and made successful cultures of the largest number of species secured in any one season during the ten years that the cultural work has been in progress.

In this series of studies the amplitude of the results is largely dependent upon the kindly assistance of correspondents in providing culture material and in communicating field observations. Acknowledgments are due this year to Mr. E. Bethel, Denver, Colo., who is far in the lead with more than fifty collections of culture material, and to Messrs. H. S. Jackson, Newark, Del., J. M. Bates, Red Cloud, Neb., R. E. Stone, Auburn, Ala., A. O. Garrett, Salt Lake City, Utah, Elam Bartholomew, Stockton, Kans., E. W. Olive, Brookings, S. D., E. W. D. Holway, Minneapolis, Minn., H. J. Webber, Ithaca, N. Y., T. D. A. Cockerell, Boulder, Colo., J. L. Sheldon, Morgantown, W. Va., A. B. Seymour, Cambridge, Mass., G. P. Clinton, New Haven, Conn., P. B. Kennedy, Reno, Nev., Guy West Wilson, Fayette, Iowa, George L. Potter, Lima, Ind., J. J. Davis, Racine, Wis., A. R. Sweetser, Eugene, Ore., C. W. Edgerton, Donald Reddick and C. J. Humphrey, all three of Ithaca, N. Y., W. A. Kellerman, at the time in Guatemala, C. G. Lloyd, Zacatecas, Mex., and J. Dearness, London, Ont. This enumeration gives scanty credit where in many cases special trips, often of many miles, were undertaken at our request to secure at a definite time either dry material or live hosts, or to make observations, which would further a particular inquiry. Mention should also be made of

the assistance rendered by Dr. Wm. Trelease, of the Missouri Botanical Garden, St. Louis, Mo., who sent plants of *Porteranthus stipulatus* on which the new cedar rust was sown. The writer extends his warmest thanks to the above individuals and to others who have assisted in the year's investigations.

During the present season 204 collections of material with resting spores and 26 collections with active spores were employed, from which 565 drop cultures were made to test the germinating condition of the spores. Out of the 204 collections with resting spores 99 could not be brought to germination although seemingly in perfect condition leaving 105 collections of available material. These 105 collections with resting spores and 26 with active spores belonged to about 60 species of rusts. Altogether 321 sowings were made, employing for the purpose 114 species of hosts, these being grown in pots, so that the work of attempted infection could be conducted wholly in the greenhouse.

The results of this work are given in the following paragraphs, and are divided into negative results, positive results with species whose life cycles have already been ascertained by the writer or other investigators, and positive results with species whose life cycles are now first placed on record. •

NEGATIVE RESULTS:—Quite a number of collections gave good germination of the spores, but no infections were secured. The following may be recorded to serve for reference in future studies:

1. PUCCINIA on *Carex pennsylvanica* L., collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown on *Arabis Holboellii*, with no infection. Similar material was sown in previous seasons on thirty-eight other species of hosts.⁴

2. PUCCINIA VULPINOIDIS Diet. & Holw., on *Carex vulpinoidea* Michx., collected at Newark, Del., by Mr. H. S. Jackson, was sown on *Viola cucullata*, *Chelone glabra*, *Aster paniculatus*, *Ambrosia trifida*, *Cacalia reniformis*, *Laciniaria punctata*, *Rudbeckia laciniata* and *Senecio obovatus*. A similar collection made at London, Ontario, by Mr. J. Dearness, was sown on *Callirrhoe involucrata* and *Rudbeckia laciniata*. Still a third collection made

⁴ See Jour. Myc. 10: 10. 1904; 11: 51. 1905; 12: 12. 1906; 13: 191. 1907; and 14: 9. 1908.

by the writer at Lima, Ind., was sown on *Napaea dioica*, *Ambrosia trifida*, *Aster Drummondii*, *Boltonia asteroides*, *Cacalia reniformis*, *Laciniaria spicata*, *Rudbeckia laciniata* and *Senecio obovatus*. None of the trials resulted in infection.

3. PUCCINIA on *Carex gravida* Bailey, sent by Rev. J. M. Bates from Red Cloud, Neb., was sown on *Abronia umbellata*, *Vernonia arkansana*, and twice on *Artemisia dracunculoides*, with no infection. Similar material from the same region has been sown in previous years upon forty-four other species of hosts with negative results.⁵

4. PUCCINIA on *Carex* sp., sent by Mr. C. W. Edgerton from Ithaca, N. Y., was sown on *Iris versicolor* twice, with no infection. This was the culmination of a series of observations to ascertain the telial form belonging to aecia on *Iris*, which had been noticed for a number of seasons in one locality near the town of Ithaca. Four collections taken from the close vicinity of the rusted *Iris* were sent for trial in 1907, two of which grew well on *Aster paniculatus*, but not on *Iris*, while the other two failed to germinate. All four of these collections agreed morphologically with *Puccinia Caricis-Asteris* Arth. In continuation of the search for the true alternate form for the *Iris* rust, Mr. Edgerton sent this season from practically the same spot a rust on an undetermined *Carex*, having morphological characters quite unlike those of *P. Caricis-Asteris*, and approximating, if not identical with, *P. quadriporula* Arth. As no positive results were obtained from this material the identity of the alternate form of the aecial rust on *Iris* still remains in doubt.

5. PUCCINIA DULICHII Syd., on *Dulichium arundinaceum* (L.) Britt., collected at Seaford, Del., by Mr. H. S. Jackson, was sown on *Decodon verticillatus*, *Smilax hispida*, *Lysimachia quadrifolia* and *Senecio obovatus*, with no infection.

6. PUCCINIA EMACULATA Schw., on *Panicum capillare* L., collected at Fayette, Iowa, by Prof. Guy West Wilson, was sown on *Macrocalyx Nyctelea*, *Hydrophyllum virginicum*, *Amorpha fruticosa*, and *Napaea dioica*, with no infection. Similar material was sown in previous seasons on twenty-three other species of hosts.⁶

⁵ See Jour. Myc. 10: 10. 1904; 11: 51. 1905; 12: 12. 1906; 13: 191. 1907; and 14: 10. 1908.

7. PUCCINIA SCHEDONNARDI K. & S., on *Schedonnardus paniculatus* (Nutt.) Trel., collected at Boulder, Colo., by Mr. E. Bethel, was sown on *Thalictrum polygamum* and *Grindelia squarrosa*, with no infection. Like material was sown in previous seasons on eighteen other species of hosts.⁷

8. PUCCINIA ELLISIANA Thüm., on *Andropogon scoparius* Michx., collected at Newark, Del., by Mr. H. S. Jackson, was sown on *Actaea alba*, *Ambrosia trifida*, *Anemone virginiana*, *Dirca palustris*, *Hydrophyllum virginicum*, *Ipomoea pandurata*, *Isopyrum biterminalatum*, *Iva frutescens*, *Pentstemon hirsutus*, *Phacelia bipinnatifida*, *Psoralea Onobrychis* and *Verbena urticifolia*, with no infection. Similar material from Colorado was sown the previous year on ten other species of hosts.⁸

9. PUCCINIA VEXANS Farl., on *Atheropogon curtispendus* (Michx.) Fourn. (*Bouteloua racemosa* Lag.), collected at Stockton, Kans., by Mr. E. Bartholomew, was sown on *Apocynum cannabinum*, *Caulophyllum thalictroides*, *Dalea laxiflora*, *Delphinium tricornis*, *Hydrophyllum virginicum*, *Napaea dioica*, *Polemonium reptans*, *Symphoricarpos racemosus*, *Smilax hispida* and *Thalictrum dioicum*, with no infection. This is the first time that an attempt at infection with teliospores has been made, although the amphispores were successfully grown on the same grass host last year.

10. PUCCINIA POCULIFORMIS (Jacq.) Wettst., on *Phleum pratense* L., collected at Sayre, N. Y., by Prof. H. J. Webber, was sown May 1 on *Berberis vulgaris*. Another collection of the rust from Ithaca, N. Y., sent by Mr. Donald Reddick, was sown May 6 on five plants of *Berberis vulgaris*, and once more on May 13. As no infection showed after the usual interval, the same material was again sown May 22 on three plants of the barberry, and for three successive nights after sowing the inoculated plants were placed in an ice box at a temperature of 10° C. in order to insure more favorable conditions for the penetration of the germ tubes into the tissues of the host. Again on May 28

* See Bot. Gaz. 35: 12. 1903; Jour. Myc. 8: 52. 1902; 10: 10. 1904; 12: 12. 1906; 13: 192. 1907; and 14: 11. 1908.

⁷ See Bot. Gaz. 35: 11. 1903; Jour. Myc. 13: 192. 1907; and 14: 11. 1908.

⁸ See Jour. Myc. 14: 10. 1908.

the same material was sown on *Mahonia Aquifolium*. In each instance the ready germination of the teliospores was established by a drop culture within twenty-four hours preceding the time of sowing, as is done for all the culture work reported in this and preceding years. In no case was an infection secured.

The reasons for believing that this rust should be referred to *Puccinia poculiformis*, in spite of the failure to produce aecia on *Berberis* or *Mahonia*, have been briefly stated by Mr. Frank D. Kern,⁹ who has also recorded the history of the appearance of the rust in North America, and it is only necessary that the writer affirm his agreement with Mr. Kern's conclusions.

11. PUCCINIA ASTERIS Duby, on *Aster arenarioides* D. C. Eaton, sent from Salt Lake City, Utah, by Mr. A. O. Garrett, was sown on *Aster Drummondii*, *A. paniculatus*, *A. multiflorus* and *Callistephus hortensis*, with no infection. This adds little to the solution of the problem whether the leptopuccinial rust on various species of *Aster* in the different sections of the country are all referable to one species or not.

12. UROMYCES GRAMINICOLA Burr., on *Panicum virgatum* L., collected at Stockton, Kans., by Mr. E. Bartholomew, was sown on *Althaea rosea*, *Apios tuberosa*, *Cacalia reniformis*, *Callirrhoe involucrata*, *Decodon verticillatus*, *Hibiscus militaris*, *Napaea dioica* and *Viola cucullata*, with no infection.

13. UROMYCES ANDROPOGONIS Tracy, on *Andropogon glomeratus* (Walt.) B.S.P., collected at Lewes, Del., by Mr. H. S. Jackson, was sown on *Viola cucullata*, while a similar collection on the same species of host, sent from Auburn, Ala., by Mr. R. E. Stone, was sown twice on *Viola cucullata*, and also on *Comandra umbellata*, *Dasystema flava* and *Pentstemon hirsutus*, all with no infection. From the field observations reported by Dr. John L. Sheldon it seems almost certain that the aecia of this rust occur upon *Viola*, and the repeated failure of the cultures may have been due to the maturity of the *Viola* leaves on which the sowings were made.

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK:—
The following species of rusts were successfully grown, and the facts supplement what have been obtained from previous cultures

⁹ Kern. The Rust of Timothy. Torreya 9: 3-5. 1909.

in this series or have been recorded by other American or European investigators. In a number of cases the previous definite knowledge of the species has been materially extended.

1. PUCCINIA KUHNIAE Schw., on *Kuhnia Hitchcockii* A. Nelson, collected at Marshall, Colo., Feb. 22, 1908, by Mr. E. Bethel, was sown May 14, on *Kuhnia eupatorioides*. Numerous pycnia appeared May 24, duly followed by abundant uredinia June 4, and telia June 29. This result confirms the work in 1905,¹⁰ and shows that in all probability all collections of rust on this genus of hosts are referable to the one autoecious species.

2. PUCCINIA PECKII (DeT.) Kellerm., on *Carex stipata* Muhl., collected Oct. 23, 1907, at Lima, Ind., by Mr. George L. Potter, was sown on *Onagra biennis* (L.) Scop., April 28, and gave pycnia May 9 and aecia May 18, both in great abundance.¹¹

3. PUCCINIA SAMBUCI (Schw.) Arth., on *Carex lurida* Wahl., collected at Lagrange, Ind., by the writer, was sown on *Sambucus canadensis* L. May 15, and gave a great abundance of pycnia May 23, and aecia June 1.¹²

4. PUCCINIA CARICIS-SOLIDAGINIS Arth., on *Carex sparganoides* Muhl., collected at Lima, Ind., and again at Lagrange, Ind., both by the writer, was sown from the first named locality April 11 on *Aster Drummondii*, giving no infection and again May 4 on *Solidago canadensis* L., giving abundant infection with pycnia showing May 12, and aecia May 19. From the second locality sowings were made April 15 on *Aster paniculatus* and *Solidago canadensis*, giving no infection on the first host, but abundant infection on the second, showing pycnia April 23, and aecia May 5.¹³ This result duplicates that obtained in 1905.

5. PUCCINIA ELEOCHARIDIS Arth., on *Eleocharis palustris* (L.) R. & S., obtained at Lima, Ind., by the writer, was sown on *Eupatorium perfoliatum* L., May 13, giving rise to pycnia May 22,

¹⁰ Jour. Myc. 12: 23. 1906.

¹¹ For previous cultures see Bot. Gaz. 35: 13. 1903; Jour. Myc. 8: 55. 1902; 11: 58. 1905; 12: 15. 1906; and 13: 195. 1907.

¹² For previous cultures see Bot. Gaz. 35: 14. 1903; Jour. Myc. 8: 55. 1902; 12: 14. 1906; and 13: 195. 1907.

¹³ For previous cultures see Bot. Gaz. 35: 21. 1903; and Jour. Myc. 12: 15. 1906.

and aecia June 2, both in abundance, thus confirming the work of 1905 and 1906.¹⁴

6. PUCCINIA ANGUSTATA Peck, on what was probably *Scirpus cyperinus* (L.) Kunth, the plant showing only leaves but growing with plants with fruit, gathered at Spirit Lake, Iowa, by the writer, was sown April 13 on *Lycopus communis* Bickn., giving rise to pycnia April 25, and aecia May 3, both in abundance. It was sown again May 2 on *Lycopus americanus* Muhl., giving rise to an equal abundance of pycnia May 11, and of aecia May 19, the interval between the appearance of pycnia and aecia being exactly the same as in the first culture.¹⁵ The result is interesting in connection with an observation made by the writer while on an excursion in the vicinity of Ithaca, N. Y., June 30, 1906. An abundance of rusted *Lycopus communis* was gathered, with uredinia appearing on close-by plants of *Scirpus cyperinus*, while plants of *L. americanus* and *S. atrovirens* growing intermixed were both quite free from rust. The field observation seemed to indicate a biological difference between the rust occurring on the two species of *Scirpus* and the associated *Lycopus*, and with a view to experimental tests healthy plants of *L. communis* from the Ithaca locality were sent to the greenhouse at Lafayette, the species not occurring in Indiana or Iowa. These were the plants used in the present cultures. The results seem to warrant the tentative conclusion that *P. angustata* within some geographical areas is inclined to form races confined to certain hosts, while in other geographical areas the differentiation into races does not occur, a condition that appears to arise in other species as well, *e. g.*, *Puccinia subnitens* Diet.

7. PUCCINIA SUBNITENS Diet., on *Distichlis spicata* (L.) Greene, was available in two collections from Delaware, two from Nebraska and two from Nevada, representing three areas approximately on the fortieth parallel of latitude, but twelve hundred miles between stations in longitude. The Delaware station is on the Atlantic sea coast; the Nebraska station is midway of the continent on the great plains, with the Allegheny range of

¹⁴ For previous cultures see Jour. Myc. 12: 23. 1906; and 13: 197. 1907.

¹⁵ For previous cultures see Bot. Gaz. 29: 273. 1900; Jour. Myc. 8: 53. 1902; 11: 58. 1905; 13: 196. 1907; and 14: 14. 1908.

mountains intervening; while the Nevada station is within two hundred miles of the Pacific coast, and between it and the Nebraska station intervenes the great expanse of the Rocky Mountains.

The chief question demanding solution was whether this remarkable heteroecious rust, which forms aecia on many species of hosts belonging to the families Cruciferae, Chenopodiaceae and Capparidaceae, has developed biological differences, as previous work had indicated.¹⁶ In all thirty sowings were made. A few of these proved failures because the plants used as hosts did not grow well. The important results may be given without recording all the data.

The collections from the Atlantic coast, the first reported from east of the Mississippi river, were made by Mr. H. S. Jackson, at Lewes, Del., Nov. 16, 1907. Aecia were taken the following spring in close proximity on seedling plants, which were fruited in Lafayette, and ascertained to be *Atriplex hastata*. Ten sowings were made from these collections, using *Chenopodium album*, *C. hybridum*, *Iva frutescens* on which in the same locality aecia had also been found the following spring, and *Decodon verticillatus*, with infection only on *Chenopodium album*, which was abundant.

The mid-west collections were made, one by Rev. J. M. Bates, at Red Cloud, Neb., and the other by Mr. R. E. Stone, at Lincoln, Neb. These were sown on *Chenopodium album*, *C. hybridum*, *Sarcobatus vermiculatus*, *Monolepis Nuttalliana* and *Cardamine bulbosa*, with infection only on the first-named species.

The far-west collections were made by Prof. P. B. Kennedy, at Reno, Nev. They were sown on *Chenopodium album*, *Atriplex hastata* and *Sarcobatus vermiculatus*, at three different dates, fourteen sowings being made. Abundant infection resulted for all the hosts; nine plants giving equally vigorous results, the other five not thriving well.

These results taken with those of 1906 and 1907 show that no marked biological differences exist. The only indication of restricted adaptation is the failure to infect *Sarcobatus* from Nevada with teliospores from Nebraska, although, as predicted

¹⁶ Jour. Myc. 13: 197. 1907, and 14: 15. 1908.

two years ago,¹⁷ there is no difficulty in producing infection on *Sarcobatus* from Nevada with teliospores from the same region.¹⁸

8. PUCCINIA SEYMOURIANA Arth., on *Spartina cynosuroides* Willd., collected at Lima, Ind., by Mr. George L. Potter, was sown May 28 on *Cephalanthus occidentalis* L., giving rise to numerous pycnia June 6, and aecia June 15.¹⁹

9. PUCCINIA FRAXINATA (Schw.) Arth., collected at Lewes, Del., by Mr. H. S. Jackson, on *Spartina polystachya* Willd., was sown April 25 on *Adelia ligustrina*, *Ligustrum vulgare* and *Fraxinus lanceolata*, with infection only on the last-named species. Again on May 2 it was sown on *F. lanceolata*, giving very abundant pycnia May 13, and aecia June 2.

Another collection from the same locality, but on *Spartina stricta* Roth, was sown on *Smilax hispida* and *Fraxinus lanceolata*, with infection on the last species only.

Collections of aecia, which morphologically are identical with those of *Fraxinus*, have been made on *Ligustrum vulgare* in New York, and *Adelia segregata* in Florida. In 1904 and 1905 attempts were made to grow aecia on plants of these genera, but without success. As the telia came from the western plains, it was thought that telia from the Atlantic sea coast might show less restricted adaptation. So far we are unable to detect any difference in behavior between the rust of the salt marshes of the coast and that of the prairies of the west. It yet remains to try telia from the south along the gulf coast.²⁰

10. PUCCINIA TOMIPARA Trel., on *Bromus purgans* L., collected at Scotia, Neb., by Rev. J. M. Bates, was sown on *Clematis virginiana* L. and *Thalictrum dioicum* L., May 29, giving pycnia on the first-named host only June 7, and aecia June 16, both in abundance.²¹

11. PUCCINIA ASPERIFOLII (Pers.) Wettst., on *Secale cereale* L., collected by Mr. A. G. Johnson at Lafayette, Ind., July 21,

¹⁷ Jour. Myc. 13: 198. 1907.

¹⁸ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; and 14: 15. 1908.

¹⁹ For previous cultures see Jour. Myc. 12: 24. 1906.

²⁰ For previous cultures see Bot. Gaz. 29: 275. 1900; Jour. Myc. 11: 57. 1905; 12: 16. 1906; and 14: 14. 1908.

²¹ For previous cultures see Jour. Myc. 11: 62. 1905; and 13: 197. 1907.

1908, was sown July 22, on *Lycopsis arvensis* L. On July 31 a few pycnia appeared, but owing to the imperfect growth of the leaf no aecia followed.

This rust has usually gone under the collective name of *P. rubigo-vera* (DC.) Wint., which has been applied to most sub-epidermal grass rusts not having strongly marked morphological characters. The similar leaf-rust of wheat is clearly a distinct species, judging from the failure of European investigators to make it infect *Lycopsis*, from some morphological differences, and from its different period for germination. Teliospores of the leaf-rust from both wheat and rye were tested in the laboratory at the same time by means of drop cultures, and while the rye rust grew readily, the wheat rust showed no germination.

This unequivocal, although scanty result, the first culture of the kind to be made with American material, sets at rest any doubt regarding the identity of the American and foreign leaf-rust on rye. The writer is indebted to the kindness of Dr. P. Magnus, of Berlin, Germany, and Dr. H. O. Juel, of Upsala, Sweden, for seeds of *Lycopsis* from which plants were grown for the culture work.

12. *UROMYCES SCIRPI* (Cast.) Burr., on *Scirpus fluviatilis* (Torr.) A. Gray, collected by the writer at Spirit Lake, Iowa, was sown on *Cicuta maculata* April 6, and gave rise to pycnia April 14, and aecia April 23, both in abundance.

13. *UROMYCES HOUSTONIATUS* (Schw.) Sheldon. In the spring of 1906 Dr. J. L. Sheldon observed a rust appearing on plants of *Sisyrinchium gramineum* Curtis (*S. graminoides* Bickn.), growing in contact with plants of *Houstonia caerulea* bearing *Aecidium houstoniatum* Schw. The rust on *Sisyrinchium* proved to be *Uromyces Murrillii* Ricker, until then only once collected, at the type locality in Maine. Dr. Sheldon has since made further studies in the field, and also convincing inoculations,²³ and at the same time supplied ample material for repeating his results. The methods used for other species, however, have not proved available for this one, whose teliospores do not enter a resting condition, but germinate in the sorus as soon as mature. It is the only

²³ For previous cultures see Jour. Myc. 13: 199. 1907; and 14: 17. 1908.

²⁴ Torrey 6: 249. 1906; and 9: 54. 1909.

heteroecious rust known to the writer, having all spore forms and yet leptopuccineous. Plants of *Sisyrinchium* bearing the rust, sent by Dr. Sheldon in 1906, flourished well in the greenhouse, but the rust gradually disappeared during the following winter. The experience was repeated in 1907. In both cases by March or April the rust had died out and did not again appear, although the plants produced fresh leaves and flourished throughout the winter months and the whole year.

Living plants of *Houstonia caerulea* bearing aecia, sent by Dr. Sheldon from Morgantown, W. Va., May 3, were potted intermixed with plants of *Sisyrinchium gramineum*. On June 8 a few uredinia were observed, but did not multiply. On May 18 similar plants were sent by Mr. H. S. Jackson from Newark, Del. These were put into small pots, and on May 23 arranged over plants of *Sisyrinchium* under a belljar, where they remained three days. On June 7 a great abundance of uredinia was observed, and on July 22 telia also in abundance. As both urediniospores and teliospores are pale and inconspicuous, they doubtless appeared earlier than the record shows.

14. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw., on *Juniperus virginiana* L., was collected by Mr. F. D. Kern and the writer at Mammoth Cave, Ky., in two rather unusual forms. One form had very large galls, very irregular and much divided. The other had very small galls, with one to three telia each, the extruded part of the telia being noticeably fusiform. Both of these forms appeared so different from the forms usually collected farther north, that it seemed possible they might be specifically distinct.

The large form was sown April 13 on *Malus Malus* (L.) Britt., *M. coronaria* (L.) Mill. and *Crataegus punctata* Jacq. On *M. Malus* pycnia appeared April 23, but the infection was so pronounced that the leaves were distorted and injured to an extent that precluded the formation of aecia, the leaves gradually dropping until September 26, when two, the only ones still remaining, were removed for the herbarium. On *M. coronaria* abundant pycnia appeared April 21, followed duly by aecia of characteristic appearance. The *Crataegus* remained free from infection.

The small form was sown April 13 on *Malus coronaria* and

Crataegus punctata, giving a few pycnia on the first, not noticed until May 4, and abundant pycnia on the last, showing April 21. Both hosts matured characteristic aecia by the latter part of June.²⁴

15. *GYMNOSPORANGIUM GLOBOSUM* Farl., on *Juniperus virginiana* L., collected by Mr. A. B. Seymour at Manchester, Mass., was sown April 29 on *Malus Malus*, producing no infection, and on *Crataegus Pringlei* Sarg. (seedling from tree determined by Mr. W. W. Eggleston), giving abundant pycnia, and followed by equally abundant aecia. Another collection made by Mr. F. D. Kern and the writer at Mammoth Cave, Ky., was sown April 13, on *Crataegus* sp., giving pycnia April 25, but nothing further, due to the death of the host.²⁵

16. *GYMNOSPORANGIUM CLAVIPES* C. & P., on *Juniperus virginiana* L., collected at Mammoth Cave, Ky., by Mr. F. D. Kern and the writer, was sown on two plants of *Crataegus* sp., April 13, and gave pycnia on April 25, followed by aecia by the middle of June. A sowing two days later on *Aronia nigra* gave no infection.

Another collection on the same host, made by Dr. G. P. Clinton at New Haven, Conn., was sown May 2 on *Amelanchier erecta* with no infection, and on *Crataegus* sp., giving a few pycnia, but the early maturity of the leaves checked further development.²⁶

17. *GYMNOSPORANGIUM CLAVARIAEFORME* (Jacq.) DC., on *Juniperus Sibirica* Burgsd., collected by Mr. E. Bethel at Eldorado Springs, Colo., was sown April 28 on the leaves, petioles and stems of *Amelanchier erecta* Blanch., giving pycnia May 5, and aecia May 23, both in great abundance.²⁷

18. *GYMNOSPORANGIUM NELSONI* Arth., on *Juniperus scopulorum* Sarg., collected by Mr. E. Bethel at Eldorado Springs, Colo., was sown May 2 on *Amelanchier erecta* and *Sorbus americana*, both showing abundance of pycnia May 10. On the first host no further development took place, as the plant was not vig-

²⁴ For previous cultures see Jour. Myc. 12: 13. 1906; 13: 200. 1907; and 14: 17. 1908.

²⁵ For previous cultures see Jour. Myc. 13: 200. 1907; 14: 18. 1908.

²⁶ For previous cultures see Jour. Myc. 14: 18. 1908.

²⁷ For previous cultures see Jour. Myc. 14: 19. 1908.

orous. On the second host abundant and characteristic aecia were formed.²⁸

19. GYMNOSPORANGIUM BETHELI Kern, on *Juniperus scopulorum*, collected by Mr. E. Bethel at Eldorado Springs, Colo., was sown May 11, on *Pyrus communis*, with no infection, and on *Sorbus americana*, and *Crataegus* sp., both giving numerous pycnia, on the former host showing May 19, and on the latter not seen until May 31, although probably appearing earlier. The pycnia in both cases were followed by an abundance of characteristic aecia, well formed by July 7.²⁹

20. GYMNOSPORANGIUM BOTRYAPITES (Schw.) Kern, on *Chamaecyparis thyoides* (L.) B.S.P., collected by Mr. H. S. Jackson at Newfield, N. J., was sown on *Amelanchier intermedia* Spach, May 18, giving an abundance of pycnia May 28. Although galls followed the pycnia, no aecia were formed owing to the early maturity of the leaves. This is the *Gym. biseptatum* Ellis. The rather extended synonymy is given by Kern.³⁰ Inconclusive cultures of this species were made by Dr. W. G. Farlow in 1877 and 1883. In 1886 Dr. Roland Thaxter³¹ made cultures, and raised both pycnia and aecia, repeating his work at a later date.

21. GYMNOSPORANGIUM CORNUTUM (Pers.) nom. nov. Telia on the branches of *Juniperus Sibirica* Burgsd. were collected May 19, 1908, by Mr. F. D. Kern and Mr. E. Bethel, at Palmer Lake, Colo., and sown May 23 on *Sorbus americana*, giving an abundance of pycnia June 1, followed by numerous aecia. A second sowing was made on another plant of the same host May 25, with equally successful results, the pycnia showing June 5. In both cases the aecia were mature by August 10. A sowing May 25 on *Malus Malus* gave no infection.

Although the horn-like aecia of this species are common and often collected, this is the first time that the telia have been found in America. The telia occur on the bark of the small branches, and not at all or only rarely on the leaves. In Europe cultures of this species were made by Oersted, of Denmark, in 1866, and an account with excellent illustrations of both aecia and telia was

²⁸ For previous cultures see Jour. Myc. 13: 203. 1907; and 14: 18. 1908.

²⁹ For previous cultures see Jour. Myc. 14: 23. 1908.

³⁰ Bull. Torrey Club 35: 506. 1908.

³¹ Proc. Am. Acad. 22: 263. 1887.

published the same year.³² Cultures have also been made since, but most investigators in the discussion of their results have confused this with other species.

The form which has been most persistently confused in the telial stage with the present species is what in Europe has been called *G. tremelloides* Hartig, which has much larger and otherwise different telia on the bark of the larger branches of the same species of juniper, but whose aecia are the true *Roestelia penicillata*, and although occurring on *Sorbus*, are easily distinguished by being fimbriate instead of horn-like. Mr. Kern³³ has recently shown from partly circumstantial evidence that this species is the *Tremella juniperina* L., and should be called *G. juniperinum* (L.) Mart. This disposition of the name, *G. juniperinum*, appears to leave no available name under *Gymnosporangium* for the present species, and a new combination is therefore necessary. The earliest specific name is that given by Persoon to the aecial form in 1791, *Aecidium cornutum*, the first species listed under the newly established genus *Aecidium*.

The other form included by European investigators with the present species has very small telia on the leaves of the same juniper, and horn-like aecia on *Aronia*. This is discussed in the following paragraphs under the name *G. Davisii* Kern.

22. *GYMNOSPORANGIUM DAVISII* Kern. It is with more than usual satisfaction that I report the successful culture of this rust, as it completes a knowledge of the life cycle of a trio of species known to some extent in both Europe and America for many decades, but much confused and misunderstood. The telia occur on the leaves of *Juniperus Sibirica*, and have been sent in previous years by Dr. J. J. Davis, from Wind Lake near Racine, Wis., but could not be made to germinate. A collection made in the same locality on May 24, 1908, by Dr. J. J. Davis and Mr. F. D. Kern, was sown May 25 on *Aronia nigra*, *Amelanchier erecta* and *Sorbus americana*, with infection only on the *Aronia*, which showed pycnia June 12, and well matured aecia Sept. 17. Another sowing was made May 25 on *Aronia nigra*, producing a few pycnia

³² Overs. Danske Vid. Selsk. Forh. 1866: 185-196. pl. 3, 4, with full abstract in Bull. Soc. Roy. Dan. Sci. 1866: 15-16.

³³ Science 27: 931. 1908.

June 15, but did not further develop owing to weakness of the host.

The aecia of this species have the same horn-like appearance as those of *G. cornutum*, already discussed, and the two are usually included under the same name. The only culture known to the writer, showing that the form on *Sorbus* and the similar one on *Aronia* are distinct, was made by Dr. Ed. Fischer⁸⁴ of Bern, Switzerland, and published in November, 1907. On May 29 of that year he made a sowing of teliospores from *Juniperus communis* on *Sorbus Aria*, *S. torminalis*, *S. hybrida*, *S. Aucuparia*, *Amelanchier Botryapium* and *Aronia rotundifolia* (*Amelanchier vulgaris*), and obtained an infection only on *Aronia*. He concluded from this result that the form on *Aronia* is distinct from that on *Sorbus*, but made no suggestion regarding the nomenclature. Mr. Kern,⁸⁵ however, finds diagnostic characters to separate the forms in both aecia and telia, and has supplied a name. The cultures by Dr. Fischer were not known to the writer until long after the above studies had been concluded.

23. MELAMPSORA MEDUSAE Thüm., on *Populus tremuloides* Michx., collected at Boulder, Colo., by Mr. E. Bethel, was sown April 7 on *Ribes rubrum*, *R. Cynosbati* and *Larix laricina*. The only infection was on the *Larix*, showing pycnia April 14, and aecia April 21.⁸⁶ When the sowing was made, it was supposed that the rust in hand was *Melampsora albertensis* Arth.; but after the result was obtained a careful inspection of the remaining material of the collection brought to light the fact that while the leaves were conspicuously covered with that rust, they also bore some sori of the more common species, and it is believed that the infection came from the latter, as recorded above.

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME:—
The following species have never been cultivated, in America or elsewhere, so far as the writer knows. Much credit for the ample results is due to the mycologists who have coöperated in the work by making invaluable observations in the field and supplying suit-

⁸⁴ Archiv Sci. Phys. et Nat. 24: —. Nov. 1907.

⁸⁵ Bull. Torrey Club 35: 507. 1908.

⁸⁶ For previous cultures see Jour. Myc. 10: 13. 1904; 11: 52. 1905; and 12: 13. 1906.

able culture material with which to test their suggestions. The segregation of three additional species of western grass rusts of the type of *Puccinia rubigo-vera* is especially gratifying.

1. PUCCINIA ABSINTHII DC., on *Artemisia dracunculoides* Pursh, collected March 14, 1908, at Boulder, Colo., was sown on a plant of the same host species April 9. Another collection on the same host, collected March 24, 1908, at Spirit Lake, Iowa, by the writer, was similarly sown April 8. Both sowings gave rise to numerous pycnia first observed April 25, but doubtless appearing fully a week sooner, and were followed by abundant uredinia April 27. Owing to the early maturity of the leaves, no telia were produced in either case.

The results demonstrate that this rust has no aecial stage in its life cycle. As no pycnia in connection with the uredinia had been recorded for the species, either in America or Europe, and as aecia on various species of *Artemisia* are often collected in America, the status of the species had heretofore been most uncertain. The situation was changed, but still unsettled, by the production of aecia on *Artemisia dracunculoides* in the cultures of last year,³⁷ which were grown from telia on *Carex stenophylla*. The present cultures very satisfactorily complete our knowledge of the two most common rusts on *Artemisia*.

2. PUCCINIA on *Carex comosa* Boott, collected at Lewes, Del., Nov. 15, 1907, by Mr. H. S. Jackson (no. 1858), was sown April 25, on *Iva frutescens*, *Urtica gracilis*, and *Smilax hispida*, with no infection, the *Smilax* leaves, however, having died before infection could have shown. Another sowing was made May 22 on the same hosts, and also on *Myrica cerifera* and *Ambrosia trifida*. There was no infection except in the case of *Smilax*, on which pycnia were noticed June 8, although they might have appeared sooner, and were followed by aecia June 24.

The clues to this connection of telia and aecia were slight. In reference to his collection Mr. Jackson wrote that "in the locality from which the specimen came was a vine of *Smilax rotundifolia* with aecia," but he laid little stress on this association, and did not even retain a specimen of the *Smilax* rust. Upon visiting the locality again in April no *Smilax* aecia could be found, doubt-

³⁷ See Jour. Myc. 14: 21. 1908.

less because too early in the season. Some additional probability of the connection, however, was secured from a microscopic examination. The urediniospores of the *Carex* rust proved to be remarkably large, while the aeciospores on *Smilax*, belonging to *Aecidium macrosporum* Peck, are also unusually large, as the name indicates. But on the other hand the western *Smilax* aecia belong to a grass rust, and most *Carex* rusts have aecia on composite hosts. It is, therefore, more than usually gratifying to complete the life cycle of this heretofore undetected *Carex* rust. It is probably a more widely distributed species than shown by the range of the present known aecial collections, all of which are eastern, except one from Kansas.

***Puccinia macrospora* (Peck) nom. nov.**

(*Aecidium macrosporum* Peck, 23rd Rep. N. Y. St. Mus. 61. 1873.)

O. Pycnia epiphyllous, few in groups on slightly discolored spots, not conspicuous, subepidermal, in vertical section flattened-globoid, 128–160 μ in diameter by 80–100 μ high.

I. Aecia hypophyllous, chiefly in annular groups 1.5–5 mm. across, rather short, 0.1–0.2 mm. in diameter; peridial cells linear-rhomboidal, 32–42 μ long, outer wall thin, smooth, inner wall somewhat thicker, moderately verrucose; aeciospores globoid, very large, 32–42 by 37–51 μ , wall colorless, medium thick, 1.5–2.5 μ , thicker above, 5–10 μ , rather coarsely verrucose.

On *Smilax hispida* Muhl., Long Branch, N. J., July, 1870, G. W. Clinton; Manhattan, Kans., June 25, 1886, W. A. Kellerman; *S. rotundifolia* L., Riverhead, Suffolk Co., N. Y., 1869, Charles H. Peck (type); Brown's Mills, N. J., June 26, 1889, B. Halsted; Seaford, Del., July 9, 1907, H. S. Jackson; Lewes, Del., June 6, 1908, M. T. Cook & H. S. Jackson.

II. Uredinia amphigenous, scattered or in longitudinal series, oblong, 0.5–1 mm. long, tardily dehiscent; urediniospores obovate or narrowly ellipsoid, rather irregular, very large, 26–37 by 40–60 μ , often narrowed below to a thickened hilum; wall golden yellow, evenly thick, 2.5–3.5 μ , echinulate with prominent points 3–4 μ apart; pores obscure, 2 or sometimes 3, equatorial.

III. Telia chiefly hypophyllous, scattered or in longitudinal series, oblong or linear, 0.5–1.5 μ long, finally naked, pulvinate, chocolate-brown, ruptured epidermis noticeable; teliospores clavate, 16–23 by 61–67 μ , usually rounded or obtuse above, narrowed below, usually slightly constricted at the septum; wall pale

cinnamon-brown, paler below, medium thin, $1.5-2.5\mu$, much thicker at apex, $9-16\mu$; pedicel nearly colorless, one half to once length of spore.

On *Carex comosa* Boott, Lewes, Del., Nov. 15, 1907, *H. S. Jackson* 1858.

3. *PUCCINIA* on *Carex pratensis* Drej. An observation by Mr. E. Bethel at Tolland, Colo., July 25, 1907, when aecia on *Agoseris* were found in very close proximity to rusted *Carex pratensis*, led to a collection of telial material from the same spot in October following, and a successful culture. The teliospores were sown May 13, on a plant of *Agoseris glauca*, raised from seed previously sent by Mr. Bethel, and pycnia began to show May 19 in the greatest abundance. The infection was so heavy that the plant was killed before aecia were formed.

A study of all available data regarding this species has led to the conclusion that a very large part of all collections of aecia on the various species of *Agoseris* belong to this species, and not as sometimes assumed to *Puccinia Troximontis* Peck, which is common on the same hosts, but probably has no aecial stage. A description of the species is appended, but no attempt will be made at this time to cite the numerous known localities or to map out the range, which doubtless embraces much of the western mountainous region.

***Puccinia patruelis* sp. nov.**

O. Pycnia amphigenous, rather few, in groups $0.5-1$ mm. across, punctiform, inconspicuous, honey-yellow becoming brownish, subepidermal, in vertical section globoid, $96-125\mu$ in diameter by $80-100\mu$ high; ostiolar filaments $30-55\mu$ long.

I. Aecia amphigenous, numerous in crowded groups $1-4$ mm. across, often surrounding groups of pycnia; peridium colorless, rather short, margin finely lacerate; peridial cells rhomboidal, $18-25\mu$ long, outer wall rather thick, $3-4\mu$, striate, smooth, inner quite thin, finely verrucose; aeciospores mostly globoid, $13-16$ by $16-21\mu$; wall colorless, thin, 1μ , very finely verrucose, appearing smooth when wet.

On *Agoseris glauca* (Pursh) Greene (*Troximon glaucum* Pursh), Tolland, Colo., July 25, 1907, *E. Bethel*.

II. Uredinia chiefly hypophyllous, scattered, oblong or oval, $0.4-0.6$ mm. long, rather tardily naked, cinnamon-brown; urediniospores ellipsoid or obovate-ellipsoid, $13-19$ by $19-26\mu$; wall golden-brown, moderately echinulate, pores 2, lateral and opposite, slightly superequatorial.

III. Telia hypophyllous, scattered, numerous, oval or oblong, 0.3–0.8 mm. long, early naked, dark blackish-brown, conspicuous, ruptured epidermis noticeable; teliospores broadly clavate or spatulate, 15–23 by 32–63 μ , apex rounded or obtuse, base usually narrowed, slightly constricted at the septum; wall dark chestnut-brown, paler below, moderately thin, 1.5–2 μ , thicker at apex 7–13 μ ; pedicel slightly colored next the spore, somewhat shorter than the spore.

On *Carex pratensis* Drej., Tolland, Colo., July 25 and Oct. 19, 1907, E. Bethel (type).

4. PUCCINIA CINEREA Arth., on *Puccinellia airoides* (Nutt.) Wats. & Coult., collected at Arvada, Colo., by Mr. E. Bethel, was sown April 22 on *Oxygraphis Cymbalaria* (Pursh) Prantl (*Ranunculus Cymbalaria* Pursh), giving rise to pycnia April 30, and aecia May 4. A duplicate sowing was made May 7, and pycnia followed May 14, with aecia May 19. In each case the sori were produced in abundance.

The clue for this combination was obtained by Rev. J. M. Bates, who had found the same species of rust on *Poa* growing in proximity to rusted *Oxygraphis* in a number of places in Nebraska under conditions which seemed to make their genetic connection almost certain.⁸⁸ Unfortunately the culture material sent by him both this year and previously failed to germinate. The plants of *Oxygraphis* used for the cultures were supplied by him. The Colorado material was received unnamed, and from its general appearance was supposed to be on some species of *Poa*, until after the work was completed when the determination was made by Mrs. Agnes Chase of the agrostological division of the National Herbarium.

5. PUCCINIA on *Koeleria cristata*. A number of collections of this rust were sent by Mr. E. Bethel, who made the suggestion several times that it was probably connected with aecia on *Mahonia*, a suggestion that seemed to us unimportant, as the aecia on *Mahonia* in Europe are known to belong to *Puccinia poculiformis*, a cosmopolitan rust wholly unlike the one on *Koeleria*. As a collection made by Mr. Bethel April 25, 1908, at Plainview, Colo., showed germination, and as he had written that "the rust on *Koeleria* undoubtedly belongs to the aecia on *Mahonia*, for I have

⁸⁸ See Bull. Torrey Club 34: 584. 1907.

found hundreds of cases to substantiate it—I wish you would try it,” a sowing was accordingly made April 30 on *Mahonia Aquifolium*. Abundance of pycnia appeared May 14, and aecia May 24. Another sowing was made June 2 on *Berberis vulgaris*, but gave no infection.

Upon examination of the available collections of aecia on *Mahonia*, which had not been given careful study before, it was discovered that they differed in a characteristic way from those on *Berberis*. They are smaller, do not produce a thickening of the leaf, and cause a rounded area of the leaf on which each group is seated to die early, turning brown and dry. From our inquiry it seems probable that no aecia on *Mahonia* belonging to *Puccinia poculiformis* have yet been found in America, although they have been so cited, but that they all should go under the present species, a description of which follows.

***Puccinia Koeleriae* sp. nov.**

O. Pycnia chiefly epiphyllous, numerous, rather loosely arranged in groups 0.5–2 mm. across, on discolored spots, punctiform, not conspicuous, subepidermal, honey-yellow becoming blackish, in vertical section lenticular, 80–100 μ in diameter by 45–65 μ high.

I. Aecia hypophyllous, numerous, usually crowded in groups 1–3 mm. or more across, on discolored spots 1–7 mm. across, which finally die and turn blackish-brown, short cylindrical, 0.4–0.7 mm. high by 0.1–0.2 mm. in diameter; peridium colorless, cells rhomboidal in radial section, outer wall rather thick, 5–7 μ , transversely striate, inner wall medium thin, 1–3 μ , verrucose; aeciospores globoid, 13–20 by 18–26 μ , wall colorless, rather thin, 1–1.5 μ , evenly and finely verrucose.

On *Mahonia Aquifolium* (Pursh) Nutt. (*Berberis Aquifolium* Pursh, *B. repens* Lindl.), Ouray, Colo., July 26, 1897, C. L. Shear, July 2, 1907, E. Bethel; Victor, Idaho, July 10, 1901, E. D. Merrill & E. N. Wilcox; Wild Horse Island, Mont., Aug. 13, 1908, M. E. Jones 7718; Yellow Bay, Mont., Aug. 10, 1908, M. E. Jones 7723.

II. Uredinia amphigenous, in groups on discolored spots, oblong or linear, 0.1–0.2 mm. wide by 0.5–1.5 mm. long, soon naked, pulverulent, cinnamon-brown, ruptured epidermis conspicuous; paraphyses numerous, capitate or clavate-capitate, 10–16 by 42–65 μ ; urediniospores broadly ellipsoid, 19–26 by 23–34 μ ; wall cinnamon-brown, medium thick, 2–2.5 μ , rather closely echinulate-verrucose; pores 4–6, scattered.

III. Telia hypophyllous, scattered, oblong or linear, about 0.1

mm. wide by 0.5–1.5 mm. long, sometimes confluent, long covered by the epidermis, grayish-black; teliospores clavate or oblong-clavate, 15–21 by 45–55 μ , obtuse or truncate above, narrowed below; wall chestnut-brown, paler beneath, thin, about 1 μ , thicker at apex, 3–5 μ , smooth; pedicel short, slightly colored.

On *Koeleria cristata* (L.) Pers., Ouray, Colo., Aug. 23, 1907, *E. Bethel* (type); Boulder, July 31, 1905, Plainview, Aug. 5, 1905, and April 25, 1908, Marshall, June 24, 1905, Golden, July 27, 1908, all in Colo., *E. Bethel*.

6. PUCCINIA on *Bromus*. A subepidermal rust on various species of *Bromus* is common in the western mountains. Collections made by Prof. E. W. D. Holway, Sept. 4 and 7, 1907, on *B. Pumpellianus* Scribn., at Banff, Alb., were found close to *Thalictrum* bearing aecia, and believed by him to be connected, but the teliospores could not be brought to germination. A collection on *B. Porteri* (Coul.) Nash, made by Mr. F. D. Kern, Sept. 2, 1908, at Ouray, Colo., with much more definite and certain field clues, being intermixed with *Thalictrum sparsiflorum* bearing aecia, was found more tractable and was sown April 30, on *Thalictrum dioicum*, giving rise to pycnia May 9, and aecia May 30, both in abundance.

It has long been recognized that the aecia on *Thalictrum* in America belong to a number of species. No cultures, however, have been made heretofore, and only the form associated with *Tranzschelia punctata* (*Puccinia Pruni-spinosae*), common in the eastern part of the country, has been definitely placed. In Europe cultures have shown aecial forms on *Thalictrum* to belong to telia on *Agrostis*, *Poa*, *Triticum*, *Elymus* and *Polygonum*. Whether any of these occur in America, remains to be determined, although the last two are to be expected. The species in hand appears to be unrecorded, and a description is therefore appended. It is closely related, both morphologically and in its hosts, with *P. tomiopara* Trel., which ranges throughout the central and eastern states with its aecia on *Clematis* and telia on *Bromus*. The question of their exact relationship must be left to future investigation.

***Puccinia alternans* sp. nov.**

O. Pycnia epiphyllous, crowded in groups 0.5–4 mm. across, not conspicuous, subepidermal, in vertical section globoid, 60–96 μ in diameter, 50–80 μ high.

I. *Aecia* chiefly hypophyllous, in annular or often crowded groups 1.5–5 mm. across, cylindrical, 0.4–0.8 mm. high; peridium colorless, margin slightly recurved, finely lacerate, cells rhombic in longitudinal section, 21–29 μ long, walls transversely striate, outer thick, 9–12 μ , inner somewhat thinner, 5–7 μ , finely verrucose; aeciospores globose or broadly ellipsoid, 15–20 by 17–24 μ , wall colorless, thin, 1–1.5 μ , finely and evenly verrucose.

On *Thalictrum Fendleri* Engelm., Gunnison Co., Colo., Sept. 2, 1899, *E. Bartholomew*; Salt Lake Co., Utah, July 12, 1904, *A. O. Garrett* (Sydow, Ured. 1935; Vestergren, Micr. rar. sel. 1002; and Garrett, Fungi Utah. 76); *T. occidentale* A. Gray, Victor, Idaho, July 11, 1901, *E. D. Merrill* & *E. N. Wilcox* 1256; Banff, Alberta, July 24, 1901, and July 6, 1907, *E. W. D. Holway*; *T. sparsiflorum* Turcz., Ouray, Colo., Sept. 2, 1907, *F. D. Kern*; Minnehaha, Colo., Aug. 13, 1906, *F. E. Clements*; *T. venulosum* Trel., Spicer, Routt Co., Colo., July, 1903, *L. N. Goodding*; Macdougall Park, Mont., July 31, 1908, *M. E. Jones*.

II. *Uredinia* amphigenous, scattered, oblong or linear-oblong, 0.2–0.8 mm. long, rather early naked, somewhat pulverulent, cinnamon-brown, ruptured epidermis conspicuous; urediniospores very broadly ellipsoid or slightly obovate-ellipsoid, 19–25 by 23–29 μ ; wall light cinnamon-brown, moderately thick, 2–2.5 μ , finely echinulate; pores about 6, scattered.

III. *Telia* amphigenous, scattered, oblong or linear-oblong, 0.4–1 mm. long by 0.2–0.4 mm. wide, long covered by the epidermis, dark blackish-brown; teliospores clavate or clavate-oblong, 13–19 by 31–61 μ , usually truncate or obtuse above, narrowed below, slightly or not constricted at the septum; wall chestnut-brown, paler below, rather thin, 1–1.5 μ , thicker at apex, 3–5 μ , smooth; pedicel somewhat colored, very short.

On *Bromus Porteri* (Coul.) Nash, Ouray, Colo., Sept. 2, 1907, *F. D. Kern* (type); Parley's Canyon, Utah, Aug. 18, 1908, *A. O. Garrett* 1137; *B. Pumpellianus* Scribn., Banff, Alberta, Sept. 4 and 7, 1907, *E. W. D. Holway*; *B. Richardsoni* Link, Ouray, Colo., Aug. 23, 1907, *E. Bethel*.

7. PUCCINIA on *Agropyron*. Two collections of rusted *Agropyron biflorum*, collected Sept. 2, 1907, at Lake Louise, in the Canadian Selkirks, were sent by Prof. E. W. D. Holway, with the suggestion that one of them be sown on *Thalictrum* and the other on *Aquilegia*. One collection failed to germinate, the other was sown April 18 on *Aquilegia canadensis* and *Thalictrum dioicum*, with infection only on the first, the leaves of which soon began to show hypertrophy of the tissues, and in six to seven days small yellow,

translucent spots above, followed on May 8 by aecia beneath. No pycnia were formed, as sections and microscopic examination fully proved. All American collections of aecia on *Aquilegia* in the herbarium were found to have either no pycnia associated with the groups of aecia, or more rarely only a few pycnia, a condition not before noted in heteroecious rusts of grasses and sedges.

This rust is undoubtedly quite well distributed in the western mountains, and embraces a large part of all aecia yet found in America on *Aquilegia*. It is apparently distinct from *Puccinia Agrostidis* Plowr., a European species with aecia on *Aquilegia*, and is, therefore, described as new, although there is much morphological similarity between the two.

***Puccinia obliterata* sp. nov.**

O. Pycnia few, frequently obsolete, epiphyllous, gregarious, inconspicuous, honey-yellow, in vertical section globoid, 80–107 μ in diameter; ostiolar filaments 40–75 μ long.

I. Aecia chiefly hypophyllous, thickly crowded in groups 1–5 mm. across, on slightly larger discolored spots, rather short; peridium colorless, margin somewhat erose, cells rhomboidal in longitudinal section, 16–24 μ in length; aeciospores globoid, or often somewhat angular, 15–19 by 18–25 μ , wall colorless, thin, about 1 μ , very minutely verrucose, appearing nearly smooth when wet.

On *Aquilegia caerulea* James, Buffalo Pass, Park Range, Colo., Aug. 13, 1898, C. L. Shear & E. A. Bessey (Ellis & Ev., Fungi Columb. 1474); Trapper's Lake, Colo., Aug. 14, 1894, Prof. C. S. Crandall 100; Beulah, N. Mex., June 29, 1909, Mrs. W. P. Cockerell; North Vermilion Creek, Sweetwater Co., Wyo., July 17, 1897, A. Nelson; *A. elegantula* Greene, Ouray, Colo., July 12, 1907, F. E. & E. S. Clements (Crypt. Form. Colorad. 592); *A. flavescens* Wats., Banff, Alb., July 25, 1901, Laggan, Alb., July 21, 1907, E. W. D. Holway; *A. formosa* Fisch., Skamania Co., Wash., Aug. 12, 1886, W. N. Suksdorf; *A. truncata* Fisch. & Mey., Jackson Co., Oreg., July 9, 1903, E. B. Copeland (Sydow, Ured. 1767).

II. Uredinia chiefly hypophyllous, scattered, linear, small, soon naked, pulverulent, cinnamon-brown, ruptured epidermis noticeable; urediniospores globoid or broadly ellipsoid, 16–23 by 19–29 μ ; wall light cinnamon-brown, medium thin, 1.5–2.5 μ , finely echinulate-verrucose, pores 6–8, scattered.

III. Telia chiefly epiphyllous, scattered, often crowded and con-

fluent, oblong or linear, 0.1–0.3 mm. wide by 0.5–2 mm. long, tardily naked, blackish; teliospores clavate or clavate-oblong, 13–19 by 29–51 μ , obtuse or somewhat rounded above, narrowed below, very slightly or not constricted at the septum; wall dark chestnut-brown, paler below, thin, 1–1.5 μ , thicker at apex, 3–5 μ . smooth; pedicel colored, short.

On *Agropyron biflorum* R. & S., Lake Louise, Laggan, Alb., Sept. 2, 1907, *E. W. D. Holway* (type); *A. caninum* (L.) Beauv., Laggan, Alb., Sept. 2, 1907, *E. W. D. Holway*.

8. PUCCINIA MUHLENBERGIAE Arth. & Holw. collected by Mr. E. Bartholomew, March 23, 1908, at Stockton, Kans., on *Muhlenbergia glomerata* Trin., was sown at different dates on ten different species of host plants, including *Hibiscus militaris* Cav., with no infection. Another collection with same data, but on *M. mexicana* (L.) Trin., was sown April 22 on *Dalea laxiflora* with no infection, again May 15 on same host, and on *Ceanothus americanus* and *Xanthoxylum americanum*, still with no infection. A third attempt was made by sowing June 12, on *Baptisia tinctoria*, *Rudbeckia laciniata* and *Callirrhoe involucrata*. Little culture work is done so late in the season as this last attempt, and it was supposed no infection had been secured, when on July 23 an abundance of aecia, accompanied by a few pycnia, were noticed on the plant of *Callirrhoe*. Although not under continuous observation, it is believed they came from the sowing.

Many attempts have been made to cultivate the rusts found on various species of *Muhlenbergia*,³⁹ twenty-six species of hosts having been used. The year following the reported success by Prof. W. A. Kellerman⁴⁰ in sowing rust from *Muhlenbergia mexicana*, collected in Ohio, on *Hibiscus Moscheutos*, a strong effort was made to repeat his work with material from Kansas and Nebraska, but with no definite result. Mr. E. Bartholomew more than once suggested that the material he supplied was connected with *Aecidium Napæae* A. & H., as the results have seemingly shown.

The aecia obtained by Professor Kellerman, and those secured by the writer, are quite unlike. The former are rather large and

³⁹ For record of unsuccessful sowings see Bot. Gaz. 35: 11, 1903: Jour. Myc. 11: 51, 1905; and 13: 192, 1907.

⁴⁰ Jour. Myc. 9: 109, 232, 1903.

numerous, and bright orange-yellow, the latter are small, fewer and nearly or quite colorless. Upon a careful examination of the telial material used in the two successful trials, it is found that while that from Kansas is the true *Puccinia Muhlenbergiae*, that from Ohio is *P. dochmia* B. & C., or at least quite distinct from the other. Considerable more study is needed to fully clear up the relationship of the *Muhlenbergia* rusts.

9. GYMNOSPORANGIUM LIBOCEDRI (P. Henn.) Kern. For many years the only known locality for the telia of this rust has been in northern California at a place rarely visited by botanists. While Mr. F. D. Kern during January, 1908, was working upon material in the herbarium of Dr. W. G. Farlow at Harvard University, a collection of this rust was seen from Eugene, Ore., made by Dr. A. R. Sweetser, of the University of Oregon. There was also in the herbarium a collection, from the same locality and by the same person, of *Aecidium Blasdaleanum* D. & H. on *Crataegus*. This *Aecidium* has also been taken by more than one collector from the region of the *Libocedrus* rust in California. The *Crataegus* rust is stated by Dr. Dietel, in a note appended to the original description, to be "a true *Aecidium*, and does not belong to the genus *Roestelia* comprising the aecidial stages of *Gymnosporangium*." Recent very careful study confirms Dr. Dietel's statement regarding its morphological resemblances, for in the peridial cells, the spores, and the mode of dehiscence, which provide the chief generic characters, it is wholly unlike the form genus *Roestelia*.

In order to secure culture material Dr. Sweetser was appealed to. He responded promptly with telial collections on *Libocedrus decurrens*, which came through the mails in perfectly fresh condition. For his efficient aid Dr. Sweetser is entitled to much credit. A sowing was made April 1 on *Crataegus Pringlei* and *Amelanchier canadensis*, giving no infection on the *Amelanchier*, but on the *Crataegus* numerous pycnia began to show April 12, followed on April 20 by an abundance of well-formed aecia. Another sowing was made on *Crataegus* sp. April 4, resulting in such a heavy infection, the pycnia showing April 14, that the leaves were killed before there was time for aecia to form.

The aecia secured by the culture agree perfectly with *Aecidium*

Blasdaleanum, being wholly lacking in Roestelial characters. The aberrant form of the aecia is to a certain extent paralleled by the unusual form of the telia, which led Dr. P. Hennings to describe the telial stage as a *Phragmidium*.

IO. *GYMNOSPORANGIUM* sp. nov. The series of circumstances leading to the discovery of telia that made the present cultures possible has been briefly narrated in the introductory paragraphs of this report. On April 10, 1908, a collection was made at Mammoth Cave, Ky., by Mr. F. D. Kern and the writer, on the branches of *Juniperus virginiana*, and on the following day a growing plant of the same species only six inches high with large sori on the main axis was obtained. The first collection was sown April 13 on *Porteranthus stipulatus* (*Gillenla stipulacea*), producing an abundance of pycnia April 21, but the plant did not thrive, soon dying outright. Another sowing of the same material was made April 15 on *Porteranthus* and also on *Crataegus punctata*, with no infection on the latter, but very abundant infection on the former, pycnia showing April 23, and aecia May 25. Another sowing April 16 on *Porteranthus* gave such a heavy infection, pycnia showing April 23, that the plant was soon killed. Still another sowing April 27, and one April 28, gave very abundant pycnia May 5, followed by numerous well-grown aecia that matured May 25 from the first sowing, and May 31 from the second. The small plant of *Juniperus* had been potted, and continued to thrive. Teliospores from this living plant were placed on a plant of *Porteranthus* May 11, and on May 17 an abundance of pycnia appeared, followed by numerous aecia that were mature by June 7.

The aecia from the cultures proved to be identical with those collected by Rev. Demetrio in 1884, at Perryville, Mo., and issued as No. 3323 in Rabenhorst-Winter, *Fungi europaei*. They are especially remarkable in the fact that they occur on a non-pomaceous host, an herbaceous perennial, although heretofore the aecia of all species of *Gymnosporangium* have been supposed to occur exclusively on the ligneous plants of the family Malaceae. With the aecia of this species going outside the Malaceae for its host, and those of the preceding species falling outside the genus *Roeselia*, two of the most marked characteristics pertaining to the first stage of the *Gymnosporangia* are shown to have exceptions.

Gymnosporangium exterum Arthur & Kern sp. nov.

O. Pycnia epiphyllous, rather few, very sparsely disposed in definite groups 3–6 mm. across, prominent, subepidermal, in vertical section flattened-globoid, 95–125 μ in diameter by 65–90 μ high; ostiolar filaments 48–65 μ long.

I. Aecia hypophyllous, very sparsely disposed in large groups 4–10 mm. or more across, on larger discolored areas, 0.1–0.3 mm. in diameter by 0.5–0.8 mm. high; peridium soon becoming rather finely lacerate almost to base, spreading but not revolute, cells usually seen only in face view, 10–18 by 58–100 μ , inner wall rugose with rather narrow ridges running downward and outward, side walls rugose, 3–5 μ thick; aeciospores broadly ellipsoid or globoid, 17–21 by 21–26 μ ; wall very pale cinnamon-brown, medium thick, 2–2.5 μ , very finely verrucose, pores evident, 8–10, scattered.

On *Porteranthus stipulatus* (Muhl.) Britton (*Gillenia stipulacea* Nutt., *Spiraea stipulata* Muhl.), Perryville, Mo., 1884, C. H. Demetrio (Rab.-Wint., *Fungi Eur.* 3323); Mammoth Cave, Ky., June, 1870, T. F. Allen.

III. Telia caulicolous, from a permanent mycelium, appearing on fusiform swellings 2–6 cm. long by 0.5–1.5 cm. or more in diameter, causing a considerable roughening and exfoliation of the bark, flattened, irregular and indefinite in outline, usually anastomosing over practically the whole surface of the swelling, light chocolate-brown becoming yellowish by germination; teliospores ellipsoid, 18–23 by 32–42 μ , rounded or sometimes narrowed above and below; wall light cinnamon-brown, rather thin, 1–1.5 μ , usually slightly thicker at apex, pores 1 in each cell, apical; pedicel cylindrical, uniform, slender, 3–4 μ in diameter, very long.

On *Juniperus virginiana* L., Mammoth Cave, Ky., April 10, 1908, J. C. Arthur & F. D. Kern (type).

SUMMARY

The following is a complete list of the successful cultures made during the year 1908. It is divided into two series: species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. Species Previously Reported

1. PUCCINIA KUHNIAE Schw.—Teliospores on *Kuhnia Hitchcockii* A. Nels., sown on *K. eupatorioides* L.

2. PUCCINIA PECKII (DeT.) Kellerm.—Teliospores on *Carex stipata* Muhl., sown on *Onagra biennis* (L.) Scop.

3. PUCCINIA SAMBUCI (Schw.) Arth.—Teliospores on *Carex lurida* Wahl., sown on *Sambucus canadensis* L.

4. PUCCINIA CARICIS-SOLIDAGINIS Arth.—Teliospores on *Carex sparganioides* Muhl., sown on *Solidago canadensis* L.

5. PUCCINIA ELEOCHARIDIS Arth.—Teliospores on *Eleocharis palustris* (L.) R. & S., sown on *Eupatorium perfoliatum* L.

6. PUCCINIA ANGUSTATA Peck.—Teliospores on *Scirpus cyperinus* (L.) Kunth., sown on *Lycopus communis* Bickn. and *L. americanus* Muhl.

7. PUCCINIA SUBNITENS Diet.—Teliospores on *Distichlis spicata* (L.)* Greene, sown on *Chenopodium album* L., *Atriplex hastata* L. and *Sarcobatus vermiculatus* (Hook.) Torr.

8. PUCCINIA SEYMOURIANA Arth.—Teliospores on *Spartina cynosuroides* Willd., sown on *Cephalanthus occidentalis* L.

9. PUCCINIA FRAXINATA (Schw.) Arth.—Teliospores on *Spartina polystachya* Willd. and on *S. stricta* Roth, sown on *Fraxinus lanceolata* Bork.

10. PUCCINIA TOMIPARA Trel.—Teliospores on *Bromus purgans* L., sown on *Clematis virginiana* L.

11. PUCCINIA ASPERIFOLII (Pers.) Wettst.—Teliospores on *Secale cereale* L., sown on *Lycopsis arvensis* L.

12. UROMYCES SCIRPI (Cast.) Burr.—Teliospores on *Scirpus fluviatilis* (Torr.) A. Gray, sown on *Cicuta maculata* L.

13. UROMYCES HOUSTONIATUS (Schw.) Sheldon.—Aeciospores on *Houstonia caerulea* L., sown on *Sisyrinchium gramineum* Curtis.

14. GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE Schw.—Teliospores on *Juniperus virginiana* L., sown on *Malus coronaria* (L.) Mill., *M. Malus* (L.) Britt. and *Crataegus punctata* Jacq.

15. GYMNOSPORANGIUM GLOBOSUM Farl.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus Pringlei* Sarg.

16. GYMNOSPORANGIUM CLAVIPES C. & P.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus* sp.

17. GYMNOSPORANGIUM CLAVARIAEFORME (Jacq.) DC.—Teliospores on *Juniperus Sibirica* Burgsd., sown on *Amelanchier erecta* Blanch.

18. GYMNOSPORANGIUM NELSONI Arth.—Teliospores on *Juniperus scopulorum* Sarg., sown on *Amelanchier erecta* Blanch. and *Sorbus americana* Marsh.

19. GYMNOSPORANGIUM BETHELI Kern.—Teliospores on *Juniperus scopulorum* Sarg., sown on *Crataegus* sp. and *Sorbus americana* Marsh.

20. GYMNOSPORANGIUM BOTRYAPITES (Schw.) Kern.—Teliospores on *Chamaecyparis thyoides* (L.) B.S.P., sown on *Amelanchier intermedia* Spach.

21. GYMNOSPORANGIUM CORNUTUM (Pers.) Arth.—Teliospores on *Juniperus Sibirica* Burgsd., sown on *Sorbus americana* Marsh.

22. GYMNOSPORANGIUM DAVISII Kern.—Teliospores on *Juniperus Sibirica* Burgsd., sown on *Aronia nigra* (Willd.) Britt.

23. MELAMPSORA MEDUSAE Thüm.—Teliospores on *Populus tremuloides* Michx., sown on *Larix laricina* (DuR.) Koch.

B. Species Reported Now for the First Time

1. PUCCINIA ABSINTHII DC.—Teliospores on *Artemisia dracunculoides* Pursh, sown on same host.

2. PUCCINIA MACROSPORA (Peck) Arth.—Teliospores on *Carex comosa* Boott, sown on *Smilax hispida* Muhl.

3. PUCCINIA PATRUELIS Arth.—Teliospores on *Carex pratensis* Drej., sown on *Agoseris glauca* (Pursh) Greene.

4. PUCCINIA CINEREA Arth.—Teliospores on *Puccinellia airoides* (Nutt.) Wats. & Coult., sown on *Oxygraphis cymbalaria* (Pursh) Prantl.

5. PUCCINIA KOELERIAE Arth.—Teliospores on *Koeleria cristata* (L.) Pers., sown on *Mahonia aquifolium* (Pursh) Nutt.

6. PUCCINIA ALTERNANS Arth.—Teliospores on *Bromus Porteri* (Coult.) Nash., sown on *Thalictrum dioicum* L.

7. PUCCINIA OBLITERATA Arth.—Teliospores on *Agropyron biflorum* R. & S., sown on *Aquilegia canadensis* L.

8. PUCCINIA MUHLENBERGIAE Arth. & Holw.—Teliospores on *Muhlenbergia glomerata* Trin., sown on *Callirrhoe involucrata* (T. & G.) A. Gray.

9. GYMNOSPORANGIUM LIBOCEDRI (P. Henn.) Kern.—Teliospores on *Libocedrus decurrens* Torr., sown on *Crataegus Pringlei* Sarg.

10. GYMNOSPORANGIUM EXTERUM Arth. & Kern.—Teliospores on *Juniperus virginiana* L., sown on *Porteranthus stipulatus* (Muhl.) Britt.

CULTURES OF UREDINEAE IN 1909¹

J. C. ARTHUR

The year 1909 marks the beginning of the second decade of culture work by the writer. The present report is preceded by nine other similar reports² covering work done between 1899 and 1908 inclusive, each issued annually except the second one, which covered two years. The following account of the work for the year 1909 is divided into a general introductory part, a list of negative results, in which the sowing of the spores did not bring hoped-for infection but the record seemed worth preserving for use in directing future work, and a list of positive results, in which the sowing of spores caused an infection that gave rise to characteristic fruiting bodies. The successful sowings largely belonged to species previously cultivated, and are recorded to verify or amplify existing knowledge. A small number of successful sowings were made with species never before cultivated, and whose alternate forms had never before been associated.

The work of the year was carried on under adverse and trying conditions. A new building for the experiment station was begun in the previous autumn, and was located upon the ground where for many years a great variety of plants has been grown, especially brought together for this work. It was in effect a small botanical garden filled with plants from all over the continent known to serve as hosts for different species of rusts, and from which plants were in large part drawn for the cultures. As many plants as possible were removed to another plot of ground some distance away, but many species were wholly lost. The seedlings of self-sown annuals were especially missed in providing potted plants for the spring's work. The heavy infectious work had only begun in April when it became necessary to abandon the greenhouses where the work was in progress, so they

¹ Read before the Botanical Society of America at the Boston meeting, December 29, 1909.

² See Bot. Gaz. 29: 268-276, 35: 10-23; Jour. Myc. 8: 51-56, 10: 8-21, 11: 50-67, 12: 11-27, 13: 189-205, 14: 7-26; and Mycol. 1: 225-256.

could be wrecked. The temporary quarters provided in another greenhouse were scarcely in working order before another move was necessary. This time a hastily constructed glass lean-to, placed on the east side of a frame building, was made from the wreckage of the two demolished houses. Good conditions for securing infection could not be uniformly maintained. Not only was the practical part of the work hampered in this manner, but the time required in designing the botanical rooms and furnishings for the new experiment station, making temporary adjustments in the old quarters, and finally moving into the new building, seriously interfered with the correspondence and the excursions by which material and information are brought together for making cultures of untried species.

The chief excursion of the year was made by Mr. F. D. Kern and the writer to South Carolina, with incidental stops in Tennessee and North Carolina. It occupied a week during the middle of March. The first stop was at Knoxville, Tenn., where Prof. S. M. Bain, of the University of Tennessee, courteously aided us in every way possible. Upon our return journey we spent a day at Asheville, N. C. At both places culture material was secured. The trip was especially planned, however, to visit the localities made famous to mycologists by the very important contributions of H. W. Ravenel.

Mr. Ravenel belonged to a distinguished southern family, whose estate lay some miles north of Charleston on the Santee Canal, a water way long since fallen into disuse. It was here that he obtained the material for the five centuries of his *Fungi Caroliniani Exsiccati*, issued during the decade preceding the Civil War. Nearly two days were spent most profitably in this locality. Our work was much facilitated by the intelligent interest of Mr. Octavus Cohen of Monks Corners, the nearest railway town, although not himself a botanist. We were desirous, among other things, to rediscover and identify the uncertain rust from the trunks of cedar trees, issued as no. 87 in the fifth century of the *Fungi Caroliniani*, under the name *Gymnosporangium Juniperi*. We were not only able to do this, deciding that it belongs to the multiform species, *G. nidus-avis*, and not to the one whose name it bears, but in addition we found two hith-

erto undetected species of the same genus, also inhabiting the red cedar, as well as other culture material. The locality is an interesting one, and deserving of further uredinological exploration.

We spent two days at Aiken, in the highlands of South Carolina, where Mr. Ravenel lived after the Civil War had swept away the family wealth. It was here that the work on his *Fungi Americani Exsiccati* was done. We wished especially to obtain further knowledge of *Roestelia hyalina*, a highly characteristic rust on *Crataegus* which is only known from Ravenel's original collection made at Aiken and distributed in 1878 as no. 37 in his *Fungi Americani*. We hoped to find a telial form from which the *Roestelia* could be grown, as we had done last year in the similar case of an isolated *Roestelia* from central Kentucky.³ Unfortunately we failed to obtain any trace of the sought for rust, although we secured other culture material.

During the week following my associate, Mr. Kern, joined a company from the Missouri Botanical Garden at St. Louis, in a day's collecting along the bluffs of the Mississippi River south of St. Louis, securing culture material chiefly of grass and sedge rusts.

Another brief but important trip was made by Mr. Kern the first week in June to Leland in the northern part of the southern peninsula of Michigan, about 300 miles north of Lafayette, Ind. This was in consequence of observations made by Mr. Kern and the writer in that locality during the previous September. Horn-like aecia on *Sorbus*, *Aronia* and *Amelanchier* are quite common in the northern United States and Canada, and often occur in herbaria, usually under the name *Roestelia cornuta*. Morphological studies made by Mr. Kern convinced him some time ago that the similar aecia on the three host genera belong to three independent species of rusts, and since then we have been trying to secure suitable material for cultures. Last year we were able to show that telia of *Gymnosporangium cornutum* on the branches of *Juniperus Sibirica* produced the aecia on *Sorbus*, and that telia of *G. Davisii* on the leaves of the same host produced the aecia on *Aronia*.⁴ In searching in northern Michigan for clues

³ Mycol. I: 226. 1909.

⁴ Mycol. I: 240-242. 1909.

to the *Amelanchier* form we most fortunately found a very small weather-beaten plant of *Amelanchier* not over six or eight inches high, bearing at the time about a score of leaves, and every leaf thickly covered with the characteristic horn-like aecia. No other plants of *Amelanchier* infected with the same sort of aecia could be found in the region, although they often bore aecia of other species. The plant in question did not occur near *Juniperus Sibirica*, although that juniper was very common, but much to our surprise was associated with *Juniperus horizontalis*, a trailing form of the red cedar, that produces circular mats up to fifty feet in diameter and rises only three to five inches from the ground. No other form of red cedar occurs in the region, and even this one is not abundant. In the midst of one of these red cedar mats, some six feet in diameter, we found on September 7 the heavily infected *Amelanchier* just mentioned. It was too late in the season to hope to find telia. We did, however, detect some remains of what appeared to be telial galls on the larger branches close to the infected *Amelanchier*, from which the aecia might have been derived. It was to ascertain if telia subsequently developed on this particular red cedar, and, if so, to secure some for cultures, that Mr. Kern again visited Leland. The highly satisfactory results of the trip are given later in this paper under the report of cultures of species never before recorded.

In this connection an error in the report of cultures for 1908 should be pointed out. The record of *Gymnosporangium Davisii* Kern,⁵ should have been listed among "Successful cultures reported for the first time." Studies have since shown that the form grown by Dr. Ed. Fischer of Bern, Switzerland, and which he subsequently named *G. Amelanchieris* is quite distinct from *G. Davisii*. The aecial host of the European form is a true *Amelanchier* (service-berry), and not an *Aronia* (choke-berry). The assumption that it was an *Aronia*, a genus not represented in the Swiss flora, came from confusion in interpreting the synonymy. The very similar aecia on *Amelanchier* in America produce a gall on the stems of the red cedar, as the present season's work has demonstrated, while the aecia on *Amelanchier* in Europe produce small sori on the leaves of the common juniper. The

⁵ Mycol. 1: 241-242. 1909.

whole paragraph beginning with the third line on page 242 of the last season's report is largely irrelevant, and should be stricken out.

Most of the experimental part of the culture work of each year is done in the spring, and while in progress it wholly absorbs the time of one person in addition to that of the regular workers in the department. This year Miss Louise M. Falk, of Davenport, Iowa, a senior honor student in the University of Iowa, was recommended for the position by Professor Thomas H. Macbride. Miss Falk was in charge of the work from April 1 to June 3. She showed great enthusiasm and assiduity in conducting the cultures, although the turmoil of building and moving put the possibility of entirely satisfactory manipulation out of the question, as well as introduced most annoying interference. As for the year or two past, most of the cedar rust cultures were made by Mr. Kern. The investigations as a whole are a part of the work conducted by the botanical department of the Indiana Experiment Station, and are financed from the Adams fund appropriated by the general government for scientific research.

Those who assisted this year by supplying culture material and communicating field observations are most gratefully mentioned. Mr. E. Bethel, Denver, Colo., heads the list with forty-six collections of culture material. Messrs. J. F. Brenckle, Kulm, N. D., J. M. Bates, Red Cloud, Neb., and W. P. Fraser, Pictou, Nova Scotia, each sent between twenty and thirty collections, while a much smaller number was sent by Messrs. O. E. White, Brookings, S. D., A. O. Garrett, Salt Lake City, Utah, C. F. Baker, Claremont, Calif., J. J. Davis, Racine, Wis., E. Bartholomew, Stockton, Kans., E. W. Olive, Brookings, S. D., John L. Sheldon, Morgantown, W. Va., F. D. Heald, Austin, Texas, H. W. Barre, Clemson College, S. C., W. P. Kelley, Honolulu, Hawaii, F. E. Lloyd, Zacatecas, Mex., Aven Nelson, Laramie, Wyo., F. L. Stevens, West Raleigh, N. C., and Guy W. Wilson, Fayette, Iowa. Plants for particular culture work were sent by Dr. William Trelease, of the Missouri Botanical Garden, St. Louis, Mo. Thanks are extended to the above individuals, and to others who aided in the year's investigations.

During the present season 178 collections of material with resting spores and 18 collections with active spores were employed, from which 684 drop cultures were made to test the germinating condition of the spores. Out of the 178 collections with resting spores 95 could not be brought to germination, leaving 83 collections of available material to serve for the projected cultures. These 83 collections with resting spores and 18 with active spores belonged to about 70 species of rusts. Altogether 345 sowings were made, employing for the purpose 97 species of hosts, these being grown in pots.

The results of this work are given in the following paragraphs, and are divided into negative results, positive results with species whose life cycles have already been ascertained by the writer or other investigators, and positive results with species whose life cycles are now first completed and placed on record.

NEGATIVE RESULTS:—Quite a number of collections gave good germination of the spores, and these were sown on plants in the hope of discovering the alternate host, but no infections were secured. The following may be recorded to serve for reference in future studies, although not so much importance can be attached to these results as in former years, owing to unsatisfactory conditions, as stated above:

1. PUCCINIA on *Carex tenella* Schk., collected at Pictou, Nova Scotia, by Prof. W. P. Fraser, was sown on *Boehmeria cylindrica*, *Apocynum cannabinum*, *Lepargyrea canadensis*, *Symphoricarpos pauciflorus*, *Rudbeckia laciniata* and *Iva frutescens*, with no infection.

2. PUCCINIA on *Carex tenuis* Rudge, collected at Pictou, Nova Scotia, by Prof. W. P. Fraser, was sown on *Aster paniculatus*, *Solidago canadensis*, *Erigeron annuus*, *Onagra biennis* and *Ambrosia trifida*, with no infection.

3. PUCCINIA on *Carex Bonplandii minor* Vasey, collected at Granby, Colo., by Mr. E. Bethel, was sown on *Aster Tweedii*, *A. paniculatus*, *A. multiflorus* and *A. Drummondii*, with no infection. The determination of the host was made by Mr. Theo. Holm.

4. PUCCINIA on *Carex Backii* Boott, collected in Colorado, by

Mr. E. Bethel, was sown on *Lactuca sativa*, *Artemisia dracunculoides*, *Ambrosia trifida*, *Grindelia squarrosa* and *Laciniaria spicata*, with no infection. The determination of the host was made by Mr. Theo. Holm.

5. PUCCINIA on *Carex siccata* Dewey, collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown on *Ambrosia trifida* and *Carduus undulatus*, with no infection.

6. PUCCINIA RUBIGO-VERA Auct., on *Hordeum jubatum*, collected at Brookings, S. D., by Mr. O. E. White, was sown on *Lycopsis arvensis* (on 3 different dates), *Heliotropium curasavicum* (on 3 dates), *Myosotis palustris* (3 dates), *Lithospermum canescens*, *L. arvense*, *L. angustifolium*, *Hydrophyllum virginicum*, *Ceanothus americanus*, *Callirrhoe involucrata*, *Symphoricarpos racemosus*, *Petalostemon purpureum*, *Laciniaria punctata* and *Ambrosia trifida*, with no infection.

7. PUCCINIA DISTICHLIDIS E. & E., on *Spartina gracilis* Trin., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown on *Lepargyrea canadensis*, *Mimulus ringens*, *Symphoricarpos racemosus*, *Polygala Senega*, *Grindelia squarrosa* and *Carduus undulatus*, with no infection.

8. PUCCINIA SUBSTERILIS E. & E., on *Stipa viridula* Trin., collected at Eldorado Springs, Colo., by Mr. E. Bethel, was sown on *Tithymalis arkansanus coloradensis*, *Arabis Holboellii*, *Grindelia squarrosa* and *Eupatorium serotinum*, while another collection with same data was sown on *Viola sororia*, *Mimulus ringens*, *Myosotis palustris*, *Aster ericoides* and *A. multiflorus*, all with no infection.

9. PUCCINIA STRIATULA Peck, on *Calamagrostis canadensis* (Michx.) Beauv., collected at Wind Lake, Wis., by Dr. J. J. Davis, was sown on *Thalictrum alpinum*, *T. dioicum*, *T. purpurascens*, *Actaea alba*, *Phacelia bipinnatifida*, *Hydrophyllum virginicum* and *Polygonatum biflorum*, with no infection.

10. PUCCINIA VIRGATA Ellis & Ev., on *Chrysopogon aenaceus* (Michx.) Benth., collected at Asheville, N. C., by Mr. F. D. Kern, was sown on *Dirca palustris*, *Viola sororia*, *Hydrophyllum virginicum*, *Mimulus ringens*, *Chelone glabra*, *Symphoricarpos pauciflorus* and *Ambrosia trifida*, with no infection. Similar

material from Nebraska was sown two years ago on four other species of hosts.⁶

II. PUCCINIA ELLISIANA Thüm., on *Andropogon scoparius* Michx., collected at Ayr, Neb., by Rev. J. M. Bates, was sown on *Ceanothus americanus*, *Aesculus glabra*, *Lepargyrea canadensis*, *Symphoricarpos racemosus*, *Mimulus ringens*, *Laciniaria punctata*, *Lithospermum angustifolium*, *Chelone glabra*, *Ranunculus septentrionalis* and *Mertensia virginica*.

Another collection on the same host and by the same collector from Scotia, Neb., was sown on the first six hosts mentioned, and also on *Laciniaria spicata*, *L. scariosa*, *Cassia Chamaecrista*, *Hydrophyllum virginicum*, *Polygala Senega*, *Petalostemon purpureum* and *Phacelia bipinnatifida*.

The same species of rust on *A. glomeratus* (Walt.) B.S.P., collected at Asheville, N. C., by Mr. F. D. Kern, was sown on *Cassia Chamaecrista*, *Lepargyrea canadensis* and *Petalostemon purpureum*, as in the preceding cases, and also on *Baptisia tinctoria*, *Abronia fragans* and *Viola cucullata*.

The results were uniformly negative, there being no infection. In the two preceding years this rust was sown on nineteen other species of hosts.⁷

12. UROMYCES GRAMINICOLA Burr., on *Panicum virgatum* L., collected at St. Paul, Neb., by Rev. J. M. Bates, was sown on *Callirrhoe involucrata*, *Althaea rosea*, *Hibiscus militaris*, *Sidalcea oregana* and *Viola cucullata*, with no infection. Similar material was sown last year on four of these same hosts, and on four other species without effect.⁸

13. UROMYCES JUNCII (Desm.) Tul., on *Juncus Balticus* Willd., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown on *Pulicaria dysenterica*, with no infection. Another collection on the same host from Colorado, sent by Mr. E. Bethel, was sown on *Pulicaria dysenterica*, both seedlings and strong shoots, and on *Grindelia squarrosa* and *Arnica* sp., with no infection. In 1907 a similar collection from Nebraska was sown on fifteen other species of hosts.⁹ This common American rust is usually

⁶ See Jour. Myc. 14: 10. 1908.

⁷ Jour. Myc. 14: 10. 1908; Mycol. 1: 231. 1909.

⁸ Mycol. 1: 232. 1909.

⁹ See Jour. Myc. 14: 12. 1908.

considered to be the same as the one in Europe from which it takes its name. The experiments of Fuckel, Plowright, and E. Fischer have shown that the European form produces aecia on *Pulicaria dysenterica*, and the failure of the American form to do so may mean that the two are distinct species, or that there are physiological races on different hosts. Further studies are necessary to decide the question.

14. *UROMYCES ACUMINATUS* Arth., on *Spartina cynosuroides* Willd., collected at Fayette, Iowa, by Prof. Guy West Wilson, was sown on *Steironema ciliatum*, *S. lanceolatum* and *Polemonium reptans*, with no infection. Similar material from northern Indiana has been sown in previous years on six other hosts, and also four times on *Steironema ciliatum* and two times on *S. lanceolatum*, without infection.¹⁰

Some years ago in a morphological study of all collections of *Uromyces* on *Spartina* then available the writer decided¹¹ that the form from the salt marshes of the Atlantic coast, known under the name *U. Spartinae* Farl., having somewhat larger teliospores and urediniospores, the former with more rounded apices, and the latter with thicker walls, than the western form mentioned above, occurred also in the interior of the continent, and could not be clearly separated from *U. acuminatus*. Recently my associate, Mr. F. D. Kern, has restudied the two forms, with all the data that have accumulated in the decade since my own study was completed, and is able to supplement the morphological differences which I pointed out with others, and concludes that the two forms represent distinct species. He gives the distribution of *U. acuminatus* as the wet, alluvial prairies of Iowa, Minnesota, and adjoining states, extending eastward to northern Indiana, while *U. Spartinae* is found in saline soils from Alberta southwestward to Wisconsin and Kansas, and along the Atlantic coast from Nova Scotia to Florida. Reexamining the successful cultures with *Uromyces* on *Spartina*, made in 1905 and 1907, the material for which was sent from western Nebraska,¹² it is found that the culture material agrees with *U. Spartinae* Farl. Putting all the data together, the writer's suspicions, recorded

¹⁰ See Jour. Myc. 10: 9. 1904; 13: 193. 1907.

¹¹ Bot. Gaz. 34: 3. 1902.

¹² Jour. Myc. 12: 24. 1906; and 14: 17. 1908.

both in the discussion of his morphological studies and his cultural reports, cited above, that there are two species of *Uromyces* on *Spartina*, are confirmed. The aecial form of *U. Spartinae* Farl. occurs on *Steironema ciliatum* and *S. lanceolatum*, and the aecial form of *U. acuminatus* Arth. is yet unknown, although field observations made by Mr. Guy West Wilson indicate that it may occur on *Polemonium reptans*.

15. GYMNOSPORANGIUM sp., on *Juniperus virginiana* L. collected at the Santee Canal, near Monks Corners, S. C., by Mr. F. D. Kern, was sown March 24 on the leaves of *Crataegus punctata*, *Amelanchier erecta*, and *Cydonia vulgaris*, with no infection. On April 1 it was sown again on the same three species and on *Malus coronaria*, with no infection. It was sown again April 14 on *Crataegus* sp., and *Malus Malus*, still with no infection. On April 26 a sowing was made on *Crataegus coccinea* and *Pyrus communis* (Kiefer's Hybrid), and on May 14 a further sowing on *Crataegus cerronis*, *Aronia arbutifolia*, *Sorbus americana* and *Porteranthus stipulatus*, wholly without infection.

The failure to secure infection, although sowings were made on all the genera known to harbor aecia of the *Gymnosporangia* in the eastern United States, was probably due to the maturity of the leaves, or to some accident. It is certain on morphological grounds that this cedar rust is not a form at present recognized under established names. The rust produces large brown sori, often in series, extending along the bark of the larger branches. It has somewhat the general appearance of *Gym. nidus-avis*, causes a similar swelling of the branches, but differs in having prominently projecting sori, even before gelatinization, which are much roughened on the surface.

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK: The following species of rust were successfully grown and the facts supplement those obtained from previous cultures in this series or those recorded by other American or European investigators. In a number of cases the data here presented materially extend the previously available knowledge regarding the several species.

I. PUCCINIA PECKII (DeT.) Kellerm., on *Carex lanuginosa* Michx., collected at Red Cloud, Neb., by Rev. J. M. Bates, was

sown May 19 on *Sambucus canadensis* and *Onagra biennis*, giving no infection on the former, but giving very abundant pycnia on the latter May 28, followed by aecia June 6.

Four collections on the same host, made by Dr. J. F. Brenckle, at Kulm, N. D., were used for three successful sowings on *Onagra biennis*, giving rise to pycnia in seven to twelve days, followed by aecia in five to seven days more. Sowings on *Gaura biennis* and *Carduus undulatus* gave no infection.

A collection on *Carex trichocarpa* Muhl., made by Mr. F. D. Kern at White House, St. Louis Co., Mo., after having been sown on *Sambucus canadensis* with no infection, was sown April 21 on *Gaura biennis*, giving rise to pycnia April 30, and aecia May 10.¹³

2. PUCCINIA CARICIS (Schum.) Schröt., on *Carex aristata* R. Br., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown April 6 on *Urtica gracilis*, giving rise to pycnia April 13 and aecia April 17, both in great abundance. A similar sowing April 21 on *Boehmeria cylindrica* gave no infection. Another sowing May 4 on both hosts gave no infection on *Boehmeria cylindrica*, but produced the richest possible infection on *Urtica gracilis*, showing pycnia May 9, and aecia May 15. Beside adding another species of *Carex* to the list of hosts supplying culture material for this rust,¹⁴ the results indicate that *Boehmeria* is not an aecial host.

It may be well to point out in this connection that the usual citation of Rebentisch for this species of rust is erroneous. This author in his *Florae Neomarchicae*, 1804, page 356, describes *Puccinia Caricis* as a new species in the following words: "*Sparsa minutissima punctiformis, capsulis cylindraceis apice utrinque attenuatis. In foliis Caricis praccocis Jacq.*" Only the one host species is named, neither the description nor the host tally with those known to belong to the rust having its aecia on *Urtica*, as may be seen by consulting Sydow's *Monographia Uredinearum*. They, however, do agree well with those given by Sydow under *Puccinia silvatica*, to which species Rebentisch's name should doubtless be referred.

¹³ For previous cultures see Bot. Gaz. 35: 13. 1903; Jour. Myc. 8: 55. 1902; 11: 58. 1905; 12: 15. 1906; 13: 195. 1907; and Mycol. 1: 233. 1909.

¹⁴ For previous cultures see Bot. Gaz. 29: 270. 1900; 35: 16. 1903; Jour. Myc. 8: 52. 1902; 12: 15. 1906; and 14: 14. 1908.

3. PUCCINIA UNIVERSALIS Arth., on *Carex stenophylla* Wahl., collected at Eldorado Springs, Colo., by Mr. E. Bethel, was sown April 26 on *Arabis Holboelli*, *Sambucus canadensis*, *Urtica gracilis* and *Artemisia dracunculoides*. All remained free from infection except the last, on which pycnia appeared May 5, and aecia May 14. This is a confirmation of the result obtained in 1907.¹⁵ In making the cultures and writing up the results of that year it was overlooked that the combination which was then established had been repeatedly suggested by Rev. J. M. Bates. In the spring of 1906 Rev. Bates sent a collection of rust on *Carex stenophylla*, obtained at Boelus, Neb., on June 25, 1906, and on the packet he wrote that it was associated with aecia on *Artemisia longifolia*. This came too late in the season to be tested by a culture. In a letter received in September of the same year he stated that his field observations made it almost certain that this *Carex* rust and the *Artemisia* aecia were alternate forms of one species. Both my associate, Mr. Kern, and myself were at that time of the opinion that the aecia on *Artemisia* belonged to the telia on the same host, and so firmly did we believe this error that when material for cultures was at hand the following spring, we had forgotten Rev. Bates' suggestion, and we also overlooked the memorandum in our book of suggestions for future work.

4. PUCCINIA CARICIS-ASTERIS Arth., on *Carex festiva* Dewey, the host being determined by Mr. Theo. Holm, collected August 15, 1908, at Granby, Colo., by Mr. E. Bethel, was sown May 17 in accordance with the suggestion of the collector on *Aster adscendens* Lindl. (*A. Tweedyi* Rydb.), giving rise to pycnia which were first noticed May 31, although they may have appeared earlier, and to a few aecia June 6. A sowing was also made at the same time on *Agoseris glauca* with no infection.

Another collection made in the same vicinity five days later was sown May 22 on *Aster adscendens* and produced abundant pycnia May 29, and many aecia June 4. These cultures bring forward a new set of hosts, and show the species to be of wide distribution in America.¹⁶

¹⁵ See Jour. Myc. 14: 21. 1908.

¹⁶ For previous cultures see Bot. Gaz. 35: 15. 1903; Jour. Myc. 8: 54. 1902; and 14: 13. 1908.

5. PUCCINIA SUBNITENS Diet., on *Distichlis spicata* (L.) Greene, collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown April 23 on *Corydalis aurea* Willd., with no infection, and also on *Atriplex hastata*, giving pycnia May 3, and aecia May 12. Another sowing was made April 24 on *Corydalis sempervirens* (L.) Pers. (*C. glauca* Pursh), with no infection, and also on *Atriplex hastata* and *Chenopodium album*, both of which gave infection, showing pycnia April 31, and aecia later.¹⁷ The chief object in again growing this rust was to see if it would infect species of *Corydalis* on which occur *Aecidium fumariacearum* Kellerm. & Sw. (*A. Corydalis* Webber), the aecia and aeciospores of which resemble those belonging to *Puccinia subnitens*. The results, however, are inconclusive, and further cultures must be attempted before the question can be settled.

6. PUCCINIA AMPHIGENA Diet., on *Calamovilfa longifolia* (Hook.) Hack., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown May 22 on *Smilax hispida*, and gave numerous pycnia May 31, and aecia June 4. This extends the geographical range from which material has been received for successful cultures.¹⁸

7. PUCCINIA FRAXINATA (Schw.) Arth., on *Spartina cynosuroides* Willd., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown May 22 on *Fraxinus lanceolata*, giving rise to pycnia May 29, and aecia June 4.¹⁹

8. PUCCINIA PHRAGMITIS (Schum.) Körn., on *Phragmites communis* Trin., collected at Scotia, Neb., by Rev. J. M. Bates, was sown May 14 on *Rumex crispus*, giving rise to pycnia May 22, and aecia May 29, both in the greatest abundance. Another collection by the same person, made at Grand Island, Neb., was sown May 17 on *R. crispus*, giving abundance of pycnia May 23, and aecia May 29.²⁰

9. PUCCINIA OBLITERATA Arth., on *Agropyron* sp., collected

¹⁷ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; 14: 15. 1908; and Mycol. 1: 234. 1909.

¹⁸ For previous cultures see Bot. Gaz. 35: 20. 1903; Jour. Myc. 11: 57. 1905; 12: 16. 1906; and 14: 15. 1908.

¹⁹ For previous cultures see Bot. Gaz. 29: 275. 1900; Jour. Myc. 11: 57. 1905; 12: 16. 1906; 14: 14. 1908; and Mycol. 1: 236. 1909.

²⁰ For previous cultures see Bot. Gaz. 29: 269. 1900; Jour. Myc. 9: 220. 1903; and 14: 15. 1908.

August 15, 1908, at Granby, Colo., by Mr. E. Bethel, was sown April 21 on *Thalictrum alpinum* and *T. dioicum*. There was no infection on the latter host, but on the former it was abundant, showing aecia May 6. Pycnia were so scantily produced that it required an extended search, aided with sections from the affected spots to discover any. A careful morphological study reveals no difference between the telial material used for this culture together with the aecia produced by it, and the telial material on the same host used last year, together with the aecia then produced on *Aquilegia*.²¹ The gross appearance of the infected areas, the manner of the hypertrophy, and the remarkable paucity of pycnia, also combine to indicate that the two cultures belong to one species, although the production of aecia on both *Thalictrum* and *Aquilegia* by a single species is not in accordance with similar studies made in Europe.²²

10. PUCCINIA MUHLENBERGIAE Arth. & Holw., on *Muhlenbergia glomerata* Trin., collected at Stockton, Kans., by Mr. E. Bartholomew, was sown May 17 on two plants of *Callirrhoe involucrata*, both giving rise to numerous pycnia May 31, and to aecia June 6 in one case and June 12 in the other. At the same time it was sown on *Napaea dioica*, *Althaea rosea* and *Sidalcea* sp., with no infection. These hosts are known to bear aecia of the same appearance and morphological structure as those secured by the culture on *Callirrhoe*, and the reason why they were not affected by the sowings is not clear, unless this species of rust is made up of races.²³

11. PUCCINIA IMPATIENTIS (Schw.) Arth., on *Elymus striatus* Willd., collected at Lafayette, Ind., by Mr. A. G. Johnson, was sown May 6 on *Napaea dioica*, with no infection, and at the same time on *Impatiens aurea*, giving rise to pycnia May 15, and aecia in abundance May 25. Another collection on the same host, made by Mr. F. D. Kern at White House, St. Louis Co., Mo., was sown May 11 on *I. aurea*, producing pycnia May 21, and aecia May 29. It was also sown at the same time and produced no infection on *Napaea dioica*, *Callirrhoe involucrata*, *Thalictrum*

²¹ See Mycol. 1: 250. 1909.

²² See Klebahn, Wirtsw. Rostpilze 275, 276. 1904.

²³ For previous cultures see Mycol. 1: 251. 1909.

dioicum, *Actaea alba*, *Caulophyllum thalictroides*, *Boehmeria cylindrica*, *Myosotis palustris*, *Mimulus ringens*, *Polemonium reptans*, *Hydrophyllum virginicum*, *Polygala Senega*, *Dirca palustris*, *Psoralea Onobrychis* and *Ipomoea pandurata*.

Aeciospores from *Impatiens aurca* Muhl., were sown on three species of *Elymus*. For this purpose small plants bearing aecia were taken from the field, where they grew close together, and had presumably received infection from one source. These were established in pots, and the pots adjusted over the plants of *Elymus* to be infected, so the spores would drop of themselves upon the leaves of the grass, belljars being used as usual to secure the right degree of moisture for the germination of the spores. In this manner aeciospores were sown June 4 upon *Elymus virginicus* L., *E. canadensis* L. and *E. striatus* Willd. In all three cases uredinia began to show June 17, and continued to increase for some time, but the conditions were not such as to keep the plants in healthy condition for the maturing of telia.

Former cultures²⁴ had demonstrated the genetic connection between the aecia on *Impatiens* and telia on *Elymus virginicus*. The present season's work indicates that the rust on all species of *Elymus* in the region east of the Rocky Mountains belongs to one species, *Puccinia Impatiensis*.

12. PUCCINIA POCULIFORMIS (Jacq.) Wettst., on *Agropyron pseudorepens* Scribn. & Sm., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown May 4 on *Berberis vulgaris*, giving rise to pycnia May 12, and numerous aecia May 24. Another collection on *Sitanion longifolium* J. G. Sm., made at Tolland, Colo., 9,000 feet altitude, by Mr. E. Bethel, was sown May 17 on *Berberis vulgaris*, and gave pycnia May 29, but owing to maturity of the leaves did not reach the production of aecia. Still another collection on *Sitanion longifolium*, made at Eldorado Springs, Colo., 4,500 feet altitude, by Mr. E. Bethel, was sown April 26 on *Berberis vulgaris*, and gave pycnia May 3, and aecia May 12, both in great abundance. On May 17 the barberry plant bearing aecia, produced in the last culture, was arranged over a pot in which young wheat plants (*Triticum vulgare* Vill.) were growing, in such a manner that the aeciospores could fall

²⁴ See Bot. Gaz. 35: 18. 1903; Jour. Myc. 10: 11. 1904; and 11: 57. 1905.

upon the wheat leaves. On May 29 urediniospores began to show, and their abundance increased for some time, but owing to the lateness of the season the wheat plants did not flourish, and in consequence teliospores were not formed.

This species of rust, which is the most injurious cereal rust known, is very common throughout the country, not only on cereals, but on many wild grasses. It has now been grown²⁵ in our series of cultures from telia on *Agropyron repens* from Vermont, *A. tenerum* from Iowa and Nebraska, *Agrostis alba* from Indiana and New York, *Cinna arundinacea* from Indiana, *Elymus canadensis* from Iowa and Wisconsin, and the two hosts mentioned above. In 1907 the aeciospores raised from telia on *Agrostis alba* obtained in Indiana were used to produce infection on wheat (*Triticum vulgare*) and barley (*Hordeum vulgare*), and in 1908 aeciospores raised from telia on *Agropyron tenerum* obtained in Nebraska were used for infection on oats (*Avena sativa*). This year the aeciospores raised from telia on *Sitanion longifolium* obtained in Colorado produced infection on wheat. More extended work is planned in regard to the problem of the transfer of this pernicious black or stem rust from wild grasses to the cultivated cereals, but enough has been accomplished to warrant the statement that although in the uredinial stage this rust shows racial strains that inhibit the ready transfer from one species of host to another, as has been shown by many European and American investigators, yet in the aecial stage racial strains play no part, and the barberry acts as a bridging host between each and every other gramineous host.

13. PUCCINIA SUBSTERILIS E. & E., on *Stipa viridula* Trin., collected April 16 at Eldorado Springs, Colo., by Mr. E. Bethel, bore abundance of amphispores, which were sown April 29 on plants of *Stipa viridula*, and gave rise to urediniospores in abundance, first observed May 24. A sowing at the same time on *Stipa spartea* gave no infection.

14. UROMYCES ANDROPOGONIS Tracy, on *Andropogon virginicus* L., collected at Morgantown, W. Va., by Dr. John L. Sheldon was sown June 4 on *Viola cucullata*, giving ten groups of pycnia,

²⁵ For previous cultures see Jour. Myc. 8: 53. 1902; 11: 57. 1905; 12: 17. 1906; 13: 198. 1907; and 14: 16. 1908.

first showing June 12. The leaves matured so rapidly that no aecia were formed. A sowing at the same date on *Viola primulifolia* gave no infection. This species of rust has been grown upon *Viola* by Dr. John L. Sheldon,²⁶ but previous attempts made in my own laboratory have failed.²⁷ The reason for the failures seems to be the tardiness in making the cultures, by which the violet leaves are too mature and ripen so rapidly that infection is not secured. I am indebted to Dr. Sheldon for the suggestions, field observations and culture material, which have enabled me to add this species to the list of completed life cycles.

15. UROMYCES SPARTINAE Farl., on *Spartina cynosuroides* Willd. collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown April 23 on *Lysimachia quadrifolia*, with no infection, and at the same date on *Steironema ciliatum* and *S. lanceolatum*, giving rise to pycnia May 5 on the former and May 8 on the latter. In both cases growth did not extend to the formation of aecia owing to the feeble condition of the host plants.²⁸ The confusion of this species of rust with *Uromyces acuminatus* Arth. has already been discussed above among unsuccessful cultures.

16. GYMNOSPORANGIUM GLOBOSUM Farl., on *Juniperus virginiana* L., collected at Asheville, N. C., by Mr. F. D. Kern, was sown May 15 on *Malus Ioensis*, *Crataegus punctata* and *C. coccinea*, with no infection on the first and second, but on the last giving rise to pycnia May 25 in abundance, followed by aecia which were mature July 26.²⁹

17. GYMNOSPORANGIUM CLAVIPES C. & P., on *Juniperus sibirica* Burgsd., collected at Leland, Mich., by Mr. F. D. Kern, was sown June 5 on the fruit of *Amelanchier erecta*, giving rise to pycnia June 14, and to mature aecia August 3, both in abundance. At the same time it was sown on the leaves of *Crataegus punctata*, giving rise to numerous pycnia, but as the plant was not well established further development was soon checked.³⁰ There ap-

²⁶ Torrey **9**: 55. 1909.

²⁷ See Mycol. **1**: 232. 1909.

²⁸ For previous cultures see Jour. Myc. **12**: 24. 1906; and **14**: 17. 1908, under the name *U. acuminatus*.

²⁹ For previous cultures see Jour. Myc. **13**: 200. 1907; **14**: 18. 1908; and Mycol. **1**: 239. 1909.

³⁰ For previous cultures see Jour. Myc. **14**: 18. 1908; and Mycol. **1**: 239. 1909.

pears to be no noticeable difference between the pycnia and aecia grown this year from telia on the true juniper and those grown last year from telia on the true cedar, thus confirming the unique character of this species of rust in growing upon hosts of the two quite distinct sections of the genus *Juniperus*.

18. GYMNOSPORANGIUM NIDUS-AVIS Thax. on *Juniperus virginiana* L., collected at Asheville, N. C., by the writer, was sown March 22 on *Amelanchier canadensis*, without infection, and at the same time on *Crataegus Pringlei* and *Malus Ioensis*, both giving rise to an abundance of pycnia April 6. The infection on *Crataegus* did not perfect aecia, but that on *Malus* matured aecia in abundance by April 27.³¹

The telia of this collection were on the main branches of a tree thirty feet high, and when found were fully expanded. They formed wavy masses standing out two centimeters or more from the bark and extending in long lines of four or five decimeters, like orange colored ruffles or frills. The appearance was that of a large *Tremella*, and so unlike that of any *Gymnosporangium* before seen that not until it was examined under the microscope after returning to Lafayette was it accepted as a rust. It was found that the frills were the consequence of the large sori forming in rows and cracking the bark longitudinally.

19. GYMNOSPORANGIUM BETHELI Kern, on *Juniperus scopulorum* Sarg., collected in Colorado by Mr. E. Bethel, was sown May 14 on *Crataegus cerronis*, and gave rise to pycnia May 22 in abundance, and to first appearance of aecia June 14, the aecia being fully mature August 3.³²

20. GYMNOSPORANGIUM CORNUTUM (Pers.) Arth., on *Juniperus sibirica* Burgsd., collected at Leland, Mich., by Mr. F. D. Kern, was sown June 5, on *Aronia nigra* and *Amelanchier erecta* with no infection, and at the same time on *Sorbus americana*, giving an abundance of pycnia June 15, but no aecia were formed owing to the weakness of the host plant. Another sowing was made from the same material June 7 on a cutting of *Sorbus aucuparia* placed in water, giving a few pycnia June 18, but the

³¹ For previous cultures see Jour. Myc. 14: 19. 1908.

³² For previous cultures see Jour. Myc. 14: 23. 1908; and Mycol. 1: 240. 1909.

leaves soon died. Still another sowing was made June 14 on *Sorbus americana*, producing numerous pycnia June 26, but the plant gradually died.³³

21. GYMNOSPORANGIUM FLORIFORME Thax., on *Juniperus virginiana* L., collected at Aiken, S. C., by Mr. F. D. Kern and the writer, was sown March 26 on *Malus Malus* with no infection, and at the same time on *Crataegus coccinea*, giving pycnia in abundance April 12. The after development, however, was very slow, and by the middle of July aecia had only begun to show, and grew so very slowly that they did not reach full size, although observations were continued till November 11. Another sowing from the same material was made May 15 on the same host, resulting in a few pycnia, but no aecia. In both cases the infected leaves matured too rapidly for the very slow growing aecia, and besides, the host used is not a species on which natural infection is likely to occur.

Previous cultures have been made by Dr. R. Thaxter at Cambridge, Mass., and Prof. F. S. Earle at Auburn, Ala. Only a slight notice of these cultures has been published. A description and historical account of the species was recently published by Mr. F. D. Kern.³⁴ The telial form of the species is very similar in appearance to that of the common *Gym. Juniperi-virginianae*.

22. GYMNOSPORANGIUM EXTERUM Arth. & Kern, on *Juniperus virginiana* L., a living plant a little over six inches high, which has been growing in the greenhouse since being brought from Mammoth Cave, Ky., by Mr. F. D. Kern and the writer a year ago, was sown May 14 on *Porteranthus stipulatus* (*Gillenia stipulacea*), and gave rise to an abundance of pycnia May 22. On June 14 the first aecia appeared, which were mature June 26. The work duplicates and confirms that of last year.³⁵

23. CALYPTOSPORA COLUMNARIS (A. & S.) Kühn, on *Vaccinium pennsylvanicum* Lam., collected at Pictou, Nova Scotia, by Prof. W. P. Fraser, was sown June 16 by suspending the moistened stems bearing the rust over potted plants of *Abies Fraseri*. On July 8 abundance of aecia appeared, without being preceded by

³³ For previous cultures see Mycol. 1: 240. 1909.

³⁴ Bull. Torrey Club 35: 503. 1908.

³⁵ For previous cultures see Mycol. 1: 253. 1909.

pycnia. European investigators have noted the absence of pycnia in this species, both in the field and in cultures. The suppression of the gametophytic sori, as in this case, is rare in heteroecious rusts.

This is the first culture yet made with American material. In 1880 Hartig made cultures at Munich, Germany, by using aeciospores from *Abies alba* and teliospores from *Vaccinium Vitis-idaea*, thus transferring in both directions.³⁶ The most extensive cultures were made by Dr. G. Winter in 1885 and 1886, in the garden of the Experiment Station at Halle, Germany.³⁷ He successfully sowed teliospores on *Abies nobilis*, *A. magnifica*, *A. concolor*, *A. balsamea* and *A. Fraseri*, natives of North America, and on eight other species of *Abies*, natives of various parts of the world.

After the sori made their appearance in our own cultures I wrote to Prof. Fraser, the collector of the culture material, describing the salient characters of the aecia, and inclosed infected leaves obtained by means of the culture. With this information he was able to go into the field and find the aecia on *Abies balsamea*, returning a collection which he made at Pictou, Nova Scotia, July 14, 1909,³⁸ the first known collection from North America. This stage of the fungus is probably common throughout the country, and the fact that it has been seen but once is doubtless due to its early appearance, lack of accompanying hypertrophy and discoloration, evanescent character, and general inconspicuousness.

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME: The following species have never before been cultivated, in America or elsewhere, so far as the writer knows. Although the number is small, it includes most valuable additions to our knowledge of American rusts. The study of the cedar rusts, which has been greatly advanced by the spring excursions of the last three years for personal observation and collection of material, is approaching a full survey of the species of the eastern United States, although an unknown number of species remain in the western mountains yet to be investigated.

³⁶ See Klebahn, Die wirtsw. Rostpilze 391. 1904.

³⁷ Hedwigia 26: 28. 1887.

³⁸ See Fraser, Science 30: 814. 1909.

1. PUCCINIA on *Andropogon Hallii* Hack., collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown June 3 on thirteen species of hosts with no infection, as follows: *Carduus undulatus*, *Ambrosia trifida*, *Lithospermum canescens*, *Myosotis palustris*, *Hydrophyllum virginicum*, *Lepargyrea canadensis*, *Symphoricarpos parviflorum*, *Napaea dioica*, *Boehmeria cylindrica*, *Thalictrum dioicum*, *Delphinium scaposum*, *Cassia Chamaecrista* and *Petalostemon purpureus*. The same material was sown the day following on four other species with no infection, viz., *Amorpha nana*, *Baptisia tinctoria*, *Psoralea Onobrychis* and *Xanthoxylon americanum*. Each of these hosts is known to harbor aecia whose telial connection has not yet been experimentally ascertained. The material being in unusually good condition an attempt was made to sow it on all unconnected aecial hosts available at the time, hoping in this way to strike the right one, no field clues having been secured. This is a precarious method, but in this instance it succeeded, as among the hosts was included *Ceanothus americanus*, on which a sowing was made June 3, giving rise to numerous pycnia June 12, and an abundance of aecia June 22.

The telial form of this species was first detected by the writer while preparing the material for the third fascicle of Arthur and Holway's *Uredineae Exsiccatae*, and was referred to *Puccinia Cesatii* Schröt., on account of the similarity of the urediniospores to those of that species.³⁹ Sydow in his *Monograph* rightly called this reference in question, and suggested that it might be a new species, but did not give a name or description.⁴⁰

The aecial form of this species was described by Ellis and Kellerman in 1884, under the name *Aecidium Ceanothi*, from a collection made at Manhattan, Kans. The form is not only known from Kansas, but also from Nebraska, and northwestern Wisconsin.

Puccinia Ceanothi (Ellis & Kellerm.) nom. nov. (*Aecidium Ceanothi* Ellis & Kellerm., Bull. Torrey Club **11**:114. 1884.)

O and I. On *Ceanothus ovatus* Desf., Manhattan, Kans., May 20, 1884, W. A. Kellerman (type); Rooks Co., Kans., May, 1898,

³⁹ Bull. Lab. Nat. Hist. Iowa Univ. **5**: 181. 1901.

⁴⁰ Sydow, Monog. Ured. **1**: 723. 1903.

E. Bartholomew; Nebraska, 1899, *A. J. Bell*; Gordon, Wis., July 12, 1907, *J. J. Davis*.

II. Uredinia hypophyllous, oblong-linear, pulvinate, early naked, chestnut-brown, only slightly pulverulent; urediniospores globose or nearly so, $23\text{--}33\mu$ in diameter, wall cinnamon-brown, uniformly thick, $3\text{--}6\mu$, finely and closely verrucose, pores five or more, scattered.

III. Telia hypophyllous, oblong or linear, early naked, pulvinate, firm, chocolate-brown; teliospores broadly ellipsoid or obovate, $22\text{--}30$ by $30\text{--}40\mu$, somewhat constricted at the septum, rounded at both ends, or narrowed below, wall smooth, medium thick, 3μ , much thickened at apex, $6\text{--}10\mu$, chestnut-brown; pedicel colored, once to twice length of spore.

On *Andropogon Hallii* Hack., Manhattan, Kans., no date, *M. A. Carleton*; Howard Co., Neb., September, 1889, *H. J. Webber*; Kennedy, Neb., Sept. 7, 1908, *J. M. Bates* (*Barth.*, *Fungi Columb.* 2756); Red Cloud, Neb., May 7, 1909, *J. M. Bates*.

2. GYMNOSPORANGIUM EXIGUUM Kern, on *Juniperus virginiana* L., collected at Austin, Texas, by Dr. F. D. Heald and Mr. F. A. Wolf, was sown April 26 on *Amelanchier canadensis* with no infection, and at the same time on *Crataegus Pringlei*, giving abundant pycnia May 6, and aecia June 26.

This southernmost species of cedar rust was described a year ago⁴¹ from telial material that was collected in the vicinity of that used for the cultures. The telial description may now be supplemented by a description of the pycnia and aecia. Only one collection of aecia from the field is yet known that can be assigned to this species. It was obtained at Boerne, Texas, not far from San Antonio, and is to some extent on the leaves, but mostly on the fruit of some undetermined species of *Crataegus*. While trees of red cedar of more than one species are abundant in southern Texas where the rust is found, trees of *Crataegus* are rare, and the rust is probably not common.

O. Pycnia fruticulous and epiphyllous, gregarious, in irregular groups 1–4 mm. across, on discolored hypertrophied areas, prominent, conspicuous, honey-yellow soon becoming blackish, globoid or depressed globoid, $150\text{--}165\mu$ in diameter by $100\text{--}130\mu$ high; ostiolar filaments $50\text{--}65\mu$ long.

I. Aecia fruticulous and hypophyllous, sparsely arranged in irregular groups, causing considerable hypertrophy of the veins,

⁴¹ Bull. Torrey Club 35: 508. 1908.

petioles, or fruits, cylindrical, 2-3 mm. high; peridium rupturing at the apex, margin not splitting much, erect, peridial cells, usually seen in face view, broadly lanceolate, 29-40 by 70-90 μ , inner and side walls thick, 9-14 μ , closely spinulose with spine-like papillae up to 6 μ long, outer wall thinner, about 3 μ , sculptured like the inner and side walls but with shorter papillae; aeciospores globoid or broadly ellipsoid, 22-25 by 26-31 μ , wall cinnamon-brown, medium thick, 2-3 μ , finely verrucose; pores distinct, 6-8, scattered.

On *Crataegus* sp., Boerne, Texas, June 12, 1908, G. G. Hedgcock.

3. *GYMNOSPORANGIUM* sp. nov. The chain of circumstances which led up to the detection and final culture of this very interesting species of rust is given with sufficient detail in the introduction to this paper, and need not be repeated. Material collected by Mr. F. D. Kern, June 4, 1909, at Leland Mich., on *Juniperus horizontalis* Moench, was sown, June 5, on one plant of *Amelanchier erecta*, and two plants of *A. canadensis*. Numerous pycnia appeared on all three plants, one June 14, and the other two June 16. Owing to the fact that the season was well advanced, and the foliage on the *Amelanchier* plants quite mature, by the time well developed telia could be obtained in the northern habitat, the leaves on all three plants used for cultures ripened and fell before aecia appeared. The field collection of the previous autumn, however, supplied authentic material for study, and the results are not open in the slightest degree to doubt.

It is very gratifying to establish the relationship of the horn-like aecia on *Amelanchier*, as it is now possible to distribute the three very similar forms, that have heretofore gone under one name, and supposed to belong to one cosmopolitan species. The three species are: *Gym. cornutum*, with aecia on *Sorbus*, common to Europe and America, *Gym. Davisii*, with aecia on *Aronia*, known only in America, and the present form with aecia on *Amelanchier*, also known only from America. The first two have their telia on the true juniper, while the last has telia on the red cedar. The new form has been studied morphologically by Mr. F. D. Kern, who has drawn up the following description and supplied the name.

Gymnosporangium corniculans Kern sp. nov.

O. Pycnia epiphyllous, gregarious, in small groups o. 5–1 mm. across, on discolored spots, rather prominent and conspicuous, honey-yellow, becoming blackish, slightly flattened globose, 130–175 μ in diameter by 130–160 μ high; ostiolar filaments 50–80 μ long.

I. Aecia hypophyllous, crowded in irregular or annular groups, 2–5 mm. across, cylindrical or horn-shaped, acutish at apex, 2–3.5 mm. high; peridium tardily dehiscent by longitudinal slits along the sides, peridial cells usually seen in face view, broadly lanceolate, 16–23 by 64–96 μ , inner and side walls rather thick, 5–7 μ , moderately verrucose with oval or roundish papillae and a few elongated papillae interspersed, outer wall thin, 1.5–2 μ , smooth; aeciospores globoid, 19–26 by 23–32 μ , wall dark cinnamon-brown, rather thick, 3–4 μ , finely verrucose, appearing nearly smooth.

On *Amelanchier canadensis* (L.) Medic., Burlington, Vt., Sept. 25, 1897, *W. A. Orton*; Fort Spring, W. Va., Sept. 14, 1906, *J. L. Sheldon*; Granville, Mass., Sept. 22, 1890, *A. B. Seymour* (*Seym. & Earle, Econ. Fungi 248^a*); *Amelanchier erecta* Blanch., Isle Royale, Mich., Aug. 28, 1901, *Stuntz & Allen*; Leland, Mich., Sept. 7, 1908, *Arthur & Kern*; *Amelanchier intermedia* Spach, Taughannock Falls, N. Y., Sept. 3, 1908, *Whetsel, Wallace & Reddick*.

III. Telia caulicolous, from a perennial mycelium, appearing on irregularly lobed, gall-like excrescences 2–15 mm. or more in diameter, unevenly distributed, often separated by the scars of the sori of previous seasons, conical or cylindrical-acuminate, 1.5–2 mm. in diameter at the base by 3–5 mm. high, dark chestnut-brown; teliospores 2-celled, ellipsoid, 18–21 by 35–50 μ , slightly or not constricted at the septum, slight hyaline thickenings over the germ-pores, wall cinnamon-brown, thin 1–1.5 μ ; pedicel uniform, long; pores 1–2 in each cell, near the septum.

On *Juniperus horizontalis* Moench, Leland, Mich., June 4, 1909, *F. D. Kern*.

4. GYMNOSPORANGIUM sp. nov.—Among the material collected at Santee Canal, S. C. by Mr. F. D. Kern on March 18, 1909, was an abundance of telia on *Juniperus virginiana*, in part extending along the smaller branches often for a foot or more, and referred to above under unsuccessful cultures, and in part forming rather distinct globoid galls from very small up to a half inch or even more in diameter. It was difficult to tell in the field whether there were two species associated or only the incidental

variation of a single species, as both forms bore prominent dark brown telia of quite similar appearance. The cultures, however, settled the question. Sowings were made of the gall-form March 22, on *Crataegus punctata* giving rise to yellow spots after fifteen days, on which pycnia appeared by April 12, but the leaves matured before aecia could form. Other sowings were made May 14 on *Crataegus coccinea* and *C. cerronis*, giving rise to a few belated pycnia on the former, first observed June 14, but on the latter to an abundance of pycnia May 25 and mature aecia October 27.

This fortunate culture adds another species, with life cycle known, to the Atlantic coast rusts of the common red cedar. It does not appear to be represented in herbaria, either in the aecial or telial form, except by some small unnamed fragments. Possibly collections of aecia have been referred to *G. globosum*, which grows on *Crataegus*, although the peridia differ in gross appearance. An interesting point is that this species produces cornute aecia, the first to be noticed on *Crataegus*. The following name and description have been supplied by Mr. Kern, who has also increased the number of aecial hosts by searching in phanerogamic collections.

***Gymnosporangium trachysorum* Kern, sp. nov.**

O. Pycnia epiphyllous, gregarious, in groups 1-2 mm. across, prominent, punctiform, orange-yellow becoming brownish-black, globoid, 144-165 μ in diameter by 112-128 μ high; ostiolar filaments 75-90 μ long.

I. Aecia hypophyllous, rather few in irregular groups 2-5 mm. across, on discolored slightly thickened spots 5-10 mm. or more across, cylindrical, 2-4 mm. high, 0.2-0.3 mm. in diameter; peridium remaining horn-like, finally rupturing by longitudinal slits along the sides, peridial cells long and narrow in side view, 15-19 by 32-90 μ , outer wall thin 1.5-2 μ , nearly or quite smooth, inner and side walls moderately thick, 3-6 μ , closely spinulose with short spine-like papillae interspersed with lower oval or ridge-like papillae; aeciospores globoid or ellipsoid, 15-23 by 18-27 μ , wall chestnut-brown, rather thick, about 2.5-3 μ , very minutely verrucose, appearing almost smooth; pores about 6, scattered.

On *Crataegus Marshallii* Egg. (*C. apiifolia* Michx.) Auburn, Lee Co., Alabama, Nov. 20, 1897, F. S. Earle; Aldenbridge, La.,

Nov. 1, 1898, *Wm. Trelease*; *Crataegus flavo-carius* Ashe, Salisbury, N. C., Sept. 11 and 12, 1908, *W. W. Eggleston*; *Crataegus Phaenopyrum* (L. f.) Medic. (*C. cordata* Ait.), Salisbury, N. C., Oct. 7, 1908, Catawba, N. C., Sept. 13 and 14, 1908, *W. W. Eggleston*.

III. Telia cauliculous, from a perennial mycelium, appearing on abruptly fusiform or globoid gall-like enlargements, 0.5–1.5 cm. in diam. by 0.5–3 cm. long, unevenly disposed, sometimes densely crowded, often separated by the scars of the sori of previous seasons, more or less wedge-shaped, 1.5–2 mm. broad by 2–4 mm. long at base by 6–10 mm. high, surface very rough with irregular warts and ridges, dark chestnut-brown; teliospores 2-celled, ellipsoid, 18–21 by 37–45 μ , wall cinnamon-brown, medium thin 1.5–2.5 μ ; pedicel hyaline, very long, uniform; pores 1 or 2 in each cell, near the septum.

On *Juniperus virginiana* L., Santee Canal, S. C., March 18, 1909, *Frank D. Kern* (type); Agricultural College, Miss., April 10, 1893, *S. M. Tracy*.

SUMMARY.

The following is a complete list of the successful cultures made during the year 1909. It is divided into two series, species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. Species Previously Reported.

1. *Puccinia Peckii* (DeT.) Kellerm.—Teliospores on *Carex lanuginosa* Michx. and on *C. trichocarpa* Muhl., sown on *Onagra biennis* (L.) Scop.

2. *Puccinia Caricis* (Schum.) Schröt.—Teliospores on *Carex aristata* R. Br., sown on *Urtica gracilis* Ait.

3. *Puccinia universalis* Arth.—Teliospores on *Carex stenophylla* Wahl., sown on *Artemisia dracunculoides* Pursh.

4. *Puccinia Caricis-Asteris* Arth.—Teliospores on *Carex festiva* Dewey, sown on *Aster adscendens* Rydb.

5. *Puccinia subnitens* Diet.—Teliospores on *Distichlis spicata* (L.) Greene, sown on *Atriplex hastata* L. and *Chenopodium album* L.

6. *Puccinia amphigena* Diet.—Teliospores on *Calamovilfa longifolia* (Hook.) Hack., sown on *Smilax hispida* Muhl.

7. *Puccinia fraxinata* (Schw.) Arth.—Teliospores on *Spartina cynosuroides* Willd., sown on *Fraxinus lanceolata* Borck.

8. *Puccinia Phragmitis* (Schum.) Körn.—Teliospores on *Phragmites communis* Trin., sown on *Rumex crispus* L.

9. *Puccinia obliterated* Arth.—Teliospores on *Agropyron* sp., sown on *Thalictrum alpinum* L.

10. *Puccinia Muhlenbergiae* Arth. & Holw.—Teliospores on *Muhlenbergia glomerata* Trin., sown on *Callirrhoe involucrata* (T. & G.) A. Gray.

11. *Puccinia Impatiens* (Schw.) Arth.—Teliospores on *Elymus striatus* Willd., sown on *Impatiens aurea* Muhl., and aeciospores on *Impatiens aurea* Muhl., sown on *Elymus virginicus* L., *E. canadensis* L., and *E. striatus* Willd.

12. *Puccinia poculiformis* (Jacq.) Wettst.—Teliospores on *Agropyron pseudorepens* Scribn. & Sm., and *Sitanion longifolium* J. G. Sm., sown on *Berberis vulgaris* L., and aeciospores on *Berberis vulgaris* L., sown on *Triticum vulgare* Vill.

13. *Puccinia substerilis* E. & E.—Amphisporos on *Stipa viridula* Trin., sown on same host.

14. *Uromyces Andropogonis* Tracy.—Teliospores on *Andropogon virginicus* L., sown on *Viola cucullata* Ait.

15. *Uromyces Spartinae* Farl.—Teliospores on *Spartina cynosuroides* Willd., sown on *Steironema lanceolatum* (Walt.) A. Gray and *S. ciliatum* (L.) Raf.

16. *Gymnosporangium globosum* Farl.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus coccinea* L.

17. *Gymnosporangium clavipes* C. & P.—Teliospores on *Juniperus sibirica* Burgsd., sown on *Amelanchier erecta* Blanch., and *Crataegus punctata* Jacq.

18. *Gymnosporangium nidus-avis* Thax.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus Pringlei* Sarg., and *Malus Ioensis* (Wood) Britt.

19. *Gymnosporangium Betheli* Kern.—Teliospores on *Juniperus scopulorum* Sarg., sown on *Crataegus cerronis* A. Nels.

20. *Gymnosporangium cornutum* (Pers.) Arth.—Teliospores on *Juniperus sibirica* Burgsd., sown on *Sorbus americana* Marsh., and *S. Aucuparia* L.

21. *Gymnosporangium floriforme* Thax.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus coccinea* L.

22. *Gymnosporangium exterum* Arth. & Kern.—Teliospores on *Juniperus virginiana* L., sown on *Porteranthus stipulatus* (Muhl.) Britt.

23. *Calyptospora columnaris* (A. & S.) Kühn.—Teliospores on *Vaccinium pennsylvanicum* Lam., sown on *Abies Fraseri* Pursh.

B. Species Reported Now for the First Time.

1. *Puccinia Ceanothi* (Ellis & Kellerm.) Arth.—Teliospores on *Andropogon Hallii* Hack., sown on *Ceanothus americanus* L.

2. *Gymnosporangium exiguum* Kern.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus Pringlei* Sarg.

3. *Gymnosporangium corniculans* Kern.—Teliospores on *Juniperus horizontalis* Moench, sown on *Amelanchier erecta* Blanch., and *A. canadensis* (L.) Medic.

4. *Gymnosporangium trachysorum* Kern.—Teliospores on *Juniperus virginiana* L., sown on *Crataegus punctata* Jacq., *C. coccinea* L., and *C. cerronis* A. Nels.

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.

11

CULTURES OF UREDINEAE IN 1910

J. C. ARTHUR

The present article is the eleventh of a series of reports¹ by the writer upon the culture of plant rusts, beginning in 1899. Almost uniform progress has been made during the twelve years in the prime purpose of the work, that of experimentally connecting the sporophytic and gametophytic phases of heteroecious rusts, as well as the study of autoecious species and in some cases the detection of races. The work of the year is representative in these several respects. It was under the charge of Miss Irma A. Uhde, a senior student in general science in the University of Iowa, who was recommended by Professor Thomas H. Macbride. Miss Uhde conducted the work with fine insight and untiring patience, securing a notably large number of successful infections. Some of the sowings, particularly those of the cedar rusts were made and the records kept by Dr. F. D. Kern. All the work was done under the auspices of the Indiana Experiment Station, and financed from the Adams fund.

There are some very common American rusts that collectors of culture material are likely to send in considerable abundance every year, such as *Puccinia Caricis*, *P. Peckii*, *P. angustata* and the *Aster-Solidago-Erigeron* group among the sedge rusts, and *P. poculiformis*, *P. pustulata*, *P. Andropogonis*, *P. Impatiensis* and *P. fraxinata* among the grass rusts. These are usually sown, although the life cycle is known, and when time and opportunity permit some tests are made regarding their less known aecial hosts and the possibility of races. While these and similar species take time that could usually be put upon less known forms to better advantage, there is another set of common rusts often sent by collectors, whose life cycle is not known, such as *Puccinia emaculata*, *P. Ellisiana*, *P. vexans*, and the form on *Carex Penn-*

¹ See Bot. Gaz. 29: 268-276; 35: 10-23; Jour. Myc. 8: 51-56; 10: 8-21; 11: 50-67; 12: 11-27; 13: 189-205; 14: 7-26; Mycol. 1: 225-256; and 2: 213-240.

sylvanica, which consume time with no more profit. They have been repeatedly sown, but for want of careful field observations regarding proximity of aecia, little advance is made.

Those who assisted in the work with culture material, and often with valuable suggestions, are named with special gratitude, for to them is due in considerable degree whatever of value has come from the year's labors. Mr. E. Bethel, Denver, Colo., sent 123 collections, by far the largest number contributed by one person in any year since the work began. Messrs. W. P. Fraser, Pictou, Nova Scotia, J. F. Brenckle, Kulm, N. D., and W. H. Long, Washington, D. C., sent between 30 and 40 collections each, while much smaller numbers were sent by Messrs. E. Bartholomew, Stockton, Kans., J. M. Bates, Red Cloud, Neb., H. S. Coe, Ames, Iowa, J. J. Davis, Racine, Wis., A. C. Dillman, Washington, D. C., H. S. Fawcett, Gainesville, Fla., A. O. Garrett, Salt Lake City, Utah, R. A. Harper, Madison, Wis., E. W. D. Holway, Minneapolis, Minn., Haven Metcalf, Washington, D. C., A. J. Norman, College Park, Md., E. W. Olive, Brookings, S. D., J. B. Pollock, Ann Arbor, Mich., Donald Reddick, R. E. Stone, and H. H. Whetzel, all three of Ithaca, N. Y., Guy West Wilson, Fayette, Iowa, and by Misses Louise Falk, Boulder, Colo., and Miriam Turner, Isle au Haut, Me. Many living plants were received from a number of botanists to whom requests had been sent for suitable specimens on which to make sowings of particular rusts. To all these and to others who assisted in the year's investigations the writer extends his heartiest thanks.

During the present season 294 collections of material with resting spores and 25 collections with active spores were employed, from which 987 drop cultures were made to test the germinating condition of the spores. Out of the 294 collections with resting spores 134 failed to germinate, leaving 160 collections available for experimental tests, this being a far larger number than in any previous year. Altogether about 400 sowings were made, using a great variety of hosts growing in pots in the greenhouse, and 75 infections obtained. The most important conclusions derived from a study of the results are given in the following paragraphs.

NEGATIVE RESULTS.—A number of collections giving good ger-

mination of the spores were sown on plants in the hope of discovering the alternate host but without securing infection. The following are recorded to serve for reference in future studies.

1. PUCCINIA on *Carex Pennsylvanica* L., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown on *Laciniaria punctata* (on 4 different dates), *L. spicata*, *Dirca palustris* (2 dates), and *Meriolix serrulata* (2 dates), with no infection. In preceding years this rust was sown on forty other species of hosts without infection.²

2. PUCCINIA on *Carex tenella* Schk., collected at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown on *Phryma leptostachya* (on 2 different dates), with no infection. In 1909 a similar collection was sown on six other species of hosts with no results.³

3. PUCCINIA on *Carex stellulata* Good., collected by the writer at Isle au Haut, Me., was sown on *Aster Drummondii*, *Solidago canadensis*, and *Ribes Cynosbati*, with no infection.

4. PUCCINIA on *Carex trisperma* Dewey, collected at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown on *Myrica cerifera*, *Apocynum cannabinum*, *Senecio Douglasii*, and *Solidago caesia*, with no infection.

5. PUCCINIA on *Carex arctata* Boott, collected at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown on *Lysimachia terrestris*, *L. quadrifolia*, *Chelone glabra* (on 2 different dates), *Rudbeckia laciniata*, and *R. triloba*, with no infection.

6. PUCCINIA PERMINUTA Arth., on *Agrostis hyemalis* (Walt.) B. S. P., collected by the writer at Isle au Haut, Me., was sown on *Orchis spectabilis* and *Actaea alba*, with no infection. Another collection on *A. perennans* (Walt.) Tuckerm., collected at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown on *Aquilegia canadensis*, *Thalictrum dioicum*, *Caulophyllum thalictroides*, *Anemonella thalictroides*, and *Isopyrum biternatum*, with no infection.

7. PUCCINIA ELLISIANA Thüm., on *Andropogon scoparius* Michx., collected by Dr. J. F. Brenckle, at Kulm, N. D., was

² See Jour. Myc. 10: 10. 1904; 11: 51. 1905; 12: 12. 1906; 13: 191. 1907; 14: 9. 1908; and Mycol. 1: 229. 1909.

³ See Mycol. 1: 218. 1910.

sown on *Boehmeria cylindrica*, *Uvularia grandiflora*, *Myrica cerifera*, *Lysimachia quadrifolia*, *Thalictrum polygamum*, and *Laciniaria spicata*, with no infection. Similar material from Colorado, Nebraska, Delaware and North Carolina was sown in previous seasons on thirty five other species of hosts.⁴

8. PUCCINIA SCHEDONNARDI K. & S., on *Schedonnardus paniculatus* (Nutt.) Trel., collected by Mr. E. Bethel, at Westminster, Colo., was sown on *Delphinium formosum*, *Xanthoxylum americanum*, *Symphoricarpos pauciflorus*, *Hydrophyllum virginicum*, *H. capitatum*, *Onosmodium occidentale*, *Petalostemon purpureus*, *Amorpha nana*, *Boltonia asteroides*, *Grindelia squarrosa*, *Rudbeckia triloba*, *Laciniaria punctata*, *Solidago rigida*, and *Arnica* sp., with no infection. This collection possessed clean and well developed sori, and gave strong germination. Similar material in former years was sown on fifteen other species of hosts.⁵

9. PUCCINIA VIRGATA Ellis & Ev., on *Chrysopogon avenaceus* (Michx.) Benth., collected by Mr. W. H. Long at El Reno, Okla., was sown on *Dirca palustris*, *Xanthoxylum americanum*, *Boehmeria cylindrica*, *Apios Apios*, *Petalostemon purpureus*, and *Mimulus ringens*, with no infection. Similar material from Nebraska and North Carolina was sown in previous years on nine other species of hosts.⁶

10. PUCCINIA TOSTA Arth., on *Sporobolus asperifolius* Nees & Meyen, collected by Dr. J. F. Brenckle at Kulm, N. D., was sown on *Lepargyrea canadensis*, *Dirca palustris*, *Symphoricarpos racemosus*, *Apocynum cannabinum*, *Delphinium formosum*, *Polemonium reptans*, *Laciniaria punctata*, *Aster paniculatus*, and *Arnica* sp., with no infection.

Another collection on same host, made by Mr. E. Bethel at Denver, Colo., was sown on *Symphoricarpos racemosus*, *Lepargyrea canadensis*, *Phacelia heterophylla*, *Hydrophyllum virginicum*, *Lithospermum canescens*, *Amorpha fruticosa*, *Arabis Holboellii*, and *Sidalcea oregana*, with no infection. Similar material was sown in previous years on ten other species of hosts.⁷

⁴ See Jour. Myc. 14: 10. 1908; Mycol. 1: 231. 1909; 2: 220. 1910.

⁵ See Bot. Gaz. 35: 11. 1903; Jour. Myc. 13: 192. 1907; 14: 11. 1908; and Mycol. 1: 231. 1909.

⁶ See Jour. Myc. 14: 10. 1908; and Mycol. 2: 219. 1910.

⁷ See Jour. Myc. 10: 10. 1904; and 12: 12. 1906.

11. PUCCINIA on *Phalaris arundinacea* L., collected by Dr. E. W. Olive, at Brookings, S. D., was sown on *Polygonatum commutatum*, *Vagnera stellata*, *Convallaria majalis*, *Uvularia grandiflora*, and *Trillium cernuum*, with no infection.

12. PUCCINIA DISTICHLIDIS E. & E., on *Spartina* sp., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown on *Lithospermum canescens* (on 2 different dates), *Onosmodium hispidissimum*, *Lepargyrea canadensis* (2 dates), *Elaeagnus angustifolia*, *Dirca palustris*, *Fraxinus lanceolata*, *Symphoricarpos racemosus*, *Aesculus glabra*, *Apocynum cannabinum*, *Hydrophyllum capitatum*, *Macrocalyx Nyctelea*, *Isopyrum biternatum*, *Amorpha nana*, *Cassia chamaecrista*, *Petalostemon purpureus*, *Physalis* sp., *Ambrosia trifida*, and *Carduus Flodmanii*, with no infection. A year ago the same rust was sown on three other hosts without results.⁸

13. PUCCINIA ANTHOXANTHI Fckl., on *Anthoxanthum odoratum* L., collected by Professor W. P. Fraser, at Pictou, Nova Scotia, was sown on *Berberis vulgaris*, *Myrica cerifera*, *Apocynum cannabinum*, *Tissa canadensis*, *Senecio lugens*, and *Rudbeckia triloba*, with no infection.

14. PUCCINIA on *Trisetum majus* (Vasey) Rydb. having covered telia and coronate teliospores, simulating *P. Rhamni*, collected in the foothills of Colorado, by Mr. E. Bethel, was sown on *Rhamnus alnifolia* from one collection, and on *Rhamnus cathartica* from another. A similar collection from Golden, Colo., with same data, was sown on the two sets of *Rhamnus*, while another collection from Boulder, Colo., was sown on *Mahonia Aquifolium* and *Arabis Holboellii*. In each instance there was no infection.

15. PUCCINIA MONTANENSIS Ellis, on *Elymus canadensis* L. collected by Mr. E. Bethel, at Colorado Springs, Colo., was sown on *Clematis virginiana* (on 2 different dates), *Viorna Douglasii* (2 dates), *Impatiens aurea*, *Delphinium scaposum*, *Viola septentrionalis*, *Arabis Holboellii*, *Amorpha nana*, *Senecio Douglasii*, and *Arnica* sp., with no infection. In 1907 what is thought to be the same rust was sown four times on *Delphinium tricornis* without result.⁹

⁸ See Mycol. 2: 219. 1910.

⁹ See Jour. Myc. 14: 11. 1908.

16. UROMYCES ELEOCHARIDIS Arth., on *Eleocharis palustris* (L.) R. & S., collected by Dr. E. W. Olive, at Brookings, S. D., was sown on *Laciniaria spicata*, *L. scariosa*, *Eupatorium serotinum*, *Polygala Senega*, *Hydrophyllum virginicum*, *Amorpha fruticosa*, *Symphoricarpos racemosus*, *Lepargyrea canadensis*, and *Dirca palustris*, with no infection. In 1906 the same rust was sown on five other species of hosts without results.¹⁰

17. UROMYCES SPARTINAE Farl., on *Spartina Michauxiana* A. S. Hitch. (usually listed as *S. cynosuroides*), collected by Professor W. P. Fraser, at Pictou, Nova Scotia, was sown on *Steironema ciliatum* (on 2 different dates), *Polemonium reptans*, *Phlox divaricata*, and *Tissa canadensis*, with no infection.

Another collection from the same collector and place, but on *S. patens* (Ait.) Muhl., was sown on *Steironema ciliatum* (2 dates), *Polemonium reptans*, and *Lysimachia terrestris*, with no infection.

It is evident from the present repeated inability to infect *Steironema* with *Spartina* rust from the salt marshes of the sea coast, supposedly the same species as in the interior,¹¹ that the status of this rust, or group of rusts, is not yet fully known. Either we are dealing with more species than heretofore recognized, or there are biological races yet undetermined.

18. UROMYCES PECKIANUS Farl., on *Distichlis spicata* (L.) Greene, collected by Professor W. P. Fraser, at Pictou, Nova Scotia, was sown on *Tissa canadensis* (on 2 different dates), *Mimulus ringens*, and *Rudbeckia laciniata*, with no infection.

19. UROMYCES GRAMINICOLA Burr., on *Panicum virgatum* L., collected by Mr. W. H. Long, at El Reno, Okla., was sown on *Dirca palustris*, *Apios tuberosa*, and *Boltonia asteroides*, with no infection. Another collection on the same host sent by Mr. E. Bartholomew from Stockton, Kans., was sown on *Apios tuberosa*, *Petalostemon purpureus*, *Cassia chamaecrista*, *Aesculus glabra*, *Apocynum cannabinum*, and *Laciniaria spicata*, with no infection.

The same rust has been sown on eleven other species of hosts in previous years.¹²

¹⁰ See Jour. Myc. 13: 193. 1907.

¹¹ For a statement regarding *Uromyces* on *Spartina* see Mycol. 2: 221. 1910.

¹² See Jour. Myc. 12: 13. 1906; Mycol. 1: 232. 1909; 2: 220. 1910.

20. *UROMYCES SPOROBOLI* E. & E., on *Sporobolus neglectus* Nash, collected by Dr. E. W. Olive, at Brookings, S. D., was sown on *Lepargyrea canadensis*, *Elaeagnus angustifolia*, *Amorpha nana*, *Erigeron annuus* (on two different dates), and *Arnica* sp., with no infection.¹³

21. *AECIDIUM* on *Euphorbia commutata* Engelm. was obtained in the vicinity of Lafayette, Ind., by Messrs. F. D. Kern and T. Billings. The living plants were placed in pots and continued to flourish. They bore aecia in all stages of maturity. These plants were adjusted in a moist chamber over the following hosts, so that aeciospores fell spontaneously upon the young leaves: *Astragalus canadensis*, *Pisum sativum*, *Lathyrus palustris*, *Medicago sativa*, and *Trifolium pratense*. No infection was obtained.

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK.—The facts derived by growing the following species of rusts supplement those obtained from previous cultures in this series or from cultures recorded by other American or European investigators.

1. *PUCCINIA* ^{*albheredia* Asth.} ~~*GROSSULARIAE* (Schum.) Lagerh.~~, on *Carex tenuis* Rudge, collected at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown April 7 on *Erigeron annuus*, *Solidago canadensis*, *Aster paniculatus* and *Ribes Cynosbati*, with infection only on the last,¹⁴ showing pycnia April 16, and aecia April 25. Similar material obtained by the writer at Isle au Haute, Me., was sown on the same hosts, but omitting *Erigeron*, and with similar results.

A collection on *Carex pallescens* L., made by Professor W. P. Fraser at Pictou, Nova Scotia, the previous fall, was sown April 8 on *Erigeron annuus*, *Solidago canadensis*, *Aster paniculatus* and *Ribes Cynosbati*, with infection only on the last, showing abundant pycnia April 16, and aecia April 22. A similar collection, made by Prof. Fraser in the spring, was sown April 18, without infection, on *Lysimachia terrestris*, *Lactuca scariola*, *Rudbeckia laciniata*, *Polygala Senega* and *Apocynum cannabinum*. Two days earlier it was sown on *Ribes Cynosbati*, resulting in good infection, showing pycnia April 27, and aecia May 3.

¹³ See Bot. Gaz. 35: 11. 1903.

¹⁴ For similar negative results see Mycol. 2: 218. 1910.

The *Carex* rusts having aecia on *Ribes* are yet imperfectly known. My own culture work began in 1901, and owing to the remarkably pale aecia produced, the form in hand at the time was named *Puccinia albiperidia*. Since then many cultures have been made, and the status of the species has received considerable attention, but not until recently has any well marked morphological characters been discovered. Present studies indicate that *P. albiperidia* is a species worthy of being maintained. Beside the more or less pale aecia it possesses one basal pore in the urediniospore.

It is curious to note that the only other species of monocotyledonous rust known with a single basal pore in the urediniospore, *Uromyces uniporulus* Kern, is also on *Carex*. When published it had only been found in Connecticut on *C. tenuis*. Since then it has been detected in Wisconsin on *C. gracillima*. These are also the hosts of *P. albiperidia*, together with *C. pallescens* and *C. pubescens*. Comparing the spores, it appears that the urediniospores of the *Puccinia* and of the *Uromyces* not only agree in the pore characters, but also as to form, size and color, *i. e.*, in all morphological characters. The teliospores are also alike except in number of cells, and in the consequent length. If the sori of the *Puccinia* often contained many one-celled teliospores, and the sori of the *Uromyces* often had a few two-celled spores, *U. uniporulus* might be considered a mere mesoporic form of *P. albiperidia*. But such does not appear to be the case. However, while in the present state of uredinological taxonomy the two forms are to be maintained as distinct species belonging to different genera, yet *U. uniporulus* is doubtless only a morphological race of *P. albiperidia*. Cultures of *P. albiperidia* were made in 1901, 1903 and 1904.¹⁵ No cultures have yet been made of *U. uniporulus*, but it probably has aecia on *Ribes*.

The far more common and widely distributed species, for which I am making the name *Puccinia Grossulariae* serve, has more deeply colored aecia and three equatorial pores in the urediniospore. I am inclined to think that this is the common gooseberry-*Carex* rust of this country and Europe, but I am not able at present to define its limits, neither can I say whether the

¹⁵ See Jour. Myc. 8: 53. 1902; 10: 11. 1904; and in part 11: 58. 1905.

current-*Carex* rusts belong here or not. My previous cultures¹⁶ of this form have been reported under the name *P. albiperidia*, and confused with that species.

2. PUCCINIA PECKII (DeT.) Kellerm., on *Carex lanuginosa* Michx., collected at Kulm, N. D., by Dr. J. F. Brenckle, was sown April 7 on *Onagra biennis* and *Meriolix serrulata*, with no infection on the latter, but with abundant pycnia on the former April 16, and aecia April 25.

Another collection on *Carex trichocarpa* Muhl., made at Carmel, Ind., by Messrs. F. D. Kern and A. G. Johnson, was sown April 13 on plants of the same two species of hosts with similar results. There was no infection of the *Meriolix*, but abundance of pycnia showed on the *Onagra* April 23, and aecia May 5. A duplicate sowing was made May 11, which gave a few pycnia on the *Meriolix*, but no aecia developed, while on the *Onagra* abundance of pycnia appeared May 19, and aecia May 27.¹⁷

In previous years this species of rust has been grown on *Onagra biennis* and *Gaura biennis*, the two hosts being very similar in vegetative structure. Aecia have been gathered in the field on a number of related hosts with less similarity in vegetative structure, such as *Meriolix*, but heretofore no cultural studies have been made. The present attempt may be interpreted as indicating that certain outlying hosts are infected only under exceptionally favorable circumstances, or that there exist more or less well marked races.

3. PUCCINIA CARICIS-SOLIDAGINIS Arth., on *Carex scoparia* Schk., collected by the writer at Isle au Haut, Me., was sown April 20, on *Euthamia graminifolia* (*Solidago lanceolata*) and *Solidago rugosa*, with infection only on the former, abundance of pycnia showing April 30, and aecia May 9. Another sowing was made June 10 on the same two hosts, and on *S. canadensis*, *S. nemoralis*, *Doellingeria umbellata* and *Aster paniculatus*, with

¹⁶ See Jour. Myc. 11: 58. 1905 (in part); 12: 14. 1906; 13: 196. 1907; and 14: 13. 1908.

¹⁷ For previous cultures see Bot. Gaz. 35: 13. 1903; Jour. Myc. 8: 52. 1902; 11: 58. 1905; 12: 15. 1906; 13: 195. 1907; Mycol. 1: 233. 1909; and 2: 222. 1910.

infection only on the *Euthamia*, showing pycnia June 18, and aecia July 5.¹⁸

All the hosts used in the trial are common in the vicinity where the telial material was obtained and bear aecia. It is highly probable that the aecial forms occurring on *Solidago*, *Aster*, *Erigeron*, *Euthamia*, and possibly *Doellingeria*, belong to one species made up of fairly well defined races. The form on *Euthamia* appears from present data to constitute a race distinct from that on *Solidago*, but is here included under the same name.

4. PUCCINIA CARICIS-ASTERIS Arth., on *Carex festiva* Dewey collected by Mr. E. Bethel, at Tolland, Colo., 9,000 feet altitude, was sown April 13, on *Aster adscendens* Lindl. (*A. Tweedyi* Rydb.), and the day following on *Onagra biennis*, with no infection on the latter and abundant infection on the former, giving pycnia April 27, and aecia May 2. Another collection with same data was sown on *Aster adscendens* April 9, and again on May 4, only the latter being effective, giving pycnia in abundance May 14, and aecia May 21.¹⁹

5. PUCCINIA OPIZII Bubák, on *Carex siccata* Dewey, collected by Dr. J. F. Brenckle, at Kulm, N. D., was sown as follows:

April 9, *Lactuca canadensis*: pycnia April 16, aecia April 25.

April 9, *Lactuca sativa*: pycnia April 25, aecia May 2.

April 19, *Lactuca canadensis*: pycnia April 30, aecia none.

April 19, *Lactuca sativa*: pycnia May 6, aecia none.

In the sowings on both dates the infection developed more slowly and less abundantly on the garden lettuce (*L. sativa*), than on the wild form. In both of the late sowings the aecia failed to appear, because the leaves matured too soon and died.²⁰

6. PUCCINIA UNIVERSALIS Arth., on *Carex stenophylla* Wahl., collected by Mr. E. Bethel, at Boulder, Colo., was sown April 19, on *Artemisia dracunculoides*, giving abundance of pycnia April 29, and aecia May 3.²¹

¹⁸ For previous cultures see Bot. Gaz. 35: 21. 1903; Jour. Myc. 12: 15. 1906; and Mycol. 1: 233. 1909.

¹⁹ For previous cultures see Bot. Gaz. 35: 15. 1903; Jour. Myc. 8: 54. 1902; 14: 13. 1908; and Mycol. 2: 224. 1910.

²⁰ For previous culture from an undetermined *Carex* see Jour. Myc. 13: 194. 1907.

²¹ For previous cultures see Jour. Myc. 14: 21. 1908; and Mycol. 2: 224. 1910.

7. *PUCCINIA CARICIS* (Schum.) Schröt., on *Carex aristata* R. Br., collected by Dr. J. F. Brenckle, at Kulm, N. D., was sown April 7, on *Urtica gracilis* and *Boehmeria cylindrica*, with infection only on the former, giving pycnia April 13, and aecia April 19.

Another collection on *Carex stricta* Lam., made in the vicinity of Lafayette, Ind., by Mr. A. G. Johnson, was sown April 13, on the same two hosts, producing infection only on *Urtica gracilis*, giving pycnia April 22, and aecia April 27. Similar results were obtained in previous years.²²

8. *PUCCINIA ANGUSTATA* Peck, on *Scirpus atrovirens* Muhl., collected by Messrs. F. D. Kern and A. G. Johnson, at Carmel, Ind., was sown April 7, on *Lycopus americanus*, giving pycnia April 16, and aecia April 22. Another similar collection made by Mr. A. G. Johnson near Lafayette, Ind., was sown on same host April 13, giving pycnia April 25, and aecia May 1.²³

9. *PUCCINIA ANDROPOGONIS* Schw., on *Andropogon virginicus* L., collected at Clarendon, W. Va., by Mr. W. H. Long, was sown May 13, on *Pentstemon hirsutus*, giving pycnia May 23, and aecia June 7. Another collection on *A. scoparius* Michx., made at Boulder, Colo., by Mr. E. Bethel, was sown May 12 on *Comandra umbellata* and *Pentstemon alpinus*, with infection only on the latter, and not abundant, pycnia and aecia not being observed until May 31.²⁴

10. *PUCCINIA PUSTULATA* (Curt.) Arth., on *Andropogon furcatus* Muhl., collected at Plainview, Colo., by Mr. E. Bethel, was sown April 13, on *Comandra umbellata* and *Pentstemon barbatus*, giving rise to infection only on the former, showing pycnia April 27, and aecia May 9. Another collection by Mr. Bethel from Colorado on *Andropogon* sp., was sown May 12 on *Comandra umbellata* and *Pentstemon alpinus*, with infection only on the former, giving pycnia in abundance May 20, and aecia May 31.²⁵

²² For previous cultures see Bot. Gaz. 29: 270. 1900; 35: 16. 1903; Jour. Myc. 8: 52. 1902; 12: 15. 1906; 14: 14. 1908; and Mycol. 2: 223. 1910.

²³ For previous cultures see Bot. Gaz. 29: 273. 1900; Jour. Myc. 8: 53. 1902; 11: 58. 1905; 13: 196. 1907; 14: 14. 1908; and Mycol. 1: 234. 1909.

²⁴ For previous cultures see Bot. Gaz. 29: 272. 1900; Jour. Myc. 10: 11. 1904; and 13: 197. 1907.

²⁵ For previous cultures see Jour. Myc. 10: 17. 1904; and 12: 16. 1906.

11. PUCCINIA AMPHIGENA Diet., on *Calamovilfa longifolia* (Hook.) Hack., collected by Dr. J. F. Brenckle, at Kulm, N. D., was sown April 25, on *Smilax hispida*, giving rise to pycnia in abundance May 2, and aecia May 14.²⁶

12. PUCCINIA MUHLENBERGIAE Arth. & Holw., on *Muhlenbergia racemosa* (Michx.) B. S. P., collected by Dr. J. F. Brenckle, at Kulm, N. D., was sown May 6, on *Hibiscus militaris*, *Napaea dioica* and *Callirrhoe involucrata*, with infection only on the last, giving abundance of pycnia that were first seen May 23, and aecia May 27.²⁷ Another collection of the rust on *M. gracilis*, sent by Mr. E. Bethel, from the foothills of Colorado, was sown on the same three hosts, with no infection. Still a third collection, on *M. racemosa*, sent by Mr. E. Bartholomew from Stockton, Kans., was sown May 11, on *Hibiscus militaris* and *Althaea rosea*, without infection.

13. PUCCINIA RHAMNI (Pers.) Wettst., on *Calamagrostis canadensis* (Michx.) Beauv., collected by Professor W. P. Fraser, at Pictou, Nova Scotia, was sown May 26, on *Rhamnus alnifolia*, giving a strong infection, pycnia showing June 6, and aecia June 10. The only previous cultures in the series were made with aeciospores.²⁸

14. PUCCINIA POCULIFORMIS (Jacq.) Wettst., on *Agropyron tenerum* Vasey, collected by Mr. E. Bethel, at Boulder, Colo., was sown April 25, on *Berberis vulgaris*, giving pycnia May 2, and aecia May 14. Another collection by Mr. Bethel, on *Sitanion longifolium* J. G. Sm., made at Eldorado Springs, Colo., was sown May 3, on *Berberis vulgaris*, giving pycnia May 14, and aecia May 26. Still another collection on *Agrostis alba* L., made by the writer at Isle au Haut, Me., was sown April 19, on *Berberis vulgaris*, giving pycnia April 29, and aecia May 9.²⁹

15. PUCCINIA SUBNITENS Diet., on *Distichlis spicata* (L.) Greene, collected by Dr. J. F. Brenckle, at Kulm, N. D., was sown May 4, on *Chenopodium album*, *Monolepis Nuttalliana*, and *Cory-*

²⁶ For previous cultures see Bot. Gaz. 35: 20. 1903; Jour. Myc. 10: 11. 1904; 12: 16. 1906; 14: 15. 1908; and Mycol. 2: 225. 1910.

²⁷ For previous cultures see Mycol. 1: 251. 1909; and 2: 226. 1910.

²⁸ See Jour. Myc. 11: 58. 1905.

²⁹ For previous cultures see Jour. Myc. 8: 53. 1902; 11: 57. 1905; 12: 17. 1906; 13: 198. 1907; 14: 16. 1908; and Mycol. 2: 227. 1910.

dalis aurea, with infection only on the first, giving numerous pycnia May 16, and aecia May 21. Another sowing was made May 25, on *Chenopodium album*, *Monolepis Nuttalliana*, *Corydalis sempervirens*, and *Tissa canadensis*, and again infection was only obtained on the first, giving pycnia June 5, and aecia June 16. These attempts add nothing materially to previous knowledge.³⁰

16. PUCCINIA JAMESIANA (Peck) Arth., on *Atheropogon curtispendus* (Michx.) Fourn., collected by Mr. W. H. Long, at Amarillo, Texas, was sown April 19, on *Asclepias syriaca*, giving pycnia May 3, and aecia May 9. Previous cultures were also made with Texan material sent by Mr. Long.³¹

17. PUCCINIA SEYMOURIANA Arth., on *Spartina Michauxiana* A. S. Hitch, collected by Mr. W. H. Long, at El Reno, Okla., was sown June 3, on *Cephalanthus occidentalis*, giving numerous pycnia June 11, and aecia June 24.³²

18. PUCCINIA STIPAE Arth., on *Stipa spartea* Trin., collected by Dr. E. W. Olive, at Brookings, S. D., was sown May 10, on *Aster ericoides* and *A. Novae-Angliae*, giving pycnia in both cases May 19, without developing aecia on *A. ericoides*, but giving aecia on *A. Novae-Angliae* May 26.

Another collection made by the writer on the same host, at Spirit Lake, Iowa, was sown April 28, on *Aster multiflorus*, giving pycnia May 6, and aecia May 17. A second sowing was made May 6, on *Aster Novae-Angliae*, with pycnia May 16, and aecia May 23; on *A. multiflorus*, with pycnia May 17, and aecia May 23; on *Solidago canadensis*, with pycnia May 24, and aecia June 6; and on *Grindelia squarrosa*, without infection.

Another collection made by Mr. E. Bethel, at Golden, Colo., on *Stipa* sp., was sown April 22, on *Aster Novae-Angliae*, with pycnia May 2, and aecia May 16, on *Grindelia squarrosa*, with pycnia May 2, and aecia May 16, and on the following hosts without infection: *Aster ericoides*, *A. multiflorus*, *Solidago cana-*

³⁰ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; 14: 15. 1908; Mycol. 1: 234. 1909; and 2: 225. 1910.

³¹ For previous cultures see Bot. Gaz. 35: 18. 1903.

³² For previous cultures see Jour. Myc. 12: 24. 1906; and Mycol. 1: 236. 1909.

densis, *Arnica* sp., *Boltonia asteroides*, *Laciniaria scariosa*, *Symphoricarpos racemosus*, and *Hydrophyllum virginicum*.

Still another collection of what appears to be the same species of rust was collected on *Koeleria cristata* (L.) Pers., by Miss Louise M. Falk, at Boulder Colo., and sown April 27, on *Senecio lugens*, *Grindelia squarrosa*, *Symphoricarpos racemosus*, *Hydrophyllum virginicum*, and *Arabis Holboellii*, with infection only on the first, which showed pycnia May 14, and aecia May 19.

The aecia on the several hosts, thus produced, correspond in structure, and are peculiar in having evanescent peridia, the spores being retained by the surrounding tissues of the hypertrophied leaf. The striking appearance of the aecial groups suggested one of the early synonyms: *Aecidium sclerothecioides* Ellis & Ev. These cultures, although still lacking in completeness, have enabled us to bring together a number of uncertain forms with a considerable degree of assurance, and to extend both aecial and telial hosts.

19. PUCCINIA ARGENTATA (Schultz) Wint. At my request Professor Guy West Wilson, of Fayette, Iowa, made a somewhat trying excursion to Decorah, Iowa, and with the aid of directions supplied by Professor E. W. D. Holway, who resided there for many years, obtained living plants of *Adoxa Moschatellina* L., bearing aecia, which were potted and thrived. Two sowings were made April 18, by suspending the plants of *Adoxa* bearing aecia over plants of *Impatiens aurea*. In both instances a great abundance of urediniospores began to appear May 2. Again on April 21, two more similar sowings were made on other plants of *Impatiens*, and an equal abundance of urediniospores appeared May 3. These were followed on all four plants by an unusual abundance of teliospores, the record being made June 6, although they first appeared somewhat earlier.

The aecia on *Adoxa*, which are of limited distribution in America, early attracted the writer's attention, and as early as 1883³³ a first attempt was made toward solving their life history. Since the cultures of Bubák³⁴ proved that the European form on *Adoxa* was the aecial stage of telia on *Impatiens*, I have attempted to

³³ Bot. Gaz. 10: 369. 1885.

³⁴ Centr. Bakt. 10^a: 574. 1903.

secure American material for cultures, and the ample success when finally obtained is most gratifying. The American and European collections of this interesting heteroecious rust appear alike, and the present cultures show them to be identical.

20. *PUCCINIA ABSINTHII* DC., on a densely canescent species of *Artemisia*, collected by Mr. E. Bethel, at Boulder, Colo., was sown April 20, on *A. dracunculoides*, giving pycnia May 2, and uredinia May 20, thus confirming the previous cultures of two years ago.³⁵

21. *UROMYCES PERIGYNIUS* Halst., on *Carex intumescens* Rudge, collected by Professor W. P. Fraser, at Pictou, Nova Scotia, was sown April 21, on *Solidago nemoralis*, again April 26, on *S. canadensis*, on May 13, on both *S. nemoralis* and *S. canadensis*, and also on *Aster paniculatus*, and finally May 14, on *Tissa canadensis* and *Artemisia ludoviciana*. Quite unexpectedly the only sowing producing infection was on *Aster*, giving pycnia May 19, and aecia May 31, both abundantly developed.

Another collection apparently of the same rust, sent by Professor Fraser, on *Carex deflexa* Hornem., was sown May 28, on *Solidago rugosa*, *S. canadensis* and *Aster Drummondii*, with infection only on the first, giving abundance of pycnia June 4, and aecia June 16.

A collection on *Carex deflexa*, collected by the writer at Isle au Haut, Me., was sown May 13, on *Solidago rugosa*, *S. nemoralis*, and *Aster ericoides*. On *S. rugosa* numerous pycnia appeared May 20, and aecia May 31, but *S. nemoralis* remained free. The *Aster*, moreover, showed pycnia May 24, and aecia June 6, but they were not numerous and grew slowly. *Solidago rugosa* has been taken with aecia in the telial vicinity, but *Aster ericoides* does not grow there neither does any closely related species of *Aster*.

Considerable study has been given to the species of *Uromyces* on *Carex* since the initial and only culture³⁶ in 1903. Some of the conclusions may be briefly stated, without giving the steps by which they were reached. We are doubtless dealing with races, more or less well defined, parallel with the races of the *Puccinia*-group, which latter goes under several names, two being given

³⁵ See Mycol. 1: 243. 1909.

³⁶ See Jour. Myc. 10: 15. 1904.

above under nos. 3 and 4, and which have aecia on *Aster*, *Solidago*, *Euthamia*, *Erigeron*, and close relatives. As the aecia and uredinia of the two groups, one under the genus *Puccinia* and the other under *Uromyces*, are indistinguishable, and as the teliospores of the *Uromyces* agree with the one-celled spores of the *Puccinia*, and also with the two-celled spores in all characters except number of cells and consequent length, the former doubtless are morphological races of the latter. Relationship could be shown better by putting all of these forms under one specific name, and designating the several races by varietal names. But in the present state of taxonomy of the rusts it is more convenient to dispose of them under the two genera: *Puccinia* and *Uromyces*.

The collection on *Carex intumescens* used in the culture is in all respects identical with the type collection of *Uromyces perigynius*, which was also on *C. intumescens*, but in the latter the large green perigynia also bore sori as well as the leaves, which unusual but incidental fact suggested the name. The similarity of this species with the form having aecia on *Solidago* was pointed out in 1903,³⁷ but for precautionary reasons it was thought best at that time to give the latter a separate name, *U. Solidagini-Caricis* Arth. This name now becomes a synonym of the former, or may be used to indicate the biological race with aecia on *Solidago*. The type host of this form has been determined as *C. deflexa*, and not *C. varia* as originally stated.

It is further probable that the form on *Carex scoparia* bearing the name *U. caricina* Peck, which often shows larger spores, should be referred to *U. perigynius*, the last being the oldest name of the three. A collection of this on *C. scoparia* was sent by Professor Fraser, from Pictou, Nova Scotia, and sown on *Lysimachia terrestris*, without infection. Its possible relation to the *Aster-Solidago* group did not come to mind soon enough to put the matter to a test.

22. *UROMYCES JNCI* (Desm.) Tul., on *Juncus balticus* Willd. collected at Kulm, N. Dak., by Dr. J. F. Breñckle was sown April 14 on *Carduus Flodmanii*, *Arnica* sp., *Grindelia squarrosa*, *Ambrosia trifida*, and *Sidalcea oregana*, with infection only upon the first, showing pycnia April 29, and aecia May 4. Another sowing

³⁷ L. c.

May 10 on *Carduus Flodmanii* produced pycnia May 19 and aecia June 5. Another collection from the same place but taken at a different date was sown May 19 on *Carduus Flodmanii*, showing pycnia May 28 and aecia June 5. Three other collections of what appears to be the same rust on the same host, also sent from Kulm, N. Dak., by Dr. Brenckle but collected at different times were sown on *Carduus Flodmanii* (various dates), and one of these was also sown upon eighteen other species of hosts, all with no infection. Still another collection on *J. balticus* from Granby, Colo., sent by Mr. E. Bethel was sown on *Carduus Flodmanii* without infection.

The results here given appear to support the suggestion made in the last report²⁸ that this species is composed of races. The failure to infect *Pulicaria* with American material, as there stated, seems to indicate that American and European forms represent different races. The failure to infect *Carduus* with some of the sowings was also doubtless due to the existence of races. Mr. Bethel has since suggested that his collection from Granby is probably connected with aecia on *Arnica*, and both Mr. Bethel and Dr. Brenckle are of the opinion that there is a form of this species with aecia on *Ambrosia psilostachya*.

23. UROMYCES ASTRAGALI Sacc., on *Aragallus Lamberti* (Pursh) Greene (*Oxytropis Lamberti* Pursh), collected by Mr. E. Bethel at Leyden, Colo., was sown on *Euphorbia Cyparissias*, without result.

A collection bearing uredinia (*Uredo Oxytropi* Peck) on *Aragallus Lamberti* (Pursh) Greene, sent by Mr. Bethel from Boulder, Colo., was sown September 30, on *Astragalus carolinianus*, giving rise to uredinia that were first noticed October 22.

A collection bearing uredinia on *Astragalus sulphureus* Rydb., sent by Mr. E. Bethel, from Boulder, Colo., was sown Sept. 30, on *A. carolinianus*, and on October 22, uredinia were observed, although they may have appeared somewhat earlier.

We have yet made no appreciable headway toward ascertaining the aecial condition of this rust, but the present cultures do show that the *Oxytropis* rust, which has usually been kept distinct, is

²⁸ Mycologia 2: 220. 1910.

identical with the widespread *Astragalus* rust. The species is one that does not readily produce teliospores.

24. *UROMYCES MEDICAGINIS* Pass., on *Medicago sativa* L., was sent by Mr. H. S. Coe, from Ames, Iowa. Urediniospores were sown September 26, on *Medicago sativa* in the greenhouse, and uredinia began to appear October 8. On November 14, uredinia from this culture were sown on *Medicago sativa*, *Trifolium pratense*, *T. medium*, and *T. repens*, giving uredinia on the first December 3, but with no infection of the *Trifolium* plants.

The aecia of *Medicago* rusts are not definitely known. In Europe a form usually assumed to be the same occurs on *Trifolium pratense*, and this was made by Schröter to infect *Euphorbia Cyparissias*. This form has not been detected in America. The present culture seems to show that the *Medicago* rust will not pass over to *Trifolium*, at least by means of urediniospores.

25. *GYMNOSPORANGIUM JUNIPERI-VIRGINIANAE* Schw., on *Juniperus virginiana* L., collected by Dr. F. D. Kern in the vicinity of Lafayette, Ind., was sown April 7, on *Malus Malus*, giving numerous pycnia April 19, but the leaves matured before aecia were formed.³⁹

26. *GYMNOSPORANGIUM CLAVIPES* C. & P., on *Juniperus sibirica* Burgsd., was sent by Dr. J. J. Davis, from Wind Lake, Wis., and sown May 3, on *Amelanchier erecta* and *Crataegus tomentosa*, giving numerous pycnia on both hosts May 16, and equally numerous aecia June 6, for the first host and June 11, for the second.

Aecia from this culture on *Amelanchier erecta* were used to sow June 7, on a small plant of *Juniperus sibirica*, and many finely developed telia appeared in May 1911, the exact date not recorded.⁴⁰

These cultures are interesting in showing that the telia mature in the spring following infection, and do not require an additional year as some other species of *Gymnosporangium* do.

27. *GYMNOSPORANGIUM CLAVARIAEFORME* (Jacq.) DC., on *Juni-*

³⁹ For previous cultures see Jour. Myc. 12: 13. 1906; 13: 200. 1907; 14: 17. 1908; and Mycol. 1: 238. 1909.

⁴⁰ For previous cultures see Jour. Myc. 14: 18. 1908; Mycol. 1: 239. 1909; and 2: 229. 1910.

perus sibirica Burgsd., was sent by Mr. E. Bethel, from Boulder, Colo., and sown April 7, on the young fruit of *Pyrus communis*, which fell off before time for infection to show, and also on the leaves of *Amelanchier erecta* and *Crataegus punctata*. On the *Crataegus* a few pycnia showed April 15, but no aecia developed. On the *Amelanchier* numerous pycnia appeared April 13, and many aecia April 25.⁴¹

28. GYMNASPORANGIUM NIDUS-AVIS Thaxt., on *Juniperus virginiana* L., was sent from Washington, D. C., by Dr. Haven Metcalf, and sown April 16, on leaves of *Cydonia vulgaris*, giving a few pycnia May 2, and also on the young fruit of *Amelanchier vulgaris*, giving a few pycnia first noticed May 24. In both instances no further development occurred.⁴²

29. GYMNASPORANGIUM CORNUTUM (Pers.) Arth., on *Juniperus sibirica* Burgsd., sent from Palmer Lake, Colo., by Mr. E. Bethel, was sown May 18 on *Sorbus americana*, *Aronia arbutifolia*, and *Amelanchier erecta*. Infection was secured only on the *Sorbus*, the pycnia being produced in abundance but tardily, and the date was not taken. The plant did not thrive, and no aecia matured, although on August 16 they were showing.⁴³

30. GYMNASPORANGIUM DAVISII Kern, on *Juniperus sibirica* Burgsd., sent by Dr. J. J. Davis from Wind Lake, Wis., was sown May 3, on *Aronia arbutifolia*, *A. nigra*, *Sorbus americana*, *Amelanchier erecta* and *Crataegus tomentosa*, without results. Another sowing was made May 12, on the two species of *Aronia*, which resulted in a few pycnia on *A. nigra*, showing May 27. Still another sowing on *A. arbutifolia* was made May 18, and gave a few pycnia May 25. In neither instance did aecia develop.⁴⁴ It is probable that the conditions under which the cultures are made in the greenhouse are not favorable for this rust.

31. GYMNASPORANGIUM BETHELI Kern, on *Juniperus scopulorum* Sarg., sent by Mr. E. Bethel from Boulder, Colo., was sown

⁴¹ For previous cultures see Jour. Myc. 14: 18. 1908; and Mycol. 1: 239. 1909.

⁴² For previous cultures see Jour. Myc. 14: 19. 1908; and Mycol. 2: 230. 1910.

⁴³ For previous cultures see Mycol. 1: 240. 1909; and 2: 230. 1910.

⁴⁴ For previous cultures see Mycol. 1: 241. 1909, where an error was made in assuming that this species occurs in Europe; see also Mycol. 2: 216. 1910.

April 16, on *Crataegus cerronis* A. Nels., giving rise to numerous pycnia April 25, and equally numerous aecia May 23.⁴⁵

32. GYMNOSPORANGIUM NELSONI Arth., on *Juniperus virginiana* L., sent by Professor R. A. Harper from Merrimack, Wis., was sown May 2, on *Amelanchier erecta*, *Cydonia vulgaris* and *Malus coronaria*. Infection was only on *Amelanchier*, showing an abundance of pycnia May 11, and equally numerous aecia June 8.⁴⁶ This rust is not often seen east of the Rocky Mountains. The witches' brooms which are produced have a general resemblance to those of *G. nidus-avis*, and it may sometimes be confused with that species.

33. CRONARTIUM QUERCUS (Brond.) Schröt. Aecia (*Peridermium Cerebrum* Peck) on *Pinus virginiana* Mill., were sent by Mr. W. H. Long, from the vicinity of Washington, D. C., and sown April 28, on *Quercus rubra*. The first appearance of uredinia was not recorded, but on May 20, a few uredinia and many telia were observed.⁴⁷

34. MELAMPOROPSIS ABIETINA (A. & S.) Arth., on *Ledum groenlandicum* Oeder, sent by Professor W. P. Fraser from Pictou, Nova Scotia, was sown June 15 on *Picea Mariana* (Mill.) B. S. P., giving numerous pycnia June 23, and aecia about August 12. This connection was first suggested by the field observations of Anton de Bary in the Alps, and by him proven by means of cultures in 1879.⁴⁸ A number of field observations by other mycologists were recorded, tending to fortify the result, but no other cultures were made until 1901, when Klebahn⁴⁹ verified the work of de Bary.

The probable connection of *Ledum* and *Picea rusts* in America was discussed by Professor W. G. Farlow in 1885,⁵⁰ based largely

⁴⁵ For previous cultures see Jour. Myc. 14: 23. 1908; Mycol. 1: 240. 1909; and 2: 230. 1910.

⁴⁶ For previous cultures see Jour. Myc. 13: 203. 1907; 14: 18. 1908; and Mycol. 1: 239. 1909. Studies published by Dr. F. D. Kern (Bull. N. Y. Bot. Gard. 7: 448. Oct. 1911) since this article went to press show that the form used in this culture, and also in the previous ones here referred to, has been erroneously referred to *G. Nelsoni*, it should be called *G. juvenescens* Kern.

⁴⁷ For previous cultures see Jour. Myc. 13: 194. 1907.

⁴⁸ Bot. Zeit. 37: 802. 1879.

⁴⁹ Zeitschr. Pflanzenkr. 12: 17. 1902.

⁵⁰ Proc. Amer. Acad. Sci. 20: 320. 1885.

upon his observations in the White Mountains of New Hampshire, but at that time too little study had been given to the morphological characters of the species inhabiting these two host genera to permit of accurate determination of the various collections, and the conclusions were consequently misleading.

The studies of Dr. F. D. Kern and the writer⁵¹ a few years since showed that the American aecia previously referred to this species really belonged elsewhere, and that no genuine aecia of the species had been collected in America in all probability. After completing the cultures here recorded some of the resulting material was sent to Professor Fraser, and with a knowledge of the appearance and habit of the aecia thus acquired he was able to go into the field and gather excellent specimens.⁵² The reason they have not been taken before by American collectors is doubtless due to their somewhat inconspicuous and evanescent character.

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME:—
The following species have never before been cultivated, in America or elsewhere, so far as the writer knows.

I. PUCCINIA CRANDALLII Pam. & Hume on *Festuca confinis* Vasey collected by Mr. E. Bethel, at Boulder, Colo., on March 19, 1910, was sown April 21, on *Symphoricarpos racemosus*, *Grindelia squarrosa*, *Hydrophyllum capitatum* and *Arnica* sp., with infection only on the first. The pycnia began to appear May 9, and aecia May 26, neither in abundance. This was an unsuspected result, and immediately upon detecting evidence of infection, a second sowing was made upon another plant of *Symphoricarpos racemosus* (May 10), which yielded more pronounced results. Pycnia began to appear in ten days (May 20), and aecia in eleven days more (May 31), both well formed and numerous.

A second lot of this rust, on *Festuca confinis* Vasey, was received from Professor A. O. Garrett, collected in City Creek Canyon, Salt Lake City, Utah, April 10, 1910, and sown on the same date as the previous sowing, May 10. Pycnia began to show May 20, and aecia June 6.

⁵¹ Bull. Torrey Club 33: 429, 430. 1906.

⁵² Cf. Mycologia 3: 69. 1911.

The results of these cultures agree perfectly with *Aecidium abundans* Peck which was first collected in Colorado, on *Symphoricarpos oreophilus*, the exact locality not being stated.

2. PUCCINIA QUADRIPORULA Arth., on *Carex Goodenovii* J. Gay, collected by the writer in the type locality at Isle au Haut, Me., was sown April 18 on *Iris versicolor*, *Boehmeria cylindrica*, and *Rudbeckia laciniata*, with no infection. Again April 26 it was sown on *Myrica cerifera*, *Lysimachia terrestris*, *Macrocalyx Nyctelea*, *Polemonium reptans*, *Apocynum cannabinum*, *Senecio lugens*, and *Aster paniculatus*, with infection only on the last, pycnia being first noticed May 13, and aecia appearing May 17, neither very abundant.

Field observations seemed to connect this rust with aecia on *Iris*, but previous attempts at cultures had given no certain evidence.⁵⁸ The results this year appear beyond question. No other *Carex* rust grew in the vicinity of the spot where the collection was made. The material used shows only the characteristic rust. The aecia obtained, however, are both in gross and minute characters indistinguishable from those of *P. Caricis-Asteris* Arth. These facts make the status of the species enigmatical. The marked diagnostic characters of *P. quadriporula* and *P. Caricis-Asteris* lie in the urediniospore. The former has a somewhat larger urediniospore, more usually globose, and with four, often three, equatorial pores, while the latter has a smaller urediniospore, more ellipsoid or elongated, and with two superequatorial pores. The pore characters are markedly dissimilar, and without intergradations.

Another collection with the spore characters of *P. quadriporula*, made by Professor W. P. Fraser, at Pictou, Nova Scotia, on *Carex brunnescens* (Pers.) Poir., was sown April 11, and again May 6, on *Iris versicolor*, *Urtica gracilis*, and *Ribes floridum*, with no infection.

3. PUCCINIA LITHOSPERMI E. & K., on *Evolvulus pilosus* Nutt., collected at Amarillo, Texas, by W. H. Long, was sown April 15, on the same species of host, and produced a scanty infection. Pycnia were not observed until May 2; aecia began to appear

⁵⁸ See Mycol. 1: 230. 1909.

May 6. The result shows that the species is eugyrious and autoecious.

4. *UROMYCES ACUMINATUS* Arth., on *Spartina Michauxiana* A. S. Hitch. (usually listed as *S. cynosuroides*), collected by Dr. J. F. Brenckle at Kulm, N. D., was sown April 28 on *Steironema ciliatum* and *Polemonium reptans*, with abundant infection on the latter only, showing pycnia May 9, and aecia May 14.

A similar collection made by Mr. E. Bethel in the foothills of Colorado was sown May 12, on *Steironema ciliatum*, *Hydrophyllum capitatum*, *Phlox divaricata*, and *Polemonium reptans*, with very abundant infection only on the last, showing pycnia May 20, and aecia May 26. Another collection made at Fair Oaks, Ind., by Messrs. F. D. Kern and T. Billings, was sown one week later on the same hosts, but gave no infection, doubtless due to the lateness of the season.

These results bear out the field observations of Professor Guy West Wilson, as stated in the report for 1909.⁵⁴ The aecial stage is known in literature as *Aecidium Polemonii* Peck, and occurs on species of *Phlox* as well as on *Polemonium*.

5. *COLEOSPORIUM VERNONIAE* B. & C. Freshly gathered leaves of *Pinus taeda* L., bearing *Peridermium carneum* Bosc, gathered by Mr. O. F. Burger at Gainesville, Fla., May 18, 1910, were suspended on May 21, over potted plants of *Veronia crinita*, *Elephantopus carolinianus* and *Lacinaria scariosa*. Contrary to expectation uredinia began to show in abundance June 6 on the *Veronia* only. Numerous telia began to mature by August 16.

6. *MELAMPSORA ALBERTENSIS* Arth., on *Populus tremuloides* Michx., was sent by Mr. E. Bethel on three different dates, collected at different places in the foothills of Colorado, and all showing telia in resting condition. The first collection was sown April 20, on *Larix laricina* and *Pseudotsuga mucronata*, giving infection on the latter only, showing an abundance of pycnia May 2, and an equal abundance of aecia May 9. The second collection (from Plainview, Colo.), was also sown April 20, on the same two hosts, but without results. Later on, May 18, duplicate sowings were made. This time the *Larix* remained free, and the *Pseudotsuga* after a long interval was found to have been infected,

⁵⁴ See Mycol. 2: 222. 1910.

the pycnia and aecia being first noticed June 6. The third collection was sown May 19, on the same hosts, with infection only on *Pseudotsuga*, numerous pycnia showing May 31, and equally numerous aecia June 9.

The aecia on *Pseudotsuga* were first brought to my attention by Professor E. W. D. Holway, who sent a collection from Beaver River valley, B. C., in 1907. This collection was described by the writer, and named *Caeoma occidentale*.⁵⁵ The following year Mr. E. Bethel sent collections from Eldorado Springs, Colo., and in 1909 he sent other collections from Eldorado Springs, and also from Tolland and Golden. From observations made at these places Mr. Bethel suggested that the connection between the *Caeoma* on *Pseudotsuga* and the *Melampsora* on *Populus* was unquestionable. The aecial stage is doubtless rather common throughout the range, but it is so inconspicuous and evanescent that it has been very little collected.

SUMMARY

The following is a complete list of the successful cultures made during the year 1910. It is divided into two series, species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. Species Previously Reported

1. *Puccinia* ~~*Grossulariae* (Schum.) Lagerh.~~ ^{*albiperidiae* Arth.}—Teliospores from *Carex tenuis* Rudge and from *C. pallescens* L., sown on *Ribes Cynosbati* L.

2. *Puccinia Peckii* (DeT.) Kellerm.—Teliospores from *Carex lanuginosa* Michx., sown on *Onagra biennis* (L.) Scop., and from *C. trichocarpa* Muhl., sown on *O. biennis* (L.) Scop. and *Meriopsis serrulata* (Nutt.) Walp.

3. *Puccinia Caricis-Solidaginis* Arth.—Teliospores from *Carex scoparia* Schk., sown on *Euthamia graminifolia* (L.) Nutt.

4. *Puccinia Caricis-Asteris* Arth.—Teliospores from *Carex festiva* Dewey, sown on *Aster adscendens* Lindl.

⁵⁵ Bull. Torrey Club 34: 591. 1907.

5. *Puccinia Opizii* Bubák.—Teliospores from *Carex siccata* Dewey, sown on *Lactuca canadensis* L. and *L. sativa* L.

6. *Puccinia universalis* Arth.—Teliospores from *Carex stenophylla* Wahl., sown on *Artemisia dracunculoides* Pursh.

7. *Puccinia Caricis* (Schum.) Schröt.—Teliospores from *Carex aristata* R. Br. and *C. stricta* Lam., sown on *Urtica gracilis* Ait.

8. *Puccinia angustata* Peck.—Teliospores from *Scirpus atrovirens* Muhl., sown on *Lycopus americanus* Muhl.

9. *Puccinia Andropogonis* Schw.—Teliospores from *Andropogon virginicus* L., sown on *Pentstemon hirsutus* (L.) Willd. and from *A. scoparius* Michx., sown on *Pentstemon alpinus* Torr.

10. *Puccinia pustulata* (Curt.) Arth.—Teliospores from *Andropogon furcatus* Muhl., sown on *Comandra umbellata* (L.) Nutt.

11. *Puccinia amphigena* Diet.—Teliospores from *Calamovilfa longifolia* (Hook.) Hack., sown on *Smilax hispida* Muhl.

12. *Puccinia Muhlenbergiae* Arth. & Holw.—Teliospores from *Muhlenbergia racemosa* (Michx.) B. S. P., sown on *Callirrhoe involucrata* (T. & G.) A. Gray.

13. *Puccinia Rhamni* (Pers.) Wettst.—Teliospores from *Calamagrostis canadensis* (Michx.) Beauv., sown on *Rhamnus alnifolia* L'Her.

14. *Puccinia poculiformis* (Jacq.) Wettst.—Teliospores from *Agropyron tenerum* Vasey, *Sitanion longifolium* J. G. Sm., and *Agrostis alba* L., sown on *Berberis vulgaris* L.

15. *Puccinia subnitens* Diet.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Chenopodium album* L.

16. *Puccinia Jamesiana* (Peck) Arth.—Teliospores from *Atheropogon curtispendus* (Michx.) Fourn., sown on *Asclepias syriaca* L.

17. *Puccinia Seymouriana* Arth.—Teliospores from *Spartina Michauxiana* A. S. Hitchc., sown on *Cephalanthus occidentalis* L.

18. *Puccinia Stipae* Arth.—Teliospores from *Stipa spartea* Trin., sown on *Aster ericoides* L., *A. Novae-Angliae* L., *A. multiflorus* Ait., and *Solidago canadensis* L., from *Stipa* sp., sown on *Aster Novae-Angliae* L., and *Grindelia squarrosa* (Pursh) Dunal, and from *Koeleria cristata* (L.) Pers., sown on *Senecio lugens* A. Gray.

19. *Puccinia argentata* (Schultz) Wint.—Aeciospores from *Adoxa Moschatellina* L., sown on *Impatiens aurea* Muhl.

20. *Puccinia Absinthii* DC.—Teliospores from *Artemisia* sp., sown on *A. dracunculoides* Pursh.

21. *Uromyces perigynius* Halst.—Teliospores from *Carex intumescens* Rudge, sown on *Aster paniculatus* Lam., and from *C. deflexa* Hornem., sown on *Solidago rugosa* Mill., and *Aster ericoides* L.

22. *Uromyces Junci* (Desm.) Tul.—Teliospores from *Juncus Balticus* Willd., sown on *Carduus Flodmanii* Rydb.

23. *Uromyces Astragali* Sacc.—Urediniospores from *Aragalus Lamberti* (Pursh) Greene, and from *Astragalus sulphureus* Rydb., sown on *Astragalus carolinianus* L.

24. *Uromyces Medicaginis* Pass.—Urediniospores from *Medicago sativa* L., sown on same host.

25. *Gymnosporangium Juniperi-virginianae* Schw.—Teliospores from *Juniperus virginiana* L., sown on *Malus Malus* (L.) Britt.

26. *Gymnosporangium clavipes* C. & P.—Teliospores from *Juniperus sibirica* Burgsd., sown on *Amelanchier erecta* Blanch., and *Crataegus tomentosa* L., and aeciospores from *Amelanchier erecta* Blanch., sown on *Juniperus sibirica* Burgsd.

27. *Gymnosporangium clavariaeforme* (Jacq.) DC.—Teliospores from *Juniperus sibirica* Burgsd., sown on *Amelanchier erecta* Blanch., and *Crataegus punctata* Jacq.

28. *Gymnosporangium nidus-avis* Thaxt.—Teliospores from *Juniperus virginiana* L., sown on *Cydonia vulgaris* Pers., and *Amelanchier vulgaris* Moench.

29. *Gymnosporangium cornutum* (Pers.) Arth.—Teliospores from *Juniperus sibirica* Burgsd., sown on *Sorbus americana* Marsh.

30. *Gymnosporangium Davisii* Kern.—Teliospores from *Juniperus sibirica* Burgsd., sown on *Aronia arbutifolia* (L.) Medic., and *A. nigra* (Willd.) Britt.

31. *Gymnosporangium Betheli* Kern.—Teliospores from *Juniperus scopulorum* Sarg., sown on *Crataegus cerronis* A. Nels.

32. *Gymnosporangium Nelsoni* Arth.—Teliospores from *Juniperus virginiana* L., sown on *Amelanchier erecta* Blanch.

33. *Cronartium Quercus* (Brond.) Schröt.—Aeciospores from *Pinus virginiana* Mill., sown on *Quercus rubra* L.

34. *Melampsoropsis abietina* (A. & S.) Arth.—Teliospores from *Ledum groenlandicum* Oeder, sown on *Picea Mariana* (Mill.) B. S. P.

B. Species Reported Now for the First Time

1. *Puccinia Crandallii* Pam. & Hume.—Teliospores from *Festuca confinis* Vasey, sown on *Symphoricarpos racemosus* Michx.

2. *Puccinia quadriporula* Arth.—Teliospores from *Carex Goodenovii* J. Gay, sown on *Aster paniculatus* Lam.


3. *Puccinia Lithospermi* E. & K.—Teliospores from *Evolvulus pilosus* Nutt., sown on same species of host.

4. *Uromyces acuminatus* Arth.—Teliospores from *Spartina Michauxiana* A. S. Hitch., sown on *Polemonium reptans* L.

5. *Coleosporium Vernoniae* B. & C.—Aeciospores from *Pinus taeda* L., sown on *Vernonia crinita* Raf.

6. *Melampsora albertensis* Arth.—Teliospores from *Populus tremuloides* Michx., sown on *Pseudotsuga mucronata* (Raf.) Sudw.

PURDUE UNIVERSITY
LAFAYETTE, INDIANA.



203

CULTURES OF UREDINEAE IN 1911¹

J. C. ARTHUR

The present article is the twelfth of a series of reports² by the writer upon the culture of plant rusts, extending through thirteen consecutive years. The preceding report for the year 1910, published in MYCOLOGIA for January, 1912, contained an unfortunate slip of the pen in the heading of a paragraph at the middle of page 13, where "*Grossulariae* (Schum.) Lagerh." should read *albiperidia* Arth. With this change, the discussion which follows reads correctly. The same error occurs on page 30, twelfth line from the bottom.

The very large majority of the sowings for each year are made during the months of April and May. Hot weather is inimical to the work, except for a few species. Throughout the year 1911 unusual high temperature prevailed; after the first week in May the thermometer ranged above 80° F. during the middle of the day for the remainder of the cultural season. Owing to an unfortunate delay in securing an assistant to prosecute the work, the first sowings were not made until April 19, and the work was scarcely well under way before the hot days began, making it nearly impossible to obtain germination of the spores, or in case of germination to obtain infection of the hosts.

The work of the season was conducted by Mr. Earl A. Trager, a junior high school student of South Bend, Ind., who was recommended by Miss Clara Cunningham, teacher of the natural sciences in the South Bend High School. Mr. Trager conducted the work admirably. He furthermore showed capacity for mastering the technique and for handling the problems involved which compared favorably with that of his more mature and

¹ Presented before the Botanical Society of America at the Washington meeting, December 27, 1911.

² See Bot. Gaz. 29: 268-276; 35: 10-23; Jour. Myc. 8: 51-56; 10: 8-21; 11: 50-67; 12: 11-27; 13: 189-205; 14: 7-26; Mycol. 1: 225-256; 2: 213-240; and 4: 7-33. 1912.

experienced predecessors. The paucity of results is wholly ascribable to the lateness in beginning the work and to the unseasonable weather.

Only one direct excursion was made to supply material for this year's cultures. Early in March the writer, accompanied by Mr. Ray Stretch, a graduate of the Lafayette High School, who rendered efficient service and proved a keen observer, visited the region bordering the Mississippi Sound from Ocean Springs to Pass Christian, Miss., well known from the thorough field work and numerous publications of Professor S. M. Tracy, whose home is at Biloxi, between the two places mentioned. The special object in view was to secure material of *Gymnosporangium bermudianum*, the only autoecious species known belonging to this genus, both for culture and for morphological work. Hope was also entertained that fresh material of species of *Peridermium*, with field observations to assist in culture work, might be secured. The region was found to possess the fewest rusts, both in number of species and in their abundance, of any section yet visited for observational purposes.

Upon request a visit to Newfield, N. J., was made by Dr. Frank D. Kern, studying during the collegiate year at Columbia University, New York, accompanied by Mr. B. O. Dodge, a graduate student of the same institution. The object was to secure material of several species of *Gymnosporangium* for cultures. Newfield was chosen, as it was for many years the home of Mr. J. B. Ellis, and his collections show a number of hitherto poorly understood species, whose aecia are still unknown. Probably the most interesting of these is a small foliicolous form on the white cedar, recently described as *G. fraternum* Kern. A note found in the Ellis collection at the New York Botanical Garden gave evidence that it was common in a certain swamp twenty-five years ago. The particular spot was found, and the fungus secured. One day was spent in this vicinity, and seven species of *Gymnosporangium* were collected. Among these were *G. Ellisii*, whose aecial stage is suspected to be the rare *Roestelia hyalina*, and the recently named *G. effusum*. The last is a large form on branches, very destructive to the red cedar, and yet never issued in exsiccati. It is the only one collected on this trip from which infection was obtained.

An extended excursion, but too late for the season's cultures, was made by the writer and Dr. Frank D. Kern during August and September to the foothills of Colorado, between Boulder and Pueblo, and to some extent in the adjacent mountains. This is the richest rust flora, both in species and frequency of occurrence, yet encountered. The dryness of the atmosphere, which promotes the growth of the rust on the individual hosts, while checking the spread from plant to plant, makes the region an exceptionally fine one for field study of relationships between the alternate stages of heteroecious species. Our work was enormously promoted by assistance from Mr. E. Bethel, of Denver, whose exact, enthusiastic, and prolonged observations over the whole region visited cannot be too highly commended. The freedom with which he turned over for our use his most important discoveries and conclusions must unfortunately be inadequately repaid. It was due to his assistance that this excursion proved the richest in results by far of any yet undertaken, results that are only slightly reflected in this report, but have paved the way for important cultures in 1912.

On the eleventh of November, after a day of summer heat, a hurricane did great injury to the conservatory and greenhouse of the Experiment Station, in which many plants for the next season's experiments were growing. At about nine o'clock in the evening a large part of the glass in these houses, and in the offices and laboratories of the department of botany, was broken in by the violence of the wind. The heavy rain which was falling soon turned to snow, and the temperature dropped to many degrees below freezing. When the damage was detected at about eight o'clock the next morning, the plants were largely beyond recovery.

Hearty thanks are due to the following persons who contributed material for study: Mr. E. Bethel, Denver, Colo., heading the list with 87 collections; Messrs. E. W. Olive, Brookings, S. D., J. M. Bates, Red Cloud, Neb., J. Dearness, London, Ont., and W. P. Fraser, Pictou, Nova Scotia, each sent between 10 and 30 collections, while much smaller numbers were sent by Messrs. E. Bartholomew, Stockton, Kans., C. F. Baker, Claremont, Calif., J. F. Brenckle, Kulm, N. D., J. C. Blumer, Tucson,

Ariz., H. S. Coe, Ames, Iowa, H. M. Jennison, Crawfordsville, Ind., S. Kusano, Tokio, Japan, E. F. Smith, Hannaford, N. D., E. M. Wilcox, Lincoln, Neb., J. J. Wolf, Durham, N. C., and F. Vasku, Oberlin, Ohio. Seeds and living plants were also sent by a number of botanists to provide host plants of native species required in the work. To all these and to others who aided in the work of the year grateful acknowledgment is due and is hereby extended. The investigations were carried out under the auspices of the Indiana Experiment Station, and financed from the Adams fund.

During the present season 193 collections of material with resting spores and 37 collections with active spores were employed, from which 691 drop cultures were made to test the germinating condition of the spores. Out of the 193 collections with resting spores 156 failed to germinate, leaving 37 collections available for experimental tests. Altogether about 235 sowings were made and 32 infections obtained. All but three sowings were made on plants growing in pots in the greenhouse. The most important conclusions derived from a study of the results are given in the following paragraphs.

NEGATIVE RESULTS.—It has been customary in these reports to record sowings with germinating spores when no infections were obtained, to serve as a guide in selecting hosts for future attempts. This year only a few instances will be given, as all sowings made after the heated term began, May 8, are deemed too uncertain to be of value.

1. PUCCINIA TOSTA Arth., on *Sporobolus asperifolius* (Nees & Meyen) Thurb., collected at Denver Colo., by Mr. E. Bethel, was sown April 19, on *Atriplex confertifolia* and *Malvastrum coccineum*, with no infection. The day following a collection with same data from Delta, Colo., was sown on *Aesculus glabra* and *Xanthoxylum americanum*, and again, May 10, on ten other hosts, with no infection.

The resemblance of this rust and of its host to that of *Puccinia subnitens* Diet., on *Distichlis spicata*, is very marked, as seen in the field. The two species grow under the same conditions, often intermixed, and might be expected to have the same aecial

hosts, a possibility barely touched by the present attempt at culture.

2. PUCCINIA SCHEDONNARDI K. & S., on *Schedonnardus paniculatus* (Nutt.) Trel., collected at Stockton, Kans., by Mr. E. Bartholomew, was sown April 19, on *Aesculus glabra*, *Xanthoxylum americanum*, *Hydrophyllum capitatum*, *Sidalcea oregana*, *Callirhoe involucrata*, and *Onagra pallida*, with no infection. Similar material in former years was sown on twenty-eight other species of hosts.³

3. GYMNOCONIA INTERSTITIALIS (Schl.) Lagerh. No attempts have been made, so far as the writer knows, to propagate any species of rust by means of its pycniospores, except one made by Dr. Frank D. Kern in 1910, and not heretofore reported. He sowed pycniospores from *Amelanchier erecta*, belonging to *Gymnosporangium clavariaeforme*, upon young leaves of *A. erecta* by pricking and otherwise mutilating the epidermis, but without results. It is well known that the growth of such spores soon ceases in a liquid culture the same as with any other rust spores, only sooner, as they are much smaller and contain less nutriment. But it has not been shown that they will not form a mycelium when suitably placed upon or within the tissues of a host plant. The prominent and abundant pycnia of the blackberry rust, which mature in advance of the aecia, seem especially favorable for such a trial. Pycniospores from *Rubus allegheniensis* taken when perfectly fresh were sown May 9 on young leaves of two different plants of the same species, which were well established in pots. The spores were not only placed on the surface of the partly grown leaves, but were also pricked into the tissues in places with a needle. This was done to imitate the probable dispersion of such spores by insects, for which the nectar secreted by the sori may have an attraction. No infection was obtained. Neither in this attempted culture nor in that by Dr. Kern was any examination made to ascertain what growth the pycniospores may have made.

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK.—The facts derived by growing the following species of rusts supple-

³ See Bot. Gaz. 35: 11. 1903; Jour. Myc. 13: 193. 1907; 14: 11. 1908; Mycol. 1: 231. 1909; and 4: 10. 1912.

ment those obtained from previous cultures in this series or from cultures recorded by other American or European investigators.

1. PUCCINIA PECKII (DeT.) Kellerm., on *Carex lanuginosa* Michx., collected at Red Cloud, Neb., by Rev. J. M. Bates, was sown May 20 on *Onagra biennis* and *Merioliix serrulata*, with no infection on the latter, but with abundant pycnia on the former May 29, and aecia June 1.⁴ Similar cultures on *Onagra biennis* were made from undetermined species of *Carex* collected by Mr. E. Bethel, at Denver, Colo., and by Dr. J. F. Brenckle, at Kulm. N. D.

2. PUCCINIA ANGUSTATA Peck, on *Scirpus cyperinus* (L.) Kunth, collected at London, Ont., by Mr. J. Dearness, was sown May 25 on *Lycopus americanus*, giving rise to pycnia first seen June 3, and aecia June 5.⁵

3. PUCCINIA PHRAGMITIS (Schum.) Körn., on *Phragmites communis* Trin., collected at Cowles, Neb., by Rev. J. M. Bates, was sown May 9 on *Rumex crispus*, giving rise to abundant pycnia and aecia first observed May 23.⁶

4. PUCCINIA CINEREA Arth., on *Puccinellia airoides* (Nutt.) Wats. & Coult., collected at Lewis Station, Colo., by Mr. E. Bethel, was sown May 10 on *Oxygraphis Cymbalaria*, giving rise to pycnia May 16, and an abundance of aecia May 20.⁷

5. PUCCINIA SUBNITENS Diet., on *Distichlis spicata* (L.) Greene, collected at Lewis Station, Colo., by Mr. E. Bethel, was sown May 2, on *Sarcobatus vermiculatus*, *Monolepis Nuttalliana*, *Cleome spinosa*, *Atriplex hastata*, and *Chenopodium album*, with no infection on the first two, but with numerous pycnia on the others, appearing May 11, 12 and 16, respectively, followed by aecia on the *Cleome* and *Atriplex*, on both appearing May 15.⁸

⁴ For previous cultures see Bot. Gaz. 35: 13. 1903; Jour. Myc. 8: 52. 1902; 11: 58. 1905; 12: 15. 1906; 13: 195. 1907; Mycol. 1: 233. 1909; 2: 222. 1910; and 4: 15. 1912.

⁵ For previous cultures see Bot. Gaz. 29: 273. 1900; Jour. Myc. 8: 53. 1902; 11: 58. 1905; 13: 196. 1907; 14: 14. 1908; Mycol. 1: 234. 1909; and 4: 17. 1912.

⁶ For previous cultures see Bot. Gaz. 29: 269. 1900; Jour. Myc. 9: 220. 1903; 14: 15. 1908; and Mycol. 2: 225. 1910.

⁷ For a previous similar culture see Mycol. 1: 246. 1909.

⁸ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; 14: 15. 1908; Mycol. 1: 234. 1909; 2: 225. 1910; and 4: 18. 1912.

6. *UROMYCES PECKIANUS* Farl., on *Distichlis spicata* (L.) Greene, obtained in the field March 29, 1911, at Pictou, Nova Scotia, by Professor W. P. Fraser, was sown April 19 on *Tissa canadensis* and *Lepidium virginicum*, with no infection. Another collection with same data but obtained in the field April 13, 1911, was sown on *Bursa Bursa-pastoris*, *Lepidium virginicum*, *Corydalis montanum*, *Tissa canadensis*, *Cleome spinosa*, and *Atriplex hastata*, with no infection except on the last, which showed numerous pycnia May 16, and an abundance of aecia May 22. Still another collection with same data but obtained in the field April 27, 1911, was sown May 5 on *Chenopodium album* and on the same six hosts as the last, with infection only on *Atriplex*, showing pycnia May 17, and aecia May 29, both in abundance.

A former attempt at cultures with this species proved futile,⁹ but Professor Fraser¹⁰ met with better success in cultures made by himself during the same season of 1910. He was able to abundantly infect both *Atriplex hastata* and *Chenopodium album* from teliospores on *Distichlis spicata*. Material from his cultures was most generously sent to the writer. Since then he has sent material of his more extensive and important cultures of 1911, which need not be specifically mentioned here, although they strengthen the conclusions about to be stated.

A careful morphological study of herbarium material, both as collected in the field and as grown from cultures, shows no appreciable difference in the gross or microscopical characters between the several stages of *Puccinia subnitens* Diet. and *Uromyces Peckianus* Farl., except in one particular—the unilocular or bilocular condition of the teliospore. When the teliospore is two-celled, as in the *Puccinia*, it is correspondingly longer than, but essentially the same otherwise as the one-celled teliospore, found in the *Uromyces*. The aecia in their peridial cells and aeciospores, and the uredinia in their appearance and in their urediniospores, when taken by themselves are indistinguishable. The only character with which to separate the so-called two species is the presence or absence of a septum in the teliospore.

Both the *Puccinia* and the *Uromyces* show marked racial tendencies in the selection of aecial hosts, seemingly correlated with

⁹ See Mycol. 4: 12. 1912.

¹⁰ Mycol. 3: 72-74. 1911.

geographical position, but more information is needed regarding the races of the *Uromyces* before a full comparison can be instituted. Whether the aecia of the *Uromyces* ever occur upon any family other than the *Chenopodiaceae*, as do those of the *Puccinia*, yet remains uncertain, but it is confidently expected that such will be the case. In any event there is every reason, except that of nomenclatorial expediency, to consider *Puccinia subnitens* and *Uromyces Peckianus* telial races of one and the same species which in turn may be separable into geographical races in accordance with their selection of aecial hosts.

7. *UROMYCES MEDICAGINIS* Pass. The urediniospores from plants of *Medicago sativa* L., carried over the winter in the greenhouse, were sown March 8 on *Medicago sativa*, *Trifolium pratense*, *T. medium*, and *T. repens*, producing infection only on the first, uredinia showing March 22. A similar set of sowings was made April 28 on other plants of the same four hosts, with similar result, only the *Medicago* being infected, showing uredinia May 12. The work of 1910 is thus confirmed.¹¹

8. *GYMNOSPORANGIUM NIDUS-AVIS* Thax., on *Juniperus virginiana* L., was sent by Dr. Frank D. Kern from Newfield, N. J., and sown May 4 on leaves of *Cydonia vulgaris*, *Malus coronaria*, *Amelanchier erecta*, and also on the fruit of the last. The only infection was on the fruit of the *Amelanchier*, showing numerous pycnia May 12, and aecia in great abundance May 24. Another collection on the same host sent by Professor E. Mead Wilcox from Lincoln, Neb., was sown May 11 on leaves of the same three hosts, with infection only on the *Malus*, giving pycnia June 2, but the leaves dying before aecia formed.¹²

9. *GYMNOSPORANGIUM CLAVARIAEFORME* (Jacq.) DC., on *Juniperus sibirica* Burgsd., was sent by Mr. E. Bethel from Lake Eldora, Colo., and sown May 25 in the open orchard on fruits of pears and apples, and in the greenhouse on leaves of *Cydonia vulgaris* and fruits of *Amelanchier erecta*, with no results except on fruits of *Amelanchier*, giving abundant pycnia May 31, and very abundant aecia June 15.¹³

¹¹ See Mycol. 4: 24. 1912.

¹² For previous cultures see Jour. Myc. 2: 230. 1910; and 4: 25. 1912.

¹³ For previous cultures see Jour. Myc. 14: 18. 1908; Mycol. 1: 239. 1909; and 4: 24. 1912.

10. *GYMNOSPORANGIUM INCONSPICUUM* Kern, on *Juniperus utahensis* (Engelm.) Lemmon, sent by Mr. E. Bethel from Paonia, Colo., was sown April 7 on leaves of *Amelanchier erecta* and of *A. vulgaris*, with infection only on the latter, showing pycnia April 24, but not maturing aecia.¹⁴

11. *GYMNOSPORANGIUM LIBOCEDRI* (P. Henn.) Kern, on *Libocedrus decurrens* Torr., sent by an unknown correspondent, was sown April 17 on *Amelanchier vulgaris*, *Crataegus tomentosa*, *C. cerronis*, and *Sorbus aucuparia*, with no infection on the last, but pycnia showing on the other hosts April 25, 26 and 28 respectively, and abundant aecia on the *Amelanchier*, showing May 16.¹⁵

12. *GYMNOSPORANGIUM JUNIPERINUM* (L.) Mart., on *Juniperus sibirica* Burgsd., sent by Mr. E. Bethel from Palmer Lake, Colo., was sown April 26 on *Sorbus aucuparia*, without producing infection. It was again sown May 5 on *S. americana*, and produced pycnia May 20 in abundance, but did not develop aecia.

The species has not been cultivated before from American material. The first cultures were made in Europe by Robert Hartig¹⁶ about 1882 at Munich, and the species named *G. tremeloides*, from its conspicuous telia. The Linnaean name appears to have been transferred by Oersted in 1866 to a much less conspicuous form, as pointed out by Kern,¹⁷ but it seems best now to follow the original usage. The galls used in the present culture were on small branches and about one centimeter across.

13. *COLEOSPORIUM VERNONIAE* B. & C. A collection of *Peridermium carneum* Bosc, on *Pinus taeda* L., collected by Mr. Ray Stretch and the writer at Mississippi City, Miss., was sown March 6 on *Laciniaria scariosa* and *Vernonia gigantea*, with infection only on the latter, uredinia showing March 22. Three other collections on *Pinus taeda* L., made by the same persons at Biloxi, Miss., were each sown March 8 on *Laciniaria scariosa* and *L. punctata*, with no infection. The results confirm the work of 1910.¹⁸

¹⁴ For previous cultures on fruit of *Amelanchier* see Jour. Myc. 14: 24. 1908.

¹⁵ For previous cultures see Mycol. 1: 252. 1909.

¹⁶ Hartig. Lehrb. Baum-Kr. 133. 1882.

¹⁷ Science 27: 930. 1908; Bull. Torrey Club 35: 499. 1908; and Bull. N. Y. Bot. Gard. 7: 458. 1911.

¹⁸ See Mycol. 4: 29. 1912.

14. MELAMPSORA ALBERTENSIS Arth., on *Populus tremuloides* Michx., from Palmer Lake, Colo., sent by Mr. E. Bethel, was sown April 20 on *Larix laricina*, *Ribes Cynosbati* and *Pseudotsuga mucronata*, with infection only on the last, showing pycnia in abundance May 4, and aecia May 9.¹⁹ On our excursion to Colorado in September Dr. Kern and the writer in company with Mr. Bethel observed great areas of the mountain sides covered with the yellowed foliage of *P. tremuloides*, almost every leaf of which showed uredinia and telia of this rust. It seems remarkable there should be so few collections of it in herbaria, and also of its aecia on *Pseudotsuga*.

15. MELAMPSORELLA ELATINA (A. & S.) Arth. Part of a large witches' broom of *Aecidium elatinum* A. & S., on *Abies lasiocarpa* Nutt., was sent by Mr. E. Bethel from Lake Eldora, Colo., 9,000 feet altitude, and sown August 8 on *Cerastium oreophilum*, giving an exceedingly abundant infection of uredinia, first recorded on September 7. This is the first culture of the species with American material. In Europe cultures with aecio-spores have been made by von Tubeuf,²⁰ Klebahn,²¹ and Ed. Fischer,²² and indications of races have been found. This is an interesting species of rust from the unusual fact of both phases having perennial mycelium.

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME.—The following species have never before been cultivated, in America or elsewhere, so far as the writer knows. It is much to be regretted that some of the species could not be brought to full development, but although the results are in part imperfect, they represent most important additions to previous knowledge.

I. PUCCINIA LYGODESMIAE Ellis & Ev., on wintered-over stems of *Lygodesmia juncea* (Pursh) D. Don, collected April 6, 1911, by Mr. E. Bartholomew, at Stockton, Kans., was sown on plants

¹⁹ For previous cultures see Mycol. 4: 29. 1912.

²⁰ Deuts. Bot. Ges. 19: 433. 1901; Arb. Biol. Abth. Land.-Forstw. Kais. Gesundh. 2: 368.

²¹ Jahr. Wiss. Bot. 35: 699. 1901; Zeits. Pfl.-Kr. 12: 139. 1902; and Jahr. Hamb. Wiss. Anst. 20³: 31. 1902.

²² Ber. Deut. Bot. Ges. 19: 397. 1901; Zeits. Pfl.-Kr. 11: 321. 1901; and 12: 193. 1902.

of the same species April 19, and characteristic telia were observed May 3, without being preceded by pycnia or other spore-forms. The species clearly produces but the one form of spore in its life cycle. The aecia often found on this host are undoubtedly heteroecious.

2. *AECIDIUM MONOICUM* Peck, on *Arabis* sp. Living plants of some smooth leaved species of *Arabis* bearing aecia were sent by Mr. E. Bethel from Boulder, Colo., 5,000 feet altitude, and arranged May 9 over plants of *Koeleria cristata*, *Stipa viridula*, and *Trisetum subspicatum*, followed by infection only on the last, uredinia and telia being first observed June 1. Similar plants bearing aecia were also sent by Mr. Bethel from Lake Eldora, Colo., 9,000 feet altitude, and placed over plants of *Koeleria cristata* and *Trisetum majus*, followed by infection on the latter only, uredinia and telia being first observed July 24.

The results of the cultures appear unequivocal. The aecia used belong to a form on *Arabis*, and probably also on related genera, very common throughout the Rocky mountain region, which infests the whole plant and usually prevents it from flowering, consequently the determination of hosts is usually difficult and often impossible. Whether all collections labelled *Aecidium monoicum* Peck belong here may be left to future examination, but most of them doubtless do so, although there may be races going to different species of grasses. A bright yellow form on *Cheiranthus Menziesii* from Nevada was named *Aecidium auriellum* by Mr. Peck, and may be identical with the *Arabis* forms, as the difference in color appears to be incidental.

The telial phase has passed under the name *Puccinia Triseti* Erikss., a name which belongs to a species with covered telia, that has not with certainty been found in America. The rust with similar naked telia on *Koeleria* and *Stipa*, *Puccinia Stipae* Arth., is almost identical in morphological characters, but it forms the curious *Aecidium sclerothecioides* E. & E. on composites. There is, moreover, an adaptive distinction—the *Trisetum* form is capable of germination as soon as the teliospores are mature, while in *P. Stipae* the teliospores require a period of rest, and first show their viable character the following spring. Teliospores from the first of the above recorded cultures were tested

in drop culture, and gave abundant and vigorous germination after twelve hours. Sowings were at once made June 29 on two plants of *Arabis* in the rosette stage, grown from seed sent by Mr. Bethel from Colorado. One plant flowered later and showed no evidence of infection. The other plant gradually developed numerous lateral buds, forming a compact mass of small rosettes. This rather abnormal development seems to indicate a probable infection, but the proof must await the elongation of the stems at flowering time next spring.

The credit for detecting the probable connection of these aecial and telial forms is to be shared by Mr. A. O. Garrett and Mr. E. Bethel. On packet 75 of the Fungi Utahensis, *Aecidium monoicum* on *Arabis Drummondii*, Mr. Garrett adds the note, "apparently connected with a rust on *Trisetum subspicatum*." This collection was made July 22, 1905, and in a letter dated April 30, 1906, he writes: "On July 22 I made a collection of aecidia on *Arabis Drummondii*. The plants were in an open place on the mountain side between spruce timber on either side. On August 21 I returned to the spot to hunt for the alternate form of the *A. monoicum*. Upon reaching the locality I found a plant of *Trisetum subspicatum*, and on it I found teleutospores [distributed in Fungi Utahensis 194]. Immediately next to it I found a dried up plant of *A. Drummondii* with abundant aecidia. Looking further, I found that wherever I found the III, I found I, although in a few cases I found I without running across III." It should be borne in mind that these observations were made in the arid region of the Rocky mountains, where juxtaposition is more significant than in more humid regions. Mr. Bethel made similar observations at various times in Colorado, and is, moreover, convinced from his field studies that the same species of rust occurs on *Koeleria* and *Stipa*. This may be true, and collections in the herbarium seem to justify the opinion, at least for *Koeleria*, but cultures are yet wanting, material for which should be gathered in late summer or autumn, and not in spring. In a letter dated April 9, 1911, Mr. Bethel makes the significant statement: "The *Koeleria* and *Trisetum* rusts have a strange way of disappearing. It is almost impossible to find them in the spring. I brought home plants of both *Koeleria* and

Trisetum last fall which were very badly rusted, and planted in the garden. However, this spring I can see the telia on only one leaf, and that is the *Trisetum*." Even the rust on the one leaf may have been another species. The evanescent character of this species corresponds to that of *Puccinia Eatoniae* Arth., having aecia on *Ranunculus abortivus* from a diffused mycelium and appearing over the whole surface of the leaf early in spring.

As the rust is now for the first time clearly recognized, it is herewith distinctively named and characterized.

Puccinia monoica (Peck) n. nom. (*Aecidium monoicum* Peck, Bot Gaz. 4: 230. 1879.)

O. Pycnia amphigenous, thickly scattered over large areas, preceding or among the aecia, honey-yellow becoming brownish, sub-epidermal, flattened-globose, 90-160 μ in diameter by 60-112 μ high; ostiolar filaments 30-90 μ long.

I. Aecia chiefly hypophyllous, evenly and thickly scattered, usually occupying the whole under surfaces of the leaves, cupulate or short cylindrical, 0.3-0.4 mm. in diameter; peridium whitish, the margin erect or spreading, somewhat lacerate, the peridial cells rhomboidal, 29-34 μ long, the outer wall 7-10 μ thick, striate, the inner wall 3-3.5 μ thick, verrucose; aeciospores globoid, 15-23 by 18-25 μ , the wall colorless, 1.5-2.5 μ thick, rather finely verrucose.

II. Uredinia chiefly epiphyllous, somewhat gregarious, oval or oblong, 0.5-1 mm. long, cinnamon-brown, pulverulent; urediniospores broadly ellipsoid or obovoid, 19-21 by 24-31 μ , the wall cinnamon-brown, about 2 μ thick, finely and closely echinulate, the pores 6-8, scattered.

III. Telia chiefly epiphyllous, more or less gregarious. oval, oblong, or roundish, 0.5-1 mm. long, pulvinate, chocolate-brown or cinereous by germination at maturity, early naked; teliospores ellipsoid or clavate-oblong, 16-24 by 34-45 μ , the wall cinnamon-brown, 1-1.5 μ thick, thicker at apex, 5-10 μ , smooth; pedicel nearly or quite colorless, rather slender, once to twice length of spore.

O and I. Pycnia and aecia on various species of *Arabis* throughout the Rocky mountain region, type collection from Colorado, on *Arabis retrofracta*, made by T. S. Brandegee.

II and III. Uredinia and telia on various species of *Trisetum*, the present known geographical range not so great as for the aecial stage.

3. **GYMNOSPORANGIUM NELSONI** Arth. (*G. durum* Kern), on *Juniperus utahensis* (Engelm.) Lemmon, sent by Mr. E. Bethel from Delta, Colo., was sown April 5 on *Amelanchier vulgaris*,

A. erecta, *Crataegus cerronis*, *Philadelphus coronarius*, and on the last species once more April 12. The only infection was on *Amelanchier vulgaris*, showing pycnia April 24, but failing to mature aecia. Other sowings made in May were without results. The connection with aecia on *Amelanchier* had been predicted by Mr. Bethel from his field observations in Colorado from 1907 to the present season, and also by Mr. A. O. Garrett in Utah, 1910. The same kind of observation is recorded by Tracy & Earle for southern Colorado in 1898.²³ The galls used for these sowings were on small twigs, globoid, and from 1 to 2 cm. in diameter. This form, generally distributed under the name of *G. durum* Kern, has recently been united by Dr. Kern²⁴ with *G. Nelsoni* Arth. On the type specimens of the latter the galls are small, only 1-8 mm. in diameter, and hence not at first readily identified with the large woody galls, which have been called *G. durum*.

All cultures heretofore reported in this series under the name *G. Nelsoni* belong not to this species but to *G. juvenescens* Kern, as stated in the report for 1910.²⁵ The latter is a species producing witches' brooms, but not woody galls.

4. GYMNOSPORANGIUM KERNIANUM Bethel, on *Juniperus utahensis* (Engelm.) Lemmon, sent by Mr. Bethel from Paonia, Colo., was sown April 7 on *Amelanchier vulgaris*, and *Crataegus cerronis*, with infection only on the *Amelanchier*, showing pycnia April 17, but not maturing aecia. Another sowing on *Amelanchier vulgaris* April 17 was without result, and the same was true of another collection from Paonia, Colo., sown on the same day. The failure to secure aecia makes it impossible to identify the aecia of this species among the many forms occurring on *Amelanchier*, although it is doubtless already in the hands of collectors. So far as the evidence goes it bears out Mr. Bethel's surmise²⁶ regarding the aecial hosts. This culture is referred to by Kern²⁷ in his monograph on the genus *Gymnosporangium*.

5. GYMNOSPORANGIUM EFFUSUM Kern, on *Juniperus virginiana*

²³ Greene, *Plantae Bakerianae* 1: 19. 1901.

²⁴ Bull. N. Y. Bot. Gard. 7: 448, 470. 1911.

²⁵ Mycol. 4: 26. 1912.

²⁶ See Mycol. 3: 158. 1911.

²⁷ See Bull. N. Y. Bot. Garden 7: 449. 1911.

L., collected at Newfield, N. J., by Messrs. F. D. Kern and B. O. Dodge, was sown May 4 on *Aronia arbutifolia*, *Amelanchier canadensis*, *Pyrus communis*, *Malus coronaria*, and *M. Malus*, with infection on the first only, showing pycnia in abundance June 15, but failing to develop aecia.

Although this infection did not proceed to a sufficient development to show the identity of the aecia, yet there are some reasons, chiefly relating to host and geographical distribution for thinking that we are dealing with *Roestelia transformans* Ellis, which was described by Mr. Ellis from material collected at Newfield, N. J., on *Aronia arbutifolia*.

6. *GYMNOSPORANGIUM GRACILENS* (Peck) Kern & Bethel (*G. speciosum* Peck), on *Juniperus monosperma* (Engelm.) Sarg., sent by Mr. Bethel from Trinidad, Colo., was sown April 26 on *Crataegus tomentosa*, *Sorbus aucuparia*, and *Philadelphus coronarius*, with heavy infection on the last, showing pycnia May 6, and aecia May 29. Before the infection had become certain another sowing was made May 1 on *Amelanchier vulgaris*, and the day following again on another plant of the same host, and also on the fruit of *A. erecta*, as well as the leaves of *Philadelphus coronarius*. Again infection was secured only on the *Philadelphus*, the pycnia showing in the greatest abundance May 13, and aecia June 8.

This connection was suggested by Mr. Bethel, who has given a history of his observations in a recent number of MYCOLOGIA.²⁸ The result of this set of cultures was communicated to Dr. F. D. Kern, then residing in New York, which enabled him to complete the description and synonymy of the species and to list the aecial hosts in his monograph of the genus *Gymnosporangium*.²⁹ The connection is especially notable, as it carries the aecial hosts of *Gymnosporangium* outside the families of Malaceae and Rosaceae, into the Hydrangiaceae. As the studies of this genus progress more and more evidence is secured to show that it possesses outlying species approaching in form and habit some of those in other genera.

²⁸ Bethel, Notes on some species of *Gymnosporangium* in Colorado, Mycol. 3: 156-160. 1911.

²⁹ See Bull. N. Y. Bot. Garden 7: 458. 1911.

The ease with which infection of the garden *Philadelphus*, originally a native of the Caucasus, was secured proved a surprise. Every effort was made to obtain native species of the genus, but without success until too late for culture work.

SUMMARY

The following is a complete list of the successful cultures made during the year 1911. It is divided into two series, species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. SPECIES PREVIOUSLY REPORTED

1. *Puccinia Peckii* (DeT.) Kellerm.—Teliospores from *Carex lanuginosa* Michx., sown on *Onagra biennis* (L.) Scop.
2. *Puccinia angustata* Peck.—Teliospores from *Scirpus cyperinus* (L.) Kunth, sown on *Lycopus americanus* Muhl.
3. *Puccinia Phragmitis* (Schum.) Körn.—Teliospores from *Phragmites communis* Trin., sown on *Rumex crispus* L.
4. *Puccinia cinerea* Arth.—Teliospores from *Puccinellia airoides* (Nutt.) Wats. & Coult., sown on *Oxygraphis Cymbalaria* (Pursh) Prantl.
5. *Puccinia subnitens* Diet.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Cleome spinosa* L., *Atriplex hastata* L., and *Chenopodium album* L.
6. *Uromyces Peckianus* Farl.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Atriplex hastata* L.
7. *Uromyces Medicaginis* Pass.—Urediniospores from *Medicago sativa* L., sown on same species of host.
8. *Gymnosporangium Nidus-avis* Thax.—Teliospores from *Juniperus virginiana* L., sown on fruits of *Amelanchier erecta* Blanch. and leaves of *Malus coronaria* (L.) Mill.
9. *Gymnosporangium clavariaeforme* (Jacq.) DC.—Teliospores from *Juniperus sibirica* Burgsd., sown on fruits of *Amelanchier erecta* Blanch.
10. *Gymnosporangium inconspicuum* Kern.—Teliospores from *Juniperus utahensis* (Engelm.) Lemmon, sown on leaves of *Amelanchier vulgaris* Moench.

11. *Gymnosporangium Libocedri* (P. Henn.) Kern.—Teliospores from *Libocedrus decurrens* Torr., sown on *Amelanchier vulgaris* Moench, *Crataegus tomentosa* L., and *C. cernonis* A. Nels.

12. *Gymnosporangium juniperinum* (L.) Mart. (*G. tremeloides* R. Hartig).—Teliospores from *Juniperus sibirica* Burgsd., sown on *Sorbus americana* Marsh.

13. *Coleosporium Vernoniae* B. & C.—Aeciospores from *Pinus taeda* L., sown on *Vernonia gigantea* (Walt.) Britton.

14. *Melampsora albertensis* Arth.—Teliospores from *Populus tremuloides* Michx., sown on *Pseudotsuga mucronata* (Raf.) Sudw.

15. *Melampsorella elatina* (A. & S.) Arth.—Aeciospores from *Abies lasiocarpa* Nutt., sown on *Cerastium oreophilum* Greene.

B. SPECIES REPORTED NOW FOR THE FIRST TIME

1. *Puccinia Lygodesmiae* Ellis & Ev.—Teliospores from *Lygodesmia juncea* (Pursh) D. Don, sown on the same species of host.


2. *Puccinia monoica* (Peck) Arth.—Aeciospores from *Arabis* sp., sown on *Trisetum subspicatum* (L.) Beauv., and *T. majus* (Vasey) Rydb.

3. *Gymnosporangium Nelsoni* Arth. (*G. durum* Kern).—Teliospores from *Juniperus utahensis* (Engelm.) Lemmon, sown on *Amelanchier vulgaris* Moench.

4. *Gymnosporangium Kernianum* Bethel.—Teliospores from *Juniperus utahensis* (Engelm.) Lemmon, sown on *Amelanchier vulgaris* Moench.

5. *Gymnosporangium effusum* Kern.—Teliospores from *Juniperus virginiana* L., sown on *Aronia arbutifolia* (L.) Ell.

6. *Gymnosporangium gracilens* (Peck) Kern & Bethel.—Teliospores from *Juniperus monosperma* (Engelm.) Sarg., sown on *Philadelphus coronarius* L.



CULTURES OF UREDINEAE IN 1912, 1913 AND 1914.¹

J. C. ARTHUR

The present article is the thirteenth of a series of reports² by the writer upon the culture of plant rusts, beginning in 1899 and completing sixteen consecutive years. The work for the three years covered by the present report has been done under the auspices of the Indiana Experiment Station, as a part of a research project supported by the Adams Fund.

The heaviest part of the work each year falls in April and May, and during this time the regular staff of the botanical department of the Experiment Station is supplemented in order to take care of the largely increased routine part of the work. In 1912 the assistant for the culture work was Mr. L. O. Overholts, a senior student of Miami University, Ohio, recommended by Dr. Bruce Fink; in 1913 Mr. Ezra Levin, junior student with credits at the Agricultural College of Michigan, recommended by Dr. Ernst A. Bessey, was in charge; and in 1914 Mr. Carl B. Gibson, senior student of Wabash College, Indiana, recommended by Prof. H. W. Anderson, did the work.

A large number of correspondents have assisted as in previous years by sending culture material, often by supplying information from field observations, and sometimes by making special trips to secure additional material or search for cultural clues. To all such persons, and especially to those who have been to trouble and expense in response to the wishes of the writer for local aid, the most hearty thanks are accorded. Without the assistance of observers in the field, the work of studying the life histories of the rusts extending over the vast territory of North

¹ Presented before the Botanical Society of America at the Philadelphia meeting, December 29, 1914.

² See Bot. Gaz. 29: 268-276; 35: 10-23; Jour. Myc. 8: 51-56; 10: 8-21; 11: 50-67; 12: 11-27; 13: 189-205; 14: 7-26; Mycol. 1: 225-256; 2: 213-240; 4: 7-33, 49-65.

America, many species of which are local, would proceed much more slowly.

An important aid in bringing together information regarding relationship of the rusts, and especially regarding obscure species, and in securing cultural material of critical forms, has been the excursions, often of considerable length, undertaken by the writer and members of his staff.

Early in April, 1912, Dr. F. D. Kern and the writer paid a visit to Auburn, Ala., where in company with Prof. F. E. Lloyd, field conditions of *Peridermium fusiforme* and *Puccinia angustatoides*, the latter on *Rhynchospora*, were studied.

In the latter part of May, 1912, the writer and Mr. F. J. Pipal spent two days in LaGrange county on the northern border of Indiana, in a vain search for the alternate host of the *Carex* rust, *Puccinia vulpinoidis*.

An excursion on the last of May, 1912, was made to the coast of Maine by Mr. C. R. Orton and the writer. The localities visited were on the Isle au Haut, where the writer had found a number of imperfectly known rusts during several vacational sojourns. A station for the *Puccinia* on *Carex maritima* on Deer Isle was also visited. All previous observations had been made between July and October, and this long journey of over a thousand miles was for the purpose of seeking out probable aecial hosts under spring conditions. Upon the return journey, Mr. Orton stopped in Vermont and secured cultural material, especially forms on *Carex*.

Between June 17 and 20, 1912, the writer made observations in company with Dr. J. J. Davis about Madison, Wis., and northward.

From the middle of July to the middle of August, 1912, Dr. Kern and the writer traveled over a thousand miles through the high mountains of southern Colorado, going west through the middle of the state, and returning along the southern border. A week was spent in the wonderful valley at Ouray and some days at Pagosa Springs. Very helpful information was gleaned regarding grass rusts, and particularly of the leaf and stem forms which the older mycologists listed as *Puccinia graminis* and *P. rubigo-vera*.

Three weeks of August, 1913, were spent in company with Mr. H. C. Travelbee, in northern Michigan in the vicinity of Leland. Here very abundant field confirmation was obtained of the correctness of the 1913 spring culture work in associating *Puccinia vulpinoidis* with aecia on *Solidago*, and material was secured for repeating the work.

Two days were profitably given in November, 1913, accompanied by Dr. F. D. Fromme, to an exploration of the Kankakee marshes in northern Indiana, and as much time in December following, accompanied by Mr. C. A. Ludwig, to a reconnoissance about French Lick in southern Indiana.

During February and the early part of March, 1914, an extended trip by Dr. Fromme and the writer was made through the Southwest. Field work began at Denison, on the northern border of Texas. At Denton the localities made interesting to uredinologists by the extended field work of Mr. W. H. Long were visited. Stops on the way southward to Austin, and a divergence to Houston and Galveston, gave interesting results. Observations in the arid region were made principally at San Antonio and El Paso, Texas, the region about the Agricultural College, N. Mex., and at Douglas and Tucson, Ariz. At Tucson through the kindness and material assistance of Dr. D. T. MacDougal and his corps of investigators at the Desert Botanical Laboratory, the rust flora of the vicinity was examined, and a very important culture on *Brodiaea* was carried to completion.

The dominant ideas actuating the above mentioned geographical explorations are not so much those of the ordinary collector, to find new species, but rather those of the student, to secure additional knowledge of species already named but imperfectly known, and to gather facts bearing upon relationships.

To indicate the extent of the labor involved in securing the results recorded in this paper the following statistics are given. During the three seasons covered by this report, 380 collections with resting spores, and 68 with active spores were available, but scarcely one third of those with resting spores could be made to germinate. To test the germinating condition of the spores over 2500 drop cultures were made. Altogether 650 sowings were undertaken upon growing hosts and 84 infections obtained.

NEGATIVE RESULTS.—It has been customary in these reports to record failures to ascertain the alternate host, when sowings were made with spores known to be capable of germination and made upon plants that were in proper condition for infection. As the work progresses, and fewer species are left to be connected with alternate hosts, the need of such records diminishes, especially as more and more dependence is placed upon field observations for the clues to relationship. A few trials during the last three years with negative results appear to be sufficiently significant to be worthy of record at this time.

1. PUCCINIA MCCLATCHIEANA Diet. & Holw.—A collection of this species on *Scirpus microcarpus* (*S. rubrotinctus*), from Vaughns, Washington Co., N. Y., sent by Mr. Stewart H. Burnham, was used for sowings made April 1, 1914, on *Chelone glabra*, *Hydrophyllum virginicum*, *H. Fendleri*, *Actaea alba*, *Dirca palustris*, and *Iris versicolor*, all without infection.

This species has been confused with *Puccinia angustata* Peck. The name was first applied to a Californian collection thought to be on *Scirpus sylvaticus*, but now determined as *S. microcarpus*. It is a common species along the Pacific coast on the last named host, known in one instance as far into the mountains as Belgrade near Bozeman, in southwestern Montana. It also occurs along the Atlantic coast on the same host (usually called *S. rubrotinctus*), being known from Nova Scotia to Delaware, and inland as far as Albany, N. Y. It was a collection of this species and host that was cited by Peck in establishing his *Puccinia angustata*, as on "*Scirpus sylvaticum*," from West Albany, N. Y. No clues to the identity of the alternate host have yet been secured.

2. PUCCINIA CRYPTANDRI Ellis & Barth.—A good teliosporic collection of this rust on *Sporobolus cryptandrus* was obtained by Dr. Fromme and the writer February 20, 1914, at Mesilla Park, N. Mex., and sown March 20 on *Sphaeralcea lobata*, *S. incana*, and *Callirhoe digitata*. Eight days later it was sown on other plants of *S. incana* and *C. digitata*, and on *Hibiscus militaris*. Again on March 9, it was sown on *Hydrophyllum Fendleri*, *Phacelia tanacetifolia*, *Thalictrum Fendleri*, and *Abronia umbellata*.

A collection similar to the last was obtained on the preceding day, but thought at the time to be *Puccinia tosta*, which was

sown April 17 on *Lithospermum officinale*, *Aesculus glabra*, *Elegagnus argentea*, *Lepargyrea canadensis*, and *Doellingeria umbellata*. It was sown again March 20 on *Sphaeralcea lobata*, *Callirhoe digitata* and *C. involucrata*. No infection was secured.

This is the first attempted culture of this species with teliospores, although once grown from amphispores.³ Most collections show only the amphisporic stage of the rust. No clue to the alternate host has yet been obtained.

3. PUCCINIA EMACULATA Schw.—This exceedingly common rust on *Panicum capillare* has been used in previous years for sowings on 26 different species of hosts with no infection.⁴ A careful morphological study shows that the species in its uredinial and telial conditions is very like *Puccinia Pammelii* Arth. (*P. Panici* Diet.), occurring commonly on *Panicum virgatum*, whose aecia have been grown upon *Euphorbia corollata*. Since this fact was ascertained, attempts have been made to grow *P. emaculata* upon *Euphorbia corollata*. Telial material from the vicinity of Lafayette, Ind., was sown accordingly on April 28, 1913, March 24, 31, and April 6, 1914. Material collected by Dr. Fromme at Lakehurst, N. J., was sown May 8, 1914, on both *E. corollata* and *E. cyparissias*. A collection from Lafayette was also sown March 31, 1914, on *Chelone glabra*, and *Dirca palustris*, which had not previously been tried. All attempts were equally fruitless. It is hoped that some time a fortunate field observation may lead to the solution of the problem.

4. UROMYCES RHYNOSPORA ELLIS.—No satisfactory field clues to the alternate host of this species have yet been obtained. Morphological study has led to the suggestion, improbable as it may seem at first, that it can belong to the very common *Carex-Aster-Solidago* complex. To test this suggestion, material obtained by Dr. Kern and the writer at Auburn, Ala., was sown April 22, 1912, on *Aster paniculatus*, *Solidago canadensis*, and *Helianthus angustifolius*. Another set of sowings was made on May 8 following upon other plants of the same three hosts, and on *Ruellia strepens*, and *Apocynum cannabinum*. No infection

³ Jour. Myc. 14: 20. 1908.

⁴ Bot. Gaz. 35: 12. 1903; Jour. Myc. 8: 52. 1902; 10: 10. 1904; 12: 12. 1906; 13: 192. 1907; 14: 11. 1908; and Mycol. 1: 230. 1909.

was obtained. Cultures were attempted on *Menyanthes* and *Decodon* in 1907, also without results.⁵

5. UROMYCES SPOROBOLI E. & E.—While on a visit to Mr. E. Bartholomew at Stockton, Kans., in August, 1911, the spot was pointed out where this rust on *Sporobolus longifolius* had been observed for several seasons following close upon a luxuriant development of an *Aecidium* on *Allium reticulatum*, as if the two might have genetic connection. Excellent material for testing the assumption was supplied the following spring, and a sowing was made April 29, 1912, upon *Allium reticulatum*, and also on *Malvastrum coccineum*, *Cassia chamaecrista*, *Baptisia bracteata*, *Apios tuberosa*, *Corydalis aurea*, *Zanthoxylum americanum*, *Physalis pubescens*, *Asclepias verticillata*, *Vagnera stellata*, and *Erigeron annuus*, all known to have aecia of uncertain connection, but without infection.⁶

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK.—The facts derived from growing the following species of rusts supplement those obtained from previous cultures in this series or from cultures recorded by other American or European investigators. In some cases the additional information recorded is of as great value as if it were entered under the next heading of cultures not before reported. For instance, the hitherto accredited species, *Puccinia vulpinoidea*, *P. Dulichii*, and *P. tosta*, are reduced to synonymy, and in so far simplify the naming of collections, beside permitting of a clearer conception of the variation of specific characters. A few cultures were made which are not reported, as they add no new facts to those already established.

CULTURES OF 1912

I. PUCCINIA GROSSULARIAE (Schum.) Lagerh.—The following successful cultures were made, all being sown on *Ribes Cynosbati*.

From *Carex pubescens*, Lafayette, Ind., sown April 20, showing pycnia April 29, and aecia May 9.

⁵ Jour. Myc. 14: 12. 1908.

⁶ For previous attempts see Bot. Gaz. 35: 11. 1903; and Mycol. 1: 13. 1912.

- From *Carex crinita*, St. Anne de Bellevue, Quebec, sown May 8, showing pycnia May 16, and aecia May 24.
- From *Carex arctata*, St. Anne de Bellevue, Quebec, sown May 8, showing pycnia May 22, and aecia May 27.
- From *Carex tenuis*, St. Anne de Bellevue, Quebec, sown May 13, showing pycnia May 22, and aecia May 27.

In the report of cultures for 1910⁷ the status of the name *P. albiperidia*, as representing a distinct species of *Carex-Ribes* rust, was discussed, but left somewhat unsettled. It was, however, thought to belong to a form possessing urediniospores with one basal pore, while the more common form on the same hosts, *P. Grossulariae*, has urediniospores with three equatorial pores. Subsequently Mr. C. R. Orton went over the material involved, including the type of *P. albiperidia*, and concluded⁸ that 'this name should be a synonym of *P. Grossulariae*, and that the form having urediniospores with one basal pore is entitled to be considered a distinct species to which he gave the name *P. uniporula*, a species correlated with *Uromyces uniporulus* Kern, the aecia of both species being unknown.

To gather further information I have had single sori removed from the type collections of both species of *Puccinia* involved, and have had the spores of each sorus separately counted by using a mechanical stage. The results are given in the following table. The type of *P. albiperidia* is on wintered-over leaves, having been gathered April 30, 1901, at Lafayette, Ind., and provides few urediniospores, while that of *P. uniporula* was gathered August 20, 1910, at London, Ontario, and gives a fair number of urediniospores. Both types are on *Carex pubescens*. As usual when urediniospores are taken from mature telial sori, many of the spores are not in condition to show the pores. When the pores could not be ascertained with fair certainty, even after using lactic acid or chloral hydrate with iodine, the spores have been classed as uncertain. It was also necessary to take the number of cells in the teliospore into account, as *Carex pubescens* also bears *Uromyces uniporulus*, chiefly distinguishable by the teliospores.

⁷ Mycol. 4: 13-15. 1912.

⁸ Mycol. 4: 200, 201. 1912.

SPORES FROM TYPE COLLECTIONS OF *Puccinia albiperidia* and *P. uniporula*:
EACH SORUS GIVEN SEPARATELY.

Number of Sorus	Teliospores with 1-cell (<i>Uromyces</i>)	Teliospores with 2-cells (<i>Puccinia</i>)	Urediniospores with One Basal Pore	Urediniospores with Three Equatorial Pores	Urediniospores with Pores Uncertain
<i>Puc. albiperidia</i>	1	0	Not counted	0	0
	2	0	231	0	0
	3	0	317	0	0
	4	0	363	3	1
	5	0	886	4	2
	6	1	327	0	4
	7	29	1325	0	3
	8	314	3	1?	0
	9	422	1	0	0
	10	697	2	0	1
	11	Not counted	0	0	0
<i>Puc. uniporula</i>	12	0	142	17	5
	13	3	853	4	5
	14	3	871	3	1
	15	4	1455	5	1
	16	5	19	12	7

Taking first the two columns of teliospores in the above table, it may be assumed that when a few only of either one- or two-celled teliospores occur in a sorus they are to be considered as incidental, possibly mesosporic. We may exclude from our present consideration four sori (8 to 11 incl.) from the type of *P. albiperidia*, as belonging to another species, *Uromyces uniporulus*, in termixed on the same leaf blades.

Of the remaining seven sori taken from the type of *P. albiperidia*, two of them (numbers 4 and 5) show a few urediniospores with one basal pore, and one sorus (number 6) shows one urediniospore with apparently three equatorial pores, while all others give no urediniospores whose pores could be made out with certainty.

Of the five sori (12 to 16 incl.) taken from the type of *P. uniporula* all show a number of urediniospores with one basal pore, and in addition three of the sori (numbers 12, 13, and 16) show urediniospores with three equatorial pores, as well as a number of spores whose pores could not be located. It is curious to note that in this type material of *P. uniporula* about one tenth of the urediniospores possess equatorial pores, and that these spores are intermixed in the same sori with the one-pored spores.

So far as the morphological evidence goes, there appears to be

no absolute difference between the types of *P. albiperidia* and *P. uniporula*. But *P. albiperidia* has been cultured on *Ribes*, producing aecia that can not be distinguished from those *Carex* rusts which show urediniospores with equatorial pores only. Whether aeciospores grown from *P. albiperidia* material would reproduce urediniospores, when sown back on a suitable *Carex*, with only three-pored or only one-pored urediniospores, or with sori containing a mixture of the two, is yet to be demonstrated. In the meantime, it seems best to use the name *P. albiperidia* as representing a form with aecia on *Ribes*, and synonymous with *P. Grossulariae*, while *P. uniporula* can be retained for such collections as show a preponderance of one-pored urediniospores. It is interesting to note in this connection that in Europe no *Carex* rust has yet been found agreeing with the uniporulate forms here discussed.

The essential specific unity of all *Carex-Ribes* rusts in both America and Europe was the conclusion reached by Dr. H. Klebahn in 1907. Dr. Klebahn's extended cultural work on this group of rusts began in 1892, and resulted in the separation of five species. In 1904 and 1906 he studied the behavior of American material grown from teliospores transmitted by the writer. Taking into account both European and American material, he came to the conclusion⁹ that the six described species of *Carex-Ribes* rusts were biological forms of one collective species, for which he suggested the name, *Puccinia Ribesii-Caricis*. This conclusion is upheld by the above study, although an earlier name is preferred for the species.

2. PUCCINIA CARICIS-ASTERIS Arth. (*P. Caricis-Solidaginis* Arth.)—Five successful cultures of this rust were secured. They are as follows:

Teliospores from *Carex* sp., London, Ontario, sown April 10 on *Aster* sp., showing pycnia April 16, and aecia April 27.

Teliospores from *Carex* sp., Lafayette, Ind., sown April 11 on *Aster* sp., showing pycnia April 23, and aecia April 29.

Teliospores from *Carex retrorsa*, St. Anne de Bellevue, Quebec, sown May 14 on *Aster paniculatus*, showing pycnia May 22, and aecia May 27.

Teliospores from *Carex scoparia*, St. Anne de Bellevue, Quebec, sown May 13 on *Aster paniculatus*, showing pycnia May 22, and aecia

⁹ Klebahn, Zeits. Pflanzenkr. 3: 134. 1907.

May 27; also sown same date on *Euthamia graminifolia*, showing pycnia May 22, at aecia June 4.

The significant thing about these cultures is that the material from *Carex scoparia*, which was sent by Mr. W. P. Fraser, grew on both *Aster* and *Euthamia*. The rust on this species of *Carex*, as represented in the herbarium, was for a long time considered sufficiently diverse morphologically to constitute a distinct species. Two years ago material on *Carex scoparia* from Maine was cultured on *Euthamia*,¹⁰ but did not grow on *Aster paniculatus* or *Solidago canadensis*. This year sowings were made on the three hosts named and results obtained on two of them. It was pointed out in the discussion of the results two years ago that the *Aster-Solidago-Erigeron* group of *Carex* rusts probably constitutes a single species with a number of more or less defined races. The same view has been expressed elsewhere.¹¹ Numerous confirmatory facts of diverse nature have been accumulating, until it seems advisable to adjust the nomenclature to accord with present knowledge.

This species is one of the most common forms of rust in North America. It evidently is less abundant in South America and in the eastern hemisphere. The morphological study of similar European forms, rated as species, discloses some that undoubtedly are to be classed in the same category with the American group. Without taking space to record the evidence, the conclusion has been reached that the most available name for the American and European constituents of the species here represented, but possibly not the oldest one, is *Puccinia extensicola* Plowr. This name was founded on telial material from *Carex extensa*, obtained at Norfolk, England, and cultured on *Aster Tripoli*, and is in every way comparable with the *Carex-Aster* forms of America.¹²

3. PUCCINIA ANGUSTATA Peck.—Teliospores on *Scirpus atrovirens*, collected at Lafayette, Ind., by L. O. Overholts, were sown

¹⁰ Mycol. 4: 15. 1912.

¹¹ Arthur, The physiologic aspect of the species question. Amer. Nat. 42: 246. 1908.

¹² For previous American cultures of this specific group, see Bot. Gaz. 35: 15, 21. 1903; Jour. Myc. 8: 53, 54. 1902; 11: 58. 1905; 12: 15. 1906; 14: 13. 1908; Mycol. 1: 233. 1909; 2: 224. 1910; and 4: 15, 16. 1912.

May 9 on *Lycopus americanus*, giving rise to pycnia May 16, and aecia May 24. Another collection believed to be the same rust and on the same host, collected at London, Ontario, by J. Dearness, was sown May 13 on *L. Americanus*, giving rise to pycnia May 20, and aecia May 27. Corresponding cultures have been made many times before.¹³ The rust is very common throughout the eastern United States, especially northward, but has not been seen in the Rocky mountain region or on the Pacific coast. Professor Peck based the name, *Puccinia angustata*, which was published in the Bulletin of the Buffalo Society of Natural History, volume 1, page 67, July, 1873, upon material from "leaves of *Scirpus sylvaticum* and *S. Eriophorum*; West Albany and Watkins, September." Upon examination of type material, it transpires that the collection on "*S. sylvaticum*" was made at Watkins, N. Y., and that on *S. Eriophorum* at West Albany, N. Y., and furthermore, that of the two hosts cited only *S. Eriophorum*, collected at Watkins, N. Y., although the second one mentioned, bears teliospores that correspond to the description. The other collection on "*S. sylvaticum*," found to be in reality *S. microcarpus* (*S. rubrotinctus*), bears a distinctly different form of teliospore, and must be considered to belong to some other species than *P. angustata*. The type of *P. angustata* Peck is, therefore, the collection in the herbarium of the New York State Museum, at Albany, N. Y., collected in September [1871?], at Watkins, N. Y., on *Scirpus Eriophorum*, by Prof. C. H. Peck. Thanks are due to Prof. Peck for the loan of the type material and for much assistance in ascertaining numerous facts connected therewith.

4. PUCCINIA ELLISIANA Thüm.—A collection on *Andropogon* sp., made by Dr. J. F. Brenckle, at Kulm, N. D., was used to sow, April 9, on *Viola cucullata*, *V. Nuttallii*, *V. primulaefolia*, *Laciniaria punctata* and *Lithospermum angustifolium*, with infection only on the two first named species of *Viola*. In both cases pycnia began to show in abundance May 8, and aecia May 12.

A number of vain attempts have been made in previous

¹³ For previous cultures see Bot. Gaz. 29: 273. 1900; Jour. Myc. 8: 53. 1902; 11: 58. 1905; 13: 196. 1907; 14: 14. 1908; Mycol. 1: 234. 1909; 4: 17 and 54. 1912.

years¹⁴ to culture this rust, thirty-five species of hosts having been used other than those used this year. Only once was a plant of *Viola* used, *V. striata*, a caulescent species on which such aecia have not yet been found, and are not very likely to occur.

The successful cultures were inspired by field observations by Dr. Brenckle, who sent us material with which to test his prediction. In addition to Dr. Brenckle's opinion there was also at hand the opinion of Mr. C. R. Orton, at that time working on the rusts in my laboratory, which was drawn from a study of correlation between this species and *Uromyces pedatatus*, in a paper read December 28, 1911, but not published until later,¹⁵ the latter species having its aecia on acaulescent violets. Since that time Mr. W. H. Long has published¹⁶ extended studies, both cultural and morphological, with important bearings which can not be taken into consideration in this connection.

5. PUCCINIA STIPAE Arth.—Two collections with teliospores on *Stipa comata*, gathered by Mr. E. Bethel, from different spots at Boulder, Colo., were used for cultures. One was sown May 15 on *Senecio lugens*, *S. spartioides*,¹⁷ *Chrysopsis villosus*, *Grindelia squarrosa*, *Gutierrezia Sarothrae*, and *Solidago mollis*, all considered probable hosts for the aecia. Infection occurred only on *Gutierrezia Sarothrae*, showing pycnia May 22, and aecia May 27, both in abundance.

The other collection was sown May 17 on the same set of hosts with infection only on *Senecio spartioides*, showing numerous pycnia May 23, and aecia June 1.

This species has previously been cultured¹⁸ on *Aster multiflorus*, *A. ericoides*, *A. Novae-Angliae*, *Solidago canadensis*, *Grindelia squarrosa*, and *Senecio lugens*. The present study adds two

¹⁴ See Jour. Myc. 14: 10. 1908; Mycol. 1: 231. 1909; 2: 220. 1910; and 4: 9. 1912.

¹⁵ Mycol. 4: 199, 200. pl. 70, figs. 5 and 6. 1912.

¹⁶ Notes on three species of rusts on *Andropogon*, Phytopath. 2: 164-171. August, 1912; and Influence of the host on the morphological characters of *Puccinia Ellisiana* and *Puccinia Andropogonis*, Jour. Agric. Research 2: 303-319. July, 1914.

¹⁷ The same host that was erroneously called *S. Douglasii* in report for 1910. Mycol. 4: 9, 11. 1912.

¹⁸ See Jour. Myc. 11: 63. 1905; and Mycol. 4: 19. 1912.

aecial hosts to the list previously known, and further strengthens the view that the species consists of a number of loosely defined races.

6. PUCCINIA AGROPYRI E. & E.—Three collections on *Elymus canadensis* from two widely separated and very different habitats were successfully cultured. One collection made by Mr. E. Bethel at Boulder, Colo., from plants on which he had previously placed leaves of *Clematis ligusticifolia* covered with aecia, brought from thirty miles distant, was sown April 27, on *Clematis ligusticifolia*, *C. Douglasii*, *Anemone cylindrica*, *Delphinium Geyeri*, and *Thalictrum Fendleri*, all believed to be probable hosts of this rust, and on *Phacelia heterophylla*, *Hydrophyllum capitatum*, *H. Fendleri*, and *Onosmodium occidentale*, which have been suspected from field observations to belong to the list of hosts. Infection only occurred on *Clematis ligusticifolia*, showing pycnia May 8, and aecia May 20.

Another collection by Mr. Bethel from plants growing with aecia-bearing *Clematis lingusticifolia*, at Boulder, Colo., was sown May 14, on the same nine species of hosts, with infection only on *Clematis ligusticifolia*, showing pycnia May 21, and aecia May 29.

The third collection by Dr. Brenckle from Kulm, N. Dak., was sown on *Clematis ligusticifolia*, *C. Douglasii*, *C. virginiana*, *Anemone cylindrica*, *Delphinium* sp. from Colorado, *Thalictrum Fendleri*, *T. alpinum*, *Aquilegia caerulea*, and *A. flavescens*, all belonging to a quite possible group of hosts, and on the outlying hosts, *Phacelia heterophylla*, *Hydrophyllum Fendleri*, *Onosmodium occidentale*, and *Elaeagnus argentea*. Infection was obtained only on *Anemone cylindrica*, showing a few pycnia May 20, but without maturing aecia.

Another collection of the same rust on *Agropyron Smithii* (host determined by Prof. A. S. Hitchcock), collected by the writer at Pueblo, Colo., was sown April 29, on *Clematis ligusticifolia*, *C. Douglasii*, *Anemone cylindrica*, *Delphinium* sp. from Colorado, *Thalictrum Fendleri*, *Hydrophyllum capitatum*, *H. Fendleri*, and *Onosmodium occidentale*, with infection only on the first named. The pycnia began to show May 8 and aecia May 17.

Cultures from *Elymus* on *Clematis ligusticifolia* are now reported for the first time. It has seemed quite probable from field observations that the aecia occurring on this host in great abundance throughout the Rocky Mountains were probably connected with telia on other hosts than *Agropyron*, where they have usually been assigned in this country and Europe, but this is the first direct proof by cultures. In 1904 a rust on *Bromus* from Iowa, Indiana, and Wisconsin, believed to be *Puccinia tomipara* Trel., was grown on *Clematis virginiana*. In a discussion of the results¹⁹ it was considered that the aecia were the form known as *Aecid. Clematidis* Schw., and distinct from the form in the Rocky Mountains, going to telia on *Agropyron*. The latter form, called *Aecid. Clematidis* DC., was grown in 1907²⁰ from Rocky Mountain material on *Agropyron*, but on the eastern host *C. virginiana*, no plants of *C. ligusticifolia* being available at the time. This was considered a demonstration that the form known and cultured in Europe as *P. Agropyri* E. & E., on *Agropyron*, is identical with the western form, but distinct from the eastern *Bromus-Clematis* rust.

In 1908 a rust on *Bromus* from the Rocky Mountains was grown on *Thalictrum dioicum* with success. The same season a similar subepidermal rust on *Agropyron* from the western mountains was grown on *Aquilegia*. These two forms were considered to represent distinct species and were named respectively *Puccinia alternans* and *P. obliterated*.²¹

The first cultural study of this group of subepidermal rusts began in 1903 with a supposed culture of *Dirca aecia* on *Bromus*,²² an error which was rectified in the report of cultures the year following. From that time to the present morphological studies, field observations, and careful cultures have multiplied until now there seems to be no further doubt that this group of subepidermal forms, passing under various names, represents only one species, but a species broken up into a number of races of considerable

¹⁹ Jour. Myc. 11: 62-63. 1905; also 13: 197. 1907; and Mycol. 1: 236. 1909.

²⁰ Jour. Myc. 14: 15. 1908.

²¹ Mycol. 1: 248-251. 1909; also 2: 225. 1910.

²² Jour. Myc. 10: 19. 1904; also 11: 62. 1905.

fixity. The telia are on *Agropyron*, *Elymus*, and *Bromus* chiefly and the aecia on *Clematis*, *Thalictrum*, *Aquilegia*, *Anemone*, and probably other Ranunculaceous hosts, and possibly on some hosts of other families.

7. PUCCINIA MONOICA (Peck) Arth.—In the report of cultures for 1911²³ record was made of sowings of teliospores from *Trisetum subspicatum* made June 20 upon two plants of *Arabis* (grown from Colorado seed), one plant of which indicated infection by a pathological change into a glomerate mass of rosettes, somewhat paler than normal. In this condition the plant passed the winter. Early in spring it began to send up a half dozen or more shoots instead of the usual single shoot of normal plants. Pycnia first were seen March 23, 1912, scattered over the considerably drawn shoots. Before there was time for the aecia to mature the plant accidentally died.

Freshly gathered plants of an *Arabis* bearing aecia, obtained May 13 at Palmer Lake, Colo., were received from Mr. Bethel, and aeciospores from them sown May 18 on leaves of *Koeleria cristata* and *Trisetum subspicatum*. Infection occurred only on the *Koeleria*, uredinia first being noticed June 18, and telia June 24.

There is no present need of adding to the general discussion of this species given in the last report of cultures.²⁴ We have now grown the rust from both aeciospores and teliospores, and shown that it occurs on both *Trisetum* and *Koeleria*, with some indication of biological races.

8. UROMYCES PERIGYNIUS Halst.—A collection on *Carex intumescens*, made by Dr. Charles E. Fairman at Lyndonville, N. Y., was sown April 24, on *Aster paniculatus*, *Solidago canadensis*, *Erigeron annuus*, *Euthamia graminifolia*, and *Onagra biennis*. On May 7 pycnia began to show in great abundance on the *Aster*, followed on May 10 by aecia. On the *Solidago* a few pycnia appeared May 8, but no aecia developed, although the host plant was in good condition.

In former cultures²⁵ material on this host from Nova Scotia produced infection on *Aster*, but not on *Solidago*. Material on

²³ Mycol. 4: 60. 1912.

²⁴ Mycol. 4: 59. 1912.

²⁵ See Jour. Myc. 10: 15-17. 1904; Mycol. 4: 21, 22. 1912.

other hosts from Maine and Indiana produced strong infection on *Solidago*, and in one case a sparing infection also on *Aster*. In the first culture report on the species, the close resemblance between this species and the parallel form under *Puccinia*, that we are now calling *P. extensicola*, was pointed out, and in the second report the evidence of well defined biological races was adduced. Both of these points are further emphasized by the cultures here reported.

In this connection an error should be corrected in the report of cultures for 1910. Quite anomalous results²⁶ were obtained in that year by sowing material of *Puccinia quadriporula* Arth. from *Carex Goodenowii* from the type locality, upon *Aster paniculatus*. It was at that time pointed out that the resulting aecia were indistinguishable from those of *P. Caricis-Asteris* Arth. A careful re-examination of the culture records has revealed the fact that the sowing on April 26, 1910,²⁷ was immediately preceded by a very successful sowing of *Uromyces perigynius* on another plant of the same species of *Aster*. The inference is that the supposed result from the spores of *P. quadriporula* in reality came from stray spores of *U. perigynius* accidentally intermixed during the operation, and do not represent a culture of *P. quadriporula*.

Furthermore, a careful and extended morphological study of a number of collections of *P. quadriporula*, made in different years from the type locality and its vicinity, leave no doubt that the form should be placed under *P. Grossulariae*, a *Carex* rust having aecia on *Ribes*. The four-pored feature of the urediniospore, from which the name is derived, is found to be no more marked than in some other collections proven to be a part of that species.

9. *UROMYCES JUNCTI* (Desm.) Tul.—It was stated in the report of cultures for 1910²⁸ that both Mr. Bethel and Dr. Brenckle held the opinion that this species in some one of its forms would be found to have aecia on *Ambrosia psilostachya*. Both gentlemen provided material for a test the present season, which verified their prediction, as the following record of cultures shows. The telial host in each instance was *Juncus balticus*.

²⁶ Mycol. 4: 28. 1912.

²⁷ Mycol. 4: 21. 1912.

²⁸ Mycol. 4: 23. 1912.

Telia from	Prediction for Aecia	Date of Sowing	Host for Culture	First Pycnia	First Aecia
North Dakota ...	<i>Carduus</i>	April 22	{ <i>Carduus Flodmanii</i> <i>Ambrosia psilostachya</i>	May 7	May 12
Colorado	<i>Ambrosia</i>	April 23	{ <i>Ambrosia psilostachya</i> <i>Ambrosia trifida</i>	May 8 May 8	May 12 —
Montana	May 6	{ <i>Carduus Flodmanii</i> <i>Ambrosia psilostachya</i> <i>Ambrosia trifida</i>	— — —	— — —
			{ <i>Carduus Flodmanii</i> <i>Ambrosia psilostachya</i> <i>Ambrosia artemisiæifolia</i> <i>Ambrosia trifida</i>	May 16 — May 22 —	May 21 — May 27 —
North Dakota ...	<i>Ambrosia</i>	May 11	{ <i>Carduus Flodmanii</i> <i>Silphium perfoliatum</i> <i>Laciniaria scariosa</i> <i>Xanthium canadense</i>	May 20 — — —	May 27 — — —
North Dakota ...	<i>Ambrosia</i>	May 11	{ <i>Ambrosia psilostachya</i> <i>Ambrosia trifida</i> <i>Xanthium canadense</i>	May 27 — —	— — —

The three collections sent by Dr. Brenckle from Kulm, N. Dak., bore out the prediction that he had based upon field observations. One of the collections grew upon both *Ambrosia* and *Carduus*, indicating that the races are not invariably fixed. The collection sent by Mr. Bethel from Boulder, Colo., also bore out the prediction which he had based on a field observation. No suggestions came with the collection sent by Mr. Vasku from Nihill, Mont. As stated in the North American Flora (7: 238. 1912), only *Carduus* has heretofore been proven by cultures in this country to be a host to this species, although both *Ambrosia* and *Arnica* have been considered to be hosts, a conclusion derived from morphological and field studies.²⁹

10. *UROMYCES ACUMINATUS* Arth.—A collection made by Mr. Bethel at Boulder, Colo., on *Spartina Michauxiana*, showing the characteristic slender, acuminate teliospores to which this name has been applied, was suspected from field observations to belong to aecia found on *Collomia*. Sowings were made April 29 on *Collomia linearis*, *Steironema ciliatum* and *S. lanceolatum*. Infection resulted only on *Collomia*, showing a great abundance of pycnia May 8, and aecia May 12.

This culture adds one more host experimentally proven to belong to this species, although it had been associated with the spe-

²⁹ For previous cultures see Jour. Myc. 14: 12. 1908; Mycol. 2: 220. 1910; 4: 22. 1912.

cies and with this particular race from morphological and field studies.³⁰

11. GYMNOSPORANGIUM NELSONI Arth. (*G. durum* Kern).—Galls of this rust a half inch in diameter from *Juniperus scopulorum*, gathered by Mr. Bethel at Cimarron, Colo., were used for sowing May 25 on *Amelanchier canadensis* and *Crataegus punctatus*. Infection occurred only on *Amelanchier*, showing abundant pycnia June 4, but giving only a few aecia, first noticed July 17.³¹

12. GYMNOSPORANGIUM BETHELI Kern.—A collection of galls on small branches of *Juniperus scopulorum*, made by Mr. Bethel at Plainview, Colo., were used to sow, June 4, on *Crataegus Pringlei*, giving rise to pycnia June 14, and aecia July 17.³²

13. GYMNOSPORANGIUM GRACILENS (Peck) Kern & Bethel.—A collection on *Juniperus utahensis*, made by Mr. Bethel at Glenwood Springs, Colo., was used for sowing on *Philadelphus coronarius*, giving an abundance of pycnia May 31, and aecia June 14. Another sowing was made at the same time on a horticultural form closely related to *P. coronarius*, imported from France, *P. Keteleerii*, which resulted in a luxuriant growth of pycnia May 30, and aecia June 22. These results confirm previous work.³³

CULTURES OF 1913

14. PUCCINIA ALBIPERIDIA Arth.—A collection made by Mr. L. S. Orton at Walden, Vt., on a narrow-leaved *Carex*, and communicated by Mr. C. R. Orton, was used to sow, May 29, on *Ribes Cynosbati*, giving abundant infection with pycnia showing June 6, and aecia June 20. The rust was labelled by Mr. Orton *P. uniporula*, and our examination confirms this view, many urediniospores having been seen with one basal pore and none with equatorial pores. This does not, however, preclude the possibility of the infection coming from the three-pored form, which may be intermixed with the other, and the species is listed accordingly

³⁰ See North American Flora 7: 231. 1912. For previous cultures see Mycol. 4: 29. 1912; also Fraser in Mycol. 4: 186. 1912.

³¹ For previous cultures see Mycol. 4: 61. 1912.

³² For previous cultures see Jour. Myc. 14: 23. 1908; Mycol. 1: 240. 1909; 2: 230. 1910; 4: 25. 1912.

³³ For previous cultures see Mycol. 4: 63. 1912.

as in the similar culture work of 1912, discussed above under number 1.

15. *PUCCINIA VULPINOIDIS* D. & H.—A collection of this rust on *Carex vulpinoidea* (host determined by Dr. Theo. Holm) made by Mr. Overholts at Elkton, Ohio, was used to sow April 17 on *Aster paniculatus*, *A. Drummondii*, *Solidago canadensis*, *S. glaberrima* (*S. missouriensis* of most manuals), *S. Rugosa*, and *S. mollis*. There was no infection of *Asters*, but a most abundant infection of the four species of *Solidago*, pycnia showing in each case April 27, and aecia May 7.

Puccinia vulpinoidis has been considered a distinctive and easily recognized species on account of the covered telial sori. A careful morphological study, chiefly by Dr. F. D. Kern, had shown however, that aside from this character the spore structure and range of hosts agree with *P. Caricis-Solidaginis*, or as we now say, *P. extensicola*, and to this morphological study was due the suggestion which led to the above successful cultures. The permanently covered telial sorus must be considered in the light of this study to be associated with the structural peculiarities of the host, and not a character to be used without qualification.

16. *GYMNOSPORANGIUM CLAVARIAEFORME* (Jacq.) DC.—Material on *Juniperus sibirica*, sent by Mr. Bethel from Tolland, Colo., was sown May 21 on *Crataegus cernuus* and gave rise to abundant pycnia June 1, but no aecia matured.³⁴

17. *PERIDERMIIUM FUSIFORME* Arth. & Kern.—Through the kindness of Dr. F. A. Wolf of Auburn, Ala., typical material of this striking rust was received, gathered from a grove of *Pinus taeda*, which Dr. Kern and myself had visited in April, 1912, and in which this form of *Peridermium* is very abundant.

The first collection, sent March 22, 1913, was from a main stem an inch in diameter, the fusiform gall being one and a half inches in diameter at the middle, and six inches long. It was sown March 24 on two plants of *Quercus rubra*. Uredinia began to appear sparingly on one plant by April 3, but failed to appear on the other, although telia developed on both plants April 14, in ample and perfect development.

³⁴ For previous cultures see Jour. Myc. 14: 19. 1908; Mycol. 1: 239. 1909; 4: 24. 1912; and 4: 56. 1912.

The second consignment was received April 5, 1913, consisting of a much larger gall, three inches in diameter by six inches long, but less typical in appearance. This material was sown April 6 on *Quercus rubra* and *Q. Phellos*. On the former, uredinia began to appear April 14, and on the latter April 18, followed by telia in both cases April 28.

This result shows without question that the form known under the name of *Peridermium fusiforme* is identical specifically with *P. Cerebrum*, both being the aecial stage of *Cronartium Quercus*. This cultural result is briefly referred to by Dr. Kern in *Mycologia* 6: 112, 135. 1914. The non-appearance of the repeating stage in one case is an interesting phenomenon apparently connected with some condition of the host.

18. *PERIDERMIMUM CARNEUM* (Bosc) Seym. & Earle.—Leaves of *Pinus taeda* bearing this rust were gathered by Prof. P. H. Rolfs, at Gainesville, Fla., February 12, 1913, and two days later were used by use to make a sowing on *Vernonia fasciculata*. Uredinia began to appear in abundance on March 3. Another collection of the rust was gathered by Mr. H. E. Stevens from *Pinus palustris* in the vicinity of Gainesville, Fla., on March 1. This material was from small plants in the open, over which leaves of *Ipomoea pandurata* well covered with *Coleosporium Ipomoeae* had been placed the previous fall. The field condition appeared to warrant the inference that the pine aecia were derived from the *Ipomoea* telia. A sowing of the material was made March 10 on *Vernonia fasciculata*, but no plants of *Ipomoea* were available for a culture. Uredinia appeared on the *Vernonia* in abundance on March 29, and in the typical form of *Coleosporium Vernoniae*.

This result does not preclude the possibility that *Coleosporium Ipomoeae* is a form of *C. Vernoniae*, but judging from the microscopic appearance of the urediniospores, that species is more likely to be a form of *C. Solidaginis* than of *C. Vernoniae*.

CULTURES IN 1914

19. *PUCCINIA EXTENSICOLA* Plowr.—A collection of the form known as *P. vulpinoidis*, collected by Mr. Travelbee and the writer

on *Carex vulpinoidea*, at Leland, Mich., Aug. 26, 1913, was used to sow April 2, on *Solidago canadensis* and *Aster paniculatus*. Abundant infection occurred on the *Solidago*, pycnia showing April 11, and aecia April 20, but the *Aster* remained free. The collectors found in many instances old aecia on *S. canadensis* in the field, intermixed with rusted *Carex vulpinoidea*. The inference from field observation, and also the cultural work of last year as recorded above under number 15, is confirmed by the culture.

A collection of *P. Dulichii* Syd., on *Dulichium arundinaceum*, gathered Jan. 17, 1914, at Gainesville, Fla., by Mr. H. E. Stevens, was accompanied by young aecia on a species of *Aster*. This association suggested that they might be genetically connected. A sowing from the *Dulichium* material was made, Jan. 22, on *Aster Drummondii*, *A. paniculatus*, and on an undetermined *Aster*, which had been obtained from a field near New Orleans, La., also on *Solidago canadensis* and *Senecio obovatus*. Another sowing from the same material was made, Jan. 31, on the same three species of *Aster*, and on *A. Tweedyi*. The only infection was a sparing production of pycnia on *Solidago canadensis*, showing Feb. 3, which did not continue into aecia. As soon as this result was noticed, another sowing from the same material was made, Feb. 4, on *Solidago canadensis*, which resulted in an abundant infection, showing pycnia Feb. 16, and aecia Feb. 25. From this result, together with a careful microscopic study of herbarium material, it is inferred that *P. Dulichii* is a part of the common *P. extensicola*, although the telial host is not a *Carex*. It is the first time that any *Carex* rust has been traced to a telial host outside of the genus *Carex*.

20. PUCCINIA TOSTA Arth.—A collection was made by Dr. Fromme and the writer at Mesilla Park, N. Mex., on what was thought at the time to be *Muhlenbergia Porteri*, but which later proved to be the very similar appearing *Sporobolus asperifolius*. Thinking that it was *P. Muhlenbergiae*, known to have its aecia on malvaceous hosts, it was sown, March 20, on *Callirhoe involucrata*, *C. digitata*, and *Sphaeralcea incana*. Infection was obtained only on the last host, pycnia showing March 27, and aecia April 3, both in great profusion. Another sowing was at once

made of the same material on *S. lobata*, *C. digitata*, *Hibiscus militaris*, and *Malvastrum coccineum*, with infection only on the *Sphaeralcea*, pycnia showing April 6, but the aecia being destroyed by aphids before maturing.

Another collection of identical appearance was made five days later than the one above, at Ysleta, Texas, a few miles from El Paso. This was sown, March 28, on two plants of *S. lobata*, on *C. digitata*, and *H. militaris*. Both plants of *Sphaeralcea* gave infection, showing pycnia April 6, but resulting in few aecia, owing to accident. Another sowing from the same collection was made, May 2, on *Napaea dioica*, without infection.

Putting the above cultural results from *P. tosta*, with the gross appearance and subsequent microscopic study, and comparing with similar data from *P. Muhlenbergiae*, there appears to be no ground upon which to keep the two forms separate. The fact that the telial hosts belong to two genera of grasses is not in this case a difference of importance, as *Sporobolus* and *Muhlenbergia* intergrade, and are kept separate upon technical grounds. The previous cultural studies³⁵ of *P. Muhlenbergiae* have indicated that the species is a complex of races. It has been grown on *Hibiscus militaris* and *Callirhoe involucrata*, but the similar aecia on *Napaea*, *Malvastrum*, and *Sidalcea* have not yet been grown, although attempted, the failure believed to be due to a lack of the proper racial telia. The above is the first successful culture with material on *Sporobolus*, although previous attempts³⁶ have been made.

Hereafter it will be considered advisable to treat *P. tosta* as a synonym of *P. Muhlenbergiae*.

21. PUCCINIA AGROPYRI E. & E.—A collection of this rust on *Elymus virginicus* was made by Dr. Fromme and the writer on Feb. 13, 1914, at Austin, Texas, and at the same time the observation was made that *Clematis Drummondii*, not then in leaf, was in the same spot, and abundant in the vicinity. Dormant roots of this wild *Clematis* were secured, and later grown for the culture work.

³⁵ See Jour. Myc. 11: 51. 1905; 13: 192. 1907; Mycol. 1: 251. 1909; 2: 226. 1910; and 4: 18. 1912.

³⁶ See Jour. Myc. 10: 10. 1904; 12: 12. 1906; Mycol. 4: 10 and 52. 1912.

A sowing of telia was made April 1 on *Clematis Drummondii*, *C. Douglasii*, *C. virginiana*, *Aquilegia flavescens*, *A. canadensis*, *Thalictrum Fendleri*, and *T. dioicum*. Abundant infection occurred on the first named host, but on no others, pycnia appearing April 5, and aecia April 18.

The results are in accord with the cultures of 1912, reported above under number 6, but indicate another race not met with before.

22. *UROMYCES PERIGYNIUS* Halst.—A collection of this species on *Carex tribuloides* made at French Lick, Ind., by Mr. Ludwig and the writer, was sown April 1 on *Aster paniculatus*, *A. Drummondii*, *A. Tweedyi*, *Solidago canadensis*, *S. rugosa*, and *Euthamia graminifolia*. Infection was secured only on *Aster Tweedyi*, and then so sparingly that it was overlooked until April 8, when the aecia were observed. Cultures for 1912 are reported above under number 8.

This species of rust from other *Carex* hosts has previously been grown³⁷ on two other species of *Aster*, and five species of *Solidago*.

23. *UROMYCES SCIRPI* (Cast.) Burr.—Material on *Scirpus fluviatilis*, sent by Mr. E. T. Bartholomew from Madison, Wis., was sown April 22 on *Sium cicutaefolium*, giving rise to a few pycnia May 5, but without further development. Another similar sowing April 24 gave rise to an abundance of pycnia May 5, and aecia May 11.

The former cultures³⁸ with American material have been on *Cicuta maculata*.

24. *GYMNOSPORANGIUM NIDUS-AVIS* Thax.—Telial material on *Juniperus virginiana*, gathered by Dr. Fromme at Woods Hole, Mass., was sown May 11 on *Amelanchier vulgaris*, giving rise to pycnia May 19, and a great abundance of aecia June 20.³⁹

25. *GYMNOSPORANGIUM BOTRYAPITES* (Schw.) Kern.—Telial material on *Chamaecyparis thyoides* sent by Dr. Fromme from Lakehurst, N. J., was sown May 6 on the leaves of *Amelanchier canadensis* and *Aronia arbutifolia*, with no infection on *Aronia*,

³⁷ Jour. Myc. 10: 15. 1904; and Mycol. 4: 32. 1912.

³⁸ Jour. Myc. 13: 199. 1907; 14: 17. 1908; and Mycol. 1: 237. 1909.

³⁹ For previous cultures see Jour. Myc. 14: 19. 1908; Mycol. 2: 230. 1910; 4: 25 and 56. 1912.

but very abundant infection on *Amelanchier*, giving pycnia May 18, and aecia October 1.

Another collection on the same host was sent by Dr. Fromme four days later from Woods Hole, Mass., and sown May 11 on leaves of *Amelanchier canadensis*, giving pycnia June 5, and aecia October 27. The results are in accord with previous cultures.⁴⁰

26. *COLEOSPORIUM VERNONIAE* B. & C.—A collection of *Peridermium carneum* on *Pinus taeda*, gathered at East Lake, Fla., by Mr. H. E. Stevens, was sown April 13 on *Aster paniculatus*, *Solidago canadensis*, *Euthamia graminifolia*, *Laciniaria punctata*, *L. Langloisii* (the plant obtained from Texas), and *Vernonia fasciculata*. A sparing infection was obtained on the *Vernonia* only, uredinia being first noticed May 8.

A similar collection sent by the same collector from Gainesville, Fla., was sown May 8 on *Solidago canadensis*, *Laciniaria Langloisii*, *Elephantopus carolinianus*, *Amsonia salicifolia*, and *Vernonia fasciculata*. Although all the hosts used were possible hosts for such a *Peridermium*, yet infection only occurred on the *Vernonia*, showing uredinia May 25 in abundance.

Uredinia from the last culture was sown May 17 on another plant of *Vernonia fasciculata*, with abundant infection, showing uredinia May 26. Another sowing from the same source was made May 28 on *Aster paniculatus* and *Laciniaria Langloisii*, with no infection.

The results are in accord with previous cultures,⁴¹ and add but little to our knowledge of the numerous southern species of *Coleosporium*.

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME: The following species have never before been cultivated, in America or elsewhere, so far as the writer knows. Some of those included in the above list, such as *Puccinia vulpinoidis*, *P. Dulichii*, *P. tosta*, and *Peridermium fusiforme*, might with some propriety have been placed here, as not till after the cultures were made was their true status as species known.

⁴⁰ Mycol. 1: 240. 1909.

⁴¹ Mycol. 4: 29 and 57. 1912.

CULTURES IN 1913

1. *UROMYCES ELEGANS* (B. & C.) Lagerh.—This autoecious rust, very common in the Southern States, is one of the group of species which produce no uredinia, so far as known, very few of which have been cultivated. Growing plants of *Trifolium carolinianum* bearing aecia were sent by Dr. F. A. Wolf from Auburn, Ala., and the aeciospores sown March 29 on plants free from the fungus. Teliospores began to appear about April 18 as the result.

This result does not disclose whether the species possesses both primary and secondary aecia, or whether pycnia ever occur. A culture with teliospores should be kept in view.

CULTURES IN 1914

2. *PUCCINIA NODOSA* Ell. & Hark.—While upon a visit to the Desert Botanical Laboratory at Tucson, Ariz., an exceptional opportunity was offered to study the life history of another autoecious species of rust, which like the one last mentioned, possesses no uredinia. A strong plant of *Brodiaea pauciflora*, growing near the door of the laboratory was moistened on February 26, sprinkled with aeciospores brought from some distance, and covered with a belljar. The temperature at the time was favorable for infection, the belljar being shielded from the direct rays of the sun. The experiment was left in charge of Dr. W. A. Cannon of the Laboratory staff, who kindly forwarded the leaves on March 18, when the sori first opened. Only telia were produced.

As in the preceding case the possibility of both primary and secondary aecia occurring in the life cycle is not touched upon.

3. *PUCCINIA SPLENDENS* Vize.—Through the courtesy of the Desert Botanical Laboratory, Dr. Fromme and the writer were enabled to make an excursion on February 28 to the Santa Rita Mountains in the vicinity of Tucson, Ariz., where we secured teliosporic specimens of *P. splendens* on *Hymenoclea monogyra*. Through the kindness of Prof. J. J. Thornber of the University of Arizona we received after our return to Indiana a number of thrifty young plants of this host, which soon started into leaf in the green house. A sowing of teliospores was made April 7,

and another April 15, with no result. A third sowing on April 25 was better done, and gave rise to pycnia on the leaves May 6, and aecia May 20.

Aeciospores from this culture were sown May 26, which resulted in the production of uredinia June 15, not numerous but well formed. Uredinia continued to be produced until they were finally followed sparingly by telia July 10.

In every sowing an abundance of spores was used, which were applied to both leaves and stems. Tests of the spores showed unusually strong germination. Why the infection was so sparing and only on the leaves, while in the field the rust is chiefly on the stems, was not apparent. The cultures supply a knowledge of the pycnia and uredinia, neither of which were before known.

4. *PUCCINIA MINUTISSIMA* Arth.—Viable material of this species on *Carex filiformis* was secured at much labor especially for this work by Mr. J. Dearness of London, Ontario, from the southeastern shore of Lake Huron. A collection made in December, 1911, was sown the following spring on seven hosts of as many genera without infection. Another collection of May, 1912, was similarly tested, and even more thoroughly, without success. A collection made in November, 1913, was sown April 18, 1914, on *Decodon verticillatus*, with an abundant infection, showing pycnia April 27, and aecia May 7.

The first suggestion for this connection was made by Prof. James B. Pollock of the University of Michigan, who wrote on August 3, 1909, as follows: "I found a rust on a patch of *Carex filiformis*, forming a half circle with a radius of about two rods around a specimen of *Decodon verticillatus*, some of whose leaves had an *Aecidium* on them. I send herewith specimens of both. No other *Aecidium* was found near the rusted sedge. The whole situation seems to me to indicate very closely the *Decodon* plant as a center of infection for the *Carex* rust."

The aecial stage of this rust is *Aecidium Nesaeae* Ger., but *Puccinia Nesaeae* Ellis & Ev. does not belong here, having been founded on a telial collection with the host erroneously determined. The error was detected by Prof. E. W. D. Holway.

5. *GYMNOSPORANGIUM ELLISII* (Berk.) Farl.—Material on *Chamaecyparis thyoides* was sent by Dr. Fromme from Lakehurst

N. J., and sown May 6 on *Myrica cerifera*, giving rise to pycnia May 15, and aecia June 6. This most interesting result was in accord with field observations made by Dr. Fromme, who has recorded the steps which led to the inference of relationship, and has also discussed the results, in a paper⁴² anticipating this report.

The aecia of this species are of the aecidioid form, and not roestelioid, as in the majority of the species of the genus. Moreover, the host belongs to a family more divergent from the Malaceae, which bears most of the Gymnosporangial aecia, than heretofore supposed to be possible. The telial stage was once made the basis of a separate genus, *Hamaspora*, on account of the slender, more than two-celled teliospores. Completing a knowledge of the life history of a species with so many outlying characters is an especially notable achievement.

SUMMARY

The following is a complete list of the successful cultures made during the years 1912, 1913, and 1914. It is divided into two series, species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. SPECIES PREVIOUSLY REPORTED

1, (8) and 14. PUCCINIA GROSSULARIAE (Schum.) Lagerh. (*P. albiperidia* Arth., *P. quadriporula* Arth.)—Teliospores from *Carex arctata* Boott, *C. crinita* Lam., *C. pubescens* Muhl., and *C. tenuis* Rudge, sown on *Ribes Cynosbati* L.

2, 15 and 19. PUCCINIA EXTENSICOLA Plowr. (*P. Caricis-Asteris* Arth., *P. Caricis-Solidaginis* Arth., *P. vulpinoidis* D. & H., *P. Dulichii* Syd.)—Teliospores from *Carex retrorsa* Schw., sown on *Aster paniculatus* Lam.; from *Carex scoparia* Schk., sown on *A. paniculatus* Lam. and *Euthamia graminifolia* (L.) Nutt.; from *Carex vulpinoidea* Michx., sown on *Solidago canadensis* L., *S. glaberrima* Martens, *S. rugosa* Mill. and *S. mollis* Barth.; from *Dulichium arundinaceum* (L.) Britt., sown on *Solidago canadensis* L.

⁴² Fromme, D. A. A new Gymnosporangial connection. Mycol. 6: 226-230. 1914.

3. PUCCINIA ANGUSTATA Peck.—Teliospores from *Scirpus atrovirens* Muhl., sown on *Lycopus americanus* Muhl.

4. PUCCINIA ELLISIANA Thüm.—Teliospores from *Andropogon* sp., sown on *Viola cucullata* Ait. and *V. Nuttallii* Pursh.

5. PUCCINIA STIPAE Arth.—Teliospores from *Stipa comata* Trin. & Rupr., sown on *Gutierrezia Sarothrae* (Pursh) B. & R., and *Senecio spartioides* T. & G.

6 and 21. PUCCINIA AGROPYRI E. & E.—Teliospores from *Elymus canadensis* L., sown on *Clematis ligusticifolia* Nutt., and *Anemone cylindrica* A. Gray; from *Elymus virginicus* L., sown on *Clematis Drummondii* T. & G.; and from *Agropyron Smithii* Rydb., sown on *Clematis ligusticifolia* Nutt.

7. PUCCINIA MONOICA (Peck) Arth.—Teliospores from *Trisetum subspicatum* (L.) Beauv., sown on *Arabis* sp., and aeciospores from *Arabis* sp., sown on *Koeleria cristata* (L.) Pers.

20. PUCCINIA MUHLENBERGIAE A. & H. (*P. tosta* Arth.).—Teliospores from *Sporobolus asperifolius* (Nees & Meyen) Thurb. sown on *Spaeralcea incana* Torr. and *S. lobata* Wooton.

8 and 22. UROMYCES PERIGYNIUS Halst.—Teliospores from *Carex intumescens* Rudge, sown on *Aster paniculatus* Lam., and *Solidago canadensis* L.; from *Carex tribuloides* Wahl., sown on *Aster Tweedyi* Rydb.

9. UROMYCES JUNCII (Desm.) Tul.—Teliospores from *Juncus balticus* Willd., sown on *Ambrosia psilostachya* DC., *A. trifida* L., and *Carduus Flodmanni* Rydb.

10. UROMYCES ACUMINATUS Arth.—Teliospores on *Spartina Michauxiana* A. S. Hitch., sown on *Collomia linearis* Nutt.

23. UROMYCES SCIRPI (Cast.) Burr.—Teliospores from *Scirpus fluviatilis* (Torr.) A. Gray, sown on *Sium cicutaefolium* Schrank.

11. GYMNOSPORANGIUM NELSONI Arth. (*G. durum* Kern).—Teliospores from *Juniperus scopulorum* Sarg., sown on *Amelanchier canadensis* (L.) Medic.

12. GYMNOSPORANGIUM BETHELI Kern.—Teliospores from *Juniperus scopulorum* Sarg., sown on *Crataegus Pringlei* Sarg.

13. GYMNOSPORANGIUM GRACILENS (Peck) Kern & Bethel.—Teliospores from *Juniperus utahensis* (Engelm.) Lemmon, sown on *Philadelphus coronarius* L. and *P. Keteleerii* Carr.

16. GYMNOSPORANGIUM CLAVARIAEFORME (Jacq.) DC.—Telio-

spores from *Juniperus sibirica* Burgsd., sown on *Crataegus cernuus* A. Nels.

24. GYMNOSPORANGIUM NIDUS-AVIS Thax.—Teliospores from *Juniperus virginiana* L., sown on *Amelanchier vulgaris* Moench.

25. GYMNOSPORANGIUM BOTRYAPITES (Schw.) Kern.—Teliospores from *Chamaecyparis thyoides* (L.) B. S. P., sown on *Amelanchier canadensis* (L.) Medic.

17. CRONARTIUM QUERCUS (Brond.) Schröt. (*Peridermium fusiforme* Arth. & Kern).—Aeciospores from *Pinus taeda* L., sown on *Quercus rubra* L., and *Q. Phellos* L.

18 and 26. COLEOSPORIUM VERNONIAE B. & C.—Aeciospores from *Pinus taeda* L. and *P. palustris* Mill., sown on *Vernonia fasciculata* Michx.; urediniospores from *Vernonia fasciculata* Michx., sown on same host.

B. SPECIES REPORTED NOW FOR THE FIRST TIME

1. UROMYCES ELEGANS (B. & C.) Lagerh.—Aeciospores from *Trifolium carolinianum* Michx., sown on same host, producing telia.


2. PUCCINIA NODOSA Ell. & Hark.—Aeciospores from *Brodiaea pauciflora* (Torr.) Standley, sown on same host, producing telia.

3. PUCCINIA SPLENDENS Vize.—Teliospores from *Hymenoclea monogyra* T. & G., sown on same host, producing pycnia and aecia; aeciospores sown on same host, producing uredinia and telia.

4. PUCCINIA MINUTISSIMA Arth. (*Aecidium Nesaeae* Ger.)—. Teliospores from *Carex filiformis* L., sown on *Decodon verticillatus* (L.) Ell.

5. GYMNOSPORANGIUM ELLISII (Berk.) Farl.—Teliospores on *Chamaecyparis thyoides* (L.) B.S.P., sown on *Myrica cerifera* L.

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.



CULTURES OF UREDINEAE IN 1915¹

J. C. ARTHUR

The present article is the fourteenth of a series of reports² by the writer upon the culture of plant rusts, beginning in 1899 and completing seventeen consecutive years. With this report it is proposed to bring the series to a close. Hereafter the record of such cultures as may be undertaken will be made in whatever connection may be found advantageous. To render the work brought together in the present series more readily accessible, and to make clear the changing point of view dominating the work, it is proposed to prepare an index and a brief historical statement, to be issued in the early future.

During the year 1915, little traveling was undertaken for the purpose of securing culture material and information. Two trips were made by the writer, the first one in April, the second in June, the first one in company with Mr. H. E. Ford, in order once more to explore the Kankakee marshes, in the northern part of Indiana, especially to gather information about *Puccinia Seymouriana* on *Spartina*. The rust was found in the greatest profusion, and specimens were taken from different parts of the region. Only one of these specimens showed viability, without much strength, and no infection was obtained from it. It is difficult to surmise what could cause such low viability, especially as the winter was mild and favorable to vegetation.

Correspondents in various parts of the country, as in previous years, have sent material for cultures, of both the rusts and the living host plants. A number of correspondents took extra trouble to respond to requests for particular species, and to such

¹ Presented before the Botanical Society of America at the Columbus meeting, December 30, 1915.

² See Bot. Gaz. 29: 268-276; 35: 10-23; Jour. Myc. 8: 51-56; 10: 8-21; 11: 50-67; 12: 11-27; 13: 189-205; 14: 7-26; Mycol. 1: 225-256; 2: 213-240; 4: 7-33, 49-65; 7: 61-89.

especially not only the writer feels much indebted but the scientific public is placed under obligation. Among those who contributed in more or less degree to the studies of the present year the following are especially entitled to mention: Messrs. F. McAllister, I. M. Lewis and B. C. Tharp, Austin, Texas; W. A. Archer, Mesilla Park, N. Mex.; J. M. Bates, Red Cloud, Neb.; E. Bartholomew, Stockton, Kans.; E. Bethel, Denver, Colo.; J. F. Brenckle, Kulm, N. Dak.; H. L. Bolley, Fargo, N. Dak.; J. J. Davis, Madison, Wis.; A. O. Garrett, Salt Lake City, Utah; H. D. House, Albany, N. Y.; H. S. Jackson, Corvallis, Ore.; C. H. Kauffman and E. B. Mains, Ann Arbor, Mich.; Roy Latham, Orient, N. Y.; W. H. Long, Albuquerque, N. Mex.; C. R. Orton, State College, Pa; J. L. Weimer and H. H. Whetzel, Ithaca, N. Y.

To indicate the extent of the work in making the cultures here reported the following statistics may be given. There were available 118 collections with resting spores, and 18 with active spores, *i. e.*, taken from growing plants. Over 240 tests were made in a hanging drop to determine the germinating condition of the spores. Only 48 collections of resting teliospores could be brought to germination, from which 110 sowings were made, and 16 infections secured. From the 18 collections of fresh spores 34 sowings were made, and 3 infections obtained. No extra assistant was employed for the work, as has been customary in preceding years, but it was carried forward by the regular staff of the laboratory, the larger share falling to Mr. H. C. Travelbee.

NEGATIVE RESULTS.—A number of collections giving good germination of spores produced negative results when sown upon hosts which are presumably aecial hosts for the species, but possibly not adapted to the racial material in hand. A few collections of species, for which no definite suggestions were available, were sown upon the seemingly most likely aecial host. In both cases the lack of positive results appears worth recording.

1. PUCCINIA AMPHIGENA Diet., on *Calamovilfa longifolia* (Hook.) Hack., collected by Mr. E. Bethel at Colorado Springs, Colo., Oct. 18, 1914, and sent immediately to Lafayette, Ind.,

was sown March 31, on *Smilax hispida*; another collection from the same locality, made May 16, 1915, was sown on another plant of the same host May 24, both without infection. The leaves of the two collections sent by Mr. Bethel were thickly covered with the prominent, blackish telia. The teliospores germinated well, especially so in the October collection. Mr. Bethel stated on the label of the latter specimen that although the rust was very abundant, there were no *Smilax* plants in the region. In sending the May collection he stated on the label that the aecial stage occurred on *Leucocrinum*, but desired to have the material tested on *Smilax*. In the accompanying letter of same date he says: "I am inclosing *Puccinia amphigena* on *Calamovilfa longifolia*, which I wish you would sow on *Smilax*, which I believe you give as host in the east. I have fine young plants of native *Smilax*, but have failed to inoculate them. With us this does not normally belong to *Smilax*, and may be another race. It belongs to *Leucocrinum*, on which it is epidemic everywhere this year." This species of rust was first cultured on *Smilax* in 1902, from telial material gathered at Callaway, Neb., and in the year following from material gathered at the type locality in Chicago, Ill. It has been cultured altogether six times,³ the westernmost locality for telial material being central Nebraska, on the plains, some two hundred miles from the foothills of the Rocky Mountains, where this season's material was obtained.

2. PUCCINIA EMACULATA Schw., on *Panicum capillare* L., collected at Lafayette, Ind., was sown, May 21, on *Euphorbia corollata*, having shown strong germination, but without results. The reasons for this attempt, with citation of other trials, are given in the previous report of cultures.⁴

3. PUCCINIA SIMILLIMA Arth., on *Phragmites communis* Trin., collected by Dr. J. F. Brenckle, at Wiedmer's Lake, N. Dak., on April 11, 1915, was sown May 14, on *Anemone cylindrica* and *Ranunculus acris*, without infection. It was sown again June 18 on two plants of *Ranunculus sceleratus*, but with no infection.

³ See Bot. Gaz. 35: 20. 1903; Jour. Myc. 10: 11. 1904; 12: 16. 1906; 14: 15. 1908; Mycol. 2: 225. 1910; and 4: 18. 1912.

⁴ Mycol. 7: 65. 1915.

This species was successfully cultured in 1902 and again in 1907 on *Anemone canadensis*.⁵ A recent monographic study of American grass rusts confirms the early opinion⁶ that this species is similar, morphologically and in host requirements, to *P. Magnusiana* of Europe, which has been found to have aecia on *Ranunculus acris* and *R. bulbosus*. Aecia were collected by Dr. Brenckle on *R. sceleratus*, May 30, 1908, near Kulm, N. Dak., which are structurally similar to the American form on *Anemone*, as well as to the European form on *Ranunculus*. An appeal to Dr. Brenckle for living plants of *R. sceleratus* was met with some difficulty upon his part, but successfully, and telial material also was sent from a locality not far away from the place where aecia on *R. sceleratus* had been obtained, but nothing definite has been proven. It still seems probable, however, that *P. simillima* is but a racial variant of *P. Magnusiana*, and that a race may finally be found in America with aecia on *Ranunculus*, although the common form is on *Anemone*.

4. PUCCINIA RHAMNI (Pers.) Wettst., on *Nothololcus lanatus* (L.) Nash (*Holcus lanatus* L.), sent by Prof. H. S. Jackson from Corvallis, Ore., was sown April 2 on *Rhamnus cathartica* and *Lepargyrea canadensis*, with no infection. Another collection of the rust on *Scolochloa festuacea* (Willd.) Link, sent by Dr. J. F. Brenckle from Kulm, N. Dak., was sown May 8 on *Lepargyrea canadensis* and *Eleagnus argentea*, and again May 21 on *Rhamnus cathartica*, all without infection. Aecia are known to be common about Corvallis on *Rhamnus Purshiana*, but not found on *Lepargyrea*, the host being absent from the region, while at Kulm aecia are common on *Eleagnus*, but whether the latter belong to a race of *P. Rhamni*, or to an independent species is not yet known.

5. PUCCINIA AGROPYRI E. & Ev., on *Hordeum jubatum* L., sent by Dr. Brenckle from Wiedmer's Lake, N. Dak., was sown May 13 on *Anemone cylindrica*, *Clematis ligusticifolia*, and *Aquilegia* sp., without infection. Recent monographic study of the

⁵ Bot. Gaz. 35: 20. 1903; and Jour. Myc, 14: 15. 1908.

⁶ Arthur, The Uredineae occurring upon *Phragmites*, *Spartina* and *Arundinaria* in America. Bot. Gaz. 34: 18. 1902.

grass rusts has shown the probability that this form, usually reported under the name *P. rubigo-vera*, is a part of the comprehensive species, *P. Agropyri*, with aecia on different Ranunculaceous hosts, forming well defined races.⁷

6. *UROMYCES SCIRPI* (Cast.) Burr., on *Scirpus fluviatilis* (Torr.) A. Gray, sent by Dr. J. F. Brenckle from Kalmbach Lake, Lamoure Co., N. Dak., was sown March 26 on *Sium cicutaefolium* and *Hydrocotyle australe*, and again May 19 on other plants of the same two species, without infection. The species apparently is made up of races, a study of which was the aim in this attempt at cultures.⁸

7. *UROMYCES ARCHERIANUS* Arth. & Fromme, on *Chloris elegans* H. B. K., collected Nov. 12, 1914, and again Feb. 7, 1915, by Mr. W. A. Archer, at Mesilla Park, N. Mex., was sown April 15, each collection on a different plant of *Chenopodium album*, with no infection. This new species of rust was discovered in abundance upon the campus of the New Mexico Agricultural College, with no distinctive aecia in the vicinity. Because of its morphological resemblance to *Uromyces Peckianus*, it was tried upon *Chenopodium*.

8. *AECIDIUM IRIDIS* Ger., on *Iris versicolor* L., from the Renwick Swamp, Ithaca, N. Y., was sent by Mr. J. L. Weimer in abundance and in excellent condition, and on July 1, the third day after collection, was sown on a large and especially thrifty plant of the same species of *Iris*, but gave no infection. A test of the spores showed that seventy-five to ninety per cent. were in germinating condition. Field observations have given little or no grounds for considering this rust autoecious, and the present trial further emphasizes this view. However, up to the present time no one has detected a probable alternate host.

SUCCESSFUL CULTURES SUPPLEMENTING PREVIOUS WORK.—The facts derived by growing the following species of rusts supplement in a variety of ways the facts obtained from previous cultures in this series from cultures recorded by other American

⁷ For previous attempts at cultures see Mycol. 2: 219. 1910.

⁸ For previous culture work see Jour. Myc. 13: 199. 1907; 14: 17. 1908; Mycol. 1: 237. 1909; and 7: 83. 1915.

or European investigators. The extension of aecial hosts for *Puccinia Seymouriana* to two families not closely related to the one previously known is especially important, and the behavior of rye rust upon *Anchusa* appears to have significance.

I. PUCCINIA EXTENSICOLA Plowr. (*P. Dulichii* Syd.).—A collection of this rust on *Dulichium arundinaceum*, made at DeMotte, in the Kankakee marshes of northern Indiana, by Mr. H. E. Ford and the writer on April 6, 1915, was sown April 19, on two plants of *Aster paniculatus*, one brought from the spot where the collection was made, and the prevailing plant at the place, and also on a plant of *Solidago canadensis*. Abundant pycnia began to show on the *Solidago* April 26, and aecia May 9, while the two *Aster* plants were unaffected. The result agrees with the facts obtained in 1914⁹ with similar material from Florida.

2. PUCCINIA GROSSULARIAE (Schum.) Lagerh.—Material collected by Mr. Roy Latham at Greenport, Long Island, N. Y., on *Carex tenuis*, was sown March 25 on *Ribes floridum* with no infection, and March 31 on *R. Cynosbati*, giving rise to pycnia April 13, and aecia May 4. The aeciospores thus produced were sown May 4 on *Carex pubescens*, with no infection. Another collection made by C. H. Kauffman and E. B. Mains at Lake Placid, N. Y., on *Carex arctata*, was sown March 15, on *Ribes Cynosbati*, giving a few pycnia March 26, but failing to develop further on account of injury to host. The same material was sown again March 26 on another plant of the same sort, giving pycnia April 2, and aecia April 26, the growth being slow. Both the original telial collections gave many urediniospores, all of which appeared to have but one basal pore, and they may be considered pure representatives of *Puccinia uniporula* Orton. The aecia were not distinguishable from those grown in previous years from material showing equatorially three-pored urediniospores. It was hoped that aecia so grown might be carried back to the telial host, and the character of the resulting urediniospores ascertained, but although an attempt was made, it failed.

A collection of aecia on *Ribes longiflorum* sent from Denver, Colo., by Mr. E. Bethel, was sown June 4, two days after collec-

⁹ Mycol. 7: 81. 1915.

tion, upon *Carex durifolia*, a species from which the aecia were supposed to have been derived, and also upon *C. Jamesii*, with no infection.¹⁰

3. PUCCINIA ERIOPHORI Thüm.—Observations by Dr. H. D. House of the New York State Museum, made near Oneida, N. Y., in June of this year, led to the recognition of this species of rust in America and the discovery of the alternate stage. On June 27 Dr. House wrote that "of thousands of plants of *Senecio* in the marsh practically every one is affected by the *Aecidium*." He found that of the numerous marsh plants the one having a corresponding abundance of rust on the dead leaves from the preceding year was *Eriophorum viridi-carinatum*. At the same time he sent growing plants of both the *Senecio* and *Eriophorum*, the former with leaves well spotted with aecia. All the plants continued to flourish.

On June 30 a sowing of aeciospores from *Senecio aureus* was made on the young leaves of *Eriophorum viridi-carinatum*. After twenty-four hours a test of the spores remaining on the leaves of the *Eriophorum* showed that from twenty to forty per cent. of them were germinating. Daily observation of the plant was not made, but on July 15 both uredinia and telia were found to be present. The rust on American species of *Eriophorum* is morphologically very similar to *Puccinia angustata* Peck on various species of *Scirpus*, and usually has been listed under that name. As *P. angustata* has its alternate stage on the labiate, *Lycopus*, the same had been supposed to be true of the rust on *Eriophorum*, and thus to differ from the similar rust in Europe.

Tranzschel¹¹ has reported the infection in 1907 of *Ligularia sibirica* (*Senecio cacaliaefolius*) and *Senecio paluster* (*Cineraria palustris*) from teliospores on *Eriophorum angustifolium*, and has listed the European stations for the rust, showing that it is quite rare. In America it has been taken on *Eriophorum angustifolium* Roth, at Decorah, Iowa, June 29, 1884, E. W. D. Holway, Kennedy, Neb., July 20, 1892, J. M. Bates, Newfane, Vt., Oct. 16,

¹⁰ For previous cultures see Jour. Mycol. 12: 58. 1905; 12: 14. 1906; 13: 196. 1907; 14: 13. 1908; Mycol. 4: 13. 1912; and 7: 66, 78. 1915.

¹¹ Beiträge zur Biologie der Uredineen, III.

1892, *A. J. Grout*; on *E. polystachyon* L., Mt. Hood, Ore., at 5,000 feet altitude, July 23, 1915, *H. S. Jackson*; on *E. tenellum* Nutt., at Isle au Haute, Me., Sept. 11, 1899, *J. C. Arthur*; on *E. virginicum* L., at Avilla, Ind., August, 1884, *W. B. VanGorder*, Granville, Mass., August 1889, *A. B. Seymour* (Seym. & Earle, Econ. Fungi 54), Isle au Haute, Me., Sept. 6, 1899, *J. C. Arthur*, Central Village, Conn., Aug. 20, 1900, *John L. Sheldon*, Jackson, Ind., July 28, 1905, *C. C. Deam*, Elm Lake, Wis., Sept. 12, 1907, *C. L. Shear*, Winona Lake, Ind., Aug. 26, 1914, *G. N. Hoffer*; on *E. viridi-carinatum* (Engelm.) Fernald, at Avilla, Ind., August, 1884, *W. B. VanGorder*, Oneida, N. Y., June 27, 1915, *H. D. House*; on *Senecio aureus* L., at Buffalo, N. Y., without date, *G. W. Clinton*, Decorah, Iowa, June, 1883, *E. W. D. Holway*, Ann Arbor, Mich., June 8, 1898, *C. H. Kauffman*, Mt. Chocorua, N. H., July 3, 1906, *W. G. Farlow*, Radisson, Wis., July 6, 1906, *J. J. Davis*, Merrimac, Wis., June 19, 1912, *Davis & Arthur*, Oneida, N. Y., June 27, 1915, *H. D. House*; on *S. ductoris* Piper, Mt. Hood, Ore., at 5,000 feet altitude, July 23, 1915, *H. S. Jackson*. It is evident that the rust is widespread in America, especially northward, but not particularly abundant, and the aecia have been collected over nearly the same territory as have the telia.

The morphological differences between *P. angustata* and *P. Eriophori* are very considerable in the aecia, and while less marked in the uredinia and telia are yet noticeable. The urediniospores of *P. Eriophori* are more globoid, while the teliospores are somewhat shorter ($35\text{--}60\mu$ long, against $42\text{--}67\mu$ in *P. angustata*) and the apex thinner ($4\text{--}10\mu$, against $7\text{--}16\mu$ in the other) with more tendency to acuteness.

4. PUCCINIA AGROPYRI E. & EV. (*P. alternans* Arth.)—A collection on *Festuca Thurberi* Vasey, sent from Lake Eldora, Colo., by Mr. E. Bethel, was sown May 13, on *Anemone cylindrica*, *Aquilegia canadensis*, *Clematis ligusticifolia*, and *Thalictrum dioicum*. Infection was obtained on the last named host only, which began to show pycnia May 23, and aecia May 30. In sending this material Mr. Bethel wrote that he thought it had been derived in the field from aecia on *Thalictrum Fendleri*, which the culture confirms as highly probable. The first collection of this

kind sent the writer by Mr. Bethel was dated Sept. 17, 1910, and was intended for cultures on *Thalictrum*. This could not be made to germinate when time for culture work arrived, nor could a half dozen other collections sent subsequently at various dates. With a specimen dated April 5, 1912, Mr. Bethel states that he has "proven by most positive field cultures" that it goes to *Thalictrum Fendleri*. Again in May, 1915, Mr. Bethel sent fine material from his garden, showing the telia that had been brought there and the aecia on *Thalictrum* derived therefrom. The reasons for listing the *Thalictrum* form under *P. Agropyri* were stated in the last report.¹² The aecia are especially large and prominent in this particular race on *Festuca*, as shown by a number of collections sent from the same locality.

5. PUCCINIA ASPERIFOLII (Pers.) Wettst.—Two plants of *Anchusa officinalis* L. were given ample space in the experimental garden of the Indiana Experiment Station and attained a fine development, each plant measuring five or six feet across. On July 2, the weather being especially damp with occasional light showers, stems of rye, heavily infested with rust, were laid upon the two plants in the garden, doubtless a hundred or more stems to each plant. The plants were not covered in any manner. The date of the appearance of the first pycnia was not recorded, but on July 13, the plants were conspicuously dotted with yellow spots bearing groups of pycnia. About a week later careful search brought to light two groups of aecia. Although the vigor of the plants and the condition of the weather seemed favorable, and the great numbers of yellow spots with their groups of pycnia continued to show, yet no further development of the rust took place.¹³

The reason why the infection should have started out with such marked vigor and yet failed to mature aecia is not at all apparent. The weather for the whole period was favorable for aecial growth. It is possible, and yet scarcely probable, that the explanation lies in the lessened vigor for the American rye rust, which is propagated by repeating spores alone, the aecial hosts being practically wanting in America.

¹² Mycol. 7: 74. 1915.

¹³ For a previous culture of similar character see Mycol. 1: 236. 1909.

6. PUCCINIA SEYMOURIANA Arth. (*Aecidium obesum* Arth.).— This rust on *Spartina* at the time it was described in 1902 was predicted upon morphological and geographical grounds to have its alternate form upon the Rubiaceous genus *Cephalanthus*,¹⁴ the prediction being established by cultures in 1905, and confirmed in subsequent seasons.¹⁵ It was not until June, 1913, that additional suggestions came to light, when Rev. J. M. Bates wrote that his observations in the field led him to believe that in Nebraska this rust on *Spartina* was connected with an *Aecidium* on *Apocynum hypericifolium*. He sent a specimen of the aecia, which proved to be *Aecidium obesum* Arth. This collection was distributed as 4103 of Barth. Fungi Columbiani, and 1301 of Barth. N. Amer. Ured. Later in the year a careful microscopic comparison of these aecia with those on *Cephalanthus* established their essential similarity. Owing to adverse seasonal conditions Mr. Bates was unable to supply culture material for the 1914 cultures, but on May 8, 1915, he sent telial material on *Spartina Michauxiana* from Eight Mile Creek, near Red Cloud, Neb. It was sown May 12, on *Apocynum cannabinum*, *Amsonia salicifolia*, *Asclepias syriaca*, and *Cephalanthus occidentalis*, producing a scanty infection only on *Apocynum*, pycnia showing June 10, but without developing aecia.

A specimen of aecia on *Asclepias pulchra*, collected by Mr. Roy Latham, of Orient, N. Y., June 29, 1914, was reported to the collector upon cursory examination only, as aecia of *Puccinia Jamesiana*, that being the only species at that time known to have aecia with a limited mycelium on *Asclepias*, and it was suggested that he search for telial material on *Bouteloua*. Not long afterward he wrote that *Bouteloua* was not known upon Long Island, and that among the infected milkweeds, which occur on "a patch about 100 feet in length by 25 in width, many plants being actually covered from ground up, stem, leaves, and all," the only grass or sedge bearing rust was *Spartina cynosuroides*, of which he sent leaves covered thickly with telia remaining over from the preceding year, and young leaves of the season with uredinia. The *Spartina* rust

¹⁴ Bot. Gaz. 34: 13. 1902.

¹⁵ Jour. Myc. 12: 24. 1906; Mycol. 1: 236. 1909; 4: 19. 1910.

proved to be *P. Seymouriana*, and the aecia on *Asclepias* resembled those belonging to that species. Mr. Latham kindly sent viable material for cultures, collected at the same spot June 2, 1915, which was sown June 10 on plants of the four hosts used in the previous culture. Only *Asclepias syriaca* became infected, showing an abundance of pycnia June 17 and great numbers of aecia June 23.

It may fairly be concluded that this species of rust is one composed of well-marked races in accordance with the aecial hosts. Besides the three races here indicated, another doubtless occurs in connection with *Amsonia*, the characteristic aecia having been found on this host from Missouri.

7. PUCCINIA SUBNITENS Diet.—A collection of this rust on *Distichlis spicata*, very common in alkaline regions, was sent by Prof. H. S. Jackson from LaGrand, Ore., and sown April 15, on *Chenopodium album*. Pycnia began to show April 25, and aecia May 8, chiefly on the petioles of the leaves.¹⁶ Telial material has now been cultured from the states of Nebraska, Colorado, Delaware, Nevada, and Oregon, extending from the Atlantic to the Pacific coasts.

8. PUCCINIA WINDSORIAE Schw.—Much attention has been given to finding the telial host for the aecia on *Dirca palustris*, beginning with the illusory success of 1903 and continuing to the present time.¹⁷ Many telial collections have been used, secured from widely separated localities, and representing many species of rusts. During the last year a search through the herbarium for aecia on other hosts, having similar microscopic characters, led to the possibility that it might be a racial part of the common *Puccinia Windsoriae*. To test this hypothesis telial material was secured near Lafayette, on *Tridens flavus*, from the vicinity of *Dirca* bushes, annually showing the lemon-yellow spots carrying the aecia. Sowings were made May 3, on *Dirca palustris*, May

¹⁶ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; 14: 15. 1908; Mycol. 1: 234. 1909; 2: 225. 1910; and 4: 18, 54. 1912.

¹⁷ For previous attempts see Jour. Myc. 10: 19. 1904; 11: 56. 1905; 13: 191, 192, 196. 1907; 14: 12. 1908. Mycol. 1: 231. 1909; 2: 219, 227. 1910; 4: 9, 10, 11, 12. 1912; 7: 64, 65. 1914.

22, on *Dirca* and *Ptelea trifoliata*, May 24, on *Ptelea*. Only on *Ptelea* was infection secured, abundant pycnia showing from both sowings June 2, and aecia June 7.¹⁸

SUCCESSFUL CULTURES REPORTED NOW FOR THE FIRST TIME.—The following species have never before been cultivated in America or elsewhere, so far as the writer knows.

1. PUCCINIA TUMIDIPES Peck.—Excellent telial material of this species on *Lycium pallidum*, was sent by Mr. W. A. Archer, collected in the Organ Mountains, N. Mex., on Oct. 9, 1914. As it was found the teliospores would germinate, it was sown Dec. 1, 1914, on plants of *Lycium vulgare*, giving a few pycnia only by Dec. 18, with no further development, possibly owing to the poor condition of the host plant. It was sown again on another plant of the same sort Dec. 12, 1914, giving rise to a few groups of pycnia by Dec. 21, and a single uredineal sorus Jan. 16, 1915.

Although the growth of the fungus was not vigorous, and did not continue to the final stage, yet it seems safe to conclude that the rust is autoecious, and without cupulate aecia. It clearly belongs in the genus *Bullaria*, where it becomes *B. tumidipes* (Peck) comb. nov.

2. PUCCINIA DISTICHLIDIS Ellis & Ev.—This rust in the first place was sent to Mr. Ellis in 1891 by F. D. Kelsey of Helena, Mont., and labeled as on "*Distichlis maritima*," but afterward was shown by the writer¹⁹ to be on *Spartina gracilis*. On account of this erroneous determination of the host plant, the rust was renamed *P. Kelseyi* by Sydow.²⁰ In a study of "Correlation between certain species of Puccinia and Uromyces" Orton²¹ came to the conclusion from a comparison of the morphological characters and geographical distribution of *Uromyces Spartinae* and the rust in hand, that it was "extremely probable that its aecial host is some member of the primrose family, perhaps *Steironema*," this being one of the aecial hosts for the *Uromyces*. It has been

¹⁸ For previous successful cultures see Bot. Gaz. 29: 273. 1900; 35: 16. 1903; Jour. Myc. 11: 56. 1905.

¹⁹ Bull. Lab. Nat. Hist. Univ. Iowa 5: 324. 1902.

²⁰ Sydow, Monog. Ured. 1: 806. 1904.

²¹ Mycol. 4: 202. 1912.

difficult to locate this rust in localities from which culture material could be secured. Dr. Brenckle sent material from Kulm, N. Dak., from which cultures were attempted in 1909 and 1910²² upon a score of different hosts, but not including *Steironema*. Again material on *S. Michauxiana* was obtained from Dr. Brenckle, collected April 8, 1915, at Kulm, N. Dak., and also from Rev. J. M. Bates, collected April 20, 1915, at Loup City, Neb.

The North Dakota material was sown May 8, on *Steironema ciliatum*, and pycnia began to show May 16, followed by an abundance of aecia May 22. The Nebraska material was sown May 8, on *Steironema ciliatum* and *Polemonium reptans*. The *Polemonium* plant remained uninfected, but many pycnia began to show on the *Steironema* May 14, followed by a great abundance of aecia May 20. Although these cultures were exceedingly vigorous and in so far seemed beyond question, yet there exists a possible small source of error. The correlated *Uromyces* is a common rust, and occasionally grows upon the same leaves with the *Puccinia*. In the Nebraska material no admixture could be found, but there were sori of *Uromyces* on the North Dakota material. Care was exercised, however, to avoid all sori with one-celled spores in making the cultures, and as the two forms were mostly on separate leaves, there is little reason to doubt that the cultures were pure. Correctness of the general conclusion was obtained from a wholly independent source, however, when Dr. Brenckle sent a collection of aecia on *Steironema ciliatum*, made by Prof. O. A. Stevens near Fargo, N. Dak., May 23, 1915. On June 5 Dr. Brenckle accompanied Prof. Stevens to the spot where the collection was made, to institute a search for *Spartina*, as Prof. Stevens had reported that the grass did not grow within miles of the place. Dr. Brenckle writes, June 16, that he "found a small isolated bunch of *Spartina* in the midst of the infected spot; the rust on the *Spartina* was *Puccinia*!" The collection of aecia has been issued as *Fungi Dakotenses* 316, under the name of *Puccinia Distichlidis*. This is the only field collection of aecia positively known to belong to the *Puccinia* form.

3. PUCCINIA MONTANENSIS Ellis.—There has been much con-

²² Mycol. 2: 219. 1910; 4: 11. 1912.

fusion in the application of this name. Not until within the present year has it been possible to secure a clearly defined set of characters with which to delimit the species, especially to distinguish it from *Puccinia Agropyri* E. & E., with which it often grows, and which it resembles in gross appearance. It is now found to be separable from *P. Agropyri*, by the slightly thinner-walled urediniospores, having more pores (8 to 10, instead of 6 to 8 in *P. Agropyri*), sometimes accompanied by paraphyses, but more especially by the far broader teliospores (18 to 34μ wide, against $13\text{--}24\mu$ in the other species), which generally approximate an oblong form with convex sides, in contrast with terete spores usually with straight sides in *P. Agropyri*.

The rust in question has often been labeled *P. apocrypta* E. & T. The type of *P. apocrypta* was collected at Canon City, Colo., August 21, 1887, and was recorded as on *Asprella Hystrix*. The type collection is now in the herbarium of the Missouri Botanical Garden, and has been carefully examined by a number of students of the grasses. The specimen is scanty, and consists of leaves only. It can not be the species of grass named, which does not occur within the region. It seems most likely to be some species of *Sitanion* possibly *S. elymoides*, a common species of the region much resembling *Hystrix*. The rust is certainly *P. Agropyri*, although the teliospores are rather broader than usual. The type material of *P. montanensis*, which is in the herbarium of the New York Botanical Garden, has been examined and bears out the published statement that it is on *Elymus condensatus*. It was collected at Helena, Mont., July 25, 1891, by F. D. Kelsey.

The fortunate observation which led to the elucidation of this species was made by Mr. A. O. Garrett, of Salt Lake City, Utah, who wrote on May 23, 1915: "I am sending by this mail some leaves of *Hydrophyllum* [*capitatum*] heavily infected with *Aecidium Hydrophylli*. I think this rust has the alternate stage on *Agropyron*. I always find the *Agropyron* plant plentiful, and it is affected by the rust, wherever the *Hydrophyllums* grow." The aecia on *Hydrophyllum* sent by Mr. Garrett came in good condition, and were sown May 28, on *Agropyron tenerum* and *Elymus virginicus*. Uredinia began to show in abundance June 7, on the

Agropyron, followed by telia June 11. On the *Elymus* only a few uredinia developed, not observed until June 23. A study of the uredinia and telia on the *Agropyron* disclosed the characters of *Puccinia montanensis*. Field observations by Dr. Brenckle of North Dakota, Mr. Garrett of Utah, and Mr. Bethel of Colorado, independently reported, associated aecia on *Lithospermum*, *Onosmodium*, and *Phacelia*, with *Agropyron* and *Elymus* rust, but material sent to establish the connection by cultures failed to yield results. Subsequent herbarium studies leave little chance for doubt that *Puccinia Agropyri* has its alternate form on Ranunculaceous hosts, while *P. montanensis* has its alternate form on Hydrophyllaceous and Borraginaceous hosts.

Two former attempts at culture of *P. montanensis*²³ are shown by a reexamination of the original material to have been made by using *P. Agropyri*, and not *P. montanensis*, as published.

4. UROMYCES HORDEI Tracy.—Telial material on *Hordeum pusillum* Nutt., sent by F. McAllister and B. C. Tharp from Austin, Texas, was sown March 15, on *Nothoscordium striatum* and *Ornithogalum umbellatum*, and again March 30 on the latter host, with infection only on the *Nothoscordium*, showing pycnia March 30, and aecia April 6, both strongly developed.

When the report of culture experiments for the years 1911 to 1913 by W. Tranzschel²⁴ came to hand, the account of the successful growth of barley rust on *Ornithogalum umbellatum* suggested the renewal of a study of the correlated American species of *Uromyces*, *U. Hordei* Tracy. There is no morphological difference between the uredinia and telia of the latter species and those of *Puccinia anomala* Rostr. (*P. simplex* Eriks. & Henn.), except that part, rarely all, of the teliospores of the *Puccinia* are two-celled. *Ornithogalum umbellatum* is the Star-of-Bethlehem of the florists, and has escaped from gardens and become a weed in the southern states as far northward as the Ohio river. Aecia on it have not been reported for America, but they are known on a near relative, *Nothoscordium bivalve* (L.) Britton (*Ornithogalum bivalve* L.), from Texas. An appeal to Dr. McAl-

²³ Jour. Myc. 14: 11. 1908; and Mycol. 1: 11. 1912.

²⁴ Mycol. Centr. 4: 70. 1914.

lister and Mr. Tharp, of the University of Texas, made in November, 1914, soon placed in my possession resting telia on *Hordeum pusillum* and dormant bulbs of the *Nothoscordium*, which were made to yield the above results.

In the meantime it was remembered that Mr. W. H. Long had reported this connection several years before. In a letter dated Feb. 28, 1904, he says: "I have successfully grown *Uromyces Hordei* urediniospores from sowings of aeciospores that I find on *Nothoscordium striatum* [*N. bivalve*]." Again on March 24, 1910, Mr. Long wrote: "Since writing you last I have cross-inoculated teliospores on *Nothoscordium striatum*, and aeciospores from it upon *Hordeum nodosum* [error for *H. pusillum*], and got successful cultures in both instances." Mr. Long kindly sent material to illustrate his work and also material with which to verify his conclusions. Unfortunately it was not possible to bring about conditions for the cultures, and as Mr. Long's work was done in the open, and not verified by others, the results were omitted from the North American Flora when this species was reached.²⁵

In this connection it may be well to say that the statement in the North American Flora that the species occurs in California on *Hordeum nodosum* is erroneous. The species ranges from Nebraska to Mississippi and Texas, which also includes the range of the aecial host, although the aecia have only been taken in Texas.

SUMMARY

The following is a complete list of the successful cultures made during the year 1915. It is divided into two series, species that have previously been grown in cultures and reported by the writer or other investigators, and species whose culture is now reported for the first time.

A. SPECIES PREVIOUSLY REPORTED

1. PUCCINIA EXTENSICOLA Plowr. (*P. Dulichii* Syd.).—Teliospores from *Dulichium arundinaceum* (L.) Britt., sown on *Solidago canadensis* L.

²⁵ N. Amer. Flora 7: 228. 1912.

2. PUCCINIA GROSSULARIAE (Schum.) Lagerh. (*P. uniporula* Orton).—Teliospores from *Carex tenuis* Rudge, and from *C. arctata* Boott, sown on *Ribes Cynosbati* L.

3. PUCCINIA ERIOPHORI Thüm.—Aeciospores from *Senecio aureus* L., sown on *Eriophorum viridi-carinatum* (Engelm.) Fernald.

4. PUCCINIA AGROPYRI Ellis & Ev. (*P. alternans* Arth.).—Teliospores from *Festuca Thurberi* Vasey, sown on *Thalictrum dioicum* L.

5. PUCCINIA ASPERIFOLII (Pers.) Wettst.—Teliospores from *Secale cereale* L., sown on *Anchusa officinalis* L.

6. PUCCINIA SEYMOURIANA Arth. (*Aecidium obesum* Arth.).—Teliospores from *Spartina Michauxiana* Hitchc., sown on *Apocynum cannabinum* L., and from *Spartina cynosuroides* (L.) Roth, sown on *Asclepias syriaca* L.

7. PUCCINIA SUBNITENS Diet.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Chenopodium album* L.

8. PUCCINIA WINDSORIAE Schw.—Teliospores from *Tridens flavus* (L.) Hitchc. (*Tricuspis seslerioides* Torr.), sown on *Ptelea trifoliata* L.

B. SPECIES REPORTED NOW FOR THE FIRST TIME


1. PUCCINIA TUMIDIPIES Peck.—Teliospores from *Lycium pallidum* Miers, sown on *L. vulgare* Dunal, producing pycnia and uredinia.

2. PUCCINIA DISTICHLIDIS Ellis & Ev.—Teliospores from *Spartina Michauxiana* Hitchc., sown on *Steironema ciliatum* (L.) Raf.

3. PUCCINIA MONTANENSIS Ellis (*Aecidium Hydrophylli* Peck).—Aeciospores from *Hydrophyllum capitatum* Dougl., sown on *Agropyron tenerum* Vasey and *Elymus virginicus* L.

4. UROMYCES HORDEI Tracy.—Teliospores from *Hordeum pusillum* Nutt., sown on *Nothoscordium bivalve* (L.) Britton.

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.



(15)

265

CULTURES OF UREDINEAE IN 1916 AND 1917

CULTURES OF UREDINEAE IN 1916 AND 1917¹

J. C. ARTHUR

The present article is the fifteenth in a series of reports² by the writer upon the culture of plant rusts, beginning in 1899 and completing nineteen consecutive years. The preparation of the index and summary to the series, as stated in the report for last year, has been delayed, but together with a general retrospect is expected to appear in a succeeding number of this journal. After this, if work of the present character is continued, it will be reported in some other form.

FIELD OBSERVATIONS IN 1916

The writer, by the courtesy of the botanical department of the Indiana Agricultural Experiment Station now under the direction of Professor H. S. Jackson, was enabled to make important observations in the field during 1916, which have proved of the utmost value, not only in detecting the alternate form of certain heteroecious species, but in securing a more adequate conception of the different aspects and range of hosts of particular species when occurring under unlike conditions or in the midst of plant societies composed of different elements.

The first trip of the year was to State College, Pa., in the last days of April, where Dr. F. D. Kern and his associates in the botanical department of the Pennsylvania State College gave every facility for a week's field work. Two excursions in the vicinity are especially worthy of mention, both taken under the personal direction of Professor C. R. Orton. An over-mountain road took us to Charter Oak, where the locality for the amphi-

¹ Presented in part before the Botanical Society of America at the New York meeting, December 29, 1916.

² See Bot. Gaz. 29: 268-276; 35: 10-23; Jour. Myc. 8: 51-56; 10: 8-21; 11: 50-67; 12: 11-27; 13: 189-205; 14: 7-26; Mycol. 1: 225-256; 2: 213-240; 4: 7-33, 49-65; 7: 61-89; and 8: 125-141.

sporic *Carex* rust, *Puccinia microsora* Körn., was searched for clues to the alternate host without much success. A twelve-mile ride in another direction to Bear Meadow, an extensive mountain bog, gave opportunity to study the occurrence of *P. uniporula*, and some other difficult *Carex* forms.

On May 13 a western trip of a little over three weeks was begun. The first stop was a few days given to the study of the rust flora of the semi-arid plains between Grant and Ogallala in western Nebraska, where the second telial host for *Puccinia universalis* to be proven by cultures was found.

Next came a few days (May 18-22) at Laramie, Wyo., altitude of 7,500 feet, where the season was not sufficiently advanced for the best field work, but where through the courtesy of Professor Aven Nelson and the assistance of Mr. Edwin Payson an examination of the extensive and valuable Rocky Mountain Herbarium yielded many new hosts and localities for numerous western rusts.

Interesting observations were made (May 23-24) in the vicinity of Ft. Collins, Colo., where every attention was extended by members of the biological staff of the Agricultural College. Professor W. W. Robbins undertook to continue the observation of a number of clumps of *Astragalus* and *Oxytropis* as the season advanced. These plants were growing with masses of aecia-bearing *Euphorbia robusta* intermixed. On October 24 Professor Robbins reported that no rust had appeared on any of the plants of *Astragalus* or *Oxytropis* under observation. From European studies it has seemed probable that the perennial aecia on upright *Euphorbias* and the *Uromyces punctatus* on *Astragalus* and allied hosts, both especially abundant in the Rocky Mountains, were alternating forms of the same rust, but so far neither repeated attempts at cultures nor field evidence have afforded any support to the assumption.

At Windsor, Colo., as the guest of Mr. Geo. E. Osterhout (May 25), a fine display of over-wintered *Puccinia Distichlidis* on *Spartina* was seen in the field with an abundant growth of *Stieronema ciliatum* nearby. Telial material from this locality subsequently gave successful cultures, and on June 12 Mr. Osterhout sent aecia on *Stieronema*, which he obtained from the spot

visited. This is the second culture and the second aecial field collection so far secured.

At Denver the writer was joined by Professor H. S. Jackson. While here (May 26-31) we were under the guidance of Mr. Ellsworth Bethel, whose extensive knowledge of the flora of Colorado and especially his very intimate familiarity with the rust flora of the foot hills and plains about Denver, together with his highly enthusiastic and generous disposition, made the days memorable for the number and important character of the observations. Beside excursions immediately about Denver longer trips were taken through the Municipal Mountain Parks, to Pueblo, and to Boulder, all but the last by automobile with observations along the way. The rust flora of this region is the richest and most varied known to the writer, and the visit resulted in a large increase in knowledge regarding new forms and combinations. The identity of *Puccinia Schedonnardi* with *P. Muhlenbergiae*, the status of *Aecidium Abroniae*, *Aecidium Liatridis* and the aecia on *Polygonum aviculare*, heretofore erroneously associated with *Uromyces Polygoni*, were established, and much else accomplished. A visit to Mr. Bethel's garden, in which he carries out large numbers of open-air cultures, was most instructive as well as indicative of the highly valuable character of his studies.

The final stop (June 1-2) of the journey was at Manhattan, Kans., where over thirty years ago Professor W. A. Kellerman brought to light a number of forms still imperfectly known. By the aid of Mr. L. E. Melchers and other members of the Agricultural College a fruitful reconnaissance of the vicinity was made, resulting especially in detection of the alternate form for the *Aecidium* on *Allium*, which had tentatively been assigned by different observers to no less than four very unlike telial forms.

Such excursions for observation as those just mentioned have been of inestimable value in securing knowledge for the successful prosecution of the culture work. Without numerous cultures the marvelous advance of recent years in the taxonomic study of American rusts would have been largely impossible. Moreover, without the most varied cultures brought about by observations in widely separated parts of the country the intricate

relationships, transcending all deductions derivable from morphological study alone, must have remained unrecognized, or in so far as dimly apprehended be wholly without demonstration.

A number of correspondents assisted in securing needed material for the season's work, and to them thanks are due. There were available 170 collections with resting spores, and 9 with active spores as in *Aecidium* and *Gymnosporangium*. Some 452 tests were made in a hanging drop to determine the germinating condition of the spores. Only 69 collections of resting teliospores could be brought to germination from which 182 sowings were made, and 17 infections secured. From the 9 collections of fresh spores 12 sowings were made, and 3 infections secured. The work was largely performed by Mr. C. C. Rees, a member of the regular staff of the laboratory.

NEGATIVE RESULTS IN 1916.—Of the various attempted cultures which failed to produce inoculations two are worthy of record.

1. UROMYCES GRAMINICOLA Burr. on *Panicum virgatum* L., sent by Mr. E. Bartholomew from Stockton, Kans., was sown April 25 on *Euphorbia corollata*, and again May 25 on the same host, in both instances with no apparent result. In previous seasons the same species was sown on a number of other hosts,³ but in the meantime from morphological and distributional data the conclusion had been reached that this form is probably correlated with *Puccinia Pammelii* on the same host, whose aecia are known to be on *Euphorbia corollata*. Other attempts at cultures should be made before abandoning the assumption.

2. PUCCINIA on *Carex Backii* Boott (*C. durifolia* Bailey) obtained by Mr. E. Bethel in February from near Denver, Colo., was sown April 7 on *Ribes Cynosbati*, *Boltonia asteroides* and *Urtica gracilis*, and again May 15 on the same hosts and on *Eleagnus argentea* and *Artemisia dracunculoides*. The same form obtained by Mr. Bethel in March from Boulder, Colo., was sown April 7, on *R. Cynosbati*, *B. asteroides*, and *U. gracilis*, and April 15, on *R. Cynosbati*, *U. gracilis*, and *E. argentea*.

³ See Jour. Myc. 12: 13. 1906; Mycol. 1: 232. 1909; 2: 220. 1910; 4: 12. 1912.

Another collection sent from Valentine, Neb., by Rev. J. M. Bates, was sown May 26, on *R. Cynosbati*, *B. asteroides*, *U. gracilis* and *E. argentea*. All the sowings were without effect. All three collections gave fairly strong germination of the teliospores at the date of sowing.

Cultures have been attempted once before⁴ on five hosts, all but one different from the above. The morphological characters of this form approximate those of *Puccinia Grossulariae* on various species of *Carex*, but nothing has yet been proven by cultures.

SUCCESSFUL CULTURES IN 1916 SUPPLEMENTING PREVIOUS WORK.—The culture of the following seven species adds valuable information in each case to the facts previously recorded.

1. *PUCCINIA UNIVERSALIS* Arth.—Material on *Carex filifolia*, collected by the writer May 18, 1916, at Ogallala, Neb., was sown June 2, on *Artemisia gnaphalodes*. Pycnia were detected June 15, but doubtless appeared earlier, being obscured by the heavy tomentum of the plant, and were followed by a large number of aecia, first seen June 28. This rust has been cultivated a number of times before⁵ on various species of *Artemisia*, but only with telial material from *Carex stenophylla*. *Carex filifolia*, like *C. stenophylla*, occurs on semi-arid plains. It usually grows only three or four inches high, and in dense mats. It is locally known as "nigger-wool" or "black-root," from the tough, tangled mass of fine, black roots, resisting decay for a year or two when turned up by the plow and exposed to weathering.

2. *PUCCINIA POCULIFORMIS* (Jacq.) Wettst.—This very common stem rust of grasses and grains was grown on *Berberis vulgaris* from two collections made by Mr. G. E. Osterhout, Windsor, Colo., on March 2, one from *Sporobolus cryptandrus*, sown April 23, showing pycnia May 6, but not developing aecia, and the other from *Elymus canadensis*, sown May 15, showing pycnia May 25 and aecia June 6. Another collection on *Agropyron Smithii* made by Mr. E. Bethel, in Denver, Colo., March

⁴ Mycol. 2: 248. 1910.

⁵ For previous cultures see Jour. Myc. 14: 21. 1908; Mycol. 2: 224. 1910; and 4: 16. 1912.

6, was sown on *Berberis vulgaris* on April 23, and began to show pycnia April 30, and aecia May 4.⁶

3. PUCCINIA RHAMNI (Pers.) Wettst.—A collection made by Mr. G. B. Posey in December, 1915, at Corvallis, Oregon, on *Agrostis* sp., was sown May 11, on *Rhamnus Purshiana*, and showed pycnia in fair numbers May 20, but made no further development, although the leaves remained healthy and in good growing condition for a considerable time.

4. PUCCINIA DISTICHLIDIS Ellis & Ev.—This rust was found May 24 by Mr. Geo. E. Osterhout and the writer in great abundance on over-wintered *Spartina Michauxiana* in a field at Windsor, Colo., and entirely unmixed with any other rust known to occur on the same host. The spores had not yet germinated. Large groups of *Steironema ciliatum* nearby, the supposed alternate host, were already six or eight inches high and free from infection. The teliospores were sown on *S. ciliatum* in the greenhouse at Lafayette on May 30, and gave a heavy infection, showing pycnia June 4, and numerous aecia June 10. This result confirms the work of 1915⁷ and establishes the life cycle of the species beyond doubt. On June 12 Mr. Osterhout sent a fine collection of aecia on *S. ciliatum* from the place where the cultural material had been obtained, being the second field collection for the species, the previous one being made in North Dakota.

5. PUCCINIA MUHLENBERGIAE Arth. & Holw. (*P. Schedonnardi* K. & S.).—Telial material of this rust was found May 28 by Professor H. S. Jackson and Mr. E. Bethel, on *Muhlenbergia gracillima*, a low, tufted and fine leaved species growing on the arid plains near Pueblo, Colo., associated with *Malvastrum coccineum*, suspected of being an alternate host. A sowing was made on *M. coccineum* June 2, which gave pycnia June 18, and aecia June 25, both in strong development.

Telial material of *Puccinia Schedonnardi*, on *Schedonnardus paniculatus* was obtained by Mr. Bethel, Professor Jackson and the writer at Pueblo, Colo. After the preceding trial showed signs of success, a striking resemblance was noticed between the

⁶ For previous cultures see Jour. Myc. 8: 53. 1902; 11: 57. 1905; 12: 17. 1906; 13: 198. 1907; 14: 16. 1908; Mycol. 2: 227. 1910; and 4: 18. 1912.

⁷ See Mycol. 8: 136. 1916.

two grasses in size and habit of growth and also between the gross appearance of the rusts they bore. The resemblance was furthermore found to extend to the microscopic features of the rusts. This led to sowing the teliospores upon *M. coccineum*, which was done June 23, and resulted in production of pycnia June 30, and aecia July 11. Although not so strong development as in the preceding case the gross and microscopic appearances were the same, and left no doubt that *P. Schedonnardi* is to be considered synonymous with *P. Muhlenbergiae*, a species of many races and hosts.⁸ The middle of September subsequent to these cultures a letter was received from Mr. E. Bartholomew, of Stockton, Kans., in which he gives the following account of observations, most strongly confirming the conclusion reached from cultures. He says: "Standing in the doorway of the Mt. Nebo Presbyterian Church, three and one half miles south of our home, on June 11, 1916, I noticed, very close to the building, a large number of plants of *Malvastrum coccineum* profusely attacked by *Accidium malvicola* Arth., and on examining the grasses growing among the *Malvastrum* there was found teleuto-material on dead *Schedonnardus*, and on the developing young leaves and sheaths abundant uredo of *Puccinia Schedonnardi*! Continued examinations for several weeks, as the *Puccinia* developed into the III, led me to conclude beyond a peradventure that the aecium is no more nor less than I of this fungus as the grass was infected only in the near reach (not to exceed one rod) of the *Malvastrum*. While I have collected this *Puccinia* several times in the past ten years I have not come across *Accidium malvicola* since May, 1904 (F. Col. No. 1905)."

6. PUCCINIA SUBNITENS Diet.—This rust is probably the most remarkable known for the number and diversity of its aecial hosts. The present addition of two families to the aecial hosts as previously recorded is entirely the result of information supplied by Mr. E. Bethel, who had made repeated observations of propinquity in the field, and verified his assumptions of relationship by cultural tests in his garden in Denver.

Telial material on *Distichlis spicata* obtained by Professor H.

⁸ For previous cultures see Jour. Myc. 11: 51. 1905; 13: 192. 1907; Mycol. 1: 251. 1909; 2: 226. 1910; 4: 18. 1912; and 7: 82. 1915.

S. Jackson at Denver, Colo., May 26, was sown June 9 on *Abronia fragrans* (family Nyctaginaceae) and *Polygonum aviculare*, with infection only on the *Abronia*, on which pycnia began to appear June 15, and aecia June 19, in abundance. A collection on the same host made by the writer at Ft. Collins, Colo., May 23, was sown on *Polygonum aviculare* (family Polygonaceae) June 23, giving pycnia June 30, and aecia July 3, showing strong development.⁹

7. PUCCINIA LIATRIDIS (Ellis & And.) Bethel.—After repeated assurances from Mr. E. Bethel that he had found a rust on *Koeleria cristata* that would produce aecia on *Liatris*, and had cultured it in his garden, and having received material for study, successful sowings were made fully confirming his contention. A telial collection made by Mr. Bethel April 22, at Boulder, Colo., was sown May 4, on *Laciniaria punctata* (*Liatris punctata*), showing pycnia May 15, and aecia May 22. Another collection made by Mr. Bethel and the writer May 30, at Boulder, Colo., was sown on *L. punctata* June 23, showing pycnia July 3, and aecia July 7. The aecia have long passed under the name of *Accidium Liatridis* Ellis & And., but the telial form has only recently been separated from the several other rusts on *Koeleria* in a paper by Bethel, in which he gives an account of his cultures, but which has not yet been received by the writer in printed form.

SUCCESSFUL CULTURES IN 1916 REPORTED NOW FOR THE FIRST TIME.—The following species have never been cultivated in America or elsewhere, so far as the writer knows.

1. UROMYCES SPOROBOLI Ellis & Ev. (*Accidium alliicolum* Wint.).—On June 1 the writer in company with Messrs. L. E. Melchers, G. W. Putnam and H. S. Jackson explored a number of centers of infection of *Allium stellatum* showing aecia, found in great abundance in a field adjoining the campus of the Agricultural College at Manhattan, Kans. In one place a few uredinia were found on seedling grass about three inches high, ascertained to be *Sporobolus vaginaeflorus*, while over-wintered telia were

⁹ For previous cultures see Bot. Gaz. 35: 19. 1903; Jour. Myc. 11: 54. 1905; 12: 16. 1906; 13: 197. 1907; 14: 15. 1908; Mycol. 1: 234. 1909; 2: 225. 1910; 4: 18, 54. 1912; and 8: 135. 1916.

found on the dead plants of the same annual grass, all pointing to a genetic connection. Hard clumps of earth with the young grass were taken at some distance from the aecial areas and brought to the greenhouse at Lafayette. Whole plants of the *Allium*, in size and appearance much resembling the garden onion, on which were abundant aecia, were also taken, and on June 6 a sowing was made on the seedling grass, resulting in uredinia, first noticed June 21. Another lot of *Allium* plants from the same field, bearing aecia, was sent by Mr. Melchers about two weeks later, and another sowing made June 22, giving uredinia June 29. Neither cultures developed telia, owing to the difficulty in keeping the grass growing properly in the greenhouse. No uredinia appeared on any of the grass not used for inoculation.

The first cultural attempt with the telia of this rust was made fourteen years ago,¹⁰ and again in 1910 and 1912, many hosts being used.¹¹ In 1912 the attempt was made to follow up observations by Mr. E. Bartholomew at Stockton, Kans., by sowing on *Allium reticulatum*, among other hosts, but with no success. Again this year Mr. Bartholomew sent telia on *Sporobolus neglectus*, which were sown on *A. reticulatum* and *A. canadense*, but again without success. No reason can be assigned for the failures.

2. PUCCINIA VERNONIAE B. & C.—A collection of this rust on dead stems of some undetermined species of *Vernonia*, obtained by Mr. C. H. Crabill at Cliffview, Va., March 9, was forwarded by Dr. F. D. Fromme. The sori were numerous and large, ranging from 0.5 to 1.5 cm. long. A sowing was made on the leaves of an undetermined species of *Vernonia*, which resulted in an abundance of pycnia, and some uredinia, but growth ceased before telia were formed. Exact dates were not secured, but the sowing was made about April 30, and the leaves removed for the herbarium on July 6, bearing pycnia and uredinia. This is the first record for pycnia of this very common rust. The life cycle shows that the species belongs in the genus *Bullaria*, in which it becomes ***Bullaria Vernoniae*** (B. & C.) comb. nov.

¹⁰ Bot. Gaz. 35: 11. 1903.

¹¹ See Mycol. 4: 13. 1912; and 7: 66. 1915.

SUMMARY FOR 1916

The following is a complete list of the successful cultures made during the year 1916. Those of the first series are species which have been previously cultured, but those of the second list have never been reported before.

A. SPECIES PREVIOUSLY REPORTED

1. PUCCINIA UNIVERSALIS Arth. Teliospores from *Carex filifolia* Nutt., sown on *Artemisia gnaphalodes* Nutt.
2. PUCCINIA POCULIFORMIS (Jacq.) Wettst.—Teliospores from *Sporobolus cryptandrus* (Torr.) A. Gray, *Agropyron Smithii* Rydb. and *Elymus canadensis* L., sown on *Berberis vulgaris* L.
3. PUCCINIA RHAMNI (Pers.) Wettst.—Teliospores from *Agrostis* sp., sown on *Rhamnus Purshiana* DC.
4. PUCCINIA DISTICHLIDIS Ellis & Ev.—Teliospores from *Spartina Michauxiana* Hitchc., sown on *Steironema ciliatum* (L.) Raf.
5. PUCCINIA MUHLENBERGIAE A. & H. (*P. Schedonnardi* Kellerm. & Sw.).—Teliospores from *Muhlenbergia gracillima* Torr., and from *Schedonnardus paniculatus* (Nutt.) Trel., sown on *Malvastrum coccineum* (Pursh) A. Gray.
6. PUCCINIA SUBNITENS Diet.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Abronia fragrans* Nutt., and *Polygonum aviculare* L.
7. PUCCINIA LIATRIDIS (Ellis & And.) Bethel.—Teliospores from *Koeleria cristata* (L.) Pers., sown on *Laciniaria punctata* (Hook.) Kuntze.

B. SPECIES REPORTED NOW FOR THE FIRST TIME

1. UROMYCES SPOROBOLI Ellis & Ev. (*Aecidium allii-colum* Wint.).—Aeciospores from *Allium stellatum* Ker., sown on *Sporobolus vaginaeflorus* Torr.
2. PUCCINIA VERNONIAE B. & C.—Teliospores from *Vernonia* sp., sown on the same host.

CULTURES IN 1917

No trips for observation were taken during this year, and the usual amount of time bestowed on the cultures was greatly reduced. About 25 collections with resting spores and 6 with active spores, the latter all forms of *Aecidium*, were available for the tests. About 120 drop cultures were made from the sets of resting spores, showing that 15 of the collections were more or less viable at the time. From the fifteen collections 14 successful inoculations were secured, 103 sowings having been made. The work was partly done by Mr. C. C. Rees and partly by Dr. E. B. Mains, members of the laboratory staff.

NEGATIVE RESULTS IN 1917.—It seems worth while to call attention to three attempts which wholly failed, with the hope that some one may be aided in solving the problems involved.

1. PUCCINIA TRITICINA Erikss. on *Triticum vulgare* Mill. was obtained from the border of a wheat field in September, 1916, by Mr. C. C. Rees, and sown on *Clematis Flammula* L., May 17 following, but with no result. The teliospores, however, were germinating very feebly. The conclusion was reached some two years ago from morphological and other data, that the common leaf rust of wheat is a race of the common *P. Agropyri* E. & E., occurring upon many wild grasses. *P. Agropyri* from *Agropyron glaucum* was cultured on *Clematis Vitalba* L. in Germany by Dietel in 1892. In America cultures have shown races to exist in eastern United States between *Bromus ciliatus* and *Clematis virginiana*, in Colorado between *Elymus canadensis* and *Agropyron Smithii* and *C. ligusticifolia*, in Texas between *Elymus virginicus* and *C. Drummondii*, and in North Dakota between *E. canadensis* and *Anemone cylindrica*. As *Clematis Flammula* and *C. Vitalba* are almost the only common Ranunculaceous plants through the wheat growing regions of southern Europe, northern Africa and western Asia, an area that probably includes the home of the original wild wheat, the assumption is reached that one or both these hosts can be made to bear aecia from *P. triticina* under favorable conditions.

2. PUCCINIA EMACULATA Schw. on *Panicum capillare* L. was sown May 8 on *Euphorbia corollata*, and May 9 on *E. commutata*

with no infection, from material obtained by Prof. H. S. Jackson in southern Indiana. Another collection secured by Dr. E. B. Mains at Lafayette, Ind., was sown May 17 on *E. corollata*, and again May 24, June 5 and 13, on *E. Ipecacuanhae*, with no infection. In each case the teliospores showed fair germination and the hosts were in excellent condition. Judging from morphological and host data these species of *Euphorbia* would be probable aecial hosts, but all attempts at cultures¹² have so far failed. I am indebted to Prof. J. B. S. Norton, botanist of the Maryland Agricultural Experiment Station, for a number of serviceable plants of *E. Ipecacuanhae*.

3. PUCCINIASTRUM HYDRANGEAE (B. & C.) Arth., on *Hydrangea arborescens* L., collected by Dr. E. B. Mains at Lafayette, Ind., March 31, 1917, was sown May 12 on *Tsuga canadensis*, *Abies balsamea*, *Abies concolor*, and *Picea canadensis*, with no infection. Although no clues had been obtained from field observation, yet these genera of hosts include all on which any species of *Pucciniastrum* has yet been grown, and the teliospores were germinating freely, so there had been reasonable hopes of success.

SUCCESSFUL CULTURES IN 1917 SUPPLEMENTING PREVIOUS WORK.—The successful attempts to connect the aecia on *Iris versicolor* and on *Rudbeckia laciniata* with telial forms are the culmination of efforts extending over several years, in which a number of persons have aided. Similar efforts to connect the localized aecia on *Houstonia caerulea* and on *Capnoides montanum* have so far been without success, that is, for this laboratory.

1. PUCCINIA MAJANTHAE (Schum.) Arth.—This year for the first time American material of this widely distributed and highly specialized rust has been cultured. The work was first done by Prof. H. H. Whetzel at Ithaca, N. Y., in verification of observations at North Spencer, N. Y., made during the season of 1916 by Prof. Whetzel and Prof. H. S. Jackson. The account of the work has not been published at the time of this writing. Both before and after Prof. Whetzel had obtained his results he sent

¹² For previous attempts see Bot. Gaz. 35: 12. 1903; Jour. Myc. 8: 52. 1902; 10: 10. 1904; 12: 12. 1906; 13: 192. 1907; 14: 11. 1908; Mycol. 1: 230. 1909; 7: 65. 1915; and 8: 127. 1916.

material and gave all possible aid in duplication of his work here in Indiana.

The teliospores from *Phalaris arundinacea*, obtained by Prof. Whetzel at North Spencer, N. Y., Nov. 6, 1916, were sown May 16 on *Iris versicolor*, and again May 17 on *I. versicolor*, and also on *Polygonatum commutatum*, *Vagnera racemosa*, *Convallaria majalis* and *Allium stellatum*. On May 19 they were sown on *Polygonatum biflorum* and May 20 on *Maianthemum canadense*. Only infection took place on *Iris*, the first sowing showing copious pycnia on May 21 and aecia on May 30, while the second sowing gave pycnia May 23 and aecia June 1. The only previous similar attempt was made in the cultures for 1910¹³ when telial material from South Dakota was sown on *Polygonatum commutatum*, *Vagnera stellata*, *Convallaria majalis*, *Uvularia grandiflora* and *Trillium cernuum* with no infection. It is likely that *Puccinia Majanthae* has aecia on all the hosts named, but if so the occurrence of strongly pronounced biological strains prevented infection in the two tests.

2. PUCCINIA SUBNITENS Diet.—For a number of years the aecia on *Capnoides* (*Corydalis*) known as *Aecidium fumariacearum* Kellerm. & Sw., have been associated with the telia on *Distichlis spicata* from morphological and host considerations, but the cultures were not made until the present season, although several times attempted. In June Mr. E. Bethel sent aecia on *C. montanum* grown in his garden from teliospores on *D. spicata* secured at Berkeley near Denver, Colo.

Some of the same collection of telia was transmitted by Mr. Bethel and on June 14 the teliospores were sown on *Abronia fragrans*, *Capnoides montanum* and *Chenopodium album*, with infection only on the last host, giving pycnia June 21, and aecia June 23. Another sowing was made June 21 on *C. montanum*, but gave no infection. Possibly the lateness of season prevented success with the *Capnoides* although the more susceptible *Chenopodium* was infected.

3. UROMYCES SEDITIOSUS Kern.—Observations were made by Dr. F. D. Fromme and the writer in 1914 at Houston, Texas, which appeared to show that this rust sometimes forms aecia on

¹³ Mycol. 4: 11. 1912.

Houstonia caerulea, and since then efforts have been made to secure suitable material with which to make tests. With this in view teliospores from a collection on *Aristida ramosissima* made by Prof. H. S. Jackson at Elberfield, Ind., were sown on *H. caerulea*, but without result. Again teliospores from a collection made by Prof. C. D. Learn on *A. basiramea* at Stillwater, Okla., were sown May 24 on *H. caerulea*, *Plantago Rugelii*, *P. lanceolata* and *P. aristata*, with infection only on the last two hosts, giving pycnia June 4 and aecia June 7, both in abundance.¹⁴

4. UROMYCES PERIGYNIUS Halst.—Aecia have been collected on *Rudbeckia laciniata* in the central west from Montana to Wisconsin, Nebraska and Indiana for which telial connection has been sought for some time.¹⁵ Field observations made by Prof. E. W. D. Holway at Excelsior near Minneapolis, Minn., during 1916, pointed definitely to telia on a *Carex*. The material sent by Prof. Holway was *U. perigynius* on *C. sparganioides*, and was sown May 17 on *Solidago canadensis*, *Aster lateriflorus* and *Rudbeckia laciniata*, with exceedingly abundant infection on the last host, showing pycnia May 21 and aecia May 29. The *Solidago* and *Aster* remained free of rust. Evidently *Rudbeckia* acts as a racial host for this rust parallel with *Aster* and *Solidago*.

SUCCESSFUL CULTURES IN 1917 REPORTED NOW FOR THE FIRST TIME.—Both of the following species introduce questions of relationship which it is impossible at the present time fully to answer.

1. PUCCINIA SPOROBOLI Arth.—Observations were made by Dr. J. F. Brenckle at Kulm, N. Dak., which pointed distinctly to the connection of this rust with aecia on *Lilium umbellatum*, and material consisting of telia on *Sporobolus heterolepis* and bulbs of *L. umbellatum* were sent in the fall of 1916, with which to test the matter. Further telial material was sent the following spring. A sowing was made April 26 and again April 30 and May 1 on a garden lily, *L. elegans* Thunb., closely resembling *L. umbellatum*, the Dakotan plant not being in leaf, but with no infection. On May 16 two sowings were made on the same host and also on

¹⁴ For previous cultures on *Plantago* see Bot. Gaz. 35: 17. 1903.

¹⁵ For unsuccessful tests see Jour. Myc. 12: 12, 13, 14, 25. 1906; 13: 191, 192, 202. 1907; Mycol. 1: 229, 230, 251. 1909; 2: 218. 1910; 4: 9, 12, 13, 28. 1912.

L. umbellatum, with no infection on the first, and with abundant infection on the latter, showing pycnia May 23 and aecia May 29. Another sowing was made May 29 on *Vagnera stellata*, *Uvularia grandiflora*, *Maianthemum canadense*, *Allium stellatum*, all with no infection, and also on *A. Nuttallii* giving pycnia June 4, and aecia June 9, and on *A. cernuum* giving pycnia June 9, and aecia June 12, both in abundance. Sowings June 5 on *A. stellatum* and *A. canadense* gave no result.

Although the host of this rust is one of the principal prairie grasses of the western plains, yet the rust has been collected only in three localities, one at Decorah, Iowa, in 1884, 1901 and 1902, one at Ewing, northwestern Nebraska, in 1899, and the third a recent find at Kulm, N. Dak. It differs from all other American grass rusts in having the pores of the urediniospores near the hilum.

Last year *Uromyces Sporoboli* E. & E. on *Sporobolus vaginæ-florus* was connected with aecia on *Allium* from Kansas material. The aecia from the two species seem to be indistinguishable by any technical character. The suggestion at once arises that the two forms may be genetically correlated. Examination of the telia supports this hypothesis, for the mesosporic teliospores of the *Puccinia* are indistinguishable in size and appearance from the teliospores of the *Uromyces*, but on the other hand the urediniospores of the *Puccinia* are considerably smaller than those of the *Uromyces* and somewhat thinner walled. The greatest difference, however, lies in the arrangement of pores of the urediniospores. In the *Puccinia* they are three or four and basal, while in the *Uromyces* they are four and equatorial.

A particularly close correlation appears to exist between *Puccinia Cryptandri* E. & B. on *Sporobolus cryptandrus* and *U. Sporoboli*, both in uredinia and telia, although the urediniospores of *P. Cryptandri* are inclined to assume a winter resting condition with thicker walls. Unfortunately no suitable culture of *P. Cryptandri* has yet been made, and the aecia are unknown, but it may be assumed that they will be found to occur on *Allium* or a closely related host.

Putting together what is now known regarding these three forms of rust on *Sporobolus* and comparing with what is known of the

forms of rust on *Carex* going to *Ribes*, *P. Grossulariae* (Schum.) Lagerh. (*P. uniporula* Orton),¹⁶ we seem justified in assuming that the grass forms in question represent one species made up of morphologico-physiological races, just as the sedge forms appear to do, but the proof is not so complete. The marked differences in the urediniospores of *P. Sporoboli*, *P. Cryptandri* and *U. Sporoboli*, are all such as can be harmonized with the assumption that the three forms represent only the races of one species, although it does not seem necessary now to go into the required explanation to make the matter perfectly clear. However, for convenient taxonomic reference, and until the relationship is more firmly established, it will be best to treat *P. Sporoboli*, *P. Cryptandri* and *U. Sporoboli* as independent species.

2. UROMYCES ON SPARTINA.—Field observations by Dr. J. F. Brenckle were made during the spring of 1915 at Kulm, N. Dak., which seemed to indicate connection between aecia on *Vagnera stellata* and the common *Uromyces* on *Spartina*. Such a connection seemed to be strengthened by later observations. On May 31, 1916, Dr. Brenckle says in a letter to the author: "Yesterday I went over my station carefully and found the infected plants of *Smilacina* [*Vagnera*] invariably accompanied by rusted *Spartina*. I noted also a number of well infected leaves, each of which was overhung and scraped on by a rusted leaf of *Spartina*. As the infection of *Smilacina* is only in the pycnial state it probably has not spread away from its original telial source. The *Smilacina* is abundant but the infected plants are sharply confined to those patches also inhabited by the *Spartina*. One such patch had plants of *Smilacina* which were *not* infected. I was disappointed that my theory was not proving correct until I noticed that the *Spartina* had no rust."

With such strong circumstantial evidence the success of cultures undertaken with telial material supplied by Dr. Brenckle still came as a surprise, for three or four races of the *Uromyces* on *Spartina* are already well known having aecia on three families of dicotyledonous hosts, and no heteroecious rust has heretofore been discovered having aecia on both monocots and dicots.

On May 11 teliospores from *Spartina Michauxiana* were sown

¹⁶ Mycol. 4: 13. 1912; 7: 66, 78. 1915.

on *Vagnera* (*Smilacina*) *stellata*, *Polygonatum biflorum* and *Steironema ciliatum*, with infection only on the first two, giving pycnia May 18, and aecia May 25, both in the greatest abundance and vigor. Another sowing was made May 19 on *Polygonatum biflorum*, showing pycnia May 28 and aecia June 7, also on *P. commutatum*, showing pycnia May 27 and aecia June 6, and furthermore on the following which were not infected: *Uvularia grandiflora*, *Maianthemum canadense*, *Vagnera racemosa*, *Iris versicolor* and *Trillium recurvatum*. Still another sowing was made May 23 on *Steironema lanceolatum* without infection, and May 29 on *U. grandiflora*, *M. canadense*, *V. racemosa* and *V. stellata*, with infection only on the last, only pycnia showing June 6, doubtless owing to the lateness of the season.

Upon studying the microscopic characters of the material here recorded the form is seen to readily fall into the species given in the North American Flora (7: 231) as *Nigredo Polemonii* (Peck) Arth. The aeciospores on *Vagnera* and *Polygonatum* are much larger (18–29 by 19–35 μ) than those on the same hosts which have been assigned to *Puccinia Majanthae* (Schum.) Arth. (15–21 by 16–27 μ), and have thicker walls, being characters by which the two species may be separated. A collection on *Vagnera stellata* from the valley of the Teton in northern Montana was some years ago made a new species under the name of *Aecidium magnatum* Arth., on these same characters. The aeciospores are somewhat larger than those on the other races of the *Uromyces* on *Spartina*, although there is a gradation in size within certain limits for the four races. In fact the four races of this species exhibit not only physiological specialization, but a certain amount of morphological differentiation of both aecia and telia, together with considerable geographical segregation.

For convenience in discussion of these races there would be some advantage to have distinctive names. The following outline will fairly well show the present morphologico-physiological divisions with geographical distribution, and corresponding names.

UROMYCES POLEMONII (Peck) Barth. (*Nigredo Polemonii* Arth.)

Aeciospores 14–19 by 15–23 μ , on *Caryophyllaceae*.

Teliospores generally broad and rounded above.

- I. Salt marshes of coast, Nova Scotia (III also in Delaware and Florida), and Southern California (III not known on Pacific coast).....*Uromyces Spartinae* Farl.

Aeciospores 15-23 by 16-26 μ , on *Polemoniaceae*.

Teliospores narrow and mostly acuminate above.

- I. Dry plains and thickets, Indiana and Wisconsin to North Dakota and foothills of Colorado (III same).

Uromyces acuminatus Arth.

Aeciospores 16-23 by 18-29 μ , on *Primulaceae*.

Teliospores mostly blunt or truncated above.

- I. Moist plains, Central Indiana to Central Wisconsin and foothills of Colorado and Wyoming (III same).

Uromyces Steironematis nom. nov.

Aeciospores 18-30 by 19-35 μ , on *Convallariaceae*.

Teliospores generally blunt or acute.

- I. Lake or river banks, Buffalo, N. Y., to Central Montana and Nebraska (III North Dakota)..*Uromyces magnatus* comb. nov.

The collection used for the initial culture may be taken as type of *U. Steironematis*. It was collected at Palmer, Neb., March 22, 1905, on *Spartina Michauxiana* Hitchc., by Rev. J. M. Bates, and was successfully sown May 26, 1905, on *Steironema ciliatum*.¹⁷

The forms of the teliospores and the habitats of the four forms are to be taken only as the general expression of the races, and are of no real diagnostic value except as associated with other characters. Both acuminate and rounded teliospores can usually be found in the same sorus, but the impression given by a microscopic mount from specimens of the first race is generally that the spores are prevailingly rounded above, from the second race, acuminate, etc.

The aecia of *U. Spartinae* have been collected on *Arenaria* and *Tissa* in Nova Scotia and southern California; those of *U. acuminatus* on *Collomia*, *Gilia*, *Phlox* (three species) and *Polemonium*, in Colorado, Indiana, Iowa, Minnesota, Nebraska, North Dakota, South Dakota and Wisconsin; those of *U. Steironematis* on *Dodecatheon* and *Steironema*, in Colorado, Illinois, Iowa, Kansas, Nebraska, North Dakota, South Dakota, Wisconsin and Wyoming; and those of *U. magnatus* on *Polygonatum* (two species) and *Vagnera* (two species), in Illinois, Iowa, Minnesota, Montana, Nebraska, North Dakota, South Dakota and Wisconsin.

¹⁷ Jour. Myc. 12: 25. 1906.

Exsiccati material representing aecia has been issued as follows: for *U. Spartinae* none; for *U. acuminatus*, Barth. F. Columb. 2605, Barth. N. Am. Ured. 597, Brenckle, F. Dak. 102, Ellis, N. Am. F. 1008, Rab.-Wint. F. Eur. 3637; for *U. Steironematis*, Barth. F. Columb. 2288, Brenckle, F. Dak. 134, 259, Ellis, N. Am. F. 1424, Sydow, Ured. 2401; and for *U. magnatus*, Barth. F. Columb. 4162, 4467, 4764, Barth. N. Am. Ured. 661, 1074, 1170, 1269, Brenckle, F. Dak. 1, 226, Griff. West Am. F. 243, Sydow, Ured. 2298.

SUMMARY FOR 1917

A. SPECIES PREVIOUSLY REPORTED

1. PUCCINIA MAJANTHAE (Schum.) Arth.—Teliospores from *Phalaris arundinacea* L., sown on *Iris versicolor* L.
2. PUCCINIA SUBNITENS Diet.—Teliospores from *Distichlis spicata* (L.) Greene, sown on *Chenopodium album* L.
3. UROMYCES SEDITIOSUS Kern.—Teliospores from *Aristida basiramea* Engelm. sown on *Plantago aristata* Michx. and *P. lanceolata* L.
4. UROMYCES PERIGYNIUS Halst.—Teliospores from *Carex sparganioides* Muhl., sown on *Rudbeckia laciniata* L.

B. SPECIES REPORTED NOW FOR THE FIRST TIME

1. PUCCINIA SPOROBOLI Arth.—Teliospores from *Sporobolus heterolepis* A. Gray, sown on *Allium cernuum* Roth., *A. Nuttallii* S. Wats., and *Lilium umbellatum* Pursh.
2. UROMYCES MAGNATUS Arth.—Teliospores from *Spartina Michauxiana* Hitchc., sown on *Polygonatum biflorum* (Walt.) Ell., *P. commutatum* (R. & S.) Dietr., and *Vagnera stellata* (L.) Morong.

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.

NINETEEN YEARS OF CULTURE WORK¹

J. C. ARTHUR

A series of culture experiments with the Uredinales was begun by the writer in 1899, and continued under the auspices of the Indiana Agricultural Experiment Station without interruption until 1917, making nineteen consecutive years in which this method of research was consistently pursued. The results of the work were embodied in fifteen reports, printed in the Botanical Gazette, Journal of Mycology, and Mycologia. It is now proposed very briefly to review the work, in order to set forth some of the objects accomplished, and especially to point out the more important of the changing conceptions of the problems forming the ground plan on which the work was projected.

The cultures were not undertaken as part of a distinct thesis or circumscribed problem. They were rather the aids in a general taxonomic study of American rusts, which was directed toward supplying a technical description as complete as possible for every species of Uredinales in North America recorded in literature or known to the writer. This ambitious undertaking was definitely begun sometime in the nineties at the invitation of the editors of the North American Flora.

Beginning with my first taxonomic work on the rusts in 1882 it had seemed to me highly desirable for the purposes of a full technical description of species, that every part of these microscopic plants, capable of supplying diagnostic characters, should be uniformly considered, quite as much as are the stems, leaves, inflorescence, flowers, and fruit of higher plants, and that every means should be taken to arrive at a clear understanding of the identity and relationship of the various forms and species. No effort should be spared, it was believed, to make the name applied to any form embrace also the transformations and variations

¹ Contribution from the Botanical Department of Purdue University Agricultural Experiment Station.

which that form undergoes in passing through its whole life cycle. Many rusts are commonly collected in only one or two stages of their development, or the several stages are taken as independent objects, and to grow such rusts so as to keep them under direct observation and be able to note the succession of stages seemed highly desirable, and especially so for the heteroecious species which pass their gametophytic and sporophytic stages upon wholly unlike and unrelated hosts. It was natural, therefore, to direct chief attention, especially at first, toward unraveling the tangle of heteroecious forms.

Nobody knew how many rusts were to be found on the North American continent and its islands. There were possibly a thousand or more names in existence, but how many of these names applied to single and independent life cycles, and how many to parts of cycles, or were synonyms, no one had attempted to say. It was, in fact, only with the existing names that I had to do. It was no part of my problem to discover new species, or to give new names, either in preparing manuscript for the North American Flora, or in conducting cultures, except in so far as these were required for the systematic development of the work. Many longer or shorter excursions were made during the progress of the cultures, some of them a thousand miles or more, but they were all for the purpose of making field observations upon known species, and in no case for making discovery of new species. The new species that were found were an incidental result.

The first year of the culture work, that of 1899, was very encouraging, and developed no particular difficulties calling for solution. So far custom was followed in the application of names, and it had not been necessary to apply any formula to decide what constituted a species. The assumption that forms on the same or closely related hosts, having no striking morphological differences, were of one species seemed a sufficient hypothesis, and the corollary necessarily followed that cultures would show the range of hosts for each species, as well as serve to demonstrate the stages and spore-forms in the life cycle. Certain features in connection with the common *Euphorbia* rust did indicate that difficulty might be found in the application of the

corollary, and this indication became more pronounced during the year following.

In 1902 three species of *Euphorbia* of unlike appearance and growth habits were found to bear non-interchangeable rusts, which were tentatively considered to present races of *Uromyces Euphorbiae* C. & P., and with the more confidence because no well-defined morphological distinctions could be detected. Subsequent studies strengthened this view of races, and the idea of races from this time on was constantly kept prominently in mind. The attempt to evade or simplify taxonomic and cultural difficulties by treating such races or biological strains as species, as Tranzschel² subsequently did with these same *Euphorbia* forms was not favored.

It was also in 1902 that the *Helianthus* rust was grown with indication of races, developed further in the following year, and brought to a climax in 1904, with the conclusion that a number of more or less well established races occur in *Puccinia Helianthi* Schw., having *Helianthus annuus* as a bridging species, following the lead of Marshall Ward³ in his study of the brome rusts. No further considerable effort was made to study races in autoecious species, or to pick out bridging hosts, as it was held that to ascertain the identity of species was as great a task as could be undertaken in this series of cultures, and that studies leading to the separation of a species into varieties, races, forms, or other subclasses, although of much biological and often of great economical interest, must be left for other time and hands.

The problems of the *Carex* rusts came early into view. In 1901 and 1902 the three remarkable co-species, having telia on various species of *Carex* and aecia on species of *Aster*, *Solidago* and *Erigeron* respectively were repeatedly grown from telial material, and were called *Puccinia Caricis-Asteris*, *P. Caricis-Solidaginis*, and *P. Caricis-Erigerontis*. As no single collection of teliospores was found that would infect more than one of the genera named, the forms were tentatively considered to be species and given distinctive names, following the brilliant cultural methods of Klebahn in Germany, Plowright in England, and

² Ann. Myc. 8: 1-35. 1910.

³ Ann. Myc. 1: 150. 1903.

others, although a careful comparison of the three forms made it seem "not improbable that the three represent more correctly the biological variations of one species," as was stated at the time. In the further study of these forms it was thought that the telial stage might be found to be restricted to certain species of *Carex*, or to particular sections of the genus, as was believed to be true of the European *Carex* rusts, which assumption in the case of the American forms, however, could not be established in any definite way. The hosts were shown finally to be even less restricted than supposed, as the *Aster* form was eventually carried over to *Euthamia* for its aecia and to *Dulichium* for its telia.

The necessity soon became acute to find criteria by which to judge of the standing of species among the rusts, and all the more so because the manuscript was now under preparation for the North American Flora. It was soon decided that, for the purposes of the Flora, morphological characters must be the final test for species. Yet for purposes of study outside of taxonomy it might be serviceable and desirable to maintain the so-called biological or physiological species in any rank desired, but they ought not to be recognized as species proper in taxonomic classification. Consequently in 1912 the three *Carex* forms were combined with certain European forms under the name *Puccinia extensicola* Plowr., a name which has been supplanted by *P. Asterum* (Schw.) Kern, since the cultural series closed. Furthermore, the cultures of 1913 disclosed that *P. vulpinoidis* with its covered telia had its aecia on *Solidago*, and was a part of this same species heretofore known only with naked sori, making the much emphasized character of covered telia a secondary one to be associated principally with the host.

Thus the idea of species among the rusts grew into a far more definite, although more complex form, than could have been possible without the aid of cultural studies. A liberal view was now also required regarding hosts, and also the stress on certain morphological characters called for modification, but the end was not yet.

In 1910 a number of cultures with the *Carex* rust, *Uromyces perigynius*, revealed a remarkable parallelism between this species

and *Puccinia extensicola*. Aster and Solidago races came to light, not however quite so well stabilized in some instances as with the corresponding *Puccinia* races, for in one case sowings of teliospores from the same *Carex* collection were made to grow on both Aster and Solidago. The two species, one of *Uromyces*, the other of *Puccinia*, were subjected to an extensive microscopical study, and no marked differences could be found between their several corresponding spore-forms, except in the septation of the teliospores. This unity of structure had already been observed regarding the aecia and aeciospores when a preliminary culture of the *Uromyces* was made seven years before. From the microscopical evidence, united with much collateral evidence, the following statement was made in the discussion of 1910, which holds true to the present time: "As the aecia and uredinia of the two groups [of host-races], one under the genus *Puccinia* and the other under *Uromyces*, are indistinguishable, and as the teliospores of the *Uromyces* agree with the one-celled spores of the *Puccinia* [mesospores] and also with the two-celled spores in all characters except number of cells and consequent length of spore, the former doubtless are morphological races of the latter. Relationship could be shown better by putting all of these forms under one specific name, and designating the several races by varietal names. But in the present state of taxonomy of the rusts it is more convenient to dispose of them under the two genera: *Puccinia* and *Uromyces*."⁴

If any further illustration were needed to show that *Puccinia* and *Uromyces* were not only parallel genera but actually identical, it was supplied by the cultures of the following year, 1911. During this season successful cultures on *Atriplex hastata* of both *Uromyces Peckianus* and *Puccinia subnitens*, each grown from teliospores on the grass, *Distichlis spicata*, obtained from widely separated localities, gave rise to aecia that appeared to be indistinguishable. A morphological study of these two so-called species has been reported by C. R. Orton in his article on "Correlation between *Puccinia* and *Uromyces*,"⁵ in which he finds a

⁴ *Mycologia* 4: 22. 1912.

⁵ *Mycologia* 4: 199. 1912.

slight difference in size of the urediniospores, and, of course, in the teliospores a difference in number of cells and consequent size. He points out, however, that these differences are such as are to be expected in other similar cases. The comparison of these two forms of *Distichlis* rust, as to morphology, hosts and distribution, is an interesting topic, which need not be pursued further here.

If the *Carex*-*Aster*-*Solidago*-*Erigeron* studies supplemented by studies with the *Distichlis* rust, opened up new views of the species question in relation to host influence and teliosporic dimorphism, so did the *Carex*-*Ribes* studies disclose new views in another direction. The first cultures were in 1901. As the results of sowing teliospores on *Ribes* gave peculiarly small and pale aecia, it was thought that an unrecognized species had been found, which was called *Puccinia albiperidia*. Whether this form was distinct from the common *Carex*-*Ribes* rust of the fields, distinguished as *P. Grossulariae*, and whether American forms were distinct from European forms, of which Klebahn had recognized five, were questions which received attention from year to year as opportunity permitted. In this study Dr. Klebahn graciously consented to lend assistance, and during the two seasons of 1904 and 1906 made cultures at Hamburg, Germany, from telial material supplied by the writer.

Just as the problem seemed solved, and Dr. Klebahn⁶ and myself had independently arrived at the conclusion that in both Europe and America only one heteroecious species occurred, which possessed a number of strains or races, it was discovered by C. R. Orton,⁷ while assisting with the rust studies, that the original material of *P. albiperidia* on *Carex pubescens*, as well as that on a number of American species of *Carex* similar to *C. gracillima*, possessed urediniospores with only one basal pore, in part at least, instead of the usual three or four equatorial pores. Again the *Carex*-*Ribes* rusts of America seemed to fall into two species, not based on differences in the aecia this time; but on differences in the urediniospores. From 1910 onward the question in this connection was whether or not the same species of rust

⁶ Zeits. Pflanzenkr. 17: 132-134. 1907.

⁷ Mycologia 4: 14, 200. 1912.

could possess urediniospores partly with one basal pore and partly with three or four equatorial pores. The answer involved the value and application of pore characters in defining species. After special search,⁸ which led to both kinds of urediniospores being found repeatedly in the same sorus, although for the most part they occurred in separate sori, it was concluded that only one species of rust was under consideration, but with morphological as well as physiological races, not well delimited.

It seemed probable, furthermore, that the previously described, one-pored form of *Carex* rust, known as *Uromyces uniporulus* Kern, was a race also belonging to the *Carex-Ribes* species, but it was not possible to test the matter by cultures. In this connection it is interesting to note, and provocative of speculation, that there is no form yet known with three- and four-pored urediniospores belonging under *Uromyces* in the *Carex-Ribes* aggregation, to make the parallelism with its *Puccinia* form complete.

In 1917, the last year of the culture series, the principle of basing species upon morphological characters, with a greater or less degree of mobility in interpretation, was further illustrated by the case of the *Spartina* rust, *Uromyces Polemonii* (Peck) Barth., which it was found could be segregated into four races,⁹ separable by small but appreciable differences in morphological characters of both aeciospores and teliospores, and by wholly unrelated aecial hosts, and further reinforced by some differences in habitat and geographical distribution. The correlated *Puccinia*-form for this common and widely distributed American rust is that of *Puccinia Distichlidis*, so-called because the type collection was incorrectly labelled as on *Distichlis* instead of on *Spartina*. Its range and aecial hosts, so far as known correspond to only one of the four *Uromyces* races.

At the time the culture work began the subepidermal rusts occurring on wild grasses in America with few exceptions, passed under the name of *Puccinia rubigo-vera*, along with part of the similar leaf rusts of cereals. No criteria had been found for distinguishing them, not even those which had received special

⁸ *Mycologia* 7: 67-69. 1915.

⁹ *Mycologia* 9: 309-312. 1917.

names, and every effort was consequently put forth to make headway into this obscure maze of forms. The first success was in 1902 with a form on *Elymus virginicus* and aecia on Impatiens, which became *Puccinia Impatiensis* (Schw.) Arth. The work opened up slowly. In 1903 a false move was made in connection with the rust on Bromus, but the year following this rust was shown to have aecia on *Clematis virginiana*.¹⁰

In 1907 *Puccinia Agropyri* E. & E., as it occurred in Colorado on Agropyron, was found to go to *Clematis ligusticifolia*, a connection that had been demonstrated by Dietel with European hosts fifteen years before. The following year *Puccinia cinerea* Arth. on Puccinellia was grown on *Ranunculus Cymbalaria*, a rust from *Koeleria cristata* on Mahonia, from Bromus on *Thalictrum*, from Agropyron on *Aquilegia*, the last three being described as new species. In 1915 aecia on *Hydrophyllum* from Utah were made to grow on Agropyron and Elymus, giving rise to uredinia and telia similar to those from the Ranunculaceous aecia, but believed to constitute a distinct species. In 1916 another rust on *Koeleria cristata* was grown on *Laciniaria* under the name *P. Liatridis* (Ell. & And.) Bethel. Repeated attempts were made to find the aecial host of the common leaf rust of wheat, *P. triticina* Erikss., but without success, although there were many indications that pointed to a Ranunculaceous host, and especially to *Clematis* or *Anemone*. It was thought that a favorable trial on *Clematis Flammula* would give a measure of success. At any rate it was believed to be one of the numerous races of the subepidermal leaf-rust of grasses, *P. Agropyri*, with Ranunculaceous hosts for its aecia.¹¹

The series were discontinued before the study of the subepidermal forms was completed, but ten of them had been connected with their aecia. The conviction had been growing for some time that some of these ten names represented races of *Puccinia Agropyri*, rather than independent species, as was stated in discussing the cultures of 1912. When the manuscript was pre-

¹⁰ For a full account and explanation of the mistake of 1903 in supposedly connecting aecia on *Dirca* with the Bromus rust see *Journal of Mycology* 11: 62-63. 1905.

¹¹ *Mycologia* 9: 276. 1917.

pared for the North American Flora *P. tomiþara*, *P. Agropyri*, *P. cinerea*, *P. alternans* and *P. obliterated*, as well as *P. triticina*, were placed under the one name of *P. Clematidis* (DC.) Lagerh. It is considered a great advance to bring from the limbo of *P. rubigovera*, six distinguishable species, some of them having a considerable number of recognized races, and thereby making it possible to relegate to obscurity some dozen or more names that had previously been encumbering the literature of the rusts.

In a somewhat similar way the American *Carex* rusts were in utter confusion at the beginning of the cultures. They were quite generally called *Puccinia Caricis* or *P. caricina*, no cultures with American material having been made, and diagnostic characters not having been well worked out. Altogether ten species were grown during the culture period to show their full life cycle, and in several of them a number of races was found, including the one-celled *Uromyces perigynius*. Of course, being able to separate these ten species made it possible to decide upon the identity of other species, which were not actually grown.

A view generally held when the culture work began was that the hosts of an autoecious species, or of each of the two parts of a heteroecious species, would be found to be closely related, often, indeed, to be but a single species, or genus, and certainly always within a single family. Consequently it was felt that when a grass or sedge rust was successfully cultured, the problem about hosts for that species was practically solved. This complacent opinion was quite upset in the case of *Puccinia subnitens* Diet. on *Distichlis spicata*, which in 1902 was first grown upon *Chenopodium album*. In 1904 Rev. J. M. Bates of Nebraska, who had made the field observations and suggestions for this combination, wrote that he had been continuing his observations of this species and believed that it had aecia also on hosts belonging to two other families, which seemed to the writer at the time as most incredible. Tests, however, showed it would flourish on species of *Cleome*, *Lepidium*, *Sophia* and *Erysimum*, as well as on *Chenopodium*, compelling the admission that it would grow "with equal vigor upon species belonging to three families of plants," at the time being a "remarkable fact not known for any

other species of rust." Additional genera in the same families were added from time to time for aecial hosts, until in the cultures of 1916 the species was grown on *Abronia* and *Polygonum*, thus adding two more families. Mr. E. Bethel, of Denver, Colorado, who made the field observations and suggestions for the later additions, has continued the list since the culture series stopped and brought the number up to 76 species, belonging to 19 families,¹² a truly astonishing showing, and all the more so as no clearly defined races have so far been detected. The only other species of rust with such a remarkably extended series of aecial hosts at all approaching *P. subnitens* Diet., is that of *P. Isiacae* (Thüm.) Wint. from the dry trans-Caspian region of western Asia, as reported by Tranzschel.¹³ This species with telia on *Phragmites communis* has aecia on 19 species of hosts belonging to 9 families, the aecial families being the same as for *P. subnitens*.

In still another way the conception of species was modified when in 1905 teliospores from *Ruellia ciliosa* were grown on the same host and also on *R. strepens*. The latter host, with loose, watery tissues, gave rise to aecia fully ten per cent. larger in every way than did the former host with its firm, woody tissues, thus showing that the forms recognized by the Sydows under *Puccinia lateripes* B. & Rav. and *P. Ruelliae* (B. & Br.) Lagerh.¹⁴ represent only a host influence upon one and the same species, this influence being traced not only in the aecia, but also in the other spore-forms.

Thus it will be seen that while the main work of the cultures was effective in completing the life cycles for many species, and in some cases extending and defining the range of hosts, it was at the same time most profoundly modifying the current conception of species among the rusts. Instead of a rigid ideal of a few invariable characters and a limited range of nearly related hosts to be determined by cultures, we have substituted a complex of somewhat variable morphological characters as the basis,

¹² Bethel, *Phytopathology* 9: 193. 1919.

¹³ Beiträge zur Biologie der Uredineen. Trav. Mus. Bot. Acad. Sci. St. Petersb. 3: 40. 1906; 7: 14. 1909.

¹⁴ Sydow, *Monographia Uredinearum* 1: 235. 1902.

with a more or less extended range of hosts in part determined by cultures and in part by microscopical similarities in the fungus. A species at the beginning of the work was conceived as a simple and direct succession of individuals of the same appearance, capable of being demonstrated by cultures, but at the close had become a bundle of somewhat mobile characters, often comprising many strains varying physiologically and sometimes morphologically, and to a more or less extent not interchangeable by cultures.

In some other ways than already mentioned the accepted notions regarding rusts were modified. It was found that teliospores among the grass forms were not all necessarily resting spores, and that the non-resting forms presented special problems, whose solution was not far advanced when the work came to a close. Assistance with field observations and material permitted successful cultures to be made in May, 1911, with the aeciospores from *Arabis* sown on *Trisetum*. The *Arabis* aecia arise from systemic mycelium extending throughout the stem and leaves of the plant. A month later teliospores resulting from this culture, now having become mature, were found to be capable of germination and were sown on seedling rosettes of *Arabis*. The results of this sowing first definitely showed when the axis of the *Arabis* began to elongate as growth started the following spring. A culture was similarly carried out in 1903 with *Puccinia Eatoniae*, using the aecia on *Ranunculus abortivus*, also a form with diffused mycelium, but a reciprocal culture was not made. These two species of rusts, having a systemic form of aecia, were the only ones of the kind which were brought under culture. They belong to an interesting class physiologically, with systemic aecia, and with teliospores capable of germination upon maturity, which possibly do not retain their viability through the winter, or only to an impaired degree.

The culture work began with the too prevalent idea that all rusts could be expected to conform in general to the well known *Puccinia graminis*. It closed with the conviction that the rusts are far too diversified in their morphology, their numerous characters, their physiological adaptations, and their range of hosts,

to be represented by *Puccinia graminis* in more than one out of numerous aspects. In this resumé of cultures only a few of the more prominent developments that should help to modify the too rigid and restricted ideas of rust species as commonly held have been brought forward. Yet enough has been said possibly to indicate the value of what has been accomplished and the need of more extended work along similar lines.

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.

•

17

243

MEMORANDA AND INDEX OF CULTURES
OF UREDINEAE, 1899-1917

J. C. ARTHUR

[Reprinted from MYCOLOGIA, Vol. XIII, No. 4 and 5, July-Sept., 1921.]



295

MEMORANDA AND INDEX OF CULTURES
OF UREDINEAE, 1899-1917

MEMORANDA AND INDEX OF CULTURES OF UREDINEAE, 1899-1917¹

J. C. ARTHUR

The cultures of the rusts, which were conducted under the auspices of the Purdue University Agricultural Experiment Station, and extended over a period of nineteen years, had a small beginning. For the first three years only such time was given to the work as the writer could spare from his duties as head of the Botanical Department of the Station and as Professor of Vegetable Physiology and Pathology in Purdue University. In most of the following years an assistant was especially employed during two or so months each spring, who had entire charge of the testing of spore viability, sowing of the spores, and care of the inoculated plants, the chief part of the culture work being done during May and June. The position was held by fourteen individuals, selected with the needs of the work especially in view, and ranging from a junior high school student to university instructors, who without exception showed superior ability in conducting the work. Financial support was provided by a grant from the Botanical Society of America in 1903, 1906 and 1907, and by coöperation with the Bureau of Plant Industry of the U. S. Department of Agriculture in 1904 and 1905. In the other years it was supplied by the Purdue University Agricultural Experiment Station, and from 1908 onward the work was made a part of the rust project under the Adams fund.

During the progress of the work the writer, usually accompanied by an associate, made many shorter or longer excursions for securing data and material. These field observations were directed toward detecting the juxtaposition of spore-forms that might be supposed to have genetic connection, as well as toward securing suitable culture material. The fruitfulness of this method is apparent from the fact that during the extended study

¹ Contribution from the Botanical Department of the Purdue University Agricultural Experiment Station.

of heteroecious species only three times was a discovery of alternate hosts effected that was not the outcome of a previous field observation. In two of these cases, that of *Uromyces acuminatus* (more properly *U. Steironematis*, see page 76,* Jour. Myc. 12: 25), and *Puccinia Ceanothi* (see page 196,* Mycologia 4: 27) sowings were made on all available hosts in the greenhouse, recorded as bearing aecia, and in the case of *P. fraxinata* (*P. peridermiospora*, see page 8,* Bot. Gazette 29: 275), a morphological similarity was detected between aeciospores and urediniospores, leading to successful cultures.

Beginning with the immediate vicinity of Lafayette, Indiana, the range of observations was extended to various parts of the state, and in the ninth year of the work, 1907, to other states. This year a trip was made to the foothills of Colorado, which was repeated in 1908, 1911 and 1916, observations being made from Boulder to Trinidad, and once westward to Ouray and Durango. Between 1908 and 1916 trips were made northward to Wisconsin and Michigan, eastward to Maine and Pennsylvania, to South Carolina, Alabama and Mississippi in the south, and to Texas, New Mexico and Arizona in the southwest. So far as possible places were selected where there were local collectors, or where records showed that species requiring investigation had at some time been secured. The chief collecting grounds of Ellis in New Jersey, Ravenel in North and South Carolina, Atkinson and Underwood in Alabama, and Kellerman in Kansas were visited, and the collecting grounds of Schweinitz at Salem, North Carolina, and Bethlehem, Pennsylvania, would have been visited, if opportunity had favored. In this way many obscure names in the literature were connected with living material on which fresh and more extended studies, often including cultures, could be carried out. By this method the attention given to the genus *Gymnosporangium* was made to expand our limited knowledge of a few species into an understanding of the life history of some two dozen species and of their alternate hosts. The effectiveness of the work with *Gymnosporangium* was greatly enhanced by the special interest in it taken by my asso-

* For explanation of these page numbers see p. 246 at beginning of the index.

ciate, Dr. F. D. Kern, who for ten years took part in the culture work. The grass and sedge rusts were, however, the ones that received the most extended and prolonged attention.

To carry on the work more than 2140 collections with resting spores were available, together with over 250 collections with spores not requiring a resting period. Tests of all of these, and of some many times repeated, showed that not all were viable, at least at the time tested, and therefore not serviceable. This material was provided in part by those directly connected with the work, and to a considerable extent by more than 85 botanical correspondents, many of whom contributed most generously in material and field observations year after year. Altogether about 3750 sowings, that is, attempts at cultures were made, of which about one in seven resulted in successful infection of the host. These tests were almost wholly made in a greenhouse, although a few were conducted in the open field when small plants suitable for placing in pots were not available.

It is difficult to say just how many species have been grown through some part of their life cycle during the nineteen-year period, owing to the constant shifting of accepted names as knowledge regarding them accumulated. Probably the list includes about one hundred species, as they are now rated, or nearly twice as many as they would at first have been listed, and of this number about eight were heteroecious to one autoecious. Of the heteroecious species some twenty were verifications of combinations previously established, mostly by European investigators, while about sixty-five provided alternate hosts for species whose life cycle was before unknown, most of these being grass and sedge forms not known outside of North America.

When viewing the present location of the New York Botanical Garden many years ago, it then being a rolling meadow without buildings of any kind, my companion, Professor L. M. Underwood, remarked that some day I might be called upon to supply the rust portion for the projected North American Flora, and added that if I did so he had no doubt that I would greatly reduce the number of species. The culture studies have enabled me to do this, but not quite in the way Professor Underwood

and others at that time had in mind. In many cases the first results have been to increase the number of species. Thus *Puccinia alternans* and *P. obliterata* were described as new species as result of cultures, but as the studies proceeded were reduced to synonyms of the long recognized *P. Agropyri*, together with *Aecidium Aquilegiae*, *A. Clematidis*, *Puccinia tomipara*, *P. Paniculariae*, and some others. But on the whole, as the cultures have largely dealt with heteroecious species, there has been a reduction in names as the alternate forms were brought together, and sometimes by the recognition as races of forms that were once thought distinct species.

The nomenclature of the reports has been made as conservative as possible, in order to give them reasonable uniformity. The new generic names proposed by the writer in 1906 at the Vienna Congress scarcely find an echo in them, while on the other hand the terminology for spore-forms, brought out in 1905, was put into use in the second report following, and proved highly serviceable.

In the various reports of the cultures, and as a result of them, the following thirteen specific names were transferred to other genera: *Aecidium magnatum* Arth. and *A. Silphii* Sydow to *Uromyces*, *Aecidium Ceanothi* Peck, *A. Impatientis* Schw., *A. Jamesianum* Peck, *A. macrosporum* Peck, *A. monoicum* Peck, *A. Pammelii* Trel., *A. Phrymae* Halst., *A. pustulata* Curt., *A. Sambuci* Schw. to *Puccinia*, and *Puccinia tumidipes* Peck and *P. Vernoniae* Berk. & Curt. to *Bullaria*.

Also as the result of the cultures the following sixteen species were described as new: *Gymnosporangium corniculans* Kern, *G. exterum* Arth. & Kern, *G. trachysorum* Kern, and on the authority of the writer *Puccinia albiperidia*, *P. alternans*, *P. Caricis-Asteris*, *P. Caricis-Erigerontis*, *P. Caricis-Solidaginis*, *P. Eatoniae*, *P. Koeleriae*, *P. obliterata*, *P. patruelis*, *P. universalis*, *Uromyces effusus*, *U. Solidagini-Caricis*, and *U. Steironematis*, but as the result of further studies most of these were subsequently buried in synonymy.

CORRECTIONS

In making corrections the consecutive page numbers used are those explained below at the beginning of the index, while the original pages are given in parentheses. A few of the corrections are typographical errors, or slips of the pen, but many are necessitated by information variously acquired after the reports were written and printed. Evident and inconsequential errors are not included. To save space the following abbreviations are used in the parentheses: B.G. for Botanical Gazette, J.M. for Journal of Mycology, and My. for Mycologia, and are followed by the original volume and page number.

Pages 5, 9 (B.G. 29: 272, 276), under 7 and 3 respectively, for "*Americana* Lagh." and "*Americana*," read *Andropogonis* Schw. and *Andropogonis*, respectively, and for "*Andropogi* Schw." and "*Andropogi*," read *Ellisiana* Thüm. and *Ellisiana*, respectively.

Pages 7, 9, 22, 28 (B.G. 29: 274, 276; 35: 16, 22), for "K. & S.," read E. & K.

Pages 8, 31, 51, 60, 67, 75, 76, 77, 78, 83, 103, 106, 114, 127, 146, 156, 160, 164, 174 (B.G. 29: 275; J.M. 10: 9; 11: 57, 66; 12: 16, 24, 25, 26, 27; 13: 192; 14: 14, 17, 25; My. 1: 236, 255; 2: 221, 225, 229, 239), for the species of *Spartina*, given as "*cynosuroides*" or "*cynosuroides* Willd.," read *Michauxiana* or *Michauxiana* Hitchc. The two species of grass were for a time confused and one name used for both.

Pages 11, 65, 77, 86, 94 (J.M. 8: 52; 12: 14, 26; 13: 196, 204), for a species of *Carex*, for "*tetanica*" and "*tetanica* Schk.," read *blanda* and *blanda* Dewey, respectively.

Pages 17, 45, 49, 50, 60 (B.G. 35: 11; J.M. 11: 51, 55, 56, 66), for the species of *Lepidium*, given as "*apetalum*" and "*apetalum* Willd.," read *densiflorum* and *densiflorum* Schrad., respectively.

Page 26 (B.G. 35: 20), the *Aecidium* mentioned under 5. *P. AMPHIGENA* was subsequently found not to be *A. Smilacis* Schw.

Pages 41, 42 (J.M. 10: 19, 20). The supposed infection in 1903 of *Bromus ciliatus* by the application of aeciospores from *Dirca palustris* was the most serious error that occurred in the nineteen years of culture work. The grass used for the culture was undoubtedly infected before the sowing was made, as explained on pages 56 and 57 of the report following. The combination of aecia and telia under the name "*Puccinia hydnoidea*," was unwarranted. The *Aecidium hydnoideum* was under close observation during the whole culture period, and there were a score of attempts to find the alternate host, but even to the present writing no progress has been made.

Pages 49, 50 (J.M. 11: 55, 56), under no. 4, for the species of *Sophia* from Nebraska, given as "*incisa* (Engelm.) Greene," read *intermedia* Rydb.

Pages 49, 60, 68, 77 (J.M. 11: 55, 66; 12: 17, 26), for the species of *Sophia* from Indiana used in the cultures, given as "*incisa*" and "*incisa* (Engelm.) Greene," read *brachycarpa* and *brachycarpa* Rydb.

Pages 51, 60, 67, 77, 103, 114, 127, 146, 160, 174, (J.M. 11: 57, 66; 12: 16, 26; 14: 14, 25; My. 1: 236, 255; 2: 225, 239), after *Puccinia fraxinata*, for "Schw.," read Link.

Page 62, first line of reprint, for "1," read 12.

Page 64 (J.M. 12: 13), under no. 6, for "Schw.," read Desmaz.

Pages 66, 77 (J.M. 12: 15, 26), under no. 7, for specific name "*aquatilis*" and "*aquatilis* Wahl.," read *nebraskensis* and *nebraskensis* Dewey. On page 66 the comparison of the large, thick-walled urediniospores (common on this host, the form being known as *Puccinia Garrettii* Arth.) to the amphispores of *P. Caricis-stictae* was an error. It may be pointed out here that the same mistake regarding name of the host also occurs in Sydow, *Uredineen* 2115, Barth. Fungi Columb. 2351 and 3838. *Carex nebraskensis* is a very common sedge about Denver and Boulder, Colo., while *C. aquatilis* is rare or possibly absent.

Pages 85, 92, 94 (J.M. 13: 195, 202, 204), under *Lactuca*, for "*virosa*," read *scariola*.

Pages 93, 95, 107, 114, 130, 146, 195, 201 (J.M. 13: 203, 205; 14: 18, 25; My. 1: 239, 255; 4: 26, 32), under *Gymnosporangium*, for "*Nelsoni* Arth.," read *juvenescens* Kern, and also delete the last sentence under no. 19 on page 107 (J.M. 14: 18). *Gymnosporangium Nelsoni* and *G. juvenescens* were for a time confused. Both produce aecia on *Amelanchier* and *Sorbus*, but the former gives rise to woody galls, often very small, while the latter is foliicolous.

Page 96, first line of the reprint for "1907," read 1908.

Pages 100, 180 (J.M. 14: 11; My. 4: 11), under *Puccinia*, for "*montanensis* Ellis," read *Agropyri* Ellis & Ev., as pointed out on page 263 (My. 8: 139).

Pages 109, 115 (J.M. 14: 20, 26), under no. 2, for "*Cryptandri* Ellis & Barth.," read *substerilis* Ellis & Ev., and for "*Sporobolus cryptandrus* (Torr.) A. Gray," read *Stipa viridula* Trin.

Pages 112, 115 (J.M. 14: 23, 26), under no. 6, for "*mutabilis* Ellis & Gall.," read *Blasdalei* Diet. & Holw., for "*reticulatum* Fraser," read *Brandegei* S. Wats., and for "*recurvatum* Rydb.," read *cernuum* Roth.

Page 123 (My. 1: 232), under no. 11, for "*Aster arenarioides* D. C. Eaton," read *Erigeron arenarioides* A. Gray.

Pages 129, 130, 146 (My. 1: 238, 239, 255), the small form of *Gymnosporangium* on *Juniperus virginiana*, which gave rise to pycnia and aecia on *Crataegus punctata*, should have been referred to *G. floriforme* Thaxter.

Page 133 (My. 1: 242), delete the entire paragraph beginning "The aecia of this species," etc., except the first sentence.

Page 147 (My. 1: 256), under no. 8, for "*glomerata*," read *mexicana* (L.).

Page 173 (My. 2: 238), under no. 1, change the reading thus: *Teliospores* on *Carex lanuginosa* Michx., sown on *Onagra biennis* (L.) Scop., and on *C. trichocarpa* Muhl. sown on *Gaura biennis* L.

Pages 178, 180 (My. 4: 9, 11), 19th and 6th line from bottom respectively, for "*Douglasii*," read *spartioides*.

Pages 180, 189, 197, 200, 231 (My. 4: 11, 20, 28, 31; 7: 72), as a species of *Senecio*, for "*lugens*" or "*lugens* A. Gray," read *spartioides* or *spartioides* T. & G., respectively.

Pages 197, 202 (My. 4: 28, 33), under no. 2, the material in hand from Isle au Haut, Me., was *Puc. quadriporula* (*P. Grossulariae*), but the results of infection were obtained from stray spores of *Uromyces perigynius*, as explained at page 235 (My. 7: 76) in the report of cultures for 1912.

Pages 256, 265 (My. 8: 132, 141), under no. 4, for "*Agropyri* E. & Ev. (*P. alternans* Arth.)," read *Cockerelliana Bethel*. This distinctive species was not recognized, and had not been named until long after the cultures were made.

Pages 257, 265, (My. 8: 133, 141), under no. 5, for "*Anchusa officinalis*," read *Lycopsis arvensis*.

Pages 261, 263, 265 (My. 8: 137, 139, 141), under no. 3, for "*montanensis* Ellis" and "*montanensis*," read *apocrypta* Ellis & Tracy and *apocrypta*, respectively. On page 262 three species are confused. *Puccinia apocrypta* is not a synonym of *P. Agropyri*. The characters given for *P. apocrypta* are those of the true *P. montanensis*, for which the type is the collection cited.

Pages 274, 275 (My. 9: 302, 303), under no. 2, for "B. & C." read Schw.

SUMMARY OF CULTURES

In order to give a clearer perspective of the work, and to make the data more readily available, the following tabulation is given of the heteroecious species that were successfully grown on alternate hosts. Autoecious species, and heteroecious species grown from urediniospores or amphispores only, have not been included. The years are those in which successful cultures were carried out. Only such synonymy is given as will account for the names used at different times in the reports. The page numbers are those explained below at the beginning of the index. Pages in broad faced type indicate the host from which spores were taken for culture, while pages in common type indicate the host on which the culture was successfully established.

Year	Rust	Telial host	Aecial host
1904 1905	<i>Puc. Sorghi</i> Schw.	<i>Zea Mays</i> 59, 68	<i>Oxalis corniculata</i> (O. cymosa) 59, 68
1909	<i>Puc. Ceanothi</i> (E. & K.) Arth.	<i>Andropogon Hallii</i> 168	<i>Ceanothus americana</i> 168
1912	<i>Puc. Ellisiana</i> Thüm.	<i>Andropogon</i> sp. 230	<i>Viola cucullata</i> 230 <i>V. Nuttallii</i> 230
1899 1903 1906 1910	<i>Puc. Andropogonis</i> Schw. (<i>P. americana</i> Lagerh.)	<i>Andropogon scoparius</i> 5, 6, 33, 87, 186 <i>A. virginicus</i> 186	<i>Pentstemon hirsutus</i> (<i>P. pubescens</i>) 5, 6, 33, 87, 186 <i>P. alpinus</i> 186
1903 1905 1910	<i>Puc. pustulata</i> (Curt.) Arth.	<i>Andropogon furcatus</i> 39, 67, 186 <i>A. scoparius</i> 39	<i>Comandra umbellata</i> 39, 67, 186
1904 1905 1907	<i>Puc. Pammelii</i> (Trel.) Arth. (<i>P. Panici</i> Diet.)	<i>Panicum virgatum</i> 50, 67, 105	<i>Euphorbia corollata</i> 50, 67 <i>E. marginata</i> 105
1901 1904 1905 1906 1907 1909 1910 1916	<i>Puc. poculiformis</i> (Jacq.) Wettst. (<i>P. graminis</i> Pers.)	<i>Agropyron pseudorepens</i> 162 <i>A. repens</i> 51 <i>A. Smithii</i> 270 <i>A. tenerum</i> 51, 105, 187 <i>Agrostis alba</i> 68, 88, 187 <i>Avena sativa</i> 105 <i>Cinna arundinacea</i> 12 <i>Elymus canadensis</i> 51, 88, 270 <i>Hordeum vulgare</i> 88 <i>Sitanion longifolium</i> 162, 187 <i>Sporobolus cryptandrus</i> 270 <i>Triticum aestivum</i> (<i>T. vulgare</i>) 88, 162	<i>Berberis vulgaris</i> 12, 51, 68, 88, 105, 162, 187, 270
1917	<i>Puc. Majanthae</i> (Schum.) Arth.	<i>Phalaris arundinacea</i> 278	<i>Iris versicolor</i> 278
1904 1910 1912	<i>Puc. Stipae</i> Arth.	<i>Koeleria cristata</i> 189 <i>Stipa comata</i> 231 <i>S. spartea</i> 58, 188	<i>Aster ericoides</i> 58, 188 <i>A. multiflorus</i> 58, 188 <i>A. Novae-Angliae</i> 58, 188 <i>Grindelia squarrosa</i> 188 <i>Gutierrezia Sarothrae</i> 231 <i>Senecio spartioides</i> 189, 231 <i>Solidago canadensis</i> 188

Year	Rust	Telial host	Aecial host
1917	<i>Puc. Sporoboli</i> Arth.	<i>Sporobolus heterolepis</i> 280	<i>Allium cernuum</i> 280 <i>A. Nuttallii</i> 280 <i>Lilium umbellatum</i> 280
1899 1902 1904 1905	<i>Puc. verbenicola</i> (E. & K.) Arth. (<i>P. Vilfae</i> Arth. & Holw.)	<i>Sporobolus longifolius</i> 7, 22, 50, 67	<i>Verbena stricta</i> 7, 22 <i>V. urticifolia</i> 22, 50, 67
1902 1904 1905 1906 1907 1908 1909 1910 1911 1915 1916 1917	<i>Puc. subnilens</i> Diet.	<i>Distichlis spicata</i> 25, 49, 68, 87, 104, 126, 160, 188, 208, 259, 273, 278	<i>Abronia fragrans</i> 273 <i>Atriplex hastata</i> 126, 160, 208 <i>Bursa Bursa-pastoris</i> 68, 104 <i>Chenopodium album</i> 25, 87, 104, 126, 160, 188, 208, 259, 278 <i>Cleome spinosa</i> 49, 208 <i>Erysimum asperum</i> 49, 68 <i>Lepidium densiflorum</i> (<i>L. apetalum</i>) 49 <i>L. virginicum</i> 49, 68 <i>Polygonum aviculare</i> 273 <i>Sarcobatus vermiculatus</i> 87, 126 <i>Sophia brachycarpa</i> 49, 68
1908 1909 1910 1914 1916	<i>Puc. Muhlenbergiae</i> Arth. & Holw. (<i>P. tosta</i> Arth.)	<i>Muhlenbergia gracillima</i> 271 <i>M. mexicana</i> 142 <i>M. racemosa</i> (<i>M. glomerata</i>) 161, 187 <i>Schedonnardus paniculatus</i> 272 <i>Sporobolus asperifolius</i> 240, 241	<i>Callirhoe involucrata</i> 142, 161, 187 <i>Malvastrum coccineum</i> 271, 272 <i>Sphaeralcea digitata</i> 241 <i>S. incana</i> 240 <i>S. lobata</i> 241
1902 1903 1905 1907 1909 1910	<i>Puc. amphigena</i> Diet.	<i>Calamovilfa longifolia</i> 26, 33, 67, 104, 160, 187	<i>Smilax herbacea</i> 26 <i>S. hispida</i> 26, 33, 67, 104, 160, 187
1911 1912	<i>Puc. monoica</i> (Peck) Arth.	<i>Koeleria tristata</i> 234 <i>Trisetum majus</i> 213 <i>T. subspicatum</i> 213, 234	<i>Arabis</i> sp. 213, 234
1904 1910 1916	<i>Puc. Rhamni</i> (Pers.) Wettst. (<i>P. coronata</i> Corda)	<i>Agrostis</i> sp. 271 <i>Avena sativa</i> 52 <i>Calamagrostis canadensis</i> 187	<i>Rhamnus alnifolia</i> 187 <i>R. caroliniana</i> 52 <i>R. cathartica</i> 52 <i>R. lanceolata</i> 52 <i>R. Purshiana</i> 271

Year	Rust	Telial host	Aecial host
1899 1904 1905 1907 1908 1909	<i>Puc. fraxinata</i> (Link) Arth. (<i>P. peridermi- ospora</i> Arth.)	<i>Spartina Michauxiana</i> (not <i>S. cynosuroides</i>) 8, 51, 67, 103, 160 <i>S. polystachya</i> 127 <i>S. stricta</i> 127	<i>Fraxinus lanceolata</i> (<i>F. viridis</i>) 8, 51, 67, 103, 127, 160
1915 1916	<i>Puc. Distichlidis</i> E. & E. (<i>P. Kelseyi</i> Syd.)	<i>Spartina Michauxiana</i> 261, 271	<i>Steironema ciliatum</i> 261, 271
1905 1908 1910 1915	<i>Puc. Seymouriana</i> Arth.	<i>Spartina cynosuroides</i> 259 <i>S. Michauxiana</i> (not <i>S. cynosuroides</i>) 75, 127, 188, 258	<i>Apocynum cannabinum</i> 258 <i>Asclepias syriaca</i> 259 <i>Cephalanthus occident- alis</i> 75, 127, 188
1902 1910	<i>Puc. Jamesiana</i> (Peck) Arth. (<i>P. Bartholo- maei</i> Diet.)	<i>Bouteloua curtipendula</i> (<i>Atheropogon curti- pendulus</i>) 24, 188	<i>Asclepias incarnata</i> 24 <i>A. syriaca</i> 24, 188
1899 1907 1909 1911	<i>Puc. Phragmitis</i> (Schum.) Körn.	<i>Phragmites communis</i> (<i>P. Phragmites</i>) 2, 104, 160, 208	<i>Rumex crispus</i> 2, 104, 160, 208 <i>R. obtusifolius</i> 2
1902 1907	<i>Puc. simillima</i> Arth.	<i>Phragmites communis</i> (<i>P. Phragmites</i>) 26, 104	<i>Anemone canadensis</i> 26, 104
1899 1902 1904 1915	<i>Puc. Windsoriae</i> Schw.	<i>Tridens flavus</i> (<i>Triodia cuprea</i> , <i>Tricuspis ses- lerioides</i>) 6, 22, 50, 260	<i>Ptelea trifoliata</i> 6, 22, 50, 260
1903	<i>Puc. Eatoniae</i> Arth.	<i>Eatonia pennsylvanica</i> 40	<i>Ranunculus abortivus</i> 40
1908	<i>Puc. Koeleriae</i> Arth.	<i>Koeleria cristata</i> 138	<i>Mahonia Aquifolium</i> 138
1916	<i>Puc. Liatridis</i> (E. & A.) Bethel	<i>Koeleria cristata</i> 273	<i>Laciniaria punctata</i> 273
1910	<i>Puc. Crandallii</i> Pam. & Hume	<i>Festuca confinis</i> 196	<i>Symphoricarpos race- mosus</i> 196
1915	<i>Puc. Cockerelliana</i> Bethel	<i>Festuca Thurberi</i> 256	<i>Thalictrum dioicum</i> 256
1908 1915	<i>Puc. Asperifolii</i> (Pers.) Wettst.	<i>Secale cereale</i> 128, 257	<i>Lycopsis arvensis</i> 128, 257
1915	<i>Puc. apocrypta</i> Ellis & Tracy	<i>Agropyron tenerum</i> 262 <i>Elymus virginicus</i> 262	<i>Hydrophyllum capi- tatum</i> 262

Year	Rust	Telial host	Aecial host
1904 1906 1907 1908 1909 1911 1912 1914	<i>Puc. Clematidis</i> (DC.) Lagerh. (<i>P. Agropyri</i>) E. & E., <i>P. tomipara</i> Trel., <i>P. cinerea</i> Arth. <i>P. alternans</i> Arth., <i>P. obliterata</i> Arth.)	<i>Agropyron biflorum</i> 140 <i>A. pseudorepens</i> 105 <i>A. Smithii</i> 232 <i>A. sp.</i> 161 <i>Bromus pürgans</i> 87, 127 <i>B. ciliatus</i> 56 <i>B. Porteri</i> 139 <i>Elymus canadensis</i> 232 <i>E. virginicus</i> 242 <i>Puccinellia airoides</i> 137, 208	<i>Anemone cylindrica</i> 232 <i>Aquilegia canadensis</i> 140, 161 <i>Clematis Drummondii</i> 242 <i>C. ligusticifolia</i> 232 <i>C. virginiana</i> 56, 87, 105, 127 <i>Oxygraphis Cymbalaria</i> (<i>Ranunculus Cymbalaria</i>) 137, 208 <i>Thalictrum alpinum</i> 161 <i>T. dioicum</i> 139 <i>Viorna Scottii</i> 105
1902 1903 1904 1909	<i>Puc. Impatiens</i> (Schw.) Arth.	<i>Elymus canadensis</i> 162 <i>E. striatus</i> 161, 162 <i>E. virginicus</i> 25, 33, 51, 162	<i>Impatiens aurea</i> 25, 33, 51, 161, 162
1907	<i>Puc. oblecta</i> Peck	<i>Scirpus americanus</i> 109	<i>Bidens connata</i> 109 <i>B. frondosa</i> 109
1899 1901 1904 1906 1907 1908 1910 1911 1912	<i>Puc. angustata</i> Peck	<i>Scirpus atrovirens</i> 6, 12, 52, 86, 103, 186, 230 <i>S. cyperinus</i> 125, 208	<i>Lycopus americanus</i> 6, 12, 52, 86, 103, 186, 208, 230 <i>L. uniflorus</i> (<i>L. communis</i>) 125
1915	<i>Puc. Eriophori</i> Thüm.	<i>Eriophorum viridicarinatum</i> 255	<i>Senecio aureus</i> 255
1905	<i>Puc. canaliculata</i> (Schw.) Lagerh.	<i>Cyperus esculentus</i> 74	<i>Xanthium "canadense"</i> 74
1905 1906 1908	<i>Puc. Eleocharidis</i> Arth.	<i>Eleocharis palustris</i> 74, 87, 124	<i>Eupatorium perfoliatum</i> 74, 87, 124
1908	<i>Puc. macrospora</i> (Peck) Arth.	<i>Carex comosa</i> 134	<i>Smilax hispida</i> 134
1901 1903 1904 1905 1906 1907 1910 1912 1913 1915	<i>Puc. Grossulariae</i> (Pers.) Lagerh. (<i>P. albiperidia</i> Arth.)	<i>Carex arctata</i> 226, 254 <i>C. blanda</i> 65, 86 <i>C. crinita</i> 53, 86, 102, 226 <i>C. flexuosa</i> (<i>C. tenuis</i>) 182, 226, 254 <i>C. gracillima</i> 33, 53 <i>C. pallescens</i> 182 <i>C. pubescens</i> 12, 225 <i>C. squarrosa</i> 86 <i>C. sp.</i> 237	<i>Ribes aureum</i> 53 <i>R. Cynosbati</i> 12, 33, 53, 86, 102, 182, 225, 226, 237, 254 <i>R. gracile</i> 65, 86 <i>R. rotundifolium</i> 53, 86 <i>R. uva-crispa</i> 33, 53

Year	Rust	Telial host	Aecial host
1901 1902 1905 1907 1909 1910	<i>Puc. Caricis</i> (Schum.) Schroet.	<i>Carex aristata</i> 158, 186 <i>C. nebraskensis</i> 66 <i>C. riparia</i> 22, 103 <i>C. stipata</i> 66, 103 <i>C. stricta</i> 11, 22, 186	<i>Urtica gracilis</i> 11, 22, 66, 103, 158, 186
1914	<i>Puc. minutissima</i> Arth.	<i>Carex filiformis</i> 245	<i>Decodon verticillatus</i> 245
1907 1909 1910 1916	<i>Puc. universalis</i> Arth.	<i>Carex filifolia</i> 270 <i>C. stenophylla</i> 110, 159, 185	<i>Artemisia dracuncu- lodes</i> 110, 159, 185 <i>A. gnaphalodes</i> 270
1907	<i>Puc. Phrymae</i> (Hlalt.) Arth.	<i>Carex longirostris</i> 111	<i>Phryma leptostachya</i> 111
1901 1902 1904 1905 1907 1908 1909 1910 1912 1913 1914 1915	<i>Puc. Asterum</i> (Schw.) Kern (<i>P. extensicola</i> Plow., <i>P. Caricis-Asteris</i> Arth., <i>P. Caricis-Erigerontis</i> Arth., <i>P. Caricis-Solidaginis</i> Arth., <i>P. Dulichii</i> Syd.)	<i>Carex festiva</i> 159, 185 <i>C. festucacea</i> 13, 22, 52 <i>C. foenea</i> 13, 14, 21 <i>C. Jamesii</i> 27 <i>C. retrorsa</i> 228 <i>C. rosea</i> 102 <i>C. scoparia</i> 184, 228, 229 <i>C. sparganioides</i> 66, 124 <i>C. stipata</i> 27 <i>C. sp.</i> 102 <i>C. vulpinoidea</i> 238, 240 <i>Dulichium arundinaceum</i> 240, 254	<i>Aster adscendens</i> 159, 185 <i>A. cordifolius</i> 14, 102 <i>A. paniculatus</i> 13, 14, 21, 102, 228 <i>Erigeron annuus</i> 13, 22, 52 <i>E. philadelphicus</i> 22 <i>Euthamia graminifolia</i> 184, 229 <i>Leptilon canadense</i> 22 <i>Solidago caesia</i> 27 <i>S. canadensis</i> 27, 66, 124, 238, 240, 254 <i>S. glaberrima</i> 238 <i>S. mollis</i> 238 <i>S. rigida</i> 27 <i>S. rugosa</i> 238 <i>S. serotina</i> 27 <i>S. ulmifolia</i> 27
1902 1904 1905 1906 1908 1909 1910 1911	<i>Puc. Peckii</i> (DeT.) Kellerm.	<i>Carex lanuginosa</i> 52, 66, 85, 158, 184, 208 <i>C. stipata</i> 20, 124 <i>C. trichocarpa</i> 20, 21, 52, 85, 158, 184	<i>Gaura biennis</i> 158 <i>Meriolix serrulata</i> 184 <i>Onagra biennis</i> (<i>Oenothera biennis</i>) 20, 21, 52, 66, 85, 124, 158, 184, 208
1906 1908 1910	<i>Puc. patruelis</i> Arth. (<i>P. Opizii</i> Arth. not Bubák)	<i>Carex pratensis</i> 136 <i>C. siccata</i> 185 <i>C. sp.</i> 85	<i>Agoseris glauca</i> 136 <i>Lactuca canadensis</i> 85, 185 <i>L. sativa</i> 85, 185 <i>L. virosa</i> 85

Year	Rust	Telial host	Aecial host
1901 1902 1904 1905 1906 1908	<i>Puc. Sambuci</i> (Schw.) Arth. (<i>P. Atkinsoni- ana</i> Diet., <i>P. Bolley- ana</i> Sacc.)	<i>Carex Frankii</i> 85 <i>C. lupulina</i> 65 <i>C. lurida</i> 21, 124 <i>C. trichocarpa</i> 14, 21, 52	<i>Sambucus canadensis</i> 14, 21, 52, 65, 85, 124
1904 1905	<i>Puc. Polygoni-amphibii</i> Pers.	<i>Polygonum emersum</i> 53, 69, 53	<i>Geranium maculatum</i> 53, 69
1910	<i>Puc. argentata</i> (Schultz) Wint.	<i>Impatiens aurea</i> 189	<i>Adoxa Moschatellina</i> 189
1909	<i>Urom. Andropogonis</i> Tracy	<i>Andropogon virginicus</i> 163	<i>Viola cucullata</i> 163
1902 1917	<i>Urom. seditiosus</i> Kern (<i>U. Aristidae</i> Auth. not E. & E.)	<i>Aristida basiramea</i> 279 <i>A. oligantha</i> 23	<i>Plantago aristata</i> 279 <i>P. lanceolata</i> 279 <i>P. Rugelii</i> 23
1916	<i>Urom. Sporoboli</i> E. & E.	<i>Sporobolus virginiae- florus</i> 274	<i>Allium stellatum</i> 274
1915	<i>Urom. Hordei</i> Tracy	<i>Hordeum pusillum</i> 263	<i>Nothoscordium striatum</i> 263
1911	<i>Urom. Peckianus</i> Farl.	<i>Distichlis spicata</i> 209	<i>Atriplex hastata</i> 209
1905 1907 1909 1910 1912 1917	<i>Urom. Polemonii</i> (Peck) Barth. (<i>U. acumina- tus</i> Arth., <i>U. Spar- tinae</i> Farl., <i>U. Steir- onematis</i> Arth., <i>U. magnatus</i> Arth.)	<i>Spartina Michauxiana</i> 76, 106, 164, 198, 236, 282	<i>Collomia linearis</i> 236 <i>Polemonium reptans</i> 198 <i>Polygonatum biflorum</i> 282 <i>P. commutatum</i> 282 <i>Steironema ciliatum</i> 76, 106, 164 <i>S. lanceolatum</i> 164 <i>Vagnera stellata</i> 282
1906 1907 1908 1914	<i>Urom. Scirpi</i> (Cast.) Burr.	<i>Scirpus fluviatilis</i> 89, 106, 128, 242	<i>Cicuta maculata</i> 89, 106, 128 <i>Sium cicutaefolium</i> 242
1903 1910 1912 1914 1917	<i>Urom. perigynius</i> Halst. (<i>U. Solidagini- Curicis</i> Arth.)	<i>Carex deflexa</i> 190 <i>C. intumescens</i> 190, 234 <i>C. sparganioides</i> 279 <i>C. tribuloides</i> 242 <i>C. varia</i> 37	<i>Aster ericoides</i> 190 <i>A. paniculatus</i> 190, 234 <i>A. Tweedyi</i> 242 <i>Rudbeckia laciniata</i> 279 <i>Solidago caesia</i> 37 <i>S. canadensis</i> 37, 234 <i>S. flexicaulis</i> 37 <i>S. serotina</i> 37 <i>S. rugosa</i> 190

Year	Rust	Telial host	Aecial host
1910 1912	<i>Urom. Junci</i> (Desm.) Tul.	<i>Juncus balticus</i> 191, 236	<i>Ambrosia artemisiæ- folia</i> 191 <i>A. psilostachya</i> 191 <i>A. trifida</i> 191 <i>Cirsium Flodmanii</i> 191, 236
1906 1907	<i>Urom. Silphii</i> (Syd.) Arth.	<i>Juncus tenuis</i> 92, 106	<i>Silphium perfoliatum</i> 92, 106
1908	<i>Urom. houstoniatus</i> (Schw.) Sheldon	<i>Sisyrinchium gram- ineum</i> 129	<i>Houstonia caerulea</i> 129 .
1908 1911	<i>Gym. Libocedri</i> (P. Henn.) Kern	<i>Libocedrus decurrens</i> 143, 211	<i>Amelanchier vulgaris</i> 211 <i>Crataegus cerronis</i> 211 <i>C. Pringlei</i> 143 <i>C. tomentosa</i> 211
1907 1911	<i>Gym. inconspicuum</i> Kern	<i>Juniperus utahensis</i> 113, 211	<i>Amelanchier erecta</i> 113 <i>A. vulgaris</i> 211
1909	<i>Gym. exiguum</i> Kern	<i>Juniperus virginiana</i> 169	<i>Crataegus Pringlei</i> 169
1908 1910	<i>Gym. Davisii</i> Kern	<i>Juniperus sibirica</i> 132, 194	<i>Aronia arbutifolia</i> 194 <i>A. nigra</i> 132, 194
1906 1907 1908 1910	<i>Gym. juvenescens</i> Kern	<i>Juniperus scopulorum</i> 93, 107, 130 <i>J. virginiana</i> 195	<i>Amelanchier canadensis</i> 93, 107 <i>A. erecta</i> 107, 130, 195 <i>A. intermedia</i> (A. <i>Botryapium</i>) 107 <i>Sorbus americana</i> 93, 107, 130
1911	<i>Gym. Kernianum</i> Bethel	<i>Juniperus utahensis</i> 216	<i>Amelanchier vulgaris</i> 216
1909	<i>Gym. trachysorum</i> Kern	<i>Juniperus virginiana</i> 172	<i>Crataegus cerronis</i> 172 <i>C. coccinea</i> 172 <i>C. punctata</i> 172
1908 1914	<i>Gym. Botryapites</i> (Schw.) Kern	<i>Chamaecyparis thyoides</i> 131, 242, 243	<i>Amelanchier canadensis</i> 242, 243 <i>A. intermedia</i> 131
1907 1909 1910 1911 1914	<i>Gym. nidus-avis</i> Thax.	<i>Juniperus virginiana</i> 108, 129, 165, 194, 210, 242	<i>Amelanchier erecta</i> 210 <i>A. vulgaris</i> 194, 242 <i>Crataegus Pringlei</i> 165 <i>Cydonia vulgaris</i> 194 <i>Malus coronaria</i> 129, 210 <i>M. Malus</i> 108, 129 <i>M. ioensis</i> 165

Year	Rust	Telial host	Aecial host
1907 1908 1909 1910	<i>Gym. clavipes</i> C. & P.	<i>Juniperus sibirica</i> 107, 164, 193 <i>J. virginiana</i> 130	<i>Amelanchier erecta</i> 107, 164, 193 <i>A. intermedia</i> 107 <i>Crataegus punctata</i> 164 <i>C. tomentosa</i> 193 <i>C. sp.</i> 130
1908 1909 1910	<i>Gym. cornutum</i> (Pers.) Arth.	<i>Juniperus sibirica</i> 131, 165, 194	<i>Sorbus americana</i> 131, 165, 194 <i>S. aucuparia</i> 165
1908 1909	<i>Gym. exterum</i> Arth. & Kern	<i>Juniperus virginiana</i> 144, 166	<i>Porteranthus stipulatus</i> 144, 166
1911	<i>Gym. juniperinum</i> (L.) Mart. (<i>G. tremel-</i> <i>loides</i> Hartig)	<i>Juniperus sibirica</i> 211	<i>Sorbus americana</i> 211
1911 1912	<i>Gym. gracilens</i> (Peck) Kern & Bethel	<i>Juniperus monosperma</i> 217 <i>J. utahensis</i> 237	<i>Philadelphus coronarius</i> 217, 237 <i>P. Keteleerii</i> 237
1911	<i>Gym. effusum</i> Kern	<i>Juniperus virginiana</i> 217	<i>Aronia arbutifolia</i> 217
1907 1908 1910 1911 1913	<i>Gym. clavariaeforme</i> (Jacq.) DC.	<i>Juniperus sibirica</i> 108, 130, 194, 210, 238	<i>Amelanchier erecta</i> 130, 194, 210 <i>A. intermedia</i> 108 <i>Crataegus cerronis</i> 238 <i>C. punctata</i> 194
1914	<i>Gym. Ellisii</i> (Berk.) Farl.	<i>Chamaecyparis thyoides</i> 246	<i>Myrica cerifera</i> 246
1907 1908 1909 1910 1912	<i>Gym. Betheli</i> Kern	<i>Juniperus scopulorum</i> 112, 113, 131, 165, 195, 237	<i>Crataegus cerronis</i> 165, 195 <i>C. coccinea</i> 112 <i>C. cordata</i> 113 <i>C. Pringlei</i> 237 <i>C. punctata</i> 112 <i>C. sp.</i> 131 <i>Sorbus americana</i> 112, 113, 131
1906 1907 1908 1909	<i>Gym. globosum</i> Farl.	<i>Juniperus virginiana</i> 90, 107, 130, 164	<i>Crataegus coccinea</i> 164 <i>C. Pringlei</i> 90, 130 <i>Malus coronaria</i> 90 <i>M. Malus</i> (Pyrus <i>Malus</i>) 107 <i>Sorbus americana</i> 90
1911 1912	<i>Gym. Nelsoni</i> Arth.	<i>Juniperus scopulorum</i> 237 <i>J. utahensis</i> 215	<i>Amelanchier canadensis</i> 237 <i>A. vulgaris</i> 215

Year	Rust	Telial host	Aecial host
1909	<i>Gym. corniculans</i> Kern	<i>Juniperus horizontalis</i> 170	<i>Amelanchier canadensis</i> 170 <i>A. erecta</i> 170
1908 1909	<i>Gym. floriforme</i> Thax.	<i>Juniperus virginiana</i> 129, 166	<i>Crataegus coccinea</i> 166 <i>C. punctata</i> 129
1905 1906 1907 1908 1910	<i>Gym. Juniperi-virginianae</i> Schw.	<i>Juniperus virginiana</i> 64, 90, 106, 129, 193	<i>Malus coronaria</i> 90, 129 <i>M. Malus</i> (<i>Pyrus Malus</i>) 64, 106, 129, 193
1905 1906	<i>Tranz. punctata</i> (Pers.) Arth. (<i>Puc. Prunispinosae</i> Pers.)	<i>Prunus pumila</i> 89 <i>P. serotina</i> 71, 89	<i>Hepatica acutiloba</i> 71, 89
1903 1904 1905 1908	<i>Mel. Medusae</i> Thüm.	<i>Populus deltoides</i> 35, 46, 64 <i>P. tremuloides</i> 47, 133	<i>Larix decidua</i> 35, 46, 47, 64 <i>L. laricina</i> 46, 64, 133
1910 1911	<i>Mel. albertensis</i> Arth.	<i>Populus tremuloides</i> 198, 212	<i>Pseudotsuga mucronata</i> 198, 212
1904 1906	<i>Mel. Bigelowii</i> Thüm.	<i>Salix amygdaloides</i> 54 <i>Salix</i> sp. 84	<i>Larix decidua</i> 54, 84
1910	<i>Mel'sis abietina</i> (A. & S.) Arth.	<i>Ledum groenlandicum</i> 195	<i>Picea mariana</i> 195
1910	<i>Mel'ella elatina</i> (A. & S.) Arth.	<i>Cerastium oreophilum</i> 212	<i>Abies lasiocarpa</i> 212
1909	<i>Calyp. columnaris</i> (A. & S.) Körn.	<i>Vaccinium pennsylvanicum</i> 166	<i>Abies Fraseri</i> 166
1906 1910 1913	<i>Cron. Quercus</i> (Brond.) Schroet.	<i>Quercus Phellos</i> 238 <i>Q. rubra</i> 195, 238 <i>Q. velutina</i> 84	<i>Pinus virginiana</i> 84, 195 <i>P. taeda</i> 238
1910 1911 1913 1914	<i>Coleos. Vernoniae</i> B. & C.	<i>Vernonia crinita</i> 198 <i>V. fasciculata</i> 239, 243 <i>V. gigantea</i> 211	<i>Pinus palustris</i> 239 <i>P. taeda</i> 198, 211, 239, 243

INDEX

A consecutive paging of the reports has been adopted in order to simplify the index. It corresponds to the original paging as follows:

- Pages 1-9 (Botanical Gazette 29: 268-276).
" 10-15 (Journal of Mycology 8: 51-56).
" 16-29 (Botanical Gazette 35: 10-23).
" 30-43 (Journal of Mycology 10: 8-21).
" 44-61 (Journal of Mycology 11: 50-67).
" 62-78 (Journal of Mycology 12: 11-27).
" 79-95 (Journal of Mycology 13: 189-205).
" 96-115 (Journal of Mycology 14: 7-26).
" 116-147 (Mycologia 1: 225-256).
" 148-175 (Mycologia 2: 213-240).
" 176-202 (Mycologia 4: 7-33).
" 203-219 (Mycologia 4: 49-65).
" 220-248 (Mycologia 7: 61-89).
" 249-265 (Mycologia 8: 125-141).
" 266-284 (Mycologia 9: 294-312).
" 285-296 (Mycologia 13: 12-23).
" 279-329 (Mycologia 13: 230-262).

Names in *italics* are synonyms.

Numbers in broad-faced type indicate successful cultures.

Numbers in square brackets refer to pages (1) where the common name is used for the species instead of the Latin name, or (2) where the name occurs but is not the species intended and not a synonym (*e.g.*, *Anchusa officinalis* for *Lycopsis arvensis*), or (3) where the name does not occur but some other name not a synonym (the error being due to wrong identification, *e.g.*, *Gymnosporangium Nelsoni* used for *G. juvenescens*, or to common but erroneous usage, *e.g.*, *Spartina cynosuroides* for *S. Michauxiana*).

FUNGUS INDEX

- Aecidium abundans* (Puc. Crandallii) 197
albiperidium (Puc. Grossulariae) 12, 15
alliticolum (Urom. Sporoboli) 273, 275
Asterum (Puc. extensicola) 13, 15
Berberidis (Puc. poculiformis) 15
Blasdaleanum (Gym. Libocedri) 143
Calystegiae (Puc. Convolvuli) 9
Ceanothi (Puc. Ceanothi) 168
Cephalanthi (Puc. Seymouriana) 75
Clematidis or *Clematidis* (Puc. Agropyri) 57
compositarum Silphii (Urom. Silphii) 92
cornutum (Gym. cornutum) 132
Dracunculi (Puc. universalis) 110
elatinum (Melampsorella elatina) 212
erigeronatum (Puc. extensicola) 13, 15
Euphorbiae (Urom. Euphorbiae) 9, 15
Fraxini (Puc. fraxinata) 8, 9
fumariaceum (Puc. subnitens) 278
hepaticatum (Puc. Pruni-spinosae) 71
houstoniatum (Urom. houstoniatum) 128
Hydrophylli (Puc. apocrypta) 262, 265
hynoideum 41
Impatientis (Puc. Impatientis) 24
Iridis (Puc. Majanthae) 253
Jamesianum (Puc. Jamesiana) 24
leucospermum (Urom. Lespedezae-procumbentis) 36
Liatridis (Puc. Liatridis) 273
Lycopi (Puc. angustata) 6, 9, 15
macrosporum (Puc. macrospora) 135
magnatum (Urom. magnatus) 282
malvicola (Puc. Muhlenbergiae) 272
monoicum (Puc. monoica) 213
Napaeae (Puc. Muhlenbergiae) 142
Nesaeae (Puc. minutissima) 245
obesum (Puc. Seymouriana) 258, 265
occidentale (Puc. Agropyri) 57
Oxalidis (Puc. Sorghi) 59
Pammelii (Puc. Pammelii) 50
Peckii (Puc. Peckii) 19
Penistemonis (Puc. Andropogonis) 5, 9
Phrymae (Puc. Phrymae) 111
Polemonii (Urom. acuminatus) 198
Pteleae (Puc. Windsoriae) 6, 9, 22
punctatum (Puc. Pruni-spinosae) 70
pustulatum (Puc. pustulata) 39
Ranunculi (Puc. Eatoniae) 40
rubellum (Puc. Phragmitis) 3, 9
Sambuci (Puc. Sambuci) 14, 15, 20
sanguinolentum (Puc. Polygoni-amphibii) 32, 53, 69
sclerothecioides (Puc. Stipae) 189
Silphii (Urom. Silphii) 92
Solidaginis (Puc. extensicola) 27
Urticae (Puc. Caricis) 3, 9, 15
verbenicola (Puc. verbenicola) 7, 9, 22
Bullaria tumidipes 260
Vernoniae 274
Caecoma erigeronatum (Puc. extensicola) 13
miniata (Phrag. speciosum) 4, 9
occidentale (Melampsora albertensis) 199
Ulmariae (Triphragmium Ulmariae) 9
Calyptospora columnaris 166, 175
Coleosporium Campanulae 46
Vernoniae 198, 202, 211, 219, 239, 243, 248
Cronartium Quercus 84, 94, 195, 202, 239, 248
Gymnoconia interstitialis 207

- Gymnosporangium Betheli 112, 115,
 131, 147, 165, 174, 194, 201, 237,
 247
 biseptatum (G. Botryapites) 131
 Botryapites 131, 147, 242, 248
 clavariaeforme 108, 115, 130, 146,
 193, 201, 210, 218, 238, 247
 clavipes 107, 115, 130, 146, 164,
 174, 193, 201
 corniculans 170, 171, 175
 cornutum 131, 147, 165, 174, 194,
 201
 Davisii 132, 147, 151, 194, 201
 durum (G. Nelsoni) 215, 219, 237,
 247
 effusum 216, 219
 Ellisii 245, 248
 exiguum 169, 175
 exterum 144, 147, 166, 175
 floriforme [129], [146], 166, 174
 globosum 90, 95, 107, 114, 130, 146,
 164, 174
 gracilens 217, 219, 237, 247
 inconspicuum 113, 115, 211, 218
 juniperinum 211, 219
 Juniperi-virginianae 64, 77, 90, 95,
 106, 114, 129, 146, 193, 201
 juvenescens [93], [95], [107],
 [114], [130], [146], [195],
 [201], 216
 Kernianum 216, 219
 Libocedri 143, 147, 211, 219
 macropus (G. Juniperi-virginianae)
 65
 Nelsoni [93], [95], [107], [114],
 [130], [146], [195], [201],
 215, 219, 237, 247
 Nidus-avis 108, 115, 165, 174, 194,
 201, 210, 218, 242, 248
 speciosum (G. gracilens) 217
 trachysorum 172, 175
 tremelloides (G. juniperinum)
 132, 211, 219
 Lecythea macrosora (Mel. Bigelowii)
 55
 Melampsora albertensis 198, 202,
 212, 219
 Bigelowii 54, 61, 84, 94
 Lini 91, 95
 Medusae 35, 42, 46, 60, 64, 77,
 133, 147
 paradoxa (M. Bigelowii) 55
 Melampsorella elatina 212, 219
 Melampsoropsis abietina 195, 202
 Nigredo Polemonii 282
 Peridermium carneum (Coleos. Ver-
 noniae) 198, 211, 239, 243
 Cerebrum (Cronart. Quercus) 84,
 195
 fusiforme (Cronart. Quercus) 238,
 248
 Phragmidium speciosum 4, 9, 23, 28,
 47, 60, 106, 114
 Puccinia Absinthii 134, 147, 190, 201
 Agropyri [100], 104, 114, 232,
 241, 247, 252, [256], [265], 276,
 292, 293
 albiperidia (P. Grossulariae) 12,
 15, 33, 42, 52, 61, 65, 77, 86, 94,
 102, 113, 184, 226, 227, 237, 246,
 290
 alternans (P. Agropyri) 139, 147,
 [256], [265], 293
 americana (error for P. Andro-
 pogonis) [5], [9]
 amphigena 26, 29, 33, 42, 67, 77,
 104, 114, 160, 173, 187, 200, 250
 Andropogonis [5], [9], 33, 42, 87,
 94, 186, 200
 angustata 6, 9, 12, 15, 52, 61, 86,
 94, 103, 114, 125, 146, 186, 200,
 208, 218, 229, 247
 Anthoxanthi 180
 apocrypta (partly error for P. mon-
 tanensis) [261], 262, [263],
 [265]
 argentata 189, 201
 Arundinariae 100
 Asperifolii 127, 146, 257, 265
 Asteris 123
 Asterum 288
 Atkinsoniana (P. Sambuci) 11, 20,
 21
 Bartholomaei (P. Jamesiana) 24
 Blasdalei [112], [115]
 Bolleyana (P. Sambuci) 14, 15,
 20, 21, 52
 canaliculata 74, 78

- caricina* 11, 293
Caricis 3, 9, 11, 15, 22, 28, 66, 77, 103, 113, 158, 173, 186, 200, 293
Caricis-Asteris (P. *extensicola*) 13, 15, 21, 28, 102, 113, 159, 173, 185, 197, 199, 228, 246, 287
Caricis-Erigerontis (P. *extensicola*) 12, 15, 21, 28, 52, 61, 287
Caricis-Solidaginis (P. *extensicola*) 27, 29, 66, 77, 124, 146, 184, 199, 228, 246, 287
Caricis-strictae 66
caulicola 36, 42
Ceanothi 168, 175
Chloridis 18
cinerea (P. *Agropyri*) 137, 147, 208, 218, 292, 293
Clematidis 293
Cockerelliana [256], [265]
Convolvuli 3, 9
Crandallii 64, 100, 196, 202
Cryptandri [109], [115], 223, 280
Distichlidis 154, 180, 260, 265, 271, 275, 291
Dulichii (P. *extensicola*) 121, 240, 246, 254, 264
Eatoniae 40, 42, 295
Eleocharidis 17, 74, 78, 87, 94, 124, 146
Ellisiana 99, 122, 155, 178, 230, 247
emaculata 11, 18, 32, 63, 82, 100, 121, 224, 251, 276
Eriophori 255, 265
exitiosa (P. *transformans*) 73
extensicola 229, 238, 239, 246, 254, 264, 288, 289
fraxinata 51, 60, 67, 77, 103, 114, 127, 146, 160, 174
graminis (P. *poculiformis*) 295, 296
Grindeliae 72, 78
Grossulariae 182, 199, 225, 246, 254, 265, 290
Helianthi 23, 28, 34, 42, 47, 60, 69, 78, 287
hydnoidea (error) 41, 42, 57
Impatientis 25, 29, 33, 42, 51, 60, 161, 174, 292
Isiaca 294
Jamesiana 24, 28, 188, 200
Koeleriae 138, 147
Kuhniae 74, 78, 124, 145
lateripes 69, 78, 294
Liatridis 273, 275, 292
Lithospermi 197, 202
ludibunda 46
Lygodesmiae 212, 219
macrospora 135, 147
Majanthae 277, 284
McClatchieana 223
minutissima 245, 248
monoica 215, 219, 234, 247
montanensis (partly error for P. *apocrypta*) [100], [180], [261], 262, [263], [265]
Muhlenbergiae 17, 142, 147, 161, 174, 187, 200, 241, 247, 271, 275
mutabilis [112], [115]
nigrescens (P. *caulicola*) 37
nodosa 244, 248
obliterata (P. *Agropyri*) 141, 147, 160, 174, 293
obtecta 109, 115
Opizii (P. *patruelis*) 84, 94, 185, 200
Pammelii 50, 60, 67, 77, 105, 114
Panici (P. *Pammelii*) 50
Paniculariae (P. *Agropyri*) 18
patruelis 136, 147
Peckii 11, 19, 28, 52, 61, 66, 77, 85, 94, 124, 145, 157, 173, 184, 199, 208, 218
peridermiospora (P. *fraxinata*) 8, 9
perminuta (P. *Impatientis*) 178
Phragmitis 2, 9, 104, 114, 160, 174, 208, 218
Phrymae 111, 115
poculiformis 12, 15, 51, 61, 68, 77, 88, 94, 105, 114, 122, 162, 174, 187, 200, 270, 275
Podophylli 59, 61
Polygoni-amphibii 18, 31, 53, 61, 69, 78, 82
Pruni-spinosae (Tranzschelia *punctata*) 70, 78, 89, 94
purpurea 18
pustulata 40, 42, 67, 77, 186, 200

- quadripurula* (P. Grossulariae) 197,
202, 235, 246
quadripurula (error for Urom. peri-
gynius) [197], [202], 235
Rhamni 52, 61, 187, 200, 252, 271,
275
Ribesii-Caricis (P. Grossulariae)
228
rubigo-vera 11, 128, 154, 291, 293
Ruelliae 294
Salviae-lanceolatae (P. caulicola)
37
Sambuci 21, 28, 52, 65, 77, 85, 94,
124, 146
Schedonnardi (P. Muhlenbergiae)
17, 82, 100, 122, 179, 207, 271,
275
Seymouriana 75, 78, 127, 146, 188,
200, 249, 258, 265
Silphii 72, 78, 88, 94
simillima 26, 29, 104, 114, 251
Solidaginis 73, 78
Sorgi 59, 61, 68, 78
Sporoboli 18, 279, 284
splendens 244, 248
Stipae 18, 57, 59, 61, 188, 200, 231,
247
striatula (P. Majanthae) 154
subnitens 25, 29, 48, 60, 67, 77, 87,
94, 104, 114, 125, 146, 160, 173,
187, 200, 208, 209, 218, 259, 265,
272, 275, 278, 284, 289, 293, 294
substerilis 75, 78, [109], [115],
154, 163, 174
Sydowiana (P. verbenicola) 7
tenuistipes 102
tomipara (P. Agropyri) [41], 56,
61, 87, 94, 127, 146, 233, 293
tosta (P. Muhlenbergiae) 32, 63,
179, 206, 240, 247
transformans 73, 78, 88, 94
trititica (P. Agropyri) 276, 292,
293
tumidipes 260, 265
unipurula (P. Grossulariae) 226,
227, 254, 265
universalis 110, 115, 159, 173, 185,
200, 270, 275
verbenicola [7], [9], 22, 28, 50,
60, 67, 77
Vernoniae 274, 275
vexans 32, 109, 115, 122
Vilfae (P. verbenicola) 7, 9, 22
virgata 99, 154, 179
vulpinoidis (P. extensicola) 120,
238, 246, 288
Windsoriae 6, 9, 22, 28, 50, 60,
259, 265
Xanthii 71, 78, 88, 94
Pucciniastrum Hydrangeae 277
Roestelia Betheli (Gym. Betheli) 113
cornuta (Gym. cornutum) 118, 150
Harknessianoides (Gym. inconspicuum) 113
hyalina (Gym. hyalinum) 150
penicillata (Gym. juniperinum)
118, 132
Tranzschelia punctata (Puc. *Prunispinosae*) 139
Tremella juniperina (Gym. juniperinum) 132
Triphragmium Ulmariae 4, 9
Uredo Oxytropi (Urom. Astragali)
192
rubigo-vera (Puc. Agropyri) 19,
28
Uromyces acuminatus 31, 75, 78, 83,
106, 114, 156, 198, 202, 236,
247, 283
Andropogonis 123, 163, 174
Archerianus 253
Aristidae (U. seditiosus) 23, 28
Astragali 192, 201
Caricis (Puc. Caricis-strictae) 66
effusus 83, 93
elegans 244, 248
Eleocharidis 83, 181
Euphorbiae 3, 9, 10, 15, 18, 28, 287
graminicola 64, 123, 155, 181, 269
Halstedii 17
Hordei 263, 265
houstoniatus 128, 146
Junci 17, 64, 93, 101, 155, 191,
201, 235, 247
Lespedezae-procumbentis 36, 42
magnatus 283, 284

- Medicaginis* 193, 201, 210, 218
Murrilli (*U. houstoniatus*) 128
Orobi 101
Peckianus 181, 209, 218, 289
perigynius 38, 190, [197], 201, 234, 242, 247, 279, 284, 288, 293
Phaseoli 36, 42
Polemonii 282, 291
Rhynchosporae 101, 224
Scirpi 89, 94, 106, 114, 128, 146, 242, 247, 253
seditiosus 278, 284
Silphii 92, 93, 95, 106, 114
Solidagini-Caricis (*U. perigynius*) 38, 42
Spartinae 164, 174, 181, 283
Sporoboli 17, 182, 225, 273, 275, 280
Steironematis 283
uniporulus 183, 291

HOST INDEX

- Abies alba* 167
 balsamea 17, 167, 277
 concolor 167, 277
 Fraseri 166, 167, 175
 lasiocarpa 212, 219
 magnifica 167
 nobilis 167
Abronia fragrans 155, 273, 275, 278
 umbellata 121, 223
Actaea alba 46, 51, 81, 82, 99, 122, 154, 162, 178, 223
 rubra 81
Adelia acuminata 51, 67
 ligustrina 51, 127
 segregata 51, 127
Adoxa moschatellina 189, 201
Aesculus glabra 18, 63, 81, 98, 99, 100, 101, 155, 180, 181, 206, 207, 224
Agoseris glauca 136, 147, 159
Agropyron biflorum 140, 142, 147
 caninum 142
 glaucum 276
 pseudorepens 105, 114, 162, 174
 repens 51, 61, 101, 163
 Smithii 232, 247, 270, 275, 276
 sp. 105, 160, 174
 tenerum 51, 61, 105, 114, 163, 187, 200, 262, 265
Agrostis alba 68, 77, 88, 94, 163, 187, 200
 hyemalis 178
 perennans 178
 sp. 271, 275
Allium Brandegei [112], [115]
 canadense 274, 280
 cernuum [112], [115], 280, 284
 Nuttallii 280, 284
 recurvatum [112], [115]
 reticulatum [112], [115] 225, 274
 stellatum 273, 275, 278, 280
Althaea rosea 81, 82, 123, 155, 161, 187
Ambrosia artemisiaefolia 63, 76, 92, 236
 psilostachya 192, 235, 236, 247
 trifida 6, 11, 25, 32, 45, 65, 71, 81, 82, 92, 101, 120, 121, 122, 134, 153, 154, 168, 180, 191, 236, 247
Amelanchier Botryapium 65, 107, 133
 canadensis 93, 95, 101, 107, 108, 109, 113, 114, 143, 165, 169, 170, 171, 175, 217, 237, 242, 243, 247, 248
 erecta 107, 113, 114, 115, 130, 132, 146, 157, 164, 165, 170, 171, 174, 175, 194, 195, 201, 207, 210, 211, 216, 217, 218
 intermedia 107, 108, 114, 115, 131, 147, 171
 sp. 90
 vulgaris 133, 194, 201, 211, 215, 216, 217, 218, 219, 242, 248
Amorpha fruticosa 121, 179, 181
 nana 168, 179, 180, 182
Amsonia salicifolia 243, 258
Amygdalis communis 70
 persica 71, 89
Anchusa officinalis [257], [265]
Andropogon furcatus 6, 39, 42, 67, 77, 186, 200
 glomeratus 123, 155

- Hallii* 168, 169, 175
scoparius 5, 6, 33, 39, 42, 87, 94,
 99, 122, 155, 178, 186, 200
sp. 186, 230, 247
virginicus 163, 174, 186, 200
Anemone canadensis 17, 19, 26, 29,
 64, 104, 114, 252
coronaria 70
cylindrica 26, 232, 247, 251, 252,
 256, 276
pennsylvanica 32
ranunculoides 71
virginiana 17, 26, 81, 104, 122
Anemonella thalictroides 81, 82, 98,
 178
Anthoxanthum odoratum 180
Apios Apios (A. tuberosa) 46, 81, 82,
 123, 179, 181, 225
Apocynum cannabinum 17, 24, 32,
 101, 122, 153, 178, 179, 180, 181,
 182, 197, 224, 258, 265
hypericifolium 258
Aquilegia caerulea 101, 141, 232
canadensis 64, 140, 147, 178, 242,
 256
elegantula 141
flavescens 141, 232, 242
formosa 141
sp. 252
truncata 141
Arabis Drummondii 214
Holboellii 120, 154, 159, 179, 180,
 189
retrofracta 215
sp. 99, 101, 213, 214, 219, 234, 247
Aragallus Lamberti 192, 201
Arisaema triphyllum 91
Aristida basiramea 279, 284
oligantha 23, 28
ramosissima 279
Arnica sp. 155, 179, 180, 182, 189,
 191, 196
Aronia arbutifolia 108, 157, 194, 201,
 217, 219, 242
nigra 93, 130, 132, 147, 165, 194,
 201
rotundifolia 133
Artemisia canadensis 111
dracunculoides 99, 110, 111, 115,
 121, 134, 147, 154, 159, 173, 185,
 190, 200, 201, 269
dracunculus 110, 111
frigida 111
gnaphalodes 270, 275
kansana 111
longifolia 159
ludoviciana 190
serrata 99
sp. 190, 201
Arundinaria macrosperma 100
Asclepias incarnata 24, 28, 45
pulchra 258
syriaca 24, 28, 188, 200, 258, 259,
 265
verticillata 225
Asclepiodora decumbens 24
Asprella Hystrix 262
Aster adscendens 159, 173, 185, 199
arenarioides [123]
cordifolius 11, 13, 14, 58, 102, 113
Drummondii 32, 58, 66, 121, 123,
 124, 153, 178, 190, 238, 240, 242
ericoides 32, 58, 59, 61, 75, 154,
 188, 190, 200, 201, 231
lateriflorus 279
multiflorus 57, 58, 59, 61, 75, 123,
 153, 154, 188, 200, 231
Novae-Angliae 58, 59, 61, 75, 188,
 200, 231
paniculatus 11, 12, 13, 14, 19, 20,
 21, 28, 32, 58, 66, 100, 102, 111,
 113, 120, 121, 123, 124, 153, 179,
 182, 184, 190, 197, 201, 202, 224,
 228, 229, 234, 235, 238, 240, 242,
 243, 246, 247, 254
prenanthoides 20, 32
sericeus 58
Shortii 19
Tripoli 229
Tweedyi 153, 159, 185, 240, 242,
 247
Astragalus canadensis 182
carolinianus 192, 201
sulphurescens 192, 201
Atheropogon curtispendus 24, 28,
 109, 115, 122, 188, 200

- Atriplex confertifolia* 206
 hastata 126, 146, 160, 173, 208, 209, 218, 289
Avena sativa 52, 61, 88, 105, 114, 163
Baptisia bracteata 225
 leucantha 110
 tinctoria 45, 142, 155, 168
Berberis Aquifolium 138
 repens 138
 vulgaris 12, 51, 61, 68, 77, 88, 94, 105, 114, 122, 138, 162, 174, 180, 187, 200, 270, 271, 275
Berula angustifolia 89
Bidens connata 109, 115
 frondosa 17, 101, 109, 110, 115
Boehmeria cylindrica 153, 158, 162, 168, 179, 186, 197
Boltonia asteroides 18, 32, 81, 99, 121, 179, 181, 189, 269, 270
Bouteloua curtipendula (see *Atheropogon*) 24, 32
 racemosa 109, 122
Brauneria purpurea 18
Brodiaea pauciflora 244, 248
Bromus ciliatus 11, 19, 41, 42, 56, 57, 61, 276
 Porteri 139, 140, 147
 Pumpellianus 139, 140
 purgans 57, 87, 94, 127, 146
 Richardsoni 140
Bursa bursa-pastoris 68, 77, 87, 100, 104, 114, 209
Cacalia reniformis 81, 120, 121, 123
Calamagrostis canadensis 154, 187, 200
Calamovilfa longifolia 26, 29, 33, 42, 67, 77, 104, 114, 160, 173, 187, 200, 250
Callirhoe digitata 223, 224, 240, 241
 involutrata 32, 81, 82, 83, 120, 123, 142, 147, 154, 155, 161, 174, 187, 200, 207, 224, 240, 241
Callistephus hortensis 123
Campanula americana 46
Campsis radicans 73
Capnoides montanum 277, 278
Cardamine bulbosa 100, 126
Carduus Flodmanii 180, 191, 192, 201, 236, 247
 undulatus 154, 158, 168
Carex aquatilis (error for *C. nebrascensis*) [66], [77]
 arctata 178, 226, 246, 254, 265
 aristata 158, 173, 186, 200
 Backii 153, 269
 blanda (see *tetanica*)
 Bonplandii minor 153
 brunnescens 197
 cephalophora 3
 comosa 119, 134, 136, 147
 crinita 53, 61, 86, 94, 102, 113, 226, 246
 deflexa 190, 191, 201
 Douglasii 99
 durifolia 255, 269
 extensa 229
 festiva 159, 173, 185, 199
 festucacea 13, 21, 28, 52, 61
 filifolia 270, 275
 filiformis 245, 248
 foeneia 13, 14, 21, 28
 Frankii 85, 94
 Goodenovii 197, 202, 235
 gracillima 33, 38, 39, 42, 53, 61, 183
 gravida 32, 46, 81, 99, 121
 intumescens 190, 191, 201, 234, 247
 Jamesii 27, 29, 66, 255
 lanuginosa 37, 38, 39, 52, 61, 66, 77, 85, 94, 157, 173, 184, 199, 208, 218
 longirostris 111, 112, 115
 lupulina 65, 77, 85
 lurida 11, 21, 28, 85, 124, 146
 maritima 221
 nebrascensis (under *C. aquatilis*) [66], [77]
 pallescens 182, 183, 199
 pennsylvanica 32, 45, 63, 81, 98, 120, 176, 178
 praecox 158
 pratensis 136, 137, 147
 pubescens 12, 38, 39, 183, 225, 226, 246, 254
 retrorsa 228, 246
 riparia 22, 28, 103, 113
 rosea 102, 113

- scoparia* 184, 191, 199, 228, 229, 246
siccata 154, 185, 200
sparganioides 66, 77, 124, 146, 279, 284
sp. 85, 94, 102, 121, 208, 237
squarrosa 86, 94
stellulata 178
stenophylla 110, 111, 115, 134, 159, 173, 185, 200, 270
stipata 20, 27, 28, 29, 66, 77, 103, 113, 124, 145
stricta 3, 11, 22, 28, 66, 186, 200
tenella 153, 178
tenuis 153, 182, 183, 199, 226, 246, 254, 265
tetanica (error for *blanda*) 11, 65, 77, 86, 94
tribuloides 242, 247
trichocarpa 11, 14, 19, 20, 21, 28, 52, 61, 85, 94, 158, 173, 184, 199
trisperma 178
varia 37, 38, 39, 42, [102], [191]
virescens 38, 39
vulpinoidea 120, 238, 240, 246
Cassia chamaecrista 17, 18, 32, 64, 76, 81, 83, 99, 100, 101, 155, 168, 180, 181, 225
Caulophyllum thalictroides 82, 99, 122, 162, 178
Ceanothus americanus 17, 32, 81, 82, 99, 142, 154, 155, 168, 175
ovatus 168
Cephalanthus occidentalis 75, 78, 127, 146, 188, 200, 258
Cerastium oreophilum 212, 219
Chamaecyparis thyoides 131, 147, 242, 245, 248
Cheiranthus Menziesii 213
Chelone glabra 120, 154, 155, 178, 223, 224
Chenopodium album 25, 29, 49, 50, 60, 87, 94, 104, 114, 126, 146, 160, 173, 187, 188, 200, 208, 209, 218, 253, 259, 265, 278, 284, 293
glaucum 50
hybridum 126
leptophyllum 25, 50
Chionanthus virginica 51
Chrysopsis villosus 231
Chloris elegans 253
verticillata 18
Chrysopogon avenaceus 99, 154, 179
Chrysothamnus nauseolus 73
Cicuta maculata 32, 53, 89, 90, 94, 106, 114, 128, 146, 242
Cimicifuga americana 51
racemosa 51
Cineraria palustris 255
Cinna arundinacea 12, 163
Clematis Douglasii 57, 232, 242
Drummondii 57, 241, 242, 247, 276
Flammula 276, 292
Fremontii 56, 57
lasiantha 57
ligusticifolia 57, 105, 232, 233, 247, 252, 256, 276, 292
Scottii 51, 56, 57
viorna 56, 57
virginiana 51, 56, 57, 61, 87, 94, 105, 114, 127, 146, 180, 232, 233, 242, 276, 292
vitalba 104, 276
Cleome serrulata 49, 50
spinosa 32, 49, 60, 208, 209, 218
Cleomella parviflora 50
Collomia linearis 236, 247
Comandra pallida 39
umbellata 39, 42, 67, 77, 123, 186, 200
Convallaria majalis 180, 278
Convolvulus sepium 3, 5
Corydalis aurea 160, 187, 225
glauca 160
montana 209
sempervirens 160, 188
Crataegus apiifolia 172
cerronis 157, 165, 172, 174, 175, 195, 201, 211, 216, 219, 238, 248
coccinea 65, 112, 115, 157, 164, 166, 172, 174, 175
cordata 113, 115, 173
flavo-carius 173
Marshallii 172
Phaenopyrum 173
Pringlei 90, 93, 95, 130, 143, 146,

- 147, 165, 169, 174, 175, 237, 247
punctata 106, 112, 115, 129, 130,
 144, 146, 157, 164, 172, 174, 175,
 194, 201, 237
sp. 107, 113, 130, 131, 146, 147, 157,
 170
tomentosa 108, 193, 194, 201, 211,
 217, 219
Cydonia vulgaris 157, 194, 195, 201,
 210
Cyperus esculentus 74, 78
Dactylis glomerata 19
Dalea laxiflora 122, 142
Dasystoma flava 123
Decodon verticillatus 101, 121, 123,
 126, 245, 248
Delphinium formosum 179
Geyeri 232
scaposum 168, 180
tricorne 100, 122, 180
Dirca palustris 41, 42, 56, 57, 81, 82,
 86, 101, 122, 154, 162, 178, 179,
 180, 181, 223, 224, 259
Distichlis spicata 25, 29, 48, 49, 60,
 67, 77, 87, 94, 104, 114, 125, 146,
 160, 173, 181, 187, 200, 206, 208,
 209, 218, 259, 265, 272, 275, 278,
 284, 289, 293
Dodecatheon Meadia 64
Doellingeria umbellata 184, 224
Dulichium arundinaceum 121, 240,
 246, 254, 264
Draba caroliniana 100
Eatonia pennsylvanica 40, 42
Eleagnus angustifolia 180, 182
argentea 224, 232, 252, 269, 270
Eleocharis palustris 17, 74, 78, 83, 87,
 94, 124, 146, 181
Elephantopus carolinianus 198, 243
Elymus brachystachys 100
canadensis 32, 45, 51, 61, 88, 94,
 162, 163, 174, 180, 232, 247, 270,
 275, 276
condensatus 100, 262
striatus 161, 162, 174
virginicus 25, 29, 33, 42, 51, 60, 162,
 174, 241, 247, 262, 265, 276, 292
Erigeron annuus 11, 13, 14, 19, 21, 27,
 28, 45, 52, 61, 102, 111, 153, 182,
 225, 234
arenarioides [123]
philadelphicus 22, 28
Eriocoma cuspidata 101
Eriophorum angustifolium 255
polystachyon 256
tenellum 256
virginicum 256
viridicarinatum 255, 256, 265
Erysimum asperum 49, 60, 68, 77
Euonymus obovatus 17, 46, 54
Eupatorium perfoliatum 11, 18, 32,
 74, 78, 87, 94, 124, 146
serotinum 154, 181
Euphorbia arkansana coloradensis 101
commutata 36, 182, 276
corollata 50, 60, 67, 77, 105, 224,
 251, 269, 276, 277
cyparissias 192, 193, 224
dentata, 19, 28
humistrata 18, 19, 28
Ipecacuanhae 277
maculata 4, 10, 11
marginata 18, 19, 105, 114
nutans 4, 10, 11, 18, 19, 28
robusta 267
Euthamia graminifolia 184, 199, 229,
 234, 242, 243, 246
Evolvulus pilosus 197, 202
Falcata comosa 64, 81, 99, 100
Festuca confinis 64, 100, 196, 202
Thurberi 256, 265
Forestiera porulosa 51
Fraxinus lanceolata (*F. viridis*) [8],
 51, 60, 67, 77, 103, 114, 127, 146,
 160, 174, 180
Gaura biennis 158, [173], 184
Geranium carolinianum 82
maculatum 13, 19, 22, 32, 53, 61,
 69, 78, 81
palustre 82
pratense 82
pusillum 69, 81, 82
Robertianum 69, 81
Gillenia stipulacea 117, 144, 145, 166
Glaux maritima 89, 90

- Grindelia squarrosa* 122, 154, 155, 179, 188, 189, 191, 196, 200, 231
Gutierrezia Sarothrae 64, 72, 73, 78, 231, 247
Helianthus angustifolius 224
 annuus 34, 42, 48, 60, 69, 78, 287
 decapetalus 48
 divaricatus 48, 60
 grosse-serratus 17, 23, 28, 34, 47, 48, 60, 69, 78
 hirsutus 48, 60
 Kellermani 48, 60
 laetiflorus 47, 48, 60
 Maximiliani 18, 23, 28, 34, 48
 mollis 34, 42, 47, 48, 60
 occidentalis 48, 60
 orygalis 48
 rigidus 34
 scaberrimus 48, 60
 strumosus 17, 23, 34, 48, 60
 tomentosus 34, 48, 60
 tuberosus 34, 48
Heliotropium curassavicum 154
Hepatica acuta 11
 acutiloba 71, 78, 89, 94
Hibiscus militaris 45, 123, 142, 155, 187, 223, 241
 Moscheutos 81, 82, 100, 142
Hippurus vulgaris 89
Holcus lanatus 252
Homalocenchrus virginicus 17
Hordeum jubatum 19, 154, 252
 nodosum [264]
 pusillum 263, 264, 265
 vulgare 88, 94, 163
Houstonia caerulea 92, 128, 129, 146, 277, 279
 purpurea 82, 83, 92, 99
Hydrangea arborescens 277
Hydrocotyle australis 253
Hydrophyllum appendiculatum 17, 18, 31, 64, 66
 capitatum 99, 179, 180, 196, 198, 207, 232, 262, 265
 Fendleri 223, 232
 virginicum 99, 100, 101, 121, 122, 154, 155, 162, 168, 179, 181, 189, 223
Hymenoclea monogyna 244, 248
Hypoxis erecta 99, 101
Ilex opaca 100
Impatiens aurea 11, 14, 17, 18, 19, 25, 29, 32, 33, 42, 51, 56, 60, 161, 162, 174, 180, 189, 201
Ipomoea pandurata 5, 122, 162, 239
Iris versicolor 17, 92, 99, 102, 121, 197, 223, 253, 277, 278, 282, 284
Isopyrum biternatum 18, 37, 81, 82, 122, 178, 180
Iva frutescens 122, 126, 134, 153
Juncus balticus 101, 155, 191, 192, 201, 235, 247
 dichotomus 93
 effusus 64, 82, 83
 tenuis 17, 92, 93, 95, 106, 114
Juniperus communis 133
 horizontalis 151, 170, 171, 175
 monosperma 217, 219
 scopulorum 93, 95, 107, 112, 114, 115, 130, 131, 146, 147, 165, 174, 194, 201, 237, 247
 sibirica 107, 108, 115, 130, 131, 132, 146, 147, 150, 151, 164, 165, 174, 193, 194, 201, 210, 211, 218, 219, 238, 248
 utahensis 113, 115, 211, 215, 216, 218, 219, 237, 247
 virginiana 64, 77, 90, 95, 106, 107, 108, 114, 115, 129, 130, 144, 145, 146, 147, 157, 164, 165, 166, 169, 171, 173, 174, 175, 193, 194, 195, 201, 210, 216, 218, 219, 242, 247
Koeleria cristata 137, 139, 147, 189, 200, 213, 234, 247, 273, 275, 292
Kuhnia eupatorioides 74, 78, 124, 145
 Hitchcockii 124, 145
Kuhnistera purpurea 17
Laciniaria Langloisii 243
 punctata 120, 154, 155, 178, 179, 211, 230, 243, 273, 275
 pyncnostachya 81
 scariosa 17, 18, 155, 181, 189, 198, 211, 236
 spicata 99, 100, 101, 121, 154, 155, 178, 179, 181
Lactuca canadensis 18, 32, 81, 82, 85, 92, 94, 99, 185, 200
 sativa 84, 85, 94, 154, 185, 200

- scariola (partly under *L. virosa*)
[85], [92], [94], 182
- Larix decidua* (*L. europaea*) 17, 35,
42, 46, 47, 54, 55, 60, 61, 64, 84,
94
- laricina (*L. americana*) 46, 55, 60,
64, 77, 91, 133, 147, 198, 212
- Lyallii 54, 55
- Lathyrus decapetalus* 101
- palustris 101, 182
- Ledum groenlandicum* 195, 202
- Lepachys pinnata* 99, 100
- Lepargyrea canadensis* 153, 154, 155,
168, 179, 180, 181, 182, 224, 232
- Lepidium apetalum* [17], [45], [49],
[50,] [60]
- densiflorum [17], [45], [49], [50],
[60]
- virginicum 49, 60, 68, 77, 209
- Leptilon canadense* 19, 22, 28
- Lespedeza capitata* 36, 42
- Leucocrinum* sp. 251
- Liatris punctata* 273
- Libocedrus decurrens* 143, 147, 211,
219
- Ligularia sibirica* 255
- Ligustrum ovalifolium* 51
- vulgare 51, 67, 127
- Lilium elegans* 279
- umbellatum 279, 280, 284
- Linum Lewisii* 91, 95
- usitatissimum 91, 95
- Lithospermum angustifolium* 154, 155,
230
- arvense 154
- canescens 154, 168, 179, 180
- officinalis 224
- Lobelia syphilitica* 46
- Lonicera japonica* 64
- Lycium pallidum* 260, 265
- vulgare 260, 265
- Lycopsis arvensis* (partly under *An-
chusa officinalis*) 128, 146, 154,
[257], [265]
- Lycopus americanus* 6, 12, 52, 61, 87,
94, 103, 114, 125, 146, 186, 200,
208, 218, 230, 247
- communis 125, 146
- Lygodesmia juncea* 212, 219
- Lysimachia quadrifolia* 76, 83, 100,
106, 121, 164, 178, 179
- terrestris 76, 83, 178, 181, 182, 191,
197
- thyrsiflora 76
- Macrocalyx Nyctelea* 46, 81, 82, 121,
180, 197
- Mahonia Aquifolium* 123, 138, 147,
180
- Maianthemum canadense* 278, 280, 282
- Malus coronaria* 90, 95, 107, 129, 146,
157, 195, 210, 217, 218
- ioensis 164, 165, 174
- Malus* 64, 65, 77, 106, 107, 108, 114,
115, 129, 130, 131, 146, 157, 166,
193, 201, 217
- Malvastrum coccineum* 206, 225, 241,
271, 272, 275
- Medicago sativa* 182, 193, 201, 210,
218
- Menyanthes trifoliata* 101
- Merioliix serrulata* 178, 184, 199, 208
- Mertensia virginica* 100, 155
- sp. 101
- Mimulus ringens* 45, 154, 155, 162,
179, 181
- Monolepis Nuttalliana* 126, 187, 188,
208
- Muhlenbergia diffusa* 82
- glomerata [142], [147], 161, 174
- gracilis 187
- gracillima 271, 275
- mexicana 45, 142, [147]
- Porteri [240]
- racemosa 17, 45, 187, 200
- tenuiflora 100
- Myosotis palustris* 81, 83, 100, 154,
162, 168
- Myrica cerifera* 100, 134, 178, 179,
180, 197, 246, 248
- Napaea dioica* 6, 17, 25, 32, 63, 81,
82, 83, 87, 98, 99, 100, 101, 121,
122, 123, 161, 168, 187, 241
- Naumburgia thyrsiflora* 76
- Notholcus lanatus* 252
- Nothoscordium bivalve* (*N. striatum*)
263, 264, 265

- Oenanthë aquatica* 90
californica 90
Onagra biennis (*Oenothera biennis*)
 6, 11, 19, 20, 21, 22, 27, 28, 32,
 52, 61, 66, 77, 85, 86, 94, 124, 145,
 153, 158, 173, 184, 185, 199, 208,
 218, 234
pallida 207
Onosmodium hispidissimum 180
occidentale 179, 232
Orchis spectabilis 178
Ornithogalum bivalve 263
umbellatum 363
Oryzopsis cuspidata 101
Oxalis Bowiei 68
corniculata 68
cymosa 17, 18, 32, 59, 61, 68, 78
Ortigiesi 68
violacea 46
Oxygraphis Cymbalaria 137, 147, 208,
 218
Oxypolis rigidus 89, 106
Oxytropis Lamberti 192
Panicularia americana 18
Panicum capillare 11, 18, 32, 63, 82,
 100, 121, 224, 251, 276
virgatum 50, 60, 64, 67, 77, 105,
 114, 123, 155, 181, 224, 269
Parthenium integrifolium 82, 92
Pastinaca sativa 89
Pentstemon alpinus 186, 200
barbatus 186
hirsutus (*P. pubescens*) 5, 6, 32, 33,
 39, 42, 67, 87, 94, 122, 123, 186,
 200
Petalostemon purpureus 154, 155, 168,
 179, 180, 181
Phacelia bipinnatifida 101, 122, 154,
 155
heterophylla 179, 232
tanacetifolia 223
Phalaris arundinacea 180, 278, 284
Phaseolus diversifolius 36
Philadelphus coronarius 216, 217,
 219, 237, 247
Keteleerii 237, 247
Phleum pratense 122
Phlox divaricata 17, 81, 181, 198
subulata 81
Phragmites communis (*P. Phrag-*
mites) 2, 26, 29, 104, 114, 160,
 174, 208, 218, 251, 294
Phryma leptostachya 99, 111, 115,
 178
Physalis heterophylla 32
pubescens 225
sp. 180
Physalodes Physalodes 17, 32
Picea canadensis 17, 277
mariana 195, 202
Pinus palustris 239, 248
rigida 46
taeda 198, 202, 211, 219, 238, 239,
 243, 248
virginiana 84, 94, 195, 202
Pisum sativum 182
Plantago aristata 24, 279, 284
eriopoda 24
lanceolata 23, 279, 284
Purshii 24
Rugelii 23, 28, 279
virginica 23, 24
Poa compressa 19
longiligula 101
Podophyllum peltatum 59, 61
Polemonium reptans 32, 45, 64, 65,
 76, 81, 82, 99, 101, 122, 156, 162,
 179, 181, 197, 198, 202, 261
Polygala Senega 45, 75, 76, 81, 82,
 83, 99, 101, 154, 155, 162, 181,
 182
Polygonatum biflorum 154, 278, 282,
 284
commutatum 180, 278, 282, 284
Polygonum amphibium 82
aviculare 268, 273, 275
emersum 18, 31, 53, 61, 69, 78
pennsylvanicum 18
scandens 81
virginianum 18
Polymnia canadensis 82, 92, 101
Populus angulata 36
angustifolia 36
balsamifera 36
canadensis 36
deltoides 17, 35, 36, 42, 46, 60, 64,
 77
grandidentata 36

- Medusae* 36
monilifera 36
tremuloides 36, 47, 60, 133, 147, 198, 202, 212, 219
trichocarpa 36
Porteranthus stipulatus 117, 120, 144, 145, 147, 157, 166, 175
Prunus americana 71
Cerasus 71
divaricata 70
pumila 89, 94
serotina 71, 78, 89, 94
spinosa 70, 71
virginiana 71
Pseudotsuga mucronata 198, 199, 202, 212, 219
Psoralea Onobrychis 18, 64, 76, 81, 99, 100, 101, 122, 162, 168
Ptelea trifoliata 6, 8, 22, 28, 50, 60, 260, 265
Puccinellia airoides 137, 147, 208, 218
Pulicaria dysenterica 101, 155, 156
Pulsatilla hirsutissima 26
Pyrus communis 113, 131, 157, 194, 217
japonica 93
Quamasia hyacinthina 18
Quercus alba 84
Phellos 239, 248
rubra 195, 202, 238, 239, 248
velutina 84, 94
Ranunculus abortivus 40, 42, 215, 295
acris 252
bulbosus 252
cymbalaria 137, 292
recurvatus 101
sceleratus 251, 252
septentrionalis 26, 98, 155
Rhamnus alnifolia 180, 187, 200
caroliniana 52, 61
cathartica 52, 61, 180, 252
lanceolata 52, 61
Purshiana 252, 271, 275
Ribes aureum 17, 22, 32, 33, 37, 53, 61, 65
Cynosbati 11, 12, 18, 19, 20, 22, 32, 33, 37, 38, 42, 53, 61, 86, 94, 99, 102, 111, 113, 133, 178, 182, 199, 212, 225, 237, 246, 254, 265, 269, 270
floridum 19, 20, 22, 33, 53, 103, 197, 254
gracile 12, 17, 19, 22, 65, 77, 86, 94
Grossularia 42
longiflorum 254
rotundifolium 53, 61, 66, 86, 94
rubrum 53, 65, 86, 103, 133
Uva-crispa 20, 22, 33, 42, 53, 61, 65
Roripa sinuata 49, 50
Rosa arkansana 47, 60, 106
carolina 47, 60
humilis 23, 28, 47, 60
lucida 47
nitida 47, 60
pratincta 106, 114
sp. 4
Rubus allegheniensis 207
Rudbeckia laciniata 63, 64, 65, 76, 81, 82, 92, 120, 121, 142, 153, 178, 181, 182, 197, 277, 279, 284
triloba 63, 64, 178, 179, 180
Ruellia ciliosa 69, 70, 78, 294
strepens 69, 70, 78, 224, 294
Rumex crispus 2, 104, 114, 160, 174, 208, 218
obtusifolius 2
Rynchospora alba 101
Salix amygdaloides 54, 56, 61
Bigelowii 54, 55
brachystachys 55
discolor 17
herbacea 56
longifolia 5
repens 56
sp. 84, 94
Salsola Tragus 49, 50
Salvia lanceolata 36, 42
Sambucus canadensis 14, 19, 21, 22, 28, 32, 52, 65, 77, 85, 94, 124, 146, 158, 159
Sarcobatus vermiculatus 87, 104, 126, 146, 208
Schedonnardus paniculatus 17, 100, 122, 179, 207, 271, 275
Scirpus americanus 109, 115

- atrovirens* 6, 12, 52, 61, 86, 94, 103,
 114, 125, 186, 200, 229, 247
cyperinus 125, 146, 208, 218
Eriophorum 230
fluviatilis 89, 90, 94, 106, 114, 128,
 146, 242, 247, 253
maritimus 90
microcarpus 223, 230
rubrotinctus 223, 230
sylvaticus 223, 230
Scolochloa festucacea 252
Secale cereale 88, 127, 146, [257],
 265
Senecio aureus 255, 256, 265
cacaliaefolius 255
Douglasii (error for *S. spartioides*)
ductoris 256
lugens (error for *S. spartioides*)
obovatus 17, 18, 32, 81, 82, 92, 99,
 101, 120, 121, 240
palustre 255
spartioides [178], [180], [189],
 [197], [200], [231], 247
Sidalcea oregana 155, 179, 191, 207
 sp. 161
Sieglingia seslerioides 6
Silphium integrifolium 72, 78, 82, 88,
 92, 94
laciniatum 93
perfoliatum 32, 38, 65, 72, 82, 83,
 88, 92, 93, 94, 95, 101, 106, 109,
 114, 236
terebinthinaceum 82, 88, 92, 94
Sium cicutaefolium 90, 242, 247, 253
latifolium 89
Sisyrinchium gramineum (*S. gramin-*
oides) 128, 129, 146
Sitanion elymoides 262
longifolium 162, 163, 174, 187, 200
Smilacina stellata 99, 282
Smilax herbacea 26, 29, 81
hispida 26, 29, 33, 42, 67, 77, 100,
 104, 114, 121, 122, 127, 134, 135,
 147, 160, 173, 187, 200, 251
rotundifolia 134, 135
Solidago caesia 27, 29, 38, 42, 178
canadensis 11, 14, 19, 20, 27, 29, 32,
 37, 38, 39, 42, 45, 66, 73, 77, 78,
 98, 99, 101, 102, 110, 111, 124,
 146, 153, 178, 182, 184, 188, 190,
 200, 224, 229, 231, 234, 238, 240,
 242, 243, 246, 247, 254, 264, 279
flexicaulis 37, 42
glaberrima 238, 246
lanceolata 184
missouriensis 238
mollis 231, 238, 246
nemoralis 184, 190
rigida 18, 27, 29, 32, 38, 179
rugosa 184, 190, 201, 238, 242, 246
serotina 11, 20, 21, 27, 29, 37, 38,
 42
trinervata 73, 78
ulmifolia 27, 29, 46
Sophia incisa (error for *S. brachy-*
carpa) [49], [60], [68], [77]
incisa (error for *S. intermedia*)
 [49], [50]
Sorbus americana 90, 93, 95, 100,
 107, 112, 113, 114, 115, 130, 131,
 132, 146, 147, 157, 165, 166, 174,
 194, 201, 211, 219
Aria 133
aucuparia 133, 165, 174, 211, 217
hybrida 133
terminalis 133
Spartina cynosuroides (partly for *S.*
Michauxiana) [8], [31], [51],
 [60], [67], [75], [76], [77], [78],
 [83], [103], [106], [114], [127],
 [146], [156], [160], [164], [174],
 [181], 258, 265
gracilis 154
Michauxiana (partly under *S. cyno-*
suroides) [8], [31], [51], [60],
 [67], [75], [76], [77], [78], [83],
 [103], [106], [114], [127], [146],
 [156], [160], [164], [174], 181,
 188, 198, 200, 202, 236, 247, 258,
 261, 265, 271, 275, 281, 283, 284
patens 181
polystachya 127, 146
stricta 127, 146
 sp. 180
Sphaeralcea incana 223, 240, 247
lobata 223, 224, 241, 247

- Spiraea lobata* 5
stipulata 145
Sporobolus asperifolius 63, 179, 206, 240, 247
cryptandrus (partly error for *Stipa viridula*) [109], [115], 223, 270, 275, 280
heterolepis 18, 279, 284
longifolius 7, 17, 22, 28, 50, 60, 67, 77, 225
neglectus 32, 182, 274
vaginaeflorus 273, 275, 280
Stanleya pinnata 50
Steironema ciliatum 46, 63, 65, 66, 76, 78, 83, 106, 114, 156, 157, 164, 174, 181, 198, 236, 261, 265, 267, 271, 275, 282, 283
lanceolatum 76, 83, 156, 157, 164, 174, 236, 282
Stenolobium molle 73
stans 73, 78, 88, 94
Stipa comata 75, 231, 247
spartea 18, 57, 61, 163, 188, 200
viridula (partly under *Sporobolus cryptandrus*) 75, 78, [109], [115], 154, 163, 174, 213
sp. 188, 200
Strophostyles helvola 36, 42
Stylophorum diphyllum 17
Symphoricarpos oreophilus 197
parviflorus 168
pauciflorus 45, 153, 154, 179
racemosus 17, 18, 32, 45, 63, 98, 99, 100, 101, 122, 154, 155, 179, 180, 181, 189, 196, 202
Syringa vulgaris 51
Taraxacum Taraxacum 13
Tecoma mollis 73
radicans 73
stans 73
Thalictrum alpinum 154, 161, 174, 232
dioicum 64, 76, 81, 82, 99, 122, 127, 139, 140, 147, 154, 161, 168, 178, 233, 242, 256, 265
Fendleri 140, 223, 232, 242, 256
occidentale 140
polygamum 101, 122, 179
purpurascens 154
sparsiflorum 139, 140
venulosum 140
Tissa canadensis 180, 181, 188, 190, 209
Tithymalis arkansanus coloradensis 154
Tridens flavus (*Tricuspis seslerioides*, *Triodia cuprea*) 6, 22, 28, 50, 60, 259, 265
Trifolium carolinianum 244, 248
medium 193, 210
pratense 182, 193, 210
repens 193, 210
Trillium cernuum 180, 278
recurvatum 37, 81, 82, 98, 282
Triosteum perfoliatum 81, 100, 101
Tripsacum dactyloides 18
Trisetum majus 180, 213, 219
subspicatum 213, 214, 219, 234, 247
Triticum vulgare 19, 28, 88, 94, 162, 163, 174, 276
Troximon glaucum 136
Tsuga canadensis 91, 277
Ulmaria rubra 5
Urtica gracilis 11, 19, 22, 28, 52, 63, 66, 77, 103, 109, 113, 134, 158, 159, 173, 186, 197, 200, 269, 270
Uvularia grandiflora 179, 180, 278, 280, 282
perfoliata 45
Vaccinium pennsylvanicum 166, 175
Vitis-idaea 167
Vagnera racemosa 278, 282
stellata 180, 225, 278, 280, 281, 282, 284
Verbena stricta 7, 17, 22, 28
urticifolia 18, 22, 28, 50, 60, 67, 77, 122
Vernonia arkansana 121
crinita 198, 202
fasciculata 239, 243, 248
gigantea 211, 219
sp. 274, 275
Viola cucullata 11, 32, 37, 81, 99, 100, 101, 120, 123, 155, 163, 174, 230, 247
Nuttallii 230, 247

papilionacea 63, 76
pubescens 82
primulaefolia 164, 230
septentrionalis 180
sororia 154
striata 98, 99, 231
Viorna Douglasii 180
Scottii 105, 114

PURDUE UNIVERSITY,
LAFAYETTE, INDIANA.

Xanthium canadense 11, 14, 17, 18,
19, 22, 32, 46, 71, 74, 78, 236
sp. 88, 94
Xanthoxylum americanum 18, 32, 50,
63, 100, 142, 168, 179, 206, 207,
225
Zea Mays 18, [59], 61, 68, 69, 78


330

331

332







BINDING JAN 15 1930

QK 627 A

Author Arthur, J.C.

802.

Title Cultures of Uredineae. 1899 - 1921.

DATE

NAME OF BORROWER

June 13.73

University of Toronto
Library

BOTANY ~~LIBRARY~~
University of Toronto

DO NOT
REMOVE
THE
CARD
FROM
THIS
POCKET

Acme Library Card Pocket
Under Pat. "Ref. Index File"
Made by LIBRARY BUREAU

